WWW.SURVIVALEBOOKS.COM

By Order of the Secretary of the Army:

JOHN A. WICKHAM, JR.
General, United States Army
Chief of Staff

Official:

R. L. DILWORTH
Brigadier General, United States Army
The Adjutant General

DISTRIBUTION:

Active Army, USAR, and ARNG: To be distributed in accordance with DA Form 12-11A, Requirements for Transportation Reference Data (Qty rqr block no. 390).

☆ U.S. G.P.O. 1987-185-352:70117

WWW.SURVIVALEBOOKS.COM

TABLE OF CONTENTS

		Page
PREFACE		i
CHAPTER 1.	TRANSPORTATION PLANNING AND MOVEMENT CONTROL	1-1
CHAPTER 2.	AIR TRANSPORT	2-1
Section I.	Organization and Operations	2-1
Section II.	Landing Site Selection and Preparation	2-6
Section III.	Cargo Carrying Aircraft	2-11
Section IV.	Restraint Criteria	2-41
Section V.	Airdrop	2-44
CHAPTER 3.	MOTOR TRANSPORT	3-1
Section I.	Organization and Operations	3-1
Section II.	Motor Transport Data	3-69
CHAPTER 4.	RAIL TRANSPORT	4-1
Section I.	Organization and Operations	4-2
Section II.	Rail Transport Data	4-21
CHAPTER 5.	WATER TRANSPORT AND TERMINAL OPERATION	5-1
Section I.	Organization and Planning	5-1
Section II.	Vessel Data	5-32
Section III.	Terminal Equipment, Cargo Containers, Pallets, and Markings	5-42
APPENDIX A.	ORDERS, PLANS, AND SOP FORMATS	A-1
APPENDIX B.	TRANSPORTATION-RELATED DATA	B-1
GLOSSARY		
Section I.	Abbreviations and Acronyms	Glossary-1
Section II.	Terms	Glossary-5
REFERENCES		References-1
INDEX		Index-1

WWW.SURVIVALEBOOKS.COM

FIELD MANUAL
NO 55-15

HEADQUARTERS
DEPARTMENT OF THE ARMY
Washington, DC, 9 June 1986

TRANSPORTATION REFERENCE DATA

PREFACE

This manual is both a planning guide for staff and unit officers and a digest of operational data for use as a reference by operators and users of transportation.

It includes characteristics of typical transportation equipment and facilities and methods for estimating capabilities and requirements for transportation equipment, facilities, and troop units. Personnel and equipment data for the modes of transportation and for transportation terminals are presented, as well as data for computing requirements for staff, supervisor, and control activities. Factors concerning administrative support requirements are discussed.

The manual also contains report formats and examples of orders and standing operating procedures. Loading data for water, rail, motor, and air movements; tables on weights, measures, and conversion factors; and miscellaneous data of general usefulness are included. Planning data contained herein may be modified as necessary to meet known conditions and requirements.

The proponent of this publication is HQ TRADOC. Submit changes for improving this publication on DA Form 2028 (Recommended Changes to Publications and Blank Forms) and forward it to **Commandant, US Army Transportation School, ATTN: ATSP-TDL, Fort Eustis, VA 23604-5399.**

Unless otherwise stated, whenever the masculine gender is used, both men and women are included.

*This publication supersedes FM 55-15, 28 February 1968.

WWW.SURVIVALEBOOKS.COM

CHAPTER 1

TRANSPORTATION PLANNING AND MOVEMENT CONTROL

CONTENTS

	Page
Transportation Planning	1-1
Movement Control	1-5

TRANSPORTATION PLANNING

Transportation planning is determining what must be moved, where and when it must be moved, and the best way to move it. The planner must pay attention to detail. He must realize that while working with a system that calculates detailed computations in minimal time, with the aid of a computer, the computer output must be in a form that is easy to use by transportation management personnel.

Overview

Transportation planning that supports a unified commander's operations plan covers both intertheater and intratheater movement and reception of personnel, materiel, and equipment into the theater and onward to their final destinations. In addition, the competing requirements for limited strategic lift resources, mobility support facilities, and intratheater transportation assets must be assessed in terms of impact on mission accomplishment. Priorities must be established to resolve conflicts. A movement program is prepared in light of both movement constraints and the concept of operations. The movement program is the basis for development of detailed transportation tables and schedules used in the execution phase of the plan.

The payoff in transportation planning lies in the timely delivery to planned destinations of both effective combat forces and the means for their sustained support. Effective combat forces include both unit personnel and unit-related supplies and equipment. Sustained support includes support forces, replacement and filler personnel, resupply and buildup, and construction personnel, materiel, and equipment.

Only the total force and resource requirement for movement need be covered in the movement program. At the outset of transportation planning, all requirements data are assessed in terms of point of origin and destination. After it is determined what is to be moved, requirements (force increments, personnel increments, and cargo increments) are sequenced in order of desired arrival at the destination and the mode of transportation is selected. A port of debarkation (POD) and intermediate PODs are selected at the ship's

WWW.SURVIVALEBOOKS.COM

destination meeting. Time-distance factors are applied, a departure date is reckoned, conflicting requirements for limited transportation assets and mobility support facilities are reconciled, and the movement program is tested for feasibility.

Process

The transportation planning process must be followed regardless of the type of transportation planning being done. First, determine what must be moved. Second, determine what transportation resources are available. Third, balance requirements against resources. Fourth, determine shortfalls and critical points and apply priorities. Fifth and most important, coordinate the plan with all units affected. The transportation planner must determine what the unit needs and then attempt to develop a transportation network to satisfy these needs.

Determine requirements. Each requirement for movement of troops or supplies generates at least one requirement for transportation. Initial transportation requirements can be expressed in terms of tonnage (or numbers of personnel) and distance. In the later stages of planning, the tonnages become classes of supply or even distinct items. Distances become routes between specific origins and destinations are determined.

The responsibility for providing adequate transportation support for the operation rests with the transportation planner. He estimates total requirements based on the supplies required for the supported forces and the distances involved in the phases of the operation. This estimate serves as a point of departure. It functions as a general check on whether the requirements submitted by users are realistic. It also serves to recognize every supply or personnel action as a transportation requirement and to refine those requirements as early as possible.

Some requirements may be within the capability of transport organic to the requesting unit. The planner must determine the extent of such capabilities and urge their use.

Special requirements will be generated when the corps includes an airborne or air assault division. These divisions have limited organic transport capabilities. Therefore, when committed to sustained ground combat operations, they will require significant, dedicated transportation from the corps.

Determine resources. Resources are determined by assessing transportation resources and considering —

- What types of transportation units are available.
- Characteristics and capabilities of each mode of transport.
- Capabilities of available civilian transport, based on a survey of facilities, inspection of equipment, and agreements negotiated with civilian transportation operators.
- Capabilities of host-nation transport, both civil and military, based on a survey of facilities, inspection of equipment, and agreements negotiated with the host-nation.

Balance requirements and resources. Balancing requirements and resources is a process which determines if the transportation capability is adequate to support the operation. It also establishes the work load for each segment of the transportation service. This is the most time-consuming portion of the planning process.

To provide complete transportation support, the planner considers factors other than the necessary operating units. The planner provides for adequate command and control by organizing units according to their mission, proposed locations, and area of coverage. He coordinates with planners of other services to make certain that their plans include the necessary capability for support to the transportation units. He makes recommendations on location of supply and service installations according to their requirements for transportation.

A composite statement of total requirements for transportation speeds up the planning process. Each planner selects the format that he finds most usable. One may use a chart listing

WWW.SURVIVALEBOOKS.COM

all requirements and showing origin, destination, required delivery date, weight, quantity, and class of supply for each shipment.

The process of establishing work loads for each transport mode varies according to the phase of operation. In the usual situation, the plan for the initial phase should provide sufficient motor transport for all cargo and personnel movements. Though some priority items willmove by air, this quantity will normally be only a small percentage of the total supplies.

Work loads are computed individually for each transport mode, according to the characteristics and capabilities of the operating units of that mode. The final plan, however, must combine the units and operations of all modes into a single, integrated transportation system.

During actual operations, the theater commander allocates a portion of the available airlift to the theater army for its requirements. For planning purposes, however, air movement capacity is an assumption based on coordination with Army aviation and Air Force planners. This assumed capacity seldom exceeds the requirement for movement of priority cargo. If there is an excess, planners should use it for nonprogrammed priority movements. Army transport aircraft capacity seldom exceeds the amount required for direct support of combat operations. Therefore, plans should not provide for routine movements by air of other than priority cargo.

Rarely will a transportation plan indicate extensive use of inland waterways. In only a few areas of the world are there extensive inland waterway systems compatible with the requirements for transportation. Inland waterway systems are relatively vulnerable to enemy action and sabotage and are difficult to restore to usefulness.

The planner must be certain to include all types of work loads, such as the following successive, direct, and retrograde shipments of some cargo; documentation for rehandling; requirements for rewarehousing; augmentation of unit's transportation; assistance to medical evacuation plan; and requirements to support allied and civilian organizations.

Determine critical points. Determining critical points along the proposed transportation system is done early in the planning process to identify points such as supply facilities, aerial and water ports, terminal transfer locations, and other points which may create bottlenecks. Accompanying this critical point determination is an analysis of which alternative plans would alleviate possible bottlenecks. This builds flexibility into the system.

Coordinate with other planners. Complete coordination among all planners is mandatory to ensure integrated support. Since the original guidance is seldom valid throughout the planning period, constant coordination with the other staff planners on changes to the mission, commander's concepts, assumptions, intelligence, policies, priorities, allocations, locations of facilities, and other elements necessary to keep planning current is an absolute necessity.

Tables of Organization and Equipment

For a detailed breakdown of the transportation headquarters, by TOE, mission, assignment, and capabilities, refer to Table 1-1. These are not mode oriented, will be used where appropriate, and are provided for general planning information.

WWW.SURVIVALEBOOKS.COM

Table 1-1. Tables of organization and equipment — transportation headquarters

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
Transportation command	55-002H	MISSION: To command and control units employed in the transportation service supporting an independent corps force, to coordinate transportation service support matters with other US, host nation, and allied nations as directed, and to control indigenous transportation resources allocated to the transportation service. ASSIGNMENT: To a COSCOM. CAPABILITIES: The TRANSCOM is one of the functional commands of the theater Army. It is the principal transportation headquarters in the theater and, although located in the COMMZ, provides theater-wide mode operations. The TRANSCOM may be the direct higher headquarters for the brigades or groups located in the COMMZ. At level 1, this unit — • Commands and supervises the activities of all transportation and other assigned or attached units operating the transportation service in support of an independent corps force. • Provides staff planning and coordination of transportation CSS activities by the COSCOM headquarters. • Provides liaison with US, host, and allied nations as directed by COSCOM headquarters. • Controls, as required, indigenous transportation resources allocated to the COSCOM transportation service.
Transportation composite group	55-028H	MISSION: To command units employed in the transportation service supporting an independent division-size force or a two-division separate corps force. ASSIGNMENT: To a support brigade employed in support of an independent division-size force or a two-division separate corps force. CAPABILITIES: At level 1, this unit — • Provides command of attached units (air, motor, terminal, and rail transport) required for operation of a transportation service in support of an independent division-size force. • Provides a nucleus organization for development of a transportation brigade or command during the initial stages of a logistical base buildup. • Develops plans and policies for employment of attached units. • Coordinates rear battle and ADC activities of subordinate units with the designated commander.
Transportation service organization headquarters teams: AA, platoon headquarters (component)	55-500H	MISSION: To provide command, control, and supervision of a transportation separate platoon, company, or battalion organized by attachment of operational teams. ASSIGNMENT: Normally assigned to a transportation company.

WWW.SURVIVALEBOOKS.COM

Table 1-1. Tables of organization and equipment — transportation headquarters (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITIES
		CAPABILITIES: This team provides command and control for a platoon which will normally be composed of more than one team with an aggregate strength of not less than 40 individuals and to which a commissioned officer is not organically assigned.
AB, platoon headquarters (separate)		ASSIGNMENT: Normally assigned to a transportation company. CAPABILITIES: In separate operations, this team provides command and administrative control for a platoon normally composed of more than one team with an aggregate strength of not less than 40 individuals and to which a commissioned officer is not organically assigned.
AC, company headquarters		ASSIGNMENT: Normally assigned to a transportation battalion or group or may operate separately. CAPABILITIES: This team provides command and administrative control for the equivalent of two or more platoons.
AD, battalion headquarters		ASSIGNMENT: Normally assigned/attached to a transportation group or brigade or may operate separately. CAPABILITIES: This team provides command and administrative control of three to seven transportation companies, detachments, or teams of equivalent size.

MOVEMENT CONTROL

For a detailed breakdown of movement control units by TOE, mission, assignment, and capabilities, refer to Table 1-2.

Table 1-2. Tables of organization and equipment—movement control units

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITIES
Transportation movement control agency	55-004H	MISSION: To operate under the direction of the TRANSCOM ACofS Movements, the theater army movement control center, highway traffic headquarters, transportation movement offices, and highway regulating points. ASSIGNMENT: To the TRANSCOM. CAPABILITIES: At level 1, this unit — • When augmented by teams from TOE 55-580, provides the personnel and equipment to control movement of personnel and materiel, except bulk POL by pipeline, within the COMMZ. • When augmented by teams from TOE 55-580, provides the personnel and equipment to perform highway traffic headquarters functions within the COMMZ.

WWW.SURVIVALEBOOKS.COM

Table 1-2. Tables of organization and equipment — movement control units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITIES
		• Maintains liaison with transportation elements of other US Forces and allied or host nations. • Provides command and nontechnical supervision and training of the enlisted component and provides limited unit level administrative supply and communications support to the technical movement control elements.
Transportation movement control center (COSCOM)	55-006H	Mission: To command and supervise attached or assigned units and teams engaged in movement control and highway regulation; to provide movement management for movement of personnel and materiel, except bulk POL moved by pipeline, within or out of the corps area; and to provide highway regulation services within the corps area. ASSIGNMENT: To a COSCOM. CAPABILITIES: At level 1, this unit — • Provides command and control of assigned or attached units or teams. • When augmented by teams from TOE 55-580, provides a central organization and field office necessary to perform movement control services in support of a corps. • When augmented by teams from TOE 55-580, provides personnel and equipment to perform highway traffic headquarters functions within the COMMZ. • Maintains liaison with transportation elements of other US forces and allied and host-nation transportation agencies.
Transportation movement control teams:	55-580H	ASSIGNMENT: To an MCA or MCC.
LA, movement control		MISSION: To perform movement control functions for movement of personnel and materiel, except bulk POL by pipeline. CAPABILITIES: This team is capable of providing single-shift movement control functions at intermediate transfer points, small army air terminals, or specialized supply installations and may also be used to augment a larger movement control team when the size of the operation warrants.
LB, movement control		MISSION: To perform movement control functions for movement of personnel and materiel, except bulk POL by pipeline. CAPABILITIES: This team is capable of providing single-shift movement control functions at a two-ship LOTS terminal, a one- or two-ship fixed water terminal, or an inland transfer point.
LC, movement control		MISSION: To perform movement control functions for movement of personnel and materiel, except bulk POL by pipeline. CAPABILITIES: This unit is capable of providing single-shift movement control functions to support GS supply and/or maintenance activities, a four-ship fixed water terminal operation, or a rail or motor terminal.

WWW.SURVIVALEBOOKS.COM

Table 1-2. Tables of organization and equipment — movement control units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITIES
LD, movement control (region)		MISSION: To perform movement control functions for movement of personnel and materiel, except bulk POL by pipeline. CAPABILITIES: This team is capable of coordinating the activities of up to 10 subordinate movement control teams on a 24-hour basis and may be employed as a central movement control element to support a tactical force where employment of an MCC is not warranted.
LE, movement control (region)		MISSION: To perform movement control functions for movement of personnel and materiel, except bulk POL by pipeline. CAPABILITIES: This team is capable of coordinating the activities of up to 10 subordinate MCTs on a single-shift basis and providing a central movement element to support a small tactical force where the employment of an MCC is not warranted.
LF, movement control (air terminal)		MISSION: To coordinate the expeditious clearance of Army cargo and personnel from US Air Force air terminals and to coordinate the arrival of retrograde or resupply of cargo and personnel. CAPABILITIES: This team is capable of performing the following movement control functions on a 24-hour basis. • Expediting the clearance of Army cargo and personnel arriving at a US Air Force terminal. • Coordinating local movement of retrograde or resupply of cargo or personnel. • Providing technical expertise in the functional areas of transportation, medical services, adjutant general, and supply and coordinating with functional counterparts in the COMMZ and/or corps. • Providing liaison with the US Air Force air terminal commander.
LG, movement control (air terminal)		MISSION: To coordinate the expeditious clearance of Army cargo and personnel from US Air Force air terminals and to coordinate the arrival of retrograde or resupply of cargo and personnel. CAPABILITIES: This team is capable of performing the following movement control functions during a 12-hour shift: • Expediting the clearance of Army cargo and personnel arriving by US Air Force aircraft. • Coordinating local movement of retrograde or resupply of cargo and personnel. • Providing technical expertise in the functional areas of transportation, medical services, adjutant general, and supply and coordinating with functional counterparts in TA and corps. • Providing liaison with the US Air Force air terminal commander.

WWW.SURVIVALEBOOKS.COM

Table 1-2. Tables of organization and equipment — movement control units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITIES
LH, highway regulation point team		MISSION: To operate a highway regulation point, to coordinate the movement of authorized traffic, and to effect changes in truck or convoy routings. CAPABILITIES: This team is capable of observing, following, and reporting the progress of vehicles along routes and adjusting movement schedules as necessary on a single-shift basis.

Movement in the Communications Zone

The TA MCA or MCA provides theater-wide movement control services for all US forces and coordinates with allied and host-nation forces as applicable and necessary. As the central US movement management organization (see Figure 1-1), the MCA prepares movement and port clearance plans and programs. It conducts liaison with higher and lower movement control elements, including host-nation movement control elements, and supervises the activities of subordinate movement control teams (MCTs). It provides technical supervision to the corps movement control center (MCC) and ensures proper use of available host-nation and military-transport assets. For a detailed discussion of the mission and functions of the MCA, see FM 55-10.




Figure 1-1. Movement control agency

WWW.SURVIVALEBOOKS.COM

Movement Through the COMMZ

During the early stages of transition to a wartime environment, all available transportation (US Army, allied, and host-nation) will be used to move personnel, equipment, and supplies forward in the theater. As the theater matures and CONUS-based transportation units begin arriving in the theater, US Army transportation units will perform a greater share of the US transport requirements. However, the theater will continue to use available host-nation transportation assets as required.

As cargo and equipment move through the COMMZ, a change in transportation mode may be necessary. This is particularly true for rail movements. At each location where the mode of transportation is changed, a terminal transfer unit or host-nation equivalent is needed to make the transfer.

The operation of terminal transfer points is a transportation function. It provides for the continuous movement and positive control of personnel, equipment, and supplies through the transportation net. These terminal transfer units or teams are also responsible for transferring retrograde cargo and transportation equipment (such as containers and trailers). The principal Army transportation mode operator for the theater is the transportation command (TRANSCOM).




Figure 1-2. Communications zone

WWW.SURVIVALEBOOKS.COM

Movement in the Corps

Centralized movement management and highway regulation are provided by the MCC. Movement control functions in the corps are similar to those provided by the MCA in the COMMZ. The MCC is under the staff supervision of the COSCOM assistant chief of staff (ACofS) for transportation. The MCC provides transportation control throughout the corps and plans for both logistical and tactical transportation requirements.

All movements from the COMMZ into the corps area must be coordinated by the MCA with the MCC to obtain clearance to enter the corps. Movements from the corps to the COMMZ must also be coordinated by the MCC with the MCA. This coordination is designed to prevent overloading of any segment of the transportation system (see Figure 1-3).




Figure 1-3. Transportation movement control center

Movement Through the Corps

As personnel, equipment, and supplies enter the corps, transportation will be provided by a combination of modes and operators as coordinated between the MCA and MCC.

Throughput of supplies and equipment will be used in the corps as in the COMMZ. Throughput is the direct delivery of cargo to the ultimate consignee, bypassing one or more intermediate supply points. The amount and type of throughput cargo will depend on the tactical situation and the ability of the receiving unit or agency to unload the vehicles and containers with assigned materials-handling equipment (MHE). Containerized cargo will be delivered into the corps support area (CSA). However, since some containers may move into the division support area (DSA), the receiving and unloading capability for container handling must be assured before the division is burdened with them. Containers will not be grounded where there is no container-handling capability.

The corps support command provides combat service support (CSS) to the corps. A transportation brigade is the principal transportation operating headquarters in the corps. A transportation composite group will perform that function in contingency operations (see Figure 1-4).

WWW.SURVIVALEBOOKS.COM




Figure 1-4. Corps area with its MCC

Movement in the Division

The division transportation officer (DTO) and the division support command (DISCOM) movement control officer (MCO) manage the division transportation system.

Transportation organic to the division is limited in number. Therefore, the division gets transportation assets beyond its own capability from the corps, by request from the MCO, through the DTO, to the MCC. For a detailed discussion of the role of transportation movement management within the division. see FM 55-2.

WWW.SURVIVALEBOOKS.COM

CHAPTER 2

AIR TRANSPORT

CONTENTS

		Page
Section I.	**ORGANIZATION AND OPERATIONS**	
	Aviation Transport Units	2-1
	Airlift of Materiel	2-3
II.	**LANDING SITE SELECTION AND PREPARATION**	
	Selection	2-6
	Preparation	2-9
III.	**CARGO-CARRYING AIRCRAFT**	
	External Transport Helicopters	2-11
	Internal Transport Helicopters	2-16
	Military Airlift Command Aircraft	2-22
	Civil Reserve Air Fleet Aircraft	2-25
	Characteristics of Standard Army Aircraft	2-33
IV.	**RESTRAINT CRITERIA**	
	Determining the Center of Gravity	2-41
	Securing Cargo	2-41
V.	**AIRDROP**	
	Delivery Operations	2-44
	Types of Airdrop	2-44
	Release Methods	2-45
	Low Altitude Parachute Extraction System	2-45
	Ground-Air Emergency Codes	2-46

Section I. ORGANIZATION AND OPERATIONS

AVIATION TRANSPORT UNITS

The evolution of warfare has generated a need for greater mobility in support of the Army. Army aviation is an integral part of the transportation system designed to provide efficient and effective movement of personnel and cargo. Army aviation units provide airlift in support of requirements of the theater army,

WWW.SURVIVALEBOOKS.COM

corps, and division. In addition, Army aviation units are capable of providing airlift to support a unified or specified command, a military assistance advisory group or mission operating detachment, or a separate brigade operation. Because of the high mobility requirements of today's Army, considerable reliance is placed on the air mode of transportation provided by Army aviation units.

Categories

These units are separated into two categories, divisional and nondivisional.

Divisional. Aviation elements which are organic to a division are authorized on the basis of each type division's requirement for constantly available aviation support. An air assault division which has a constant requirement for large numbers of aircraft is authorized an aviation group. Each armored, infantry (mechanized), motorized, and light infantry division is authorized a combat aviation brigade.

Nondivisional. To meet the varying requirements of subordinate divisions for aviation support and to augment the organic aviation assets of other theater army and corps elements, separate aviation organizations are included in the Army field force structure. These separate aviation units are referred to as nondivisional aviation units. They normally include helicopter elements which are capable of performing airlift missions and providing direct aerial fire support to subordinate divisions. Special-purpose airplanes, such as reconnaissance and surveillance, are also included.

Mission

The mission of Army aviation units is to provide airlift of personnel and cargo for combat service support and combat support operations as required. Missions assigned to an aviation unit are usually similar to the normal mission as stated in the TOE.

Objective

The aviation company is assigned missions with the objective of assisting in the accomplishment of the mission of the land force.

Authority

When the aviation company is assigned to support a ground unit, the ground unit commander assigns tasks to the aviation commander. The aviation commander retains authority to issue orders to elements under his command as necessary to accomplish these tasks.

Tables of organization and equipment

The table of organization and equipment (TOE) of each military unit prescribes its normal mission, organizational structure, and personnel and equipment authorization. Users who need detailed information on any specific aviation unit should use the TOE of that unit. A breakdown of the aviation companies according to TOE, task aircraft, mission, and assignment is outlined in Table 2-1.

Table 2-1. Army aviation units providing combat service support

UNIT	TOE	TASK AIRCRAFT	MISSION/ASSIGNMENT
Combat aviation company	1-258JA	15 UH-60	MISSION: To provide tactical mobility of combat supplies and equipment of the support unit within the combat zone. ASSIGNMENT: Organic to the combat aviation brigade (TOE 1-105J400).
Combat aviation company	55-167J1	16 CH-47	MISSION: To provide air transport of personnel and cargo for combat service and combat support. ASSIGNMENT: Organic to the medium helicopter battalion (TOE 55-165), either in the air assault division or to the corps transportation group; organic to the support battalion, air cavalry combat brigade (TOE 29-155); may be attached to a composite transportation battalion/group in the

WWW.SURVIVALEBOOKS.COM

Table 2-1. Army aviation units providing combat service support (cont)

UNIT	TOE	TASK AIRCRAFT	MISSION/ASSIGNMENT
			corps support command or theater army area command.
Combat aviation company	1-257J410	23 UH-1	MISSION: To provide tactical mobility of troops, supplies, and equipment within the combat zone. ASSIGNMENT: To the combat aviation brigade.
Combat aviation company	1-257J420	15 UH-60	MISSION: To provide tactical mobility of troops, supplies, and equipment within the combat zone. ASSIGNMENT: To the combat support aviation battalion of the combat aviation brigade.
Combat aviation troop	1-257J430	15 UH-60	MISSION: To provide tactical mobility of troops, supplies, and equipment within the combat zone. ASSIGNMENT: To the armored cavalry regiment.
Combat aviation company	7-269J	15 UH-60	MISSION: To provide tactical mobility of troops, supplies, and equipment within the combat zone. ASSIGNMENT: Organic to the combat aviation battalion, air assault division (TOE 7-255).
Combat aviation company	1-259J4	15 UH-60	MISSION: To provide tactical mobility of combat troops, supplies, and equipment of the supported unit within the combat zone and aerial surveillance of the combat zone. ASSIGNMENT: Organic to the combat aviation brigade (TOE 1-105J400).
Heavy helicopter company	55-259H	9 CH-54	MISSION: To provide combat service support airlift for movement of heavy supplies, vehicles, aircraft, and equipment and, as directed, to provide combat support airlift of combat units and air supply of units engaged in combat operations. ASSIGNMENT: To a combat aviation group (TOE 1-252). Normally, attached to an aviation battalion (TOE 1-256).

AIRLIFT OF MATERIEL

The Army air transport service was not designed to compete with the Air Force. Its purpose is to provide rapid-response transport for high-priority personnel, supplies, and equipment to locations inaccessible by other transportation modes and to supplement the lift capability of other Army transportation modes.

Area of Operations

Communications Zone. In the COMMZ, Army air transport is furnished by the TRANSCOM's aviation battalions, which are composed of up to six Army medium- and heavy-lift helicopter companies. These aircraft are used for the movement of high-priority cargo and personnel to and from Air Force terminals and for rapid deployment of rear area protection forces. Based on the theater movement program, these heavy- and medium-lift units are located where they can best fulfill the programmed requirements. Army helicopters complement other Army transportation modes when speed is essential and if other transportation modes cannot be used because of their inherent limiting factors.

Theater of Operations. Army air transport in the theater can be designed to provide the connecting link between theater air and ocean terminals and the receiving supply activities, the receiving units, or terminal transfer points. This air movement may be programmed or nonprogrammed. For example, the MCA may task the COMMZ aviation battalion to transport high-priority cargo daily from theater air terminals forward to the supply activity who will issue the cargo, or the MCA may pull the programmed commitment and

WWW.SURVIVALEBOOKS.COM

issue a higher-priority nonprogrammed commitment. There are both advantages and limitations to Army air transport in a theater of operations.

Advantages. Army transport helicopters offer the following advantages:

- A high degree of flexibility.
- Speed of transport.
- Internal or external transport of cargo or equipment.
- Immunity to surface or terrain conditions.

Limitations. Army transport helicopters have the following limitations:

- Vulnerability to enemy air action.
- Vulnerability to air defense weapons and other ground fire.
- Susceptibility to adverse weather conditions.
- Inherent decrease in lift capability as air density decreases due to altitude, temperature, or humidity changes.
- Higher maintenance per operating hour than other modes.
- Dependence on logistics support.

Corps. Army air transport originating in the corps is managed by the corps movement control center. The MCC obtains its combat service support medium-lift helicopters from the corps aviation brigade/group and its other transportation assets from the corps support command transportation brigade. The MCC controls and directs which logistical support missions the CH-47 helicopters will fly. MCC control of all modes of corps logistics transportation assets is essential to make sure that the best mode is selected to accomplish the mission.

Medium-lift cargo helicopter companies of the aviation brigade/group (corps) provide a highly mobile and responsive means for logistics movement of supplies and equipment. To support these operations, medium-lift helicopter units provide logistics movement of ammunition, repair parts, POL, engineer material, artillery, special weapons, troops, disabled aircraft and vehicles, and other large or heavy items. The helicopters augment surface transportation systems to meet increased transportation demands in surge operations, to overcome terrain obstacles, and to meet time-sensitive requirements.

The logistics mission for the helicopters is characterized by single-ship, independent operations. The helicopters will not routinely operate forward of the brigade support area. However, the trend to position more units forward and to dedicate aircraft for weapon system resupply will require more forward employment of the medium-lift helicopters. This may require aircraft to operate as close as 5 to 7 kilometers from the forward edge of the battle area.

Aircraft may also be required to operate beyond the forward line of own troops (FLOT). to support air-land-battle-deep operations. Logistics support of the covering force justifies additional cargo helicopter commitments in the forward area to support these maneuver units. Both external loads at high altitudes and internal loads, coupled with nap of-the-earth flying, are used, depending on the situation. The division's utility helicopters will provide most of the intradivision air transport support.

Programmed and Nonprogrammed Movements

Programmed and nonprogrammed Army air transport will performed in the COMMZ, corps, and division.

Programmed Programmed air transport permits matching movement requirements against airlift capability. It also allows for the maximum ton-mile capability of the aircraft and is the most economical method of air transport. Programmed air movements are generally (but not necessarily) carried out over established routes.

Nonprogrammed. Nonprogrammed air transport results from changing requirements which directly or indirectly affect the transportation pipeline supporting the battlefield. Some of these are shown below:

- Unplanned requirements for resupply or repositioning of existing supplies.
- Emergency movement of personnel and equipment.
- Assistance to aeromedical air ambulance units.

WWW.SURVIVALEBOOKS.COM

• Prevention of congestion at an air or ocean terminal.

Nonprogrammed air transport is an integral part of the ALOC; it may or may not be carried out over the established air lines of communications.

Employment Considerations

Although optimum utilization of airlift would be attained by use of Air Force transport aircraft to move materiel from a COMMZ depot directly to the user, this is often impracticable in a tactical situation. There normally must be a point at which wholesale airlift is terminated and retail deliveries to the user are undertaken by Army aviation elements.

Wholesale airlift. Factors to be considered in determining the point at which wholesale airlift is terminated include the following

Airfields. Suitable airfields must be available at points where materiel is to be airlanded by Air Force transport aircraft.

Enemy action. The enemy may be capable of limiting or denying the use of forward areas for airlanding by transport aircraft.

Receiving unit capability. Combat units in forward areas have a limited capability to receive, store, protect, and redistribute materiel airlanded in wholesale lots by transport aircraft.

User requirements. The user may be a unit of company size or smaller that requires resupply in retail quantities only.

Efficiency. The efficient employment of Army aviation is based upon the following considerations:

Economy of use. Aircraft should not be used to transport cargo when surface transportation is equally effective. Since there are seldom enough aviation assets to satisfy all requirements of commanders, most aviation support is allocated on a priority basis.

Ready availability. The ability to respond rapidly to demands for aviation support increases the value of air transport to supported commanders. Ready availability is obtained by locating aviation units as close as practicable to the supported units. Also, the inherent mobility of aircraft permits support to be made available to units located throughout a wide area. Ready availability is enhanced by intelligent scheduling of operational aircraft and by programming of required maintenance.

Operational Considerations

Air density. Unlike surface transportation, where the payload of a particular vehicle is relatively fixed, aircraft payloads are affected by air density. Denser air provides greater lift to an aircraft's wing or rotor blade, thus increasing the weight-lifting performance of the aircraft. Air density is affected by temperature, altitude, and humidity.

Temperature. An increase in temperature causes a decrease in air density. The amount of air that occupies 1 cubic inch at low temperature will expand and occupy 2 or 3 cubic inches as the temperature rises. It is important to recognize that the payload of a particular aircraft can change, depending on the time of day a flight is scheduled. Usually early morning temperatures favor operations, and noonday heat causes a decrease in the efficiency of the aircraft.

Altitude. An increase in altitude causes a decrease in air density. This factor is particularly important when operations are conducted from areas high above sea level. It is necessary either to decrease the aircraft weight or to increase the length of takeoff and the landing strip.

Humidity. An increase in humidity causes a decrease in air density. Air always contains some moisture in the form of water vapor, but the amount varies from almost 0 to 100 percent. This water vapor is known as humidity. As humidity increases, water particles displace the air, causing a decrease in air density and reducing the performance efficiency of the aircraft.

Distance. The distance to be flown is particularly important when using Army transport aircraft, because the allowable load is computed after the amount of fuel, plus reserve, is determined. Aircraft must carry less fuel with a relative reduction in distance flown when the maximum payload is desired, and the

WWW.SURVIVALEBOOKS.COM

payload must be reduced when the maximum distance is the important factor.

Weather. Weather conditions influence the operations of Army aviation elements. While low ceilings and limited visibility may restrict operations, such conditions may be used as an advantage to shield the aircraft from enemy observation. However, adverse weather generally reduces the efficiency of Army air transport operations. Although Army transport aircraft can operate under instrument flight conditions, commanders should establish weather minimums to preclude scheduling flights that jeopardize the safety of aircraft and personnel. Weather minimums should be established commensurate with the experience of the pilots, type of aircraft employed, urgency of mission, navigational aids available, terrain along the flight route, and time of operation.

Enemy situation. Consider the location and capabilities of enemy forces before finalizing flight routes for Army air transport operations. Avoid areas where suspected enemy antiaircraft weapons or known enemy ground fire exist. Prepare prearranged evasive-action flight plans for aviation units in case enemy aircraft are encountered.

Terrain. Consider terrain features with regard to their possible effects on each operation. Terrain influences the following:

- Location of takeoff and landing sites.
- Flight routes.
- Identification of prominent landmarks for navigational purposes.
- Location of navigational aids.
- Location of emergency landing sites.

Flight routes. Combat operations generate many demands for the use of airspace. Employment of US military aircraft, artillery, drones, and missiles must be coordinated to ensure adequate safety, proper identification, and operational efficiency. Army aviation units must ensure that flight routes are properly coordinated and approved by the appropriate air traffic control facility before beginning combat service support or combat support operations.

Communications. Combat service support and combat support airlift operations require that adequate communications be established before the beginning of a mission. Voice communication is necessary among Army airlift and command units, supported organizations, inflight aircraft, and takeoff and landing sites.

Support Requirements

Primary support requirements are the availability of petroleum, oils and lubricants (POL); ammunition; and aircraft maintenance support.

Petroleum, oils, and lubricants. Aircraft consume large quantities of fuel. POL items require special handling. Refueling facilities should be readily available.

Ammunition. The ammunition used in Army aircraft may be expended rapidly. This necessitates locating resupply facilities near the area of operations to avoid the time penalty involved in lengthy flights to obtain supplies.

Aircraft maintenance. Performance of aircraft operations on a sustained basis is dependent upon efficient aircraft maintenance. Maintenance of aircraft begins with that performed by aviation unit maintenance (AVUM) and extends through aviation intermediate maintenance (AVIM) to depot maintenance. To assure continuing availability of aircraft, close coordination is required between the aviation unit commander, the ground combat commander, and the supporting maintenance unit commander. Proper scheduling of aircraft is mandatory to prevent maintenance overload which can result in excessive downtime for aircraft.

Section II. LANDING SITE SELECTION AND PREPARATION

SELECTION

The selection of a usable pickup zone (PZ) or landing zone (LZ) is extremely important. Logistical and tactical considerations must be analyzed and taken into account to assure that the PZ/LZ is correctly placed to support the

WWW.SURVIVALEBOOKS.COM

mission. The area must be accessible to the aircraft that will use the site. The supported/receiving unit commander, in coordination with the aviation unit liaison officer, if available, will select and prepare the PZ. The aviation unit liaison officer will make the final decision concerning minimum landing requirements.

Dimensions

The size of the landing site will depend on the number of landing points within it, the size of the landing points, and the dispersion required between the landing points as the tactical situation dictates (see Figure 2-l.) The minimum size of a landing point for each size helicopter is shown in Table 2-2.

Many considerations such as helicopter type, unit proficiency, nature of loads, climatic conditions, and day or night operations may apply to the size of the landing points used. If such information is not available from the aviation unit, a size 5 landing point should be prepared. The minimum recommended distance between landing points within the landing zone, where no consideration is given to dispersion, is the same as that size helicopter's minimum diameter; only measure from the center of one landing point to the center of the other. (See Figure 2-2.)




Figure 2-1. Helicopter landing sites




Figure 2-2. Size 3 aircraft landing zone for V-formation

WWW.SURVIVALEBOOKS.COM




Figure 2-3. Determining ground slope

Table 2-2. Size helicopter for landing point

Helicopter size	Minimum diameter of landing point	Type helicopter
1	80 feet (25 meters)	OH-6, OH-58
2	125 feet (35 meters)	UH-1
3	160 feet (50 meters)	UH-60
4	264 feet (80 meters)	CH-47, CH-53, CH-54
5	328 feet (100 meters)	To be developed

Surface

The surface of the center of the landing point must be level and sufficiently firm to allow a fully loaded vehicle (1/4-ton truck for size 1 or 2 helicopters and a 3- to 5-ton truck for size 3 to 5 helicopters) to stop and start without sinking. The entire landing point must be cleared of any loose material, piles of dust, or sand which could be blown up by the aircraft's rotor blades. Landing points with sandy or dusty surfaces should be stabilized if possible. All trees, brush, stumps, or other obstacles that could cause damage to the main or tail rotor blades or to the underside of the aircraft must be cleared around the landing points. Any snow on a landing point should be packed or removed to reveal any obstacles and to reduce the amount of loose snow blown over the area. A marker panel is essential to provide a visual reference for the pilot's depth perception in a snow-covered landing zone and also to reduce the effect of whiteout.

Slope

Ideally, the ground at the landing point should be level. Where a slope is present, it should be uniform. During a daylight approach, the slope should not exceed 7 degrees (1 in 8) if the helicopter is to land. A greater slope may be acceptable for hover operations. During a night approach, a reverse slops as viewed from the approach path, is not normally acceptable. Forward and/or lateral slope should not exceed 3 degrees (1 in 19). If these criteria cannot be met, use of the landing point must be confirmed by the aviation unit. (See Figure 2-3.)

WWW.SURVIVALEBOOKS.COM

Approaches

Ideally, there should be an obstruction-free approach and exit path into the wind. Approaches which do not meet the following minimum requirements may be acceptable depending on the nature of the' operation. However, when these criteria cannot be met, the aviation unit must be consulted.

Daytime. Within the selected approach and exit paths, the normal maximum obstruction angle to obstacles during daylight hours should not exceed 6 degrees, as measured from the center of the landing point to a distance of 1,640 feet (500 meters). The maximum obstacle height at the 1,640-foot mark is 171 feet (52 meters). (See Figure 2-4.)




Figure 2-4. Maximum angle of approach (daylight)

Nighttime. The selected approach and exit paths should contain a sector of not less than 16 degrees in azimuth measured from the center of the landing point. The width of the approach and exit paths should not be less than the width of the area in the landing point cleared to 2 feet (.6 meters) in height. Less than 164 feet (50 meters) will not be acceptable; more than 328 feet (100 meters) is not necessary. Within the selected approach and exit path, the maximum obstruction angle should not exceed 4 degrees as measured from the center of the landing point to a distance of 9,843 feet (3,000 meters). The maximum obstacle height at the 9,843-foot mark is 689 feet (210 meters). (See Figure 2-5.)




Figure 2-5. Maximum angle of approach (night)

Density Altitude

Density altitude is determined by altitude, temperature, and humidity. For planning, as density altitude increases, the size of the landing zone must be increased proportionately. Generally, hot and humid conditions at a landing site will decrease the lift capabilities of helicopters using that site. Therefore, a large area and better approach and/or departure routes are required more for fully loaded helicopters than for empty or lightly loaded ones, since most helicopters cannot climb or descend vertically when fully loaded.

Concealment

A pickup zone/landing zone near the forward line of own troops should be masked whenever possible. The selection of the approach and exit routes should be based on the availability of good masking features.

PREPARATION

Receiving Flight Formations

In large tactical relocations or resupply missions, the helicopters will normally fly in formations. The PZ/LZ and the ground crew will have to be prepared to receive them. When possible, helicopters should land in the same formation in which they are flying. However, planned formations may require modification for helicopters to land in restrictive areas. If a modification in flight formation is required for landing, the change requiring the least shift of helicopters should be used and the flight leader notified as soon as radio contact is made. (See Figure 2-6.)

Many times, size 4 helicopters will not fly in standard flight formations and will be received one or two at a time. In such cases, each aircraft initially approaches and hovers at the Y and is then guided to its cargo pickup point by the signalman.

Marking the Landing Site

The landing site, during daylight hours, can be marked with signal panels but, because of the possibility of the rotor wash from the helicopter tearing them from the ground and causing a hazard, they are seldom used. During daylight operations the landing sight is usually marked with colored smoke.

WWW.SURVIVALEBOOKS.COM




Figure 2-6. Landing zone/pickup zone landing formation for size 4 helicopters

The landing site is also marked by the ground guide, who holds both arms straight up over his head or holds a folded VS-17 signal panel chest-high.

CAUTION

When using colored smoke to mark the PZ/PL, be sure the canister is far enough away from the landing point so the rotor wash does not pick up the smoke and obstruct the pilot's vision.

During night operations, the landing point for the lead aircraft is marked by amber beacon lights. The single point landing site or the landing point for the lead aircraft, if aircraft are in formation, is marked with either an inverted Y or T (see Figure 2-7). The aircraft will touch down or hover on the midpoint of the legs of the Y and to the left of the stem if the T is used. The landing points for the other aircraft in the formation are also marked with lights. For size 1 through size 3 helicopters, a single light is used to mark the landing point; size 4 and 5 helicopters have two lights spaced 10 meters apart to mark the landing point. The aircraft lands to the left of the lights.

WWW.SURVIVALEBOOKS.COM




Figure 2-7. The Y- and T-formations for single-point formation landing sites

Whenever the size of the LZ/PZ permits, the size of the landing points should be increased to the next largest size for the helicopters involved to provide an extra margin of safety for night operations.

Marking Obstacles

During daylight operations, obstacles that may be difficult to detect or impossible to remove, such as wires, holes, stumps, and rocks, are marked with red panels or by any other easily identifiable means. Devices used to mark obstacles must be colored red.

During night operations, red lights are used to mark all obstacles that cannot be easily eliminated. In most combat situations, the need for security will prohibit the use of red lights to mark the tops of trees on the approach and departure ends of the landing zone. In training, however, or in a rear area landing site, red lights should be used whenever possible. If obstacles or hazards cannot be marked, aviators should be fully advised of existing conditions by radio.

Section III. CARGO-CARRYING AIRCRAFT

EXTERNAL TRANSPORT HELICOPTERS

The helicopter method of transport can overcome many obstacles that prevent other methods of transportation from completing the mission.

Advantages

One major advantage of transporting loads externally by helicopter is that it rapidly moves heavy, outsized, or "needed now" items directly to their destinations. Another advantage is that damaged or congested highways, destroyed bridges, and most en route terrain obstacles have little impact on cargo transport. The helicopter may use different flight routes to provide a diversion and maintain security of the unit on the ground.

Another advantage of external transport is that cargo may be rapidly moved into or taken out of an area, which helps the ground unit obtain items of equipment when and where it needs them. The helicopter can also place fire power where it is needed and then relocate it in a rapidly changing battlefield situation. A PZ/LZ can be relocated rapidly to avoid detection and thus aid in ground security.

Disadvantages

The disadvantages of transporting cargo externally by helicopter appear when the size, weight, and flight characteristics of the cargo fall outside of the design limits of the aircraft. If cargo is too light or bulky, it will not fly right when suspended beneath the aircraft. If it is too heavy, the aircraft will not be able to lift it.

Generally, any restrictions which apply to helicopters also apply to sling load operations or routine training flights. Limited aviation

WWW.SURVIVALEBOOKS.COM

assets, maintenance downtime, and mission priority must be taken into account to assure that aircraft are used wisely. Weather conditions and the PZ/LZ terrain can present natural obstacles to the use of aircraft and become particularly critical factors during external sling load missions. When operations are planned during the hours of darkness or under reduced visibility, the size of the PZ/LZ must be increased to give the pilot more room to maneuver.

Responsibilities

There are normally three different elements involved in a sling load mission: the supported unit (requests the mission), the aviation unit (provides the aircraft), and the receiving unit (receives the cargo). Sometimes, such as during a unit relocation, the supported and receiving units are the same. The responsibilities and functions of each are discussed below.

Supported unit. The supported unit is responsible for—

- Selecting, preparing, and controlling the PZ. (Pathfinders can be of great assistance in this area if available.)
- Requisitioning all the equipment needed for sling load operations, including slings, A-22 cargo bags, cargo nets, and containers.
- Storing, inspecting, and maintaining all sling load equipment.
- Providing a sufficient number of trained ground crews for rigging and inspecting all the loads, guiding the helicopters, hooking up the loads, and clearing the aircraft for departure.
- Securing and protecting sensitive items of supply and equipment.
- Providing load derigging and disposition instructions to the receiving unit.
- Providing disposition instructions to the receiving and aviation units for the slings, A-22 cargo bags, cargo nets, and containers.

Aviation unit. The aviation unit is responsible for—

- Establishing coordination with the supported and receiving units and appointing a liaison officer who is thoroughly familiar with the capabilities and limitations of the unit's assigned aircraft.
- Advising the supported unit on the limitations of the size and weight of the loads which may be rigged.
- Advising the supported and receiving units on the suitability of the selected PZ/LZ.
- Providing assistance for the recovery and return to the PZ of the slings, A-22 cargo bags, cargo nets, and containers, as required by the supported unit. (The supported unit is still responsible for packaging and providing disposition instructions to the aviation unit.)
- Arranging for the aircraft to be at the PZ/LZ on schedule.
- Establishing safety procedures that will ensure uniformity and understanding of duties and responsibilities between the ground crew and flight crew. For example, determining which direction the ground crew (below the helicopter) departs from after hookup. If the ground crew moved from the aircraft in the same direction as the aircraft, injury could result. Each PZ has a different shape and obstacle. In an emergency, the pilot must know in which direction to go to set the aircraft down to avoid hitting the ground crew. (While the supported unit is responsible for ensuring that the load is properly rigged, the pilot has the prerogative to refuse the load if he notices a rigging error while approaching the load or if the load does not ride properly when first picked up to a hover.)


Receiving unit. The receiving unit is responsible for—

- Selecting, preparing, and controlling the LZ.
- Providing trained ground crews to guide the aircraft in and derig the load.
- Coordinating with the supported (sending) unit for the control and return of the slings, A-22 cargo bags, or any other items that belong to the supported unit, and returning them as soon as possible.
- Preparing, coordinating, and inspecting backloads, such as slings, A-22 cargo bags, and so forth, and having them ready for hookup or loading.


WWW.SURVIVALEBOOKS.COM

Methods


Slings. Figure 2-8 shows the three types of slings used in external air transport operations. They are the 10,000- and 25,000-pound-capacity slings, multi-leg slings, and aerial-delivery slings.



*AERIAL DELIVERY SLINGS
10,000-POUND



*NYLON AND CHAIN MULTI-LEG SLINGS,
15,000-POUND



10,000- AND 25,000-POUND-CAPACITY SLING SETS

*BEING PHASED OUT OF THE INVENTORY.

Figure 2-8. External air transport slings

WWW.SURVIVALEBOOKS.COM

Cargo nets. Figure 2-9 shows the three types of cargo nets used in external air transport operations. They are the 5,000-, 8930-, and 10,000-pound-capacity nets.




Figure 2-9. Cargo nets

WWW.SURVIVALEBOOKS.COM

Cargo bags. The A-22 cargo bag is an adjustable cotton duck cloth and webbing container consisting of a sling assembly, cover, and four suspension webs. This external carrying device can be used to transport any standard palletized load, loose cargo, and oil drums. The bag can transport up to 2,000 pounds of cargo. You may rig the cargo in the bag with or without the cover. Figure 2-10 shows the parts of the bag.




Figure 2-10. A-22 cargo bag

Personnel

The number of personnel in a ground crew may vary depending on the situation, type of cargo, and the size of the pickup zones. The unit commander determines how many crews need to be trained. Generally, three people make up the ground crew: the signalman, the hookup man, and an assistant hookup man. The commander must also provide local security for the operation. (This task is not a responsibility of the ground crew.)

Large items of equipment may require more than three people to prepare them for sling loading. For example, bridge sections or towers may need as many as eight people to manhandle them into place for aerial pickup. Although each member of the crew has specific duties during the operation, each person should be trained in how to perform all duties.

Equipment

Rigging and hookup. Each ground crew needs a separate and complete issue of rigging and hookup equipment in addition to weapons, radios, and operational equipment. This is because there might be several pickup or landing zones, and they may be spread out over a large area. Refer to FM 55-450-1 to obtain the proper method to rig loads for external air transport.

Protective. The ground crew members involved in helicopter operations are exposed to the hazards of noise and rotor downwash caused by the helicopter. Therefore, protective equipment must be worn by the ground crew members when they are performing their duties.

Pickup zone/landing zone. The following list of minimum equipment is needed to operate the PZ/LZ:

- Helmet.
- Goggles (or protective mask).
- Snap-ring pliers.
- Ear plugs.
- Gloves.
- Smoke grenades.
- Tool kit T33 (pliers and pocket knife).

Static electricity discharge. In flight, a helicopter generates and stores a charge of static electricity. When the helicopter lands, this charge is grounded out. While the helicopter is in flight, however, this charge remains stored unless a path is provided for it to be channeled into the earth. A ground crew member provides this path by contacting the helicopter cargo hook when it is positioned over a cargo hookup point. Although this charge may not cause an electrical burn, it can cause a muscular reaction which may, if the individual concerned is on unsure footing, result in injury from a fall. An individual shocked by the electricity may also suffer delayed discomfort from muscular cramps or spasms.

To avoid the possibility of a ground crew member being shocked by the static electricity, a discharge probe is used to ground the cargo hook. Since this probe channels the electricity

WWW.SURVIVALEBOOKS.COM

from the helicopter directly into the ground, the ground crew member is assured of receiving no shock when he touches the cargo hook during hookup operations.

The static electricity discharge probe is currently being procured and may not be an item of issue when this manual is published. If it is not available, one will have to be made locally. It consists basically of an insulated plastic tube with a metal hook and one end with a wire attached leading to a ground rod. The entire length of wire must be insulated, as contact with personnel will cause a severe shock. In use, the ground rod is driven into the earth and the contact rod is held by a ground crew member. As the helicopter hovers over the load, the assistant hookup man holds the contact rod against the cargo hook, thus grounding out the stored electrical charge. Meanwhile, the hookup man places the clevis on the hook.

WARNING

Contact between the discharge probe and the cargo hook must be maintained until the clevis is placed on the hook. If contact between the probe and the hook is not maintained, the ground crew member may receive a serious shock. This does not mean the ground crew should rig a spring clip to hook directly to the aircraft. If contact between the probe and hook is broken, then contact must again be made before touching the hook.




Figure 2-11. Static electricity discharge probe

INTERNAL TRANSPORT HELICOPTERS

Advantages

The helicopter method of transport can overcome many obstacles that prevent other methods of transportation from completing the mission. One major advantage of transporting the load internally is that the helicopter rapidly moves items directly to their destinations. Another advantage is that damaged or congested highways, destroyed bridges, and most en route terrain obstacles have little impact on cargo transport. The helicopter may use different flight routes to provide a diversion and to maintain security of the unit on the ground. Another advantage of internal transport is that cargo may be rapidly moved into or out of an area, which helps the ground unit obtain items of equipment when and where it needs them. The helicopter can move combat troops and weapons where they are needed and relocate them in a rapidly changing battlefield situation. A landing zone can be relocated rapidly to avoid detection and on-ground security.

Disadvantages

The disadvantages of transporting cargo internally by helicopter appear when the size and weight of the cargo may exceed the design limits of the aircraft. Any restrictions which apply to helicopters in general also apply here, whether for internal load operation or a routine training flight. In addition, aviation assets are

WWW.SURVIVALEBOOKS.COM

limited and maintenance downtime and priority of missions must be taken into account to assure that aircraft are used wisely.

Bad weather may adversely affect the operation and the LZ terrain can present natural obstacles to the use of aircraft which become particularly critical factors during internal load missions.

Responsibilities

There are normally three different elements involved in an internal load mission: the supported unit (requests the mission), the aviation unit (provides the aircraft), and the receiving unit (receives the cargo).

Supported unit. The supported unit is responsible for–

- Selecting and controlling the pickup zone. Pathfinders can be a great help in both of these.
- Assuring that advanced coordination is effected with the aviation unit.
- Assuring that before equipment is prepared all loading, tie-down, and unloading procedures; tie-down diagrams; and tiedown data tables are carefully reviewed.
- Preparing supplies and/or equipment for air transport with technical supervision and assistance as required from appropriate field support units.
- Assuring that if vehicles are loaded with cargo, the cargo is restrained in the vehicle and all other loose equipment in the vehicle is secured.
- Loading the vehicle into the helicopter, tying it down, and unloading it from the helicopter, once the helicopter commander, flight engineer, or crew chief gives approval.
- Assuring that loads are properly prepared and do not exceed any weight or size limitations imposed by the transporting helicopter.
- Providing appropriate safety equipment to all unit personnel who will be around the loading operations.
- Policing the pickup zone.

Aviation unit. The aviation unit is responsible for—

- Establishing coordination with the supported and receiving units and appointing a liaison officer who is thoroughly familiar with the capabilities and limitations of the unit's assigned aircraft.
- Advising the supported unit on size and weight limitations of the loads which may be hauled.
- Advising the supported unit and the receiving unit on the suitability of the selected PZ/LZ.
- Becoming familiar with the security, safety, and technical peculiarities of the loads which may adversely affect air transport.
- Providing all components of the 5,000- and 10,000-pound tie-down assemblies used for internal transport in helicopters. (The supported unit is still responsible for packaging and providing disposition instructions to the aviation unit.)
- Arranging for the aircraft to be at the PZ on schedule.
- Establishing safety procedures that will ensure uniformity and understanding of duties and responsibilities between the ground crew and flight crew.

Receiving unit. The receiving unit is responsible for—

- Selecting and controlling the LZ.
- Providing trained ground crews to guide the aircraft in.
- Coordinating with the supported (sending) unit for retrograde of items that belong to the supporting unit.
- Preparing, coordinating, and inspecting back loads and having them ready for loading when the aircraft arrives.

Tie-Down Rings

Several types of cargo restraint devices can be used to tie down cargo. Tie-downs must be correctly attached to prevent cargo from shifting. Each tie-down has a rated strength to prevent cargo from shifting.

WWW.SURVIVALEBOOKS.COM

UH-l Iroquois. The tie-down rings in the floor of the UH-1 have a rated holding capacity of 1,350 pounds in the vertical direction and 500 pounds in the horizontal direction. The restraint criteria are 4 g's forward, 2 g's aft, 2 g's vertical, and 1.5 g's lateral. Table 2-3 shows the dimensions of the cargo compartments by mode. Figure 2-12 shows the tie-down fittings for a UH-1 H helicopter.

Table 2-3. Dimensions of cargo compartments by model

	UH-1C/M	UH-1D/H
Height of Floor above Ground	26″	32″
Cargo Compartment		
Length	60″	92″
Width	80.5″	96″
Height	56″	52″
Cargo Door		
Width	48″	92″
Height	48″	49″




Figure 2-12. UH-1H tie-down rings

WWW.SURVIVALEBOOKS.COM

UH-60 Blackhawk. The tie-down fittings in the floor have a rated capacity of 5,000 pounds in any direction. The cargo restraint net rings on the walls and ceiling are rated at 3,500 pounds. The restraint criteria are 12 g's forward, 3 g's aft, 3 g's vertical, and 8 g's lateral with troops and cargo; 2 g's is the lateral criterion with cargo only. Table 2-4 shows internal cargo loading specifications. Figure 2-13 shows the locations of the tie-down fittings for a UH-60 helicopter.

Table 2-4. UH-60A internal cargo loading specifications

SECTION	MAXIMUM CAP (LB)	MAXIMUM LB/SQ FT	SQUARE FEET
FORWARD CABIN	5,460	300	18.2
CENTER CABIN	8,370	300	27.9
AFT CABIN	8,370	300	27.9




Figure 2-13. UH-60A tie-down rings

CH-47 Chinook. There are eighty-seven 5,000-pound-capacity tie-down rings (83 in the fuselage and 4 on the ramp) and eight 10,000-pound-capacity tie-down rings in the cargo compartment. The restraint criteria are 4 g's forward, 2 g's aft, 4 g's down, 2 g's up, and 1.5 g's lateral. 'Figure 2-14 shows the locations of the tie-down rings for a CH-47 helicopter.

CH-54 Tarhe. Interior dimensions of the pod are 106 inches wide, 78 inches high, and 328 inches long. There are ninety-six 5,000-pound-capacity tie-down rings in the floor of the pod. Pod limitation is 20,000 pounds. Restraint criteria for the pod are 2 g's forward (4 g's forward when personnel are not protected by aircraft structure and/or other barriers), 2 g's aft, 2 g's vertical, and 1.5 g's lateral. Figure 2-15 shows the locations of the tie-down rings for a CH-54 helicopter.

WWW.SURVIVALEBOOKS.COM




Figure 2-14. CH-47 tie-down rings




Figure 2-15. CH-54 tie-down rings

WWW.SURVIVALEBOOKS.COM

Loading/Unloading System

The Helicopter Internal Cargo Handling Systems (HICHS) is a roller system designed for the CH-47 helicopter and is used to expedite the loading and unloading of 463L Air Force pallets and other modularized cargo.

With the HICHS installed, a CH-47 can carry three (88 x 108-inch) 463L pallets or 12 (40 x 48-inch) standard warehouse pallets. The height of all loads is restricted to 54 inches. The HICHS can be installed in the aircraft by four men in 45 minutes and removed in 20 minutes. Figure 2-16 illustrates a CH-47 with a HICHS installed.




Figure 2-16. HICHS installed in a CH-47 helicopter

WWW.SURVIVALEBOOKS.COM

MILITARY AIRLIFT COMMAND AIRCRAFT

Personnel who prepare load plans must be familiar with the types of available aircraft and their characteristics. As mentioned before, the aircraft we are primarily concerned with are the C-130, C-141B, C-5, and KC-10. All four aircraft are designed primarily as transport aircraft. Their cargo compartments can be configured to accommodate general bulk or palletized cargo, vehicles, troops, paratroopers, and cargo rigged for airdrop. The wide range of cargo carried by these aircraft, along with the many combinations of loads, provides great flexibility in moving troops and equipment. All four aircraft have long-range mission capability, possess roller-conveyor systems for utilization of the 463L pallet system, and have hydraulically activated ramp systems for ease of loading and offloading.

C-130E/H Hercules

The C-130E/H series Lockheed aircraft is a high-winged, turbo-prop airplane designed for tactical/intratheater-type missions (see Figure 2-17). It is the primary aircraft used by MAC for tactical missions. See Table 2-5 for characteristics of C-130E/H aircraft.




Figure 2-17. C-130E/H aircraft

Table 2-5. Characteristics of C-130 aircraft

Dimensions	Cargo Compartment	Troop Door	Aircraft Ramp
Length	492 in	--	120 in
Height	108 in	72 in	--
Width	123 in	36 in	--

Palletized Cargo Restrictions		
Pallet Position	Maximum Weight	Maximum Height
1-4	10,354 lb	96 in
5	8,500 lb	96 in
6	4,664 lb	76 in

NOTE: C-130E/H aircraft can carry six 463L pallets.

Restraint Factors	
Forward	3.0 g's
Aft	1.5 g's
Vertical	2.0 g's
Lateral	1.5 g's

- Maximum passenger load: 90
- Usable loading space: 580 in
- Floor height above ground: 40 in
- Center of balance: Station 520 + 10 in
- Allowable cabin load: 25,000 lb

WWW.SURVIVALEBOOKS.COM

C-141 Starlifter

The C-141 series aircraft by Lockheed is a high-swept-wing, turbo-fan-jet airplane designed for strategic, intertheater-type missions (see Figure 2-18). The C-141 should be considered the primary aircraft for deployment to another theater of operations. See Table 2-6 for characteristics of C-141 aircraft.




Figure 2-18. C-141 aircraft

Table 2-6. Characteristics of C-141 aircraft

Dimensions	Cargo Compartment	Troop Door	Aircraft Ramp
Length	1,120 in	--	133 in
Height	109 in	72 in	--
Width	123 in	36 in	--

Palletized Cargo Restrictions		
Pallet Position	Maximum Weight	Maximum Height
1	10,354 lb	76 in
2-12	10,354 lb	96 in
13	7,500 lb	76 in

NOTE: C-141 aircraft can carry thirteen 463L pallets.

Restraint Factors	
Forward	3.0 g's
Aft	1.5 g's
Vertical	2.0 g's
Lateral	1.5 g's

- Maximum passenger load: 208
- Usable loading space: 1,220 in
- Floor height above ground: 50 in
- Center of balance: Station 960 + 20 in
- Allowable cabin load: 72,000 lb

WWW.SURVIVALEBOOKS.COM

C-5 Galaxy

The Lockheed-manufactured C-5 is a high-swept-wing, turbo-fan-jet aircraft used for strategic, intertheater missions (see Figure 2-19). It is primarily designed to transport cargo that is outsized or overweight for the C-130 or C-141 aircraft. Special features of the C-5 are its ability to load and unload from either end of the cargo compartment and its capability to "kneel" which lowers the aircraft to facilitate loading and unloading. The C-5 is also unique in that its floor does not have treadways. The "floor-bearing pressure" is the same over the entire floor. However, there are some weight restrictions that must be adhered to as shown in Table 2-7.




Figure 2-19. C-5 aircraft

Table 2-7. Characteristics of C-5 aircraft

Dimensions	Cargo Compartment	Troop Door	Aircraft Ramp
Length	1,465 in	--	116 in (fwd) 155 in (aft)
Height	108 in	72 in	
Width	123 in	36 in	--

Restraint Factors	
Forward	3. g's
Aft	1.5 g's
Vertical	2.3 g's
Lateral	1.5 g's

Palletized Cargo Restrictions		
Pallet Position	Maximum Weight	Maximum Height
1-2	7,500 lb	96 in
3-34	10,354 lb	96 in
35-36	7,500 lb	70 in

NOTE: C-5 aircraft can carry up to thirty-six 463L pallets.

- Maximum passenger load:
  - 73 normal contingency;
  - 267 cargo compartment
- Usable loading space: 1,650 in
- Floor height above ground: (variable):
  - Aft: 73 to 105 in
  - Forward: 36 to 70 in
- Center of balance: Station 1300 + 50 in
- Allowable cabin load:
  - Peacetime - 100,000 lb
  - Wartime - 205,000 lb

Weight Restrictions

- Maximum axle load: 36,000 lb
- Maximum tracked vehicle weight: 129,000 lb
- Floor limitations: per 40-in area between stations—
  - 517 and 724: 20,000 lb
  - 724 and 1884: 36,000 lb
  - 1884 and 1971: 20,000 lb

WWW.SURVIVALEBOOKS.COM

KC-10A

The KC-10A series aircraft is a swept-wing tri-jet designed to air-refuel military airplanes and airlift cargo and support personnel (see Figure 2-20). In addition to being equipped to air-refuel military airplanes requiring either a boom or hose drogue, the KC-10A may be refueled from another KC-10A or KC-135 tanker. The unobstructed cargo compartment will accept combinations of palletized cargo, vehicles, and logistics equipment and mixed cargo and support personnel. See Table 2-8 for characteristics of KC-10A aircraft.




Figure 2-20. KC-10A aircraft

Table 2-8. Characteristics of KC-10A aircraft

Dimensions	Cargo Compartment	Troop Door	Aircraft Ramp
Length	118 ft	--	--
Height	110 in	76 in	102 in
Width	144 in	42 in	140 in

- Maximum passenger load:
  w/o seat kit 20
  w/seat kit 75
- Usable loading space: 118 ft
- Floor height above ground: 15 ft 10 in
- Center of balance: Station 1325 + 50 in
- Allowable cabin load: Because of the many types of load configurations (troops, cargo, and fuel) possible, the ACL varies significantly. Contact your local ALCE to get the ACL for the load you wish to transport.

CIVIL RESERVE AIR FLEET AIRCRAFT

The Civil Reserve Air Fleet (CRAF) is composed of US civil air carriers who contractually commit themselves to provide operating and support personnel for the Department of Defense. The CRAF concept is designed to quickly mobilize the nation's resources to meet DOD requirements.

Airlift Services

CRAF airlift services are divided into four operational segments:

- Long-range international—strategic intertheater operations.
- Short-range international-intratheater operations.
- Domestic CONUS—DOD supply distribution.
- Alaskan—Aerospace Defense Command support.

Capability

The CRAF airlift capability can be activated in three stages:

Stage I. Stage I may be activated by the Commander in Chief, MAC, to perform airlift services when the MAC airlift force cannot meet simultaneously both deployment and other traffic requirements.

Stage II. Stage II. is an additional airlift expansion identified for an airlift emergency

WWW.SURVIVALEBOOKS.COM

which does not warrant national mobilization but may be activated by authority of the secretary of defense.

Stage III. Stage III makes available the total CRAF airlift capability when required for DOD operations during major military emergencies involving US forces. The secretary of defense issues the order to activate CRAF stage III only after a national emergency has been declared by the president or Congress.


Description

Table 2-9 gives dimensions and capabilities for Boeing B747 series aircraft, Table 2-10 gives the same data for the Douglas DC-10 and Lockheed L-1011 series aircraft, and Table 2-11 gives the same data for the Douglas DC-8 and Boeing B707 series aircraft. Figure 2-21 shows profiles of CRAF aircraft, while Figure 2-22 shows profiles of CRAF pallets.


Boeing B747 The Boeing B747 is a wide-body aircraft. The cargo-carrying capacity versions have an average planning cargo weight of about 180,000 pounds. The main deck can hold either 32 to 36 military or 28 commercial pallets. The passenger version can carry about 364 passengers (but only 266 on the B747SP).

Douglas DC-10. The Douglas DC-10 and Lockheed L-1011 are both wide-body aircraft. The cargo-carrying version of the DC-10 has an average cargo weight of about 120,000 pounds, and the main deck can hold either 30 military or 22 commercial pallets. The passenger version of the DC-10 can carry about 242 passengers. The L-1011 is currently available in a passenger version with a capacity of 238 to 270 seats.


Douglas DC-8 and Boeing B707. The Douglas DC-8 and Boeing B707 are narrow-body aircraft. The cargo-carrying version of the DC-8 has a planning cargo weight varying from 52,000 to 82,000 pounds; the main deck can accommodate 13 to 18 pallets, depending on the aircraft series. The cargo version of the B707 has a planning cargo weight of about 60,000 pounds, and the main deck can carry 13 military or commercial pallets. The passenger DC-8 carries 165 to 219 passengers and the B707, approximately 165 passengers. CRAF aircraft are not designed for nor intended to carry litter patients.




BOEING: B747




DOUGLAS: DC-10



LOCKHEED: L-1011



DOUGLAS: DC-8




BOEING: B707

Figure 2-21. CRAF aircraft profiles


WWW.SURVIVALEBOOKS.COM

B-747-100F/200C/200F (ALL MAIN DECK POSITIONS)




PALLETS CAN BE LOADED LENGTHWISE (104.0")
OR CROSSWISE (84.0")


DC-10 POSITIONS 1, 13, 14



DC-10 POSITIONS 2 THRU 12




DC-10 POSITION 15




(Loaded lengthwise 104.0")

NOTE: Pallet profiles are shown for left side of aircraft. Rightside pallets will be a mirror image.


DC-8 MAIN DECK POSITIONS:
DC-8-33F/50F/CF 1 THRU 11
DC-8-62CF 1 THRU 12
DC-8-61/63CF 1 THRU 16



DC-8 MAIN DECK POSITION:
DC-8-33F/50F/CF 12
DC-8-62CF 13
DC-8-61/63CF 17



DC-8 MAIN DECK POSITION:
DC-8-33F/50F/CF 13
DC-8-62CF 14
DC-8-61/63CF 18



B-707/F A POSITIONS 1 THRU 12




Figure 2-22. CRAF pallet profiles (measurement of pallet surface)

WWW.SURVIVALEBOOKS.COM




Figure 2-22. CRAF pallet profiles (measurement of pallet surface) (cont)

Table 2-9a. Dimensions of B747 series aircraft

Dimensions	Aircraft Designation				
	B747SP	B747-100/200B	B747-100F	B747-200C	B747-200F
Floor height (ACL)					
Main deck	188-196 in	193-201 in	193-201 in	186-204 in	186-204 in
Lower deck	108-122 in	109-121 in	109-121 in	109-121 in	109-121 in
Main deck cargo compartment					
Length	NA	NA	NA	NA	NA
Width	NA	NA	NA	NA	NA
Height	NA	NA	NA	NA	NA
Lower lobe (fwd)					
Length	315 in	315 in[1,5] 504 in[6]	504 in	504 in	504 in
Width	125 in[2]	125 in[2]	125 in[2]	125 in[2]	125 in[2]
Height	66 in[3]	66 in[3]	66 in[3]	66 in[3]	66 in[3]
Lower lobe (aft)					
Length	315 in	251 in[4,5] 436 in[6]	436 in	436 in	436 in
Width	125 in[2]	125 in[2]	125 in[2]	125 in[2]	125 in[2]
Height	66 in[3]	66 in[3]	66 in[3]	66[3]	66 in[3]
Door sizes					
Visor door	104 in w × 98 in h				
Main cargo door	122 in w × 120 in h				

[1]Pallets will not be planned for use in the lower lobe forward compartment of American/United Airlines B747-100 passenger aircraft.
[2]Floor width, 125 inches or 190 inches wall to wall; all cargo, however, must be on pallets or shoring.
[3]Measured from top of rollers to ceiling.
[4]Use 251 inches for American/United Airlines B747-100.
[5]With galley installed in lower lobe.
[6]Without galley installed in lower lobe.

WWW.SURVIVALEBOOKS.COM

Table 2-9b. Capabilities of B747 series aircraft

Capabilities	Aircraft Designation				
	B747SP	B747-100/200B	B747-100F	B747-200C	B747-200F
Max auth gross weight					
Takeoff	690,000 lb	733,000/775,000 lb	750,000 lb	775,000 lb	820,000 lb
Landing	450,000 lb	564,000/564,000 lb	585,000 lb	630,000 lb	630,000 lb
Operating	318,000 lb	322,800/369,820 lb	322,000 lb	344,040 lb	348,100 lb
Zero fuel	410,000 lb	508,900/526,500 lb	545,000 lb	590,000 lb	590,000 lb
Optimum load CG at fuselage station	NA	NA	1,280 ± 30 in	1,280 ± 30 in	2,280 ± 30 in
Restraining factors					
Forward	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Aft	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Vertical	2.0 g's	2.0 g's	2.0 g's	2.0 g's	2.0 g's
Lateral	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Passenger capacity	266[1]	364[1]	2	364[1]	2
Planning ACL	NA	NA	89.9 STONs	96.9 STONs[2]	99.1 STONs
463L pallet capacity	NA	NA	32[3]	32[3]	32[3]
Max pallet height	NA	NA	118 in	94 in[5]	118 in[4] 94 in[5]

[1]Maximum passenger capability will vary according to carrier configuration.
[2]Since this is a convertible aircraft, figures are based on cargo or passenger loads.
[3]Some aircraft may be configured to a 36-pallet configuration.
[4]Side door.
[5]Visor door.

WWW.SURVIVALEBOOKS.COM

Table 2-10a. Dimensions of DC-10 and L-1011 series aircraft

Dimensions	Aircraft Designation				
	DC-10-10 CF	DC-10-30 CF	DC-10-40	L-1011-100	L-1011-500
Floor height (ACL)					
Main deck	189 in	189 in	189 in	182-186 in	182-186 in
Lower deck	103-118 in	103-118 in	103-118 in	105-112 in	105-112 in
Main deck cargo compartment					
Length	1414 in[1]	1414 in[1]	NA	NA	NA
Width	218 in	218 in	NA	NA	NA
Height	84-95 in[2]	84-95 in[2]	NA	NA	NA
Lower lobe (fwd)					
Length	491 in[3]	216 in[4]	491 in[3]	500 in[5] 250 in[6]	370 in
Width	125 in[7]	125 in[7]	125 in[7]	125 in	
Height	66 in[8]	66 in[8]	66 in[8]	64 in	64 in
Lower lobe (aft)					
Length	241.5 in	241.5 in	241.5 in	250 in	190 in
Width	125 in[7]	125 in[7]	125 in[7]	125 in	125 in
Height	66 in[8]	66 in[8]	66 in[8]	64 in	64 in
Lower lobe (aft, bulk compartment)					
Length	179 in	179 in[9]	179 in[9]	170 in	170 in
Width	125 in[10]	125 in[10]	125 in[10]	125 in	125 in
Height	66 in[10]	66 in[10]	66 in[10]	64 in[10]	64 in[10]
Door sizes					
Main cargo door	140 in w × 102 in h				
Forward and center door				70 in w × 68 in h	
Aft door				44 in w × 48 in h	

[1]Length from FS 523 to 1937. A barrier net is located at FS 495. Usable cargo space is based on pallet surface.
[2]Max height of 84 inches at pallet positions 1 and 15; 88 inches at positions 2 through 14; 95 inches at the forward half of the cargo door.
[3]Length from FS 604.5 to FS 1095.5.
[4]Length from FS 879.5 to FS 1095.5.
[5]Without galley installed in lower lobe.
[6]With galley installed in lower lobe.
[7]Wall-to-wall distance is 164 inches.
[8]Measured from top of rollers to ceiling.
[9]Aircraft with an extended aft cargo compartment will have a 126-inch aft bulk cargo area and a cargo door 30 inches wide by 36 inches high.
[10]Dimensions decrease toward aft of cargo compartment.

WWW.SURVIVALEBOOKS.COM

Table 2-10b. Capabilities of DC-10 and L-1011 series aircraft

Capabilities	Aircraft Designation				
	DC-10-10CF	DC-10-30CF	DC-10-40	L-1011-100	L-1011-500
Max auth gross weight					
Takeoff	440,000 lb	555,000 lb	530,000 lb	466,000 lb	496,000 lb
Landing	363,500 lb	411,000 lb	403,000 lb	368,000 lb	368,000 lb
Operating	209,346 lb	234,591 lb	266,689 lb	253,720 lb	241,946 lb
Zero fuel	335,000 lb	391,000 lb	391,000 lb	320,000 lb	338,000 lb
Optimum load CG at fuselage station	1,323	1,323	1,323	NA	NA
Restraining factors					
Forward	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Aft	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Vertical	2.0 g's	2.0 g's	2.0 g's	2.0 g's	2.0 g's
Lateral	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Passenger capacity	242[1]	242[1]	242	273	238
Planning ACL	55.2 STONs[1]	69 STONs[1]	NA	NA	NA
463L pallet capacity	30	30	NA	NA	NA
Max pallet height	78-82 in	78-82 in	NA	NA	NA

[1]Figures on CFs are for eight ACLs or passengers, depending on the mode of aircraft use.

WWW.SURVIVALEBOOKS.COM

Table 2-11a. Dimensions of DC-8 and B707 series aircraft

Dimensions	Aircraft Designation					
	DC-8-33F	DC-8-50C F	DC-8-61C F	DC-8-62F	DC-8-63F/ CF	B707-300C/F
Floor height (ACL)						
Main deck	126-135 in	126-135 in	128-132 in	126-130 in	126-131 in	119-126 in
Lower deck	68-92 in	68-97 in	75-98 in	73-100 in	76-98 in	54-63 in
Main deck cargo compartment						
Length	1,176 in[1]	1,176 in[1]	1,622 in[2]	1,265 in[3]	1,622 in[2]	1,176 in[4]
Width	127.2 in	127.2 in	127.2 in	127.2 in	127.2 in	126 in
Height	86 in[5]	86 in[5]	86 in[5]	86 in[5]	86 in[5]	87 in[6]
Lower lobe (fwd)						
Length	330 in[7]	330 in[7]	437 in	370 in	437 in	298 in
Width	100 in	100 in	100 in	100 in	100 in	100 in
Height	51 in[8]	51 in[8]	51 in[8]	51 in[8]	51 in[8]	54 in[9]
Lower lobe (aft)						
Length	357 in[10]	357 in[10]	407 in	400 in	407 in	378 in
Width	100 in	100 in	100 in	400 in	100 in	100 in
Height	51 in[8]	51 in[8]	51 in[8]	51 in[8]	51 in[8]	54 in[9]
Door sizes						
Main cargo door	140 in w × 85 in h					134 in w × 91 in h

[1]Length from FS 302 to FS 1478.
[2]Length from FS 62 to FS 1684.
[3]Length from FS 262 to FS 1527.
[4]Length from FS 242 to FS 1418.
[5]Measured from floor to ceiling.
[6]Measured on centerline to ceiling.
[7]Measurement for entire fwd cargo compartment.
[8]Lowest point in cargo compartment to ceiling.
[9]Height of aft cargo compartment 54.5 in for the first 80 in, then tapering down.
[10]Measurement for entire aft cargo compartment.

WWW.SURVIVALEBOOKS.COM

Table 2-11b. Capabilities of DC-8 and B707 series aircraft

Capabilities	Aircraft Designation					
	DC-8-33F	DC-8-50CF	DC-8-61CF	DC-8-62F	DC-8-63F/CF	B707-300C/F
Max auth gross weight						
Takeoff	315,000 lb	315,000 lb	328,000 lb	335,000 lb	355,000 lb	331,600/ 333,100 lb
Landing	207,000 lb	240,000 lb	258,000 lb	250,000 lb	275,000 lb	247,000/ 247,000 lb
Operating	128,000 lb	131,600 lb	145,506 lb	146,000 lb	141,330 lb	146,400/ 132,174 lb
Zero fuel	192,140 lb	224,000 lb	234,000 lb	230,000 lb	261,000 lb	230,000/ 230,000 lb
Optimum load CG at fuselage station	860.0	860.0	828.0-889.0	836.1-883.8	833.9-883.8	838.3-843.7
Restraining factors						
Forward	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Aft	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Vertical	2.0 g's	2.0 g's	2.0 g's	2.0 g's	2.0 g's	2.0 g's
Lateral	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's	1.5 g's
Passenger capacity	2	165[1]	219[1]	170[1]	219[1]	165
Planning ACL	26.0 STONs	29.9 STONs[1]	47.3 STONs[1]	32.1 STONs[1]	41.4 STONs[1]	29.9 STONs[1]
463L pallet capacity	13	13	18	14	18	13
Max pallet height	62-80 in[2]	62-80 in[2]	62-80 in[2]	62-80 in[2]	62-80 in[2]	74-80 in[2]

[1]Figures on CF are for eight ACLs or passengers, depending on the mode of aircraft use.
[2]For actual max height, see CRAF pallet profiles (Figure 2-22); a general planning height of 76 inches can be used.

CHARACTERISTICS OF STANDARD ARMY AIRCRAFT

Tables 2-12 through 2-16 give data on standard Army aircraft. Table 2-12 gives capabilities and dimensions for fixed-wing aircraft. Table 2-13 gives the same data for rotary-wing aircraft. Tables 2-14 through 2-16 list speed and range factors, preparation times, and sortie capacities. Figure 2-23 shows profiles of Army aircraft.





Figure 2-23. Profiles of Army aircraft


WWW.SURVIVALEBOOKS.COM




OH-6




OH-58




UH-1




CH-54




CH-47




UH-60



AH-15



AH-1G



AH-64

Figure 2-23. Profiles of Army aircraft (cont)

WWW.SURVIVALEBOOKS.COM

Table 2-12a. Characteristics of Army fixed-wing aircraft (U-1A, U-10A, and T-41B are not included due to their low density)

Dimensions	Unit	C-12A	C-12C	C-12D	OV-1B	OV-1C	OV-1D	RC-12D	RV-1C	RV-1D	T-42A	U-8F	U-21A	U-21D	U-21F	U-21G	U-21H	RU-21A	RU-21B	RU-21C	RU-21D	RU-21H	RU-21J
Fuselage length [1]	ft-in	43'10"	43'10"	43'10"	41'9"	41'1"	41'9"	43'10"	41'9"	41'9"	27'3"	33'4"	35'10"	35'10"	39'11"	35'10"	35'10"	35'10"	35'10"	35'10"	35'10"	35'10"	35'10"
Blades																							
Length unfolded	ft-in					NA									NA							NA	
Length folded	ft-in					NA									NA							NA	
Width folded	ft-in					NA									NA							NA	
Tread width	ft-in	17'2"	17'2"	17'2"	9'2"	9'2"	9'2"	17'2"	9'2"	9'2"	9'7"	12'9"	12'9"	12'9"	13'0"	12'9"	12'9"	12'9"	12'9"	12'9"	12'9"	12'9"	12'9"
Extreme height	ft-in	15'5"	15'5"	14'9"	13'0"	13'0"	13'0"	15'5"	13'0"	13'0"	9'7"	14'2"	14'2"	14'2"	15'4"	14'2"	14'2"	14'2"	14'2"	14'2"	14'2"	14'2"	14'2"
Rotor diameter																							
Main or fwd	ft-in					NA									NA							NA	
Tail or rear	ft-in					NA									NA							NA	
Wing span	ft-in	54'6"	54'6"	55'6.5"	48'0"	42'0"	48'0"	54'6"	42'0"	45'11"	37'10"	45'11	45'11"	45'11"	45'11"	45'11"	50'11"	50'11"	45'11"	45'11"	45'11"	50'11"	55'6"
Cargo door																							
Width × height	in	27.7×51.5	27.7×51.5	52.0×52.0		NA		27.7×51.6	NA	NA	13.5×22.3	50.5×26.5	50.5×53.0	50.5×53.0	17.0×51.7	50.5×53.0	50.5×53.0	50.5×53.0	50.5×53.0	33.0×51.5	50.5×53.0	50.5×53.0	50.5×53.0
Location vs fuselage	(left/right front/rear)	left rear	left rear	left rear		NA		left rear		NA		left	left	left	left	left	left	left	left	left	left	left	left
Cargo floor																							
Hgt from ground	in	47"	47"	42"		NA		47"		NA		48"	48"	48"	45"	48"	48"	48"	48"	48"	48"	48"	42"
Usable length	in	128"	128"	128"		NA		128"		NA		110.5"	110.5"	110.5"	11"	110.5"	110.5"	110.5"	110.5"	110.5"	110.5"	110.5"	128"
Usable width	in	54"	43"	54"		NA		54"		NA		55"	55"	55"	54"	55"	55"	55"	55"	55"	55"	55"	54"
Unobstructed hgt	in	57"	57"	57"		NA		57"		NA		55"	55"	55"	57"	55"	55"	55"	55"	55"	55"	55"	57"
Max ego space	cu ft	306.5	306.5	306.5		NA		306.5		NA		158	230	230	306	230	158	158	158	158	158	158	306.5

[1] Dimension from nose to end of tail

WWW.SURVIVALEBOOKS.COM

Table 2-12b. Characteristics of Army fixed-wing aircraft (U-1A, U-10A, and T-41B are not included due to their low density)

Capabilities	Unit	C-12A	C-12C	C-12D	OV-1B	OV-1C	OV-1D	RV-12D	RV-1C	RV-1D	T-42A	U-8F	U-21A	U-21D	U-21F	U-21G	U-21H	RU-21A	RU-21B	RU-21C	RU-21D	RU-21H	RU-21J
Normal crew	per acft	2	2	2	2 (pilot & radar)	2 (pilot & IR op)	2 (pilot & op)	2	2 (pilot & IR op)	2 (pilot & op)	1 (2 for IFR)	1 (2 for IFR)	2	2	2	2	2	4 (2 pilots & 2 op)	4 (2 pilots & 2 op)	4 (2 pilots & 2 op)	4 (2 pilots & 2 op)	4 (2 pilots & 2 op)	4 (2 pilots & 2 op)
Passenger cap																							
Troop seats	ea	8	8	8	1	1		8	1	1	3	5	10	10	10	10	10			NA			
Normal cap	ea	8	8	8	1	1	1	8	1	1	3	5	6	6	7	6	6			NA			
Total w/crew	ea	10	10	10	2	2	2	10	2	2	4	6	12	12	12	12	12	4	5	4	4	4	4
Litters/ambt	ea					NA							3/3	3/3	3/3	3/3	3/3			NA			
Operational cap[1]																							
Max auth gross wt	lb	12,500	12,500	12,500	15,795	14,823	18,109	14,200	14,823	18,109	5,100	7,700	9,500	9,500	11,568	9,650	9,650	10,200	10,900	10,900	9,650	10,200	12,500
Basic wt	lb	7,869	8,084	8,084	10,983	10,011	12,054	8,143	10,011	12,054	3,480	5,490	5,383	5,383	7,012	5,434	5,434	5,450	5,945	5,945	7,170	6,814	8,084
Useful load	lb	2,131	4,416	4,416	4,812	4,812	6,055	2,078	4,812	6,055	1,620	2,210	4,117	4,117	2,756	4,216	4,216	4,750	4,945	4,945	2,480	3,386	4,416
Normal payload	lb	2,000	2,000	2,000		NA		2,000	NA	NA	1,115	590	2,000	2,000	1,800	2,000	2,000	1,845	1,845	1,845	0	962	2,000
Fuel cap[2]																							
Internal	lb/gal	2,470/386	2,470/386	2,470/388	1,930/297	1,930/297	1,790/276	2,470/386	1,930/297	1,790/276	852/142	1,380/230	2,457/378	2,457/378	2,405/370	2,457/378	2,457/378	2,405/370	2,574/396	2,574/396	2,405/370	2,405/370	2,470/386
External	lb/gal		NA		1,950/300	1,950/300	1,950/300	NA	1,950/300	1,950/300					NA								
Fuel usage[2]	lb/gal per hr	350/538	456/70	456/70	826/126.9	826/126.9	900/130	456/70	826/126.9	900/130	154.8/25.8	204.5/35	450/72	450/72	450/72	450/72	450/72	580/89.2	580/89.2	580/89.2	580/89.2	580/89.2	456/70
Normal cruise speed	knots	240	260	260	225	225	220	260	225	220	177	160	210	210	220	210	210	205	205	205	205	205	260
Endurance at cruise	hr + min	5 + 30	5 + 15	5 + 15	1 + 55[4]	1 + 55[4]	1 + 40[4]	5 + 15	1 + 55[4]	1 + 40[4]	5 + 00	5 + 30	5 + 00	5 + 00	4 + 45	5 + 00	5 + 00	3 + 45	5 + 00	4 + 15	3 + 45	3 + 45	5 + 15
(+ 30 min reserve)			NA		3 + 55[5]	3 + 55[5]	3 + 50[5]	NA	3 + 55[5]	3 + 30[5]					NA								
Fuel grade	octane	JP4/5	JP4/5	FP4/5	JP4	JP4	JP4	JP4/5	JP4	JP4	115/145	115/145	JP4	JP4	JP4	JP4	JP4	JP4/5	JP4/5	FP4/5	JP4/5	JP4/5	JP4/5
External cargo																							
Max auth load[3]			NA		2,000 ea wing	2,000 ea wing	2,000 ea wing	NA	2,000 ea wing	2,000 ea wing					NA								
Rescue hoist	lb					NA									NA								
Cgo winch cap	lb					NA									NA								
Weapons type						NA									NA								

[1] All data was computed at standard conditions at sea level but is subject to change with developmental testing. Detailed weight computations and characteristics were taken from current 55-series TMs.

[2] Aviation gas was figured on 6 lb/gal JP4 computed on 6.5 lb/gal.

[3] The maximum load the aircraft is able to lift.

[4] Without external fuel.

[5] With external fuel.

WWW.SURVIVALEBOOKS.COM

Table 2-13a. Characteristics of Army rotary-wing aircraft

Dimensions	Unit	OH-6A	OH-58A	OH-58C	CH-47B	CH-47C	CH-47D	CH-54A	CH-54B	UH-1B	UH-1C/M	UH-1D/H/V	UH-60	TH/AH-1G	AH-1S	AH-64[2]	TH-55A
Fuselage length[1]	ft-in	23'0"	32'3.5"	32'8.8"	51'0"	51'0"	51'0"	70'0"	70'0"	38'5"	42'7"	40'7"	50'7.5"	44'5.2"	44'7"	49'3"	21'11"
Blades																	
Length unfolded	ft-in	30'4"	40'11.8"	40'11.8"	99'0"	99'0"	99'0"	88'5"	88'5"	52'10.8"	52'10"	57'1"	64'10"	52'11.7"	53'1"	57'1"	28'10"
Length folded	ft-in	23'0"	NA	NA	51'0"	51'0"	51'0"	NA			NA		40'4"			NA	
Width folded	ft-in	5'6"	NA	NA	12'5"	12'5"	12'5"	NA			NA	8'7"	9'8.1"	10'4"	10'9"	16'3"	NA
Tread width	ft-in	6'9"	6'3.5"	6'5.4"	11'11"	11'11"	11'11"	19'9"	19'9"	8'4"	8'7"	8'7"	8'10.2"	7'0"	7'0"	6'6"	6'3"
Extreme height	ft-in	9'6.5"	12'0"	18'6"	18'8"	18'8"	24'5"	24'5"	24'5"	12'8"	12'8"	14'6"	17'6"	11'7"	13'9"	12'6"	8'3"
Rotor diameter																	
Main or fwd	ft-in	26'4"	35'4"	35'4"	60'0"	60'0"	60'0"	72'0"	72'0"	44'0"	44'0"	48'0"	44'0	44'0"	44'0"	48'0"	25'3"
Tail or rear	ft-in	4'3"	5'2"	5'2"	60'0"	60'0"	60'0"	16'0"	16'0"	8'6"	8'6"	8'6"	11'0"	8'6"	8'6"	9'3"	3'4"
Wing span	ft-in			NA			NA				NA			10'4"	10'4"	16'3"	NA
Cargo door																	
Width × height	in	41×34.5	40×35	40×35	90×78	90×78	90×78	104.5" (pod)	104.5" (pod)	48×48	48×48	74×48	68×54			NA	
Location vs fuselage	(left/right front/rear)	left and right	left and right	left and right	rear	rear	rear	rear	rear	left and right	left and right	left and right	left and right			NA	
Cargo floor																	
Hgt from ground	in	14"	14"	24"	19"			NA		14.5"	22.5"	22.5"	31.2"	31.2"	31.2"	27" (pod)	27" (pod)
Usable length	in	60"	60"	92"	110"			NA		69"	39"	39"	360"	362"	362"	329"	329"
Usable width	in	80.5"	80.5"	96"	72"			NA		38"	50"	50"	90"	78"	78"	104.5"	104.5"
Unobstructed hgt	in	54"	54"	49"	54"			NA		38"	50"	50"	78"	78"	78"	78"	78"
Max cgo space	cu ft	140	140	220	246.8			NA		40	20	20	1,474	1,474	1,474	1,552	1,522

[1] Dimension from nose to end of tail.

[2] Height is restricted to 54 inches with HIDHS installed.

WWW.SURVIVALEBOOKS.COM

Table 2-13b. Characteristics of Army rotary-wing aircraft

Capabilities	Unit	OH-6A	OH-58A	OH-58C	CH-47B	CH-47C	CH-47D	CH-54A	CH-54B	UH-1B	UH-1C/M	UH-1D/H/V	UH-60	TH/AH-1G	AH-1S	AH-64[2]	TH-55A
Normal crew	per acft	1 + (obs)	1 + (obs)	1 + (obs)	4	4	4	4	4	2	2	2	3	2	2	2	1
Passenger cap																	
Troop seats	ea	3	4	4	33	33	33	1 (w/pod 45)	1 (w/pod 45)	7	7	11	14	0	0	0	1
Normal cap	ea	3	4	4	33	33	33	1	1	7	7	7	14	0	0	0	1
Total w/crew	ea	4	4	4	37	37	37	5	5	9	9	13	17	0	0	0	2
Litters/ambt	ea	NA	2/4	2	24	24	24	0 (w/pod 24)	0 (w/pod 24)	3	3	6	4/6	0	0	0	NA
Operational cap[1]																	
Max auth gross wt	lb	2,400	3,000	3,200	40,000	46,000	50,000	42,000	47,000	8,500	9,500	9,500	20,250	9,500	10,000	17,400	1,600
Basic wt	lb	1,163	1,586	1,898	19,591	20,481	22,499	20,800	21,200	4,523	4,827	5,132	10,500	5,560	6,598	10,505	1,010
Useful load	lb	1,237	1,417	1,302	20,445	23,380	27,501	21,200	25,800	3,977	4,673	4,368	6,195	3,940	3,402	6,895	590
Normal payload	lb	650[5]	760[5]	837[5]	15,000	18,200	20,206	11,650[5]	16,250[5]	2,490	2,685	2,900	3,360[7]	1,785[8]	1,293[8]	4,090[8]	590[5]
Fuel cap[2]	lb/gal	400/61.5	475/73	465/71.5	4,036/621	7,351/1,131	6,695/1,030	8,794/1,353	8,794/1,353	1,072/165	1,573/242	1,358/209	2,360/362	1,755/270	1,703/262	2,405/370	150/25
Fuel usage[2]	lb/gal	143/22	189/29	175/27	2,780/427	3,038/467	2,600/400	3,614/556	4,230/651	488/75	500/77[6] 550/84[6]	550/84	960/148	546/83.6	640/98	810/124	60/10
Normal cruise speed	knots	121	120	120	150	155	145	95	110	75-95	92-140	90-120	145	0-190[9]	0-190[9]	0-161[9]	65
Endurance at cruise (+ 30 min reserve)	hrs + min	3 + 15	3 + 30	3 + 00	1 + 00	2 + 00	2 + 30	2 + 00	1 + 30	3 + 45	3 + 00	2 + 15	2 + 15	2 + 00[10]	2 + 30	1 + 45	2 + 00
Fuel grade	octane	JP4	JP4	JP4	JP4	JP4	JP4	JP4/5	JP4/5	JP4	JP4/5	JP4/5	JP4/5/8	JP4	JP4	JP4/5/8	115/145
External cargo																	
Max auth load[3]	lb	NA			20,000	20,000	28,000	20,000	25,000	3,000	3,787	4,000	8,000	NA	1,380[13]	6,200[13]	NA
Rescue hoist cap	lb	NA			600	600	600	NA			300[7, 15]	300[7, 15]	600	NA		NA	
Cgo winch cap	lb	NA			3,000	3,000	3,000	15,000	25,000					NA			
Weapons type[4]		XM27E1	XM27E1	NA	M24	M24	M24	NA	NA	XM3 M5 M6 XM16 M22 XM156	XM3 M5 M6 XM16 M22 XM156	M23 M56 M59	M23	M18 M28 M35 M157[11] M159[12] X200[12]	M65 M97 M158 M200[12] M261	HELLFIRE M200[12] M260 M230	NA

[1] All data was computed at standard conditions at sea level, but is subject to change with developmental testing. Detailed weight computations and characteristics were taken from current 55-series TMs.

[2] Aviation gas was figured on 6 lb/gal JP4 computed on 6.5 lb/gal.

[3] The maximum load the aircraft is able to lift.

[4] Type of weapons the aircraft can carry; specific armament is based on unit assignment.

[5] Does not meet 200 NM range requirement of normal mission definition.

[6] Fuel consumption at 92 knots, 77 gallons per hour; at 140 knots, 84 gallons per hour.

[7] Normal mission, internal load--probability exists to cube-out before weigh-out. Maximum load on the floor is 300 lb/sq ft.

[8] Gross weight minus basic weight minus 400 lb for crew and total fuel weight.

[9] Due to armament configurations and flight profiles.

[10] Varies with load; figure given is for normal mission profile.

[11] Has 7-round, 2.75-inch rocket pod.

[12] Has 19-round, 2.75-inch rocket pod.

[13] Has external wing stores.

[14] Subject to final development configuration.

[15] UH-1 is restricted to a hoist capacity of 300 lb because of CG conditions.

WWW.SURVIVALEBOOKS.COM

Table 2-14. Aircraft speed and range factors[1]

Aircraft Type	Average Cruise Speed (kn)[2]	Ferry Range (NMs)
AH-1	141	381
AH-1S	130	338
CH-47B	114	1,090
CH-47C	111	1,226
CH-47D	136	1,070
CH-54B	100	226
OH-6A	102	330
OH-58	102	260
UH-1C/M	92	300
UH-1H/V	111	276
EH-1H/X	111	276
UH-60A	143	960
C-12A	222	1,177
U-8F	127	1,220
U-21A	180	1,249
OV-1C	200	1,081[3]

[1]Source is FM 101-20; factors are for ferry mission configuration.
[2]True airspeed under no-wind conditions.
[3]With two 150-gallon external fuel tanks.

Table 2-15. Aircraft preparation times and sortie capacities for airlift[1]

Type Aircraft Loaded	AF Aircraft Required	Disassembly Time Per Aircraft		Reassembly Time Per Aircraft		Airlifted Aircraft Per Sortie
		Man-Hours	Elapsed Hours	Man-Hours	Elapsed Hours	
AH-1G	C-5	8	2	12	3	12
AH-1S[2]	C-5	8	2	12	2	6
CH-47	C-5	174	32	225	36	3
CH-54	C-5	180	16	225	36	3
OH-6A	C-5	6	3	6	3	26
	C-141A	6	3	6	3	6
	C-130	6	3	6	3	3
OH-58	C-5	1.5	0.5	2	1	13
	C-141A	7.5	1.5	10	3	4
UH-1C/D/H/M/V	C-5	12	3	18	5	8
EH-1H/X	C-5	12	3	18	5	8
UH-60A[3]	C-5	9	1.5	9	1.5	6
	C-141A	9	1.5	9	1.5	2
UX-8/RU-8	C-5	16	4	32	8	4
U-21	C-5	16	4	32	8	4
OV-1B/C/D	C-5	305	38	750	94	3

[1]Data taken from FM 101-20 for minimum disassembly required for air shipment.
[2]AH-1S Cobras are usually shipped with stub wings on, due to excessive reassembly time and boresighting of the TOW system.
[3]UH-60A data taken from TM 55-1520-237-23-4.

WWW.SURVIVALEBOOKS.COM

Table 2-16. Aircraft preparation times and barge capacities for sealift[1]

Aircraft Type	Man-Hours	Crew Size	Elapsed Hours	Airlifted Aircraft[2] SEABEE Barge	Airlifted Aircraft[2] LASH Lighter
AH-1G[3]	6.0	3	2.0	14[4]	8
AH-1S	6.0	3	2.0	6	5
CH-47[3]	18.0	6	3.0	Note[4]	-
OH-6A[5]	6.0	3	2.0	27	15
OH-58[3]	4.0	3	1.5	14	8
UH-1	5.0	3	2.0	94	6
UH-60A[6]	9.0	6	1.5	6	4
U-21A[7]	16.0	4	4.0	4	

[1]Based upon minimum disassembly. Preparation times include disassembly, preservation, and crating, as required. Times are rounded off to the next higher 0.5 hours (MTMC Report 74-19).
[2]TM 55-1520-400-14.
[3]MTMC Report 74-19.
[4]SEABEE has capability of loading the following numbers of aircraft on the lower deck if 12 barges are displaced: 48 CH-47s, 3 AH-1Gs, 19 UH-1Hs.
[5]Estimated by MTMC Transportation Engineering Agency (MTMCTEA) from TM 55-1520-214-5 and FM 101-20.
[6]Estimate based on information in TM 55-1520-237-23-2 and TM 55-1520-237-23-4.
[7]Estimated by MTMCTEA from TM 55-1500-200-5 and FM 101-20.

WWW.SURVIVALEBOOKS.COM

Section IV. RESTRAINT CRITERIA

DETERMINING THE CENTER OF GRAVITY

To determine the center of gravity (CG) location of a loaded aircraft, you must first know the weight of the aircraft ready for loading, then calculate the weight times the arm to determine the moment.

Arm = the horizontal distance in inches from the reference datum line to the center of gravity of an object.

Moment = the product of the weight of an item multiplied by its arm. Moment may be expressed in pound-inches; for example, 2 pounds (weight) X 10 inches (arm) = 20 pound-inches (moment).

The procedures for computing the center of gravity of a loaded aircraft areas follows:

- Calculate for moment. Weight times arm = moment.
- List aircraft ready-for-loading weight times the ready-for-loading CG = moment.
- List weight times the arm of each cargo item = moment.
- Add all the weights and enter the total.
- Add all the moments and enter the total.
- Divide the total moments by the total weight; round off any decimals.

This number is the station number at which the aircraft is balanced. If the number does not fall within the safe flight limits, the load or a part of it must be relocated and aircraft balance recomputed.

Sample problem (C-141 aircraft)

The C-141 aircraft is loaded with three M35, 2 1/2-ton trucks, each weighing 13,700 pounds, and six passengers (1,800 pounds). All trucks are positioned facing the rear of the aircraft with the center of gravity of truck 1 at station 630; the CG of truck 2 at station 920; the CG of truck 3 at station 1200; and the CG of the six passengers at station 930. The weight of the aircraft ready for loading is 271,000 pounds, with its CG at station 915.

- Weight X arm = moment
- Weight of aircraft ready for loading X CG of aircraft ready for loading
- Weight of one truck X station 630
- Weight of one truck X station 920
- Weight of one truck X station 1200
- Weight of passengers X station 930

271,000	×	915	=	247,965,000
13,700	×	630	=	8,631,000
13,700	×	920	=	12,604,000
13,700	×	1200	=	16,440,000
1,800	×	930	=	1,674,000
313,900 (total weight)				287,314,000 (total moment)

$$\frac{\text{Total moment}}{\text{Total weight}} = \frac{287,314,000}{313,900} = 915.3 \text{ or } 915$$

Station 915 is the CG of the loaded aircraft. The CG limits safe flight for the C-141 are 906.7 to 948. The aircraft balanced at station 915 is safe for flight.

SECURING CARGO

Tie-down devices secure cargo against forward, rearward, lateral, and vertical movement during takeoff, flight, and landing. To determine the number of devices needed to safely secure any given item of cargo, it is necessary to know the—

- Weight of the cargo.
- Restraint criteria for the aircraft.
- Strength of the tie-down devices and fittings.
- Angles of tie to be used.

Restraint Factors

These vary for different aircraft and are influenced by acceleration during takeoff, stability during flight, deceleration during landing, and type of landing field (improved or unimproved) for which the aircraft is designed. Restraint criteria for each aircraft are computed to counter the maximum amount of force

WWW.SURVIVALEBOOKS.COM

or thrust that cargo can be expected to exert against tie-downs under operating conditions.

Tie-Downs

The effective holding strength of a device (or fitting) is determined by the rated strength of the item and the manner in which it is employed. All tie-downs must be anchored to a tie-down fitting. The strongest tie-down is no stronger than the fitting to which it is attached. If a tie-down is stressed to its breaking point, the fitting is stressed an equal amount up to the full rated strength of the tie-down. Figure 2-24 shows a typical tie-down correct pull-off.




Figure 2-24. Correct pull-off

Number required There is one basic formula for figuring the restraint for an item of cargo:

WT = Weight of cargo
R(g's) = Restraint required (g's)
RSD = Rated strength of device
% of = Percent of angle of tie-down
FTBR = Force to be restrained
EHSD = Effective holding strength of device

$$\frac{WT \times R\,(g's)}{RSD \times \%\ of} = \frac{FTBR}{EHSD} = \text{Total number of devices required}$$

Example:

WT = 1,000 pounds
R (g's) = 4
RSD = 5,000 pounds
% of = 74.9
FTBR = 4,000 pounds
EHSD = 3,745

$$\frac{1{,}000 \times 4}{5{,}000 \times 74.9} = \frac{4{,}000}{3{,}745} = 2 \text{ devices}$$

The weight of the cargo times the restraint forces of g's equals the force to be restrained. The rated strength of the tie-down device times the percent of angle of tie equals the effective holding strength of the tie-down. When the force to be restrained is divided by the effective holding strength of the tie-down, the total number of tie-downs needed is obtained. Tie-down devices should be used in pairs, so if the total number of tie-downs is an uneven number of a decimal, it should be rounded off to the next higher even number.

If the weight of the cargo is not marked on a particular item of cargo, refer to TB 55-46-1 for its weight and dimensions. The g forces for each direction are found in the applicable aircraft -10 manual. The rated strength of each device is given in Chapter 3 of this manual.

Angle. The percent of angle of tie-down is in relation to where the load is tied in the aircraft. See Figures 2-25 and 2-26 for examples of where to figure the angles. For a 30/30 angle of tie, measure from B to C (Figure 2-25) and go one and two-thirds of CB to A; then split the corner angle of DE. For a 45-degree angle, measure one length from B to C, one length to A, then right or left one length.




Figure 2-25. Longitudinal angle of tie-down

The recommended angle of tie is the 30/30 angle, as this is the best compromise of tie-down device-holding strength and angle. This tie-down is effective up to 75 percent of its rated strength forward (or aft) to 50 percent vertically and to about 43 percent sideward. Tie-downs secured at a 45-degree angle to the cargo floor and in line with the expected thrust will hold approximately 70 percent of their rated strength against forward, aft, or vertical

WWW.SURVIVALEBOOKS.COM

movements. Tie-downs secured in this manner will hold against movement in two directions Tie-downs secured at a 45-degree angle to the cargo floor and a 45-degree angle to the longitudinal axis of the aircraft prevent cargo movement in three directions. forward (or aft), vertical, and lateral.




Figure 2-26. Vertical angle of tie-down

These tie-downs will hold about 50 percent of their rated strength against forward (or aft) and lateral movements and 70 percent of their rated strength against vertical movements. To calculate the percentage of angle of tie-down, see Figure 2.27.

Angles across the top are those formed between the tie-down device and the cabin floor. Angles down the side are those formed between the tie-down device and the longitudinal axis of the aircraft. Vertical restraint is related only to the angle between the tie-dowm device and the cabin floor. The lateral angle has no bearing on it. The unshaded area indicates the "best compromise" position.

		5°	10°	15°	20°	25°	30°	35°	40°	45°	50°	55°	60°	65°	70°	75°	80°
	VERTICAL	8.7	17.4	25.9	34.2	42.3	50.0	57.4	64.3	70.7	76.6	81.9	86.6	90.6	93.9	96.6	98.5
5°	LONG	99.2	98.1	96.2	93.6	90.2	86.3	81.6	76.3	70.4	64.0	57.2	49.8	42.1	34.1	25.8	17.3
	LAT	8.7	8.6	8.4	8.2	7.9	7.5	7.1	6.7	6.2	5.6	4.9	4.4	3.7	2.9	2.3	1.5
10°	LONG	98.1	97.0	95.2	92.6	89.2	85.3	80.7	75.5	69.9	63.3	56.5	49.3	41.7	33.7	25.5	17.1
	LAT	17.3	17.1	16.8	16.6	15.8	15.1	14.3	13.3	12.3	11.2	9.9	8.7	7.4	5.9	4.5	3.0
15°	LONG	96.2	95.2	93.3	90.8	87.5	83.7	79.1	73.9	68.3	62.1	55.4	48.3	40.9	33.0	25.0	16.8
	LAT	25.8	25.5	25.0	24.3	23.5	22.4	21.2	19.8	18.3	16.7	14.9	12.9	10.9	8.9	6.7	4.5
20°	LONG	93.6	92.6	90.8	88.4	85.2	81.4	76.9	72.0	66.5	60.4	53.9	47.0	39.8	32.1	24.3	16.6
	LAT	34.1	33.7	33.0	32.1	30.9	29.6	28.0	26.2	24.2	21.9	19.6	17.1	14.5	11.7	8.9	5.9
25°	LONG	90.2	89.2	87.5	85.2	82.1	78.5	74.2	69.4	64.1	58.3	52.0	45.3	38.3	30.9	23.5	15.8
	LAT	42.1	41.7	40.9	39.8	38.3	36.6	34.6	32.4	29.9	27.2	24.3	21.2	17.9	14.5	10.9	7.4
30°	LONG	86.3	85.3	83.7	81.4	78.5	74.9	70.9	66.3	61.2	55.7	49.7	43.3	36.6	29.6	22.4	15.1
	LAT	49.8	49.3	48.3	47.0	45.3	43.3	40.9	38.3	35.4	32.2	28.7	25.0	21.2	17.1	12.9	8.7
35°	LONG	81.6	80.7	79.1	76.9	74.2	70.9	67.1	62.7	57.9	52.7	47.0	40.9	34.6	28.0	21.2	14.3
	LAT	57.2	56.5	55.4	53.9	52.0	49.7	47.0	43.9	40.6	36.9	32.9	28.7	24.3	19.6	14.9	9.9
40°	LONG	76.3	75.5	73.9	72.0	69.4	66.3	62.7	58.7	54.2	49.3	43.9	38.3	32.4	26.2	19.8	13.3
	LAT	64.0	63.3	62.1	60.4	58.3	55.7	52.7	49.3	45.5	41.3	36.9	32.2	27.2	21.9	16.7	11.2
45°	LONG	70.4	69.6	68.3	66.5	64.1	61.2	57.9	54.2	49.9	45.5	40.6	35.4	29.9	24.2	18.3	12.3
	LAT	70.4	69.6	68.3	66.5	64.1	61.2	57.9	54.2	49.9	45.5	40.6	35.4	29.9	24.2	18.3	12.3
50°	LONG	64.0	63.3	62.1	60.4	58.3	55.7	52.7	49.3	45.5	41.3	36.9	32.2	27.2	21.9	16.7	11.2
	LAT	76.3	75.5	73.9	72.0	69.4	66.3	62.7	58.7	54.2	49.3	43.9	38.3	32.4	26.2	19.8	13.3
55°	LONG	57.2	56.5	55.4	53.9	52.0	49.7	47.0	43.9	40.6	36.9	32.9	28.7	24.3	19.6	14.9	9.9
	LAT	81.6	80.7	79.1	76.9	74.2	70.9	67.1	62.7	57.9	52.7	47.0	40.9	34.6	28.0	21.2	14.3
60°	LONG	49.8	49.3	48.3	47.0	45.3	43.3	40.9	38.3	35.4	32.2	28.7	25.0	21.2	17.1	12.9	8.7
	LAT	86.3	85.3	83.7	81.4	78.5	74.9	70.9	66.3	61.2	55.7	49.7	43.3	36.6	29.6	22.4	15.1
65°	LONG	42.1	41.7	40.9	39.8	38.3	36.6	34.6	32.4	29.9	27.2	24.3	21.2	17.9	14.5	10.9	7.4
	LAT	90.2	89.2	87.5	85.2	82.1	78.5	74.2	69.4	64.1	58.3	52.0	45.3	38.3	30.9	23.5	15.8
70°	LONG	34.1	33.7	33.0	32.1	30.9	29.6	28.0	26.2	24.2	21.9	19.6	17.1	14.5	11.7	8.9	5.9
	LAT	93.6	92.6	90.8	88.4	85.2	81.4	76.9	72.0	66.5	60.4	53.9	47.0	39.8	32.1	24.3	16.6
75°	LONG	25.8	25.5	25.0	24.3	23.5	22.4	21.2	19.8	18.3	16.7	14.9	12.9	10.9	8.9	6.7	4.5
	LAT	96.2	95.2	93.3	90.8	87.5	83.7	79.1	73.9	68.3	62.1	55.4	48.3	40.9	33.0	25.0	16.8
80°	LONG	17.3	17.1	16.8	16.6	15.8	15.1	14.3	13.3	12.3	11.2	9.9	8.7	7.4	5.9	4.5	3.0
	LAT	98.1	97.0	95.2	92.6	89.2	85.3	80.7	75.5	69.6	63.3	56.5	49.3	41.7	33.7	25.5	17.1

Figure 2-27. Percentage restraint chart

WWW.SURVIVALEBOOKS.COM

Section V. AIRDROP

DELIVERY OPERATIONS

Airdrop is a method of delivering supplies and equipment from aircraft to ground elements. As a rule, airdrop is a joint effort between Army and Air Force elements. Air Force airlift aircraft carry the airdrop items to the target area and effect delivery. Both Air Force and Army personnel support the operation on the ground.

The Army is responsible for providing airdropped supplies and equipment and airdrop equipment and ground vehicles used in recovering the items. Army divisions and separate brigades possess varying capabilities to support airdrop operations. Normally, airborne or air assault divisions have organic airdrop equipment support elements. Armored, infantry, mechanized divisions, and separate brigades require support from corps or theater air delivery units (see FM 29-51).

Advantages

Many advantages result when supplies and equipment are delivered by the airdrop method. Supplies and equipment can be airdropped directly to units, to otherwise unreachable areas, behind enemy lines, or to special operation units. Airdropping supplies and equipment takes less handling and shipping time. Emergency items can be prerigged and stored, and flight time and exposure of the aircraft to enemy fire is reduced.

Airdrop reduces the need for forward airfields or landing zones, reduces congestion during airfield off-loading, and reduces materials handling equipment requirements. It also increases aircraft availability and allows greater dispersion of forces.

Disadvantages

There are some disadvantages to the airdrop method of delivery, such as the need for specially trained personnel and appropriate airlift aircraft. The amount of cargo and troops aircraft can deliver depends on capacity and range of the aircraft. Airlift aircraft are affected by bad weather and high winds and are also vulnerable to enemy aircraft and ground fire.

Drop zones must be secured to keep items from failing into enemy hands. They also require special preparation for LAPES. In addition, the bulkiness of equipment rigged for airdrop and aircraft weight restrictions reduces the amount of the supplies aircraft can carry. There is also the possibility of loss or damage to equipment.

TYPES OF AIRDROP

Freedrop

No parachute or retarding device is used for freedrop. Energy-dissipating material may be used around the load to lessen the shock when the load hits the ground. The load descends at a rate of 130 to 150 feet per second. Fortification or barrier material, clothing in bales, and other such items may be freedropped.

High-Velocity

Ring-slot cargo, cargo-extraction, and pilot parachutes are used to stabilize loads for high-velocity airdrop. The parachute has enough drag to hold the load upright during the descent at 70 to 90 feet per second. Items to be airdropped are placed on energy-dissipating material and rigged in an airdrop container. Subsistence, packaged POL products, ammunition, and other such items may be high-velocity airdropped.

Low-Velocity

Cargo parachutes are used for low-velocity airdrop. Items are rigged on an airdrop platform or in an airdrop container. Energy-dissipating material is put beneath the load to lessen the shock when the load hits the ground. Cargo parachutes attached to the load reduce the rate of descent to no more than 28 feet per second. Fragile material, vehicles, and artillery may be low-velocity airdropped.

Halo

Halo is used to airdrop supplies and equipment at high altitudes when aircraft must fly above the threat umbrella. The rigged load is pulled from the aircraft by a stabilizing parachute and free falls to a low altitude where

WWW.SURVIVALEBOOKS.COM

a cargo parachute opens to allow a low-velocity landing.

RELEASE METHODS

Loads to be airdropped may be released by one of the following methods:

Extraction

The load and the platform on which it is rigged are pulled from the cargo compartment by an extraction parachute.

Door Load

The load is pushed or skidded out through the paratroop door.

Gravity

The aircraft is flown in a nose-up attitude. The restraint holding the load inside the aircraft is released, and the load rolls out of the cargo compartment.

LOW ALTITUDE PARACHUTE EXTRACTION SYSTEM

LAPES is a method of delivery which uses ring-slotted extraction chutes to extract palletized loads from low-flying airlift aircraft, It is used to airdrop supplies and equipment from an aircraft flying about 5 to 10 feet above the ground. Energy-dissipating material is put under the load, and the load is rigged on a LAPES airdrop platform. Webbing and load binders hold the load to the platform. The rigged load is pulled from the aircraft by extraction parachutes, which also help to slow the platform and load as it slides across the DZ, An airfield or DZ may require special preparation for a LAPES delivery. Vehicles, artillery, ammunition, supplies, equipment, and water may be delivered by LAPES.

Concept of Employment

The LAPES may be the preferred method of delivering supplies or equipment under certain conditions.

Adverse weather conditions. Use LAPES when—

- Surface or altitude winds exceed drop limitations.
- Ceilings are low and preclude airdrop of equipment in visual meteorological conditions.

Surface conditions. Use LAPES–

- In restricted terrain where accuracy is required because of cliffs, mountains, ravines, or other obstacles.
- When an airfield or assault LZ has been cratered and adequate repair equipment is not available.

Tactical conditions. Use LAPES–

- When enemy air defense capabilities pose an unacceptable threat to airlift aircraft at normal drop altitudes.
- When hostile ground fire would pose a threat to an aircraft on the ground.
- When reduced aircraft radar signature is required.

During clandestine resupply operations, where large loads and increased accuracy are required.

Extraction Zone (EZ)

The proper site selection for an EZ depends on a variety of conditions. Specific standards must be used in physically locating and marking an EZ to ensure safe operation. MAC Regulation 3-3 describes appropriate criteria.

Table 2-17. Weight limitations for cargo parachute and aerial delivery container

Parachute	*Suspended weight in pounds Minimum	Maximum
G-11A	2,270	4,250
G-11B	2,270	5,000
G-12C	501	2,200
G-12D	501	2,200
G-12E	501	2,200
G-13	200	500
T-7A	100	500

Container	Maximum weight (16)
A-7A	500
A-21	500
A-22	2,200

*Suspended weight is the total rigged weight less the weight of the cargo parachutes and their riser extensions.

WWW.SURVIVALEBOOKS.COM

GROUND-AIR EMERGENCY CODES

The symbols shown in Figure 2-28 may be made by using strips of fabric or parachute, pieces of wood, stones, or by tracking in the snow. The symbols should contrast with the background as much as possible and be 8 feet or more in length and 10 feet apart.




Figure 2-28. Ground-air emergency symbols

WWW.SURVIVALEBOOKS.COM

CHAPTER 3

MOTOR TRANSPORT

CONTENTS

		Page
Section I.	ORGANIZATION AND OPERATIONS	
	Motor Transport Units	3-1
	Administration	3-11
	Planning	3-22
	Transport Operations	3-29
II.	MOTOR TRANSPORT DATA	
	Vehicle Characteristics	3-69
	Planning Statistics	3-90

Section I. ORGANIZATION AND OPERATIONS

MOTOR TRANSPORT UNITS

A break down of Army motor transport units according to TOE, mission, assignment, and capability is outlined in Table 3-1.

Table 3-1. Tables of organization and equipment — motor transport units

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
Headquarters and headquarters company, transportation motor transport brigade	55-11H	MISSION: To command and provide planning, supervision, coordination, and control of transport groups and other assigned or attached units. Units are those required in the movement of cargo or personnel by highway transport, particularly in a continuous intersectional or other line-haul operation. ASSIGNMENT: To a theater army. Normally attached to a transportation command (TRANSCOM). CAPABILITY: This unit commands and supervises three to eight motor transport groups and supporting units of another administrative or logistical service.

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
Headquarters and headquarters detachment, transportation motor transport group	55-12H	MISSION: To provide command, control, and staff planning and attached transportation motor transport battalions. ASSIGNMENT: To a TRANSCOM or brigade. Normally attached to a motor transport brigade or may operate separately. CAPABILITY: This unit commands, plans, and supervises three to eight transportation motor transport battalions and attached supporting services.
Headquarters and headquarters detachment, transportation motor transport battalion	55-16H	MISSION: To provide command and supervision of units engaged in motor transport operations. ASSIGNMENT: To a corps support command (COSCOM) or theater army command. Normally attached to a transportation motor transport group, transportation brigade, or transportation composite group. CAPABILITY: This unit - • Provides command and supervision for three to eight transportation companies and attached supporting services as required. • Operates a truck terminal and/or trailer relay system when required. These operations require assignment of teams from TOE 55-540. • Provides unit maintenance on field radios for attached units.
Transportation light truck company	55-17H	MISSION: To provide truck transportation for movement of general cargo and personnel. ASSIGNMENT: To a theater army or COSCOM. Normally attached to a motor transport battalion. CAPABILITY (at level 1, with 75 percent vehicle availability): • SRC 55-17H510 — operates in two shifts, makes four round-trip local hauls per day (two per operating shift) and two round-trip line-hauls per day (one per operating shift). This unit transports — — Local hauls — 720 STONs of cargo (4 STONs per truck on road), (2 1/2 STONs per truck off road), or 3,600 passengers (20 passengers per truck) on/off road. — Line-hauls — 360 STONs of cargo (4 STONs per truck) on road or 1,440 passengers (16 passengers per truck) on/off road. • SRC 55-17H520 — operates in two shifts, makes four round-trip local hauls per day (two per shift) and two round-trip line-hauls per day (one per shift). This unit transports — — Local hauls — 1,080 STONs of cargo (6 STONs per truck) on road or 900 STONs of cargo (5 STONs per truck) off road, or 3,600 passengers (20 passengers per truck) on/off road. — Line-hauls — 540 STONs of cargo (6 STONs per truck) on road, or 1,620 passengers (18 passengers per truck) on/off road. • SRC 55-17H530 — operates in a single shift, makes two round-trip local hauls per day and one round-trip line-haul per day. This unit transports —

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		— Local hauls — 360 STONs of cargo (4 STONs per truck) on road, 225 STONs of cargo (2 1/2 STONs per truck) off road, or 1,800 passengers (20 passengers per truck) on/off road. — Line-hauls — 180 STONs of cargo (4 STONs per truck) on road or 720 passengers (16 passengers per truck) on/off road. • SRC 55-17H540 — operates in a single shift, makes two round-trip local hauls per day and one round-trip line-haul per day. This unit transports — — Local hauls — 540 STONs of cargo (6 STONs per truck) on road or 450 STONs of cargo (5 STONs per truck) off road or 1,800 passengers (20 passengers per truck) on/off road. — Line-hauls — 270 STONs of cargo (6 STONs per truck) on road or 810 passengers (18 passengers per truck) on/off road.
Transportation medium truck company	55-18H	MISSION: To provide transportation for the movement of containerized or general cargo, bulk petroleum products, and refrigerated cargo by motor transport. ASSIGNMENT: To an area support group or COSCOM. Normally attached to a motor transport battalion. CAPABILITY: This unit operates at full strength with 45 semitrailer combinations available, makes four round-trip local hauls per day or two round-trip line-hauls per day (one per 10-hour shift). • When equipped with 12-ton cargo semitrailers, this unit transports — — Local hauls — 2,160 STONs of cargo (12 STONs per semitrailer) or, in an emergency only, 9,000 passengers (50 passengers per semitrailer). — Line-hauls — 1,080 STONs of cargo (12 STONs per semitrailer) or, in an emergency only, 4,500 passengers (50 passengers per semitrailer). • When equipped with 34-ton semitrailers, this unit transports — — Local hauls — 3,960 STONs of cargo (22 STONs per semitrailer) or 360 20-ft containers or, in an emergency only, 6,300 passengers (35 per semitrailer). • When equipped with 5,000-gallon petroleum semitrailers, this unit transports — — Local hauls — 900,000 gal — Line-hauls — 450,000 gal • When equipped with 7 1/2-ton refrigerator semitrailer carrying 6 tons per vehicle, this unit transports: — Local hauls — 1,080 STONs — Line-hauls — 540 STONs • With a minor modification, (military desert-design tires), this unit can provide logistical and combat support in desert areas.

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
Transportation medium truck company (container/cargo, 40-foot)	5518J4	MISSION: To provide transportation for both dry and refrigerated containerized cargo, general noncontainerized cargo, and bulk water by motor transport. ASSIGNMENT: When employed in the COMMZ, to a TRANSCOM. Normally further attached to a motor transport battalion. May be attached to an area support group (ASG). When employed in the corps, normally attached to a transportation brigade with further attachment to a motor transport battalion. CAPABILITY (at strength level 1 with a 75 percent task vehicle (M915 14-ton tractor and M872 3/4-ton semitrailer) availability): This unit operates in two shifts, makes four round-trip local hauls (two per shift) or two round-trip line-hauls (one per shift) per day. This unit transports — • Containerized (dry or refrigerated) cargo. — Local hauls — 180 40-foot containers or 360 20-foot containers (total weight of 20-foot containers per transporter load not to exceed 34 STONs). — Line-hauls — 90 40-foot containers or 180 20-foot containers. • Noncontainerized cargo (palletized or package). — Local hauls — 3,960 STONs of cargo (22 STONs per semitrailer load). — Line-hauls — 1,980 STONs of cargo (22 STONs per semitrailer load). • Water. — Local hauls — 180 collapsible 4,750-gal-capacity water containers (855,000 gal of potable water). — Line-hauls — 90 collapsible 4,750-gal-capacity water containers (427,000 gal of potable water). • Passengers — 50 seated per 34-ton break-bulk/container semitrailer (in emergencies).
Transportation command transport company	55-19J3	MISSION: To provide transportation for the movement of personnel and/or light cargo by motor transport. ASSIGNMENT: • When organized under TOE 55-19J310, assigned to a theater army, a corps headquarters, or a COSCOM. Normally attached to a motor transport battalion. • When organized under TOE 55-19J320, assigned to an airborne corps headquarters. Normally attached to a motor transport battalion. CAPABILITY: At level 1, operating in a single shift, this unit provides daily motor transport support for personnel and light cargo.
Transportation medium truck company (container/cargo, 20-foot)	55-23J4	MISSION: To provide transportation for the movement of both dry and refrigerated containerized cargo, general noncontainerized cargo, and bulk water by motor transport.

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		ASSIGNMENT: When employed in the corps, normally attached to a transportation brigade, with further attachment to a motor transport battalion. When employed in the COMMZ, to a TRANSCOM; normally further attached to a motor transport battalion. May be attached to an ASG. CAPABILITY (at level 1 with a 75 percent task vehicle (M818 5-ton tractor and M871 22 1/2-ton semitrailer) availability): This unit operates in two shifts, makes four round-trip local hauls (two per shift) or two round-trip line-hauls (one per shift) per day. This unit transports — • Containerized cargo (dry refrigerated). — Local hauls — 180 20-foot containers. — Line-hauls — 90 20-foot containers. • Noncontainerized cargo (palletized/packaged). — Local hauls — 2,700 STONs of cargo (15 STONs per semitrailer). — Line-hauls — 1,350 STONs of cargo (15 STONs per semitrailer). • Water. — Local hauls — 180 collapsible 3,000-gal-capacity water containers (540,000 gal of potable water). — Line-hauls — 90 collapsible 3,000- gal water containers (270,000 gal of potable water).
Transportation cargo carrier company (tracked)	55-27H	MISSION: To provide transportation for supply distribution in regions where wheeled vehicles cannot operate effectively. ASSIGNMENT: To a theater army command, COSCOM, or FORSCOM. CAPABILITY: In sustained operations with 75 percent vehicle availability, this unit transports 228 STONs of cargo. When equipped with tank units, the unit transports 43,200 gal of fuel 50 miles forward daily.
Transportation heavy truck company	55-28H	MISSION: To provide truck transportation for tanks, heavy or bulky vehicles, and heavy, bulky, and outsize cargo. ASSIGNMENT: To a theater army command or COSCOM. Normally attached to a motor transport battalion. CAPABILITY (at level 1 with 75 percent task vehicle availability): • TOE 55-28H510 — operates in two shifts, makes four round-trip local hauls (two per shift) or two round-trip line-hauls (one per shift) per day: — Local hauls — 72 tanks or similar vehicles (one per transporter) or 2,880 STONs of cargo (40 STONs per transporter). — Line-hauls — 36 tanks or similar vehicles or 1,440 STONs (40 STONs per transporter). • TOE 55-28H520 — operates a single shift, makes two round-trip local hauls or one round-trip line-haul per day:

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT			TOE	MISSION/ASSIGNMENT/CAPABILITY
				— Local hauls — 36 tanks or similar vehicles (one per transporter) or 1,440 STONs of cargo (40 STONs per transporter). — Line-hauls — 18 tanks or similar vehicles (one per transporter) or 720 STONs of cargo (40 STONs per transporter).
Transportation company	light-medium	truck	55-67H	MISSION: To provide transportation for the movement of general cargo and personnel by motor transport. ASSIGNMENT: To a theater army command, COSCOM, or separate force. Normally attached to motor transport battalion. CAPABILITY: When operating at full strength, this unit transports — • One-time lift with all vehicles available — 360 STONs of cargo or 1,700 passengers. • One-time lift with 75 percent of vehicles available — 276 STONs of cargo or 1,300 passengers. — Local haul, 15 miles forward, two-shift operations, 75 percent of vehicles available, four trips cargo and six trips personnel--1,104 STONs of cargo or 7,800 passengers. — Line-haul, 75 miles forward, two-shift operations, 75 percent of vehicles available, two trips daily — 552 STONs of cargo or 2,600 passengers.
Transportation company	light-medium	truck	55-67J4	MISSION: To provide for movement of general noncontainerized cargo and personnel by motor transport. ASSIGNMENT: To a TRANSCOM or COSCOM. Normally further attached to a motor transport battalion. CAPABILITY: (at level 1 with 75 percent vehicle availability): This unit operates in two shifts, makes four round—trip local hauls (two per shift) or two round—trip line/long hauls (one per shift) per day. This unit transports- • Bulk cargo (5 tons per 5-ton cargo truck, 15 tons per 22 1/2-ton semitrailer): — Local Haul — STONs 5-ton cargo truck — 750 5-ton tractor (M818) and 22 1/2-ton semitrailer (M871) — 450 — 1,200 — Line-Haul — STONs 5-ton cargo truck — 375 5-ton tractor (M818) and 22 1/2-ton semitrailer (M871) — 225 — 600 • Personnel (20 per 5-ton cargo truck, local; 16 per 5-ton cargo truck, line-haul; 35 per 22 1/2-ton semitrailer (emergency only): — Local Haul — Troops 5-ton cargo truck — 3,000

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		5-ton tractor (M818) and 22 1/2-ton semitrailer (M871) 1,050 4,050 — Line-Haul Troops 5-ton cargo truck 1,200 5-ton tractor (M818) and 22 1/2-semitrailer (M871) 525 1,725
Transportation motor transport company, air assault division	55-69JO	MISSION: To provide organic motor transport to supplement division air transport of all classes of supply for the supply and transport battalion. ASSIGNMENT: Organic to supply and transport battalion, air assault division. CAPABILITY (at level 1, with 75 percent vehicle availability): This unit operates on a single shift and provides the following task vehicles daily to support division transport requirements: Task Vehicles — Each 5-ton cargo truck with 1 1/2-ton cargo trailer 13 5-ton tractor with 5,000-gal fuel semitrailer 7 5-ton tractor with 22 1/2-ton break-bulk container semitrailer or 5-ton tractor with 12-ton stake and platform semitrailer 6 5-ton cargo truck with liquid-dispensing tank and pump unit and 1 1/2-ton cargo trailer with liquid tank unit 1 10-ton tractor with 25-ton low-lid semitrailer 1 28
Transportation motor transport company, supply and transport battalion, infantry division (mechanized)	55-84H	MISSION: • To provide transportation for unit distribution of all classes of supply except Class V. • To transport division reserve supplies for which the unit is responsible. • To furnish vehicles required for displacing division headquarters and division administration company and to supplement transport means available to other elements of the division. ASSIGNMENT: Organic to supply and transport battalion, infantry division (mechanized). CAPABILITY (at level 1 with a 75 percent vehicle availability): This unit transports 270 STONs of cargo or 99,150 gal POL.
Transportation motor transport company, supply and transport battalion, armored division	55-87H	MISSION: • To provide transportation for unit distribution of all classes of supply except Class V. • To transport division reserve supplies for which the unit is responsible.

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		• To furnish vehicles required for displacing division headquarters and the division administration company and to supplement transport means available to other elements of the division. ASSIGNMENT: Organic to supply and transport battalion, armored division. CAPABILITY (at level 1 with 75 percent vehicle availability): This unit transports: General Cargo — STONs 45 trucks, cgo, 5-ton (6 STONs per vehicle) — 270 7 trucks, tractor, 5-ton with 12-ton S&P semitrailer — 84 354 or 45 trucks, cgo, 5-ton (6 STONs per vehicle) — 270 7 trucks, tractor, 5-ton with 22 1/2-ton break-bulk/container transporter (15 STONs per vehicle) — 105 375 POL — GAL 25 trucks, tractor, 5-ton with 5,000-gal fuel semitrailer (5,000 gal per semitrailer) — 125,000 4 trucks, cgo, 5-ton and 1 1/2-ton trailer with fuel pods (1,800 gal per trailer) — 7,200 132,200
Transportation motor transport company, heavy division	55-87J4	MISSION: • To provide truck transportation for unit distribution of Class I, II, IV, and VII supplies. • To transport division reserve supplies for which the main support battalion is responsible. • To furnish vehicles to assist division elements with a requirement for supplemental transportation, including unit distribution of Class V supplies. • To provide truck transportation for the movement of heavy, outsize vehicles and cargo. ASSIGNMENT: Organic to the main support battalion of the heavy division. CAPABILITY (at level 1, with 75 percent availability): This unit — • Provides the following task vehicles daily for dispatch: Task Vehicles — Each 5-ton cargo truck — 27 5-ton tractor (M818) with 22 1/2-ton semitrailer (M871) — 24 Heavy equipment transporter (HET) (M911 tractor with M747 semitrailer) — 18 69

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		• Makes a one-time lift of noncontainerized cargo as follows: Noncontainerized cargo — STONs 5-ton cargo truck — 135 5-ton tractor (M818) with 22 1/2-ton semitrailer (M871) — 360 HET or 18 tanks or equivalent vehicles. — 720 1,215
Transportation motor transport company, supply and transport battalion, infantry division	55-88H	MISSION: • To provide transportation for unit distribution of all classes of supply except Class V. • To transport the division reserve supplies for which the unit is responsible. • To furnish vehicles required for displacing division headquarters and the division administration company and to supplement vehicles available to other elements of the division. ASSIGNMENT: Organic to supply and transport battalion, armored division. CAPABILITY (at level 1 with 75 percent vehicle availability): This unit transports 270 STONs of cargo or 51,750 gal POL in a single lift.
Transportation motor transport company, infantry division (light)	55-88J8	MISSION: • To provide truck transportation for unit distribution of Class II, IV, and IX supplies. • To transport troops in support of division operations. • To transport the division reserve supplies for which the supply and transport battalion is responsible. • To provide supplemental transportation for division elements, including emergency unit distribution of Class V supplies and water. ASSIGNMENT: Organic to supply and transport battalion, infantry division, light. CAPABILITY: At level 1, this unit provides enough drivers and control personnel for 24-hour operation of unit task vehicles. For planning purposes, based on 75 percent task vehicle availability, this unit — • Provides the following task vehicles daily: Task Vehicles — Each 5-ton cargo truck — 24 5-ton tractor (M818) with 22 1/2-ton semitrailer (M871) — 6 30 or • Makes a one-time break-bulk cargo lift as follows: Break-bulk cargo — STONs 5-ton cargo truck — 120

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		5-ton tractor (M818) with 22 1/2-ton semitrailer (M871) 72 192 or • Makes a one-time troop lift as follows: One-time troop lift — Troops 5-ton cargo truck 480 5-ton tractor (M818) with 22 1/2-ton semitrailer (M871) 210 690
Transportation motor transport teams:	55-540H	
GA, car		MISSION: To transport passengers, messengers, and a limited amount of cargo by 1/4-ton utility truck, 1 1/4-ton cargo truck, or sedan. ASSIGNMENT: To a theater army or COSCOM. Normally attached to a motor transport battalion or may operate separately under the supervision of the appropriate staff transportation officer. CAPABILITY (with a 75 percent task vehicle availability (7 vehicles)): This team transports — • When equipped with 1/4-ton utility trucks, 21 passengers (3 per vehicle) and 1 3/4 STONs of cargo (1/4 STON per trailer) per lift. • When equipped with 1 1/4-ton cargo trucks, 49 passengers (7 per truck) or 8 3/4 STONs of cargo (1 1/4 STONs per truck). • When equipped with sedans, 35 passengers (5 per sedan) per lift.
GB, light truck		MISSION: To transport personnel or cargo by light truck. ASSIGNMENT: To a theater army or COSCOM. Normally attached to a motor transport company or may operate separately under supervision of the appropriate staff transportation officer. CAPABILITY (with 75 percent vehicle availability (7 trucks)): This team transports — • When equipped with 2 1/2-ton cargo trucks, 28 STONs of cargo (4 STONs per truck) on road, 17 1/2 STONs of cargo (2 1/2 STONs per truck) off road, or 140 passengers (20 per truck) per lift. • When equipped with 5-ton cargo trucks, 42 STONs of cargo (6 STONs per truck) on road, 35 STONs of cargo (5 STONs per truck) off road, or 140 passengers (20 per truck) per lift. • When equipped with 44 passenger buses, 308 passengers, or 112 litter patients.
GC, medium truck		MISSION: To transport general cargo, containers, bulk petroleum products, or refrigerated cargo by truck tractor with semitrailer combinations. ASSIGNMENT: To a theater army or COSCOM. Normally attached to a motor transport company or may operate separately under supervision of the appropriate staff transportation officer. CAPABILITY (with a 75 percent vehicle availability (7 trucks)): This team transports —

WWW.SURVIVALEBOOKS.COM

Table 3-1. Tables of organization and equipment — motor transport units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		• When equipped with 40-foot combination container/cargo semitrailers, seven 40-foot containers, fourteen 20-foot containers, or 175 STONs of noncontainerized cargo. • When equipped with 20-foot combination container/cargo semitrailers, seven 20-foot containers, or 105 STONs of noncontainerized cargo. • When equipped with 12-ton stake and platform semitrailers, 84 STONs per lift or, in an emergency, 350 passengers. • When equipped with 5,000-gal-tank semitrailers, 35,000 gal of bulk petroleum products per lift. • When equipped with 7 1/4-ton refrigerator semitrailers, 42 STONs of refrigerated cargo per lift.
GD, heavy truck		MISSION: To transport heavy or outsize cargo by heavy truck tractor-semitrailer combinations CAPABILITY (with a 75 percent vehicle availability (three trucks)): This team transports three tanks or similar vehicles (one per semitrailer) or 120 STONs of outsize or heavy-lift cargo per lift.
GE, trailer transfer point		MISSION: To operate a trailer transfer point in conjunction with a line-haul operation. ASSIGNMENT: To a transportation motor transport headquarters responsible for line of communications motor transport operations. CAPABILITY: Operates on a single shift, in conjunction with a line-haul operation, a trailer transfer point with a maximum capacity of 125 semitrailer units in and out. The operation includes — • Receiving, segregating, assembling, and dispatching loaded or empty semitrailers for convoys. • Maintaining POL-dispensing facilities to refuel operating equipment. • Servicing, inspecting, and, if required, making emergency repairs to incoming vehicles. • Preparing and maintaining required operational records and reports.

ADMINISTRATION

Standing Operating Procedures

See Figure 3-1 for sample SOP format for motor transport movements within divisions, logistical commands, and higher echelons. See Figure 3-2 for sample SOP format for motor transport service.

WWW.SURVIVALEBOOKS.COM

STANDING OPERATING PROCEDURE

1. GENERAL. *Policies and factors involved in movements.*
   a. Highway regulation. *Purpose, application/scope, responsibilities, methods and procedures.*
   b. Convoy clearance. *Minimum vehicle requirements; convoy symbols; procedures; format for requesting and furnishing clearance; routing; halts; convoy composition; restrictions on tracked, overweight, or outsize vehicles.*
   c. Highway regulation points. *Purpose, basis for, responsibilities and procedures, required records.*
   d. Traffic control. *Responsibilities, relationship to highway regulation, coordination with provost marshal.*
   e. Return loads. *Policies, methods, and procedures for securing and reporting.*
   f. Convoy commanders. *Appointment, responsibilities, and functions; relationships with transportation personnel; instructions to be furnished.*
   g. Halts. *Types; policies, procedures, and responsibilities; area policing.*
   h. Security. *Responsibilities; defensive measures.*
   i. Records and reports. *Responsibilities, methods, required reports.*
   j. Communications. *Responsibilities, means of communication.*

2. SUPPLY MOVEMENTS

   a. Releases. *When required, methods of obtaining, formats, dissemination, actions required.*
   b. Diversions and reconsignments. *Authority, request procedures.*
   c. Records and reports. *Types of required records and reports.*

Figure 3-1. Sample format for motor transport movements SOP

STANDING OPERATING PROCEDURE

1. GENERAL. *Policies for control, operation, and maintenance of facilities, equipment, and installation; command responsibility; technical supervision required and agencies involved.*

2. MISSION. *Service provided, extent of operation.*

3. ORGANIZATION. *Available operating units, location, and operating limits.*

4. FUNCTIONS. *Scheduled and nonscheduled operations; maintenance of equipment, including responsibilities, procedures, facilities, and inspection practices.*

5. PLANNING. *Troop and equipment requirements, capability estimates, communication procedure and requirements, rehabilitation requirements.*

6. OPERATIONS. *Operational procedures and controls, pooling, and equipment use.*

7. MAINTENANCE. *Responsibilities and procedures for maintenance, regulations, and reports.*

8. SUPPLY. Responsibilities for supplies, authorized levels, requisitioning procedures, accounting methods, disposal of excesses.

Figure 3-2. Sample format for motor transport service SOP

WWW.SURVIVALEBOOKS.COM

9. INTELLIGENCE AND RECONNAISSANCE. *Responsibilities for collection, collation, evaluation, and dissemination of highway transportation intelligence and reconnaissance information.*

10. SECURITY. Responsibilities for disaster and defense plans, convoy and cargo security, equipment and facilities.

11. RECORDS AND REPORTS. *Responsibilities for operational and personnel status reports, technical reports, and miscellaneous records/reports.*

12. TRAINING. *Responsibilities for unit and technical training.*

Figure 3-2. Sample format for motor transport service SOP (cont)

Vehicle Commitment Format

Use a locally reproduced format to furnish routine vehicle commitments to subordinate units. See Figure 3-3 for a sample.

20th Transportation Battalion (Truck)
APO 0000

Date 24 Sep '85

Subject: Vehicle Commitment

To: CO, 86th Trans Co, Mdm (Cgo)

Commitment No 9-108

1. Vehicles w/drivers 7-12T S&P

Report to: Major Eason

Location: Q200, Warehouse 19

Time: 0730 Date 25 Sep '85

To transport: 77 tons dry rations

Destination: Q166, Ludwigsb'g - Trans Off. Bldg. A8

2. Remarks: No return load scheduled; POL available at Q166 for refueling.

C.A. Mitchell
(Signature)

Major S-3
(Rank & Title)

Figure 3-3. Type vehicle commitment work sheet

WWW.SURVIVALEBOOKS.COM

Convoy Procedures

Briefing. Before a convoy departs on a mission, the commander briefs all convoy members. The following areas should be covered, with adjustments to suit local conditions:

1. Situation:
   - Friendly forces.
   - Support units.
   - Enemy situation.

2. Mission:
   - Type of cargo.
   - Origin.
   - Destination.

3. Execution:
   - General organization.
   - Time schedule.
   - Routes.
   - Speed.
   - Catch-up speed.
   - Vehicle distance.
   - Emergency measures (for accidents, breakdowns, and separation from convoy).
   - Action of convoy and security personnel if ambushed.
   - Medical support.

4. Administration and logistics:
   - Personnel control.
   - Billeting.
   - Messing.

5. Command and signal:
   - Convoy commander's location.
   - Assistant convoy commander designation.
   - Security forces commander's action.
   - Serial commanders' responsibilities.
   - Arm and hand signals.
   - Other prearranged signals.
   - Radio frequencies and call signs (for control personnel, security force commanders, fire support elements, reserve security elements, medical evacuation support).

6. Safety:
   - Hazards of route.
   - Weather conditions.
   - Defensive driving.

Convoy Commander's Checklist

Before departure time, convoy commanders should use the following list of questions to make sure arrangements are complete:

- Where is start point? Release point?
- What route is to be used?
- Has reconnaissance been made and condition of route determined?
- Can bridges, tunnels, underpasses, and defiles safely accommodate all loaded and tracked vehicles?
- Are critical points known and listed on strip maps?
- What is the size of serials?
- What is the size of march units?
- What is the rate of march?
- What is the vehicle interval on an open road? In built-up areas? At halt?
- What type of column will be used?
- Has provision been made for refueling if required?
- Has a suitable bivouac site been selected if required?
- Have suitable rest and mess halt areas been selected if required?
- Is road movement table needed? Prepared? Submitted?
- Have convoy clearances been obtained? What date?
- Is escort required and has it been requested?
- Are spare trucks available for emergencies?
- Are vehicles fully serviced, clean, and ready for loading?
- Is load proper, neat, and balanced?
- Are drivers properly briefed? By whom? When? Strip maps furnished?
- Is convoy marked front and rear of each march unit? With convoy number when required?
- Are guides in place? Have arrangements been made to post guides?
- Are blackout lights functioning?
- Are maintenance services alerted?
- Is maintenance truck in rear? Are medics in rear? Is there a plan for casualties?
- Are all interested parties advised of estimated time of arrived (ETA)?

WWW.SURVIVALEBOOKS.COM

- Is officer at rear of convoy ready to take necessary corrective action, such as investigating accidents and unusual incidents and changing loads? Who is trail officer?
- Is there a truck load plan? Who is responsible?
- Is there a truck unload plan? Who is responsible?
- Has a plan been made for feeding personnel?
- Have times been established for loading trucks?
- Has time been established for formation of convoy?
- Have times been established for unloading trucks?
- Has time been established for releasing trucks? Who is responsible?
- Is there a carefully conceived plan known to all convoy personnel that can be used in case of attack?
- Is a written operation order on hand if required?
- Will a log of road movement be required at end of trip? Are necessary forms on hand?
- Has a weather forecast been obtained?
- Do all personnel have proper clothing and equipment?
- Is there a communications plan?

Convoy commander's report. After a move has been completed, the convoy commander prepares a report to submit to his immediate superior officer. Use the sample report in Figure 3-4 as a guide. The report may also be submitted in the form of a strip map with an appropriate legend attached.

FORWARD LOAD

420 Trans Bn (Trk)		4401 Trans Co (Lt Trk)
28FE01C (Convoy No)	Twelve 2 1/2-Ton Trucks (No and type of task vehicles)	16 Feb XX (Date)

TIME

Departed starting point	0621 hr
Departed 1st loading point	0800 hr
Arrived 1st loading point	0630 hr
Time at 1st loading point	1 hr 30 min
Arrived highway regulating point (HRP)	1200 hr
Departed HRP	1205 hr
Time at 1st unloading point	33 min

SUPPLIES AND PERSONNEL

Cargo (STONs)	50.2
Class of supplies	I
Number of personnel	0

DISTANCE

Odometer reading of lead vehicle (at 1st loading point)	21,324 mi
Odometer reading of lead vehicle (at starting point)	21, 322 mi
Total forward (no load)	2 mi
Odometer reading of lead vehicle (at 1st unloading point)	21,381 mi
Total forward (loaded)	57 mi

Figure 3-4. Sample convoy commander's report

WWW.SURVIVALEBOOKS.COM

REMARKS

Starting point — company area, RJ 124/167

Weak bridge 6.4 mi east of 1st loading point. Road generally in poor condition between starting point and 1st unloading point.

RETURN LOAD

TIME

Departed 2d loading point	1300 hr
Arrived 2d loading point (same as 1st unloading point)	1245 hr
Time at 2d loading point	15 min
Departed 2d unloading point	1415 hr
Arrived 2d unloading point	1400 hr
Time at 2d unloading point	15 min

SUPPLIES AND PERSONNEL

Cargo (STONs)	10.0
Class of supplies	II and IV
Number of personnel	120

DISTANCE

Odometer reading of lead vehicle (at 2d unloading point)	21,396 mi
Odometer reading of lead vehicle (at 2d loading point)	21,381 mi
Total return (loaded)	15 mi
Odometer reading of lead vehicle (at starting point)	12,346 mi
Total return (no load)	40 mi

REMARKS

Road in excellent condition between 2d loading point and starting point.

ROUND-TRIP DATA

TIME

Returned to starting point	1,654 mi
Total round-trip time	10 hr 33 min
Total travel time (including halts)	8 hr
Total loading time	1 hr 45 min
Total unloading time	48 min

SUPPLIES AND PERSONNEL

Cargo (STONs of class I)	50.2
(STONs of class II and IV)	10.0
Number of personnel	120

Figure 3-4. Sample convoy commander's report (cont)

WWW.SURVIVALEBOOKS.COM

DISTANCE

Total distance (loaded)	72 mi
Total distance (unloaded)	42 mi
Total round-trip distance	114 mi

REMARKS

Average rate of march = 14.2 MIH.
Ton-miles forward = 2,861; return = 150.
Passenger-miles forward = 0; return = 1,800.

/s/

/t/ Thomas A. Young
(Convoy commander)

2d Lt, 4401 Trans Co (Lt Trk)
(Rank/grade and organization)

Figure 3-4. Sample convoy commander's report (cont)

Convoy clearance. A convoy clearance request is usually required from a unit or organization planning a move by convoy. The information required varies according to regulations and local SOP. See Figure 3-5 for a sample DD Form 1265. See FM 55-312 for detailed instructions on preparing the form.

In a theater of operations. Before beginning a road movement over a route requiring a movement credit, the unit submits a request for clearance on DD Form 1265 (Request For Convoy Clearance). Submit the request through movement channels to the highway traffic headquarters (HTH) controlling the area where the movement starts. DD Form 1265 is a dual-purpose document. It can serve either as a request or as an authorization for movement, or both. The requesting agency uses DD Form 1265 to initiate a movement via highway; the HTH uses the form to grant clearance and to issue instructions for the road movement. Information to complete this form is supplied by the unit requesting movement. Depending on the urgency of the requirement, the information on the form may be transmitted orally, electrically, or in writing. After receiving the request, the HTH schedules the movement at the time and over the route requested by the unit, if possible. When the move cannot be scheduled at the requested time or on the requested route, the HTH notifies the requester. Alternate times and routes are then arranged. After final coordination and approval, the HTH issues the necessary movement credit, convoy movement number, and any other required information. The authorization is returned to the requesting agency. In NATO operations, STANAG 2155 governs movement credits.

In CONUS. A military convoy needs permission from appropriate state and city officials to travel on public highways. Obtain permission by submitting DD Form 1265 through the installation transportation officer (ITO). Submit the DD Form 1265, a copy of the operations order, and four copies of a strip map of the proposed convoy route with one additional copy of each document for each state to be crossed and one copy for the local ITO at point of origin. The request must reach the approving authority (in most cases, the local ITO) at least 10 days before the planned move.

WWW.SURVIVALEBOOKS.COM

REQUEST FOR CONVOY CLEARANCE — DATE: 1 Jan XX

SECTION I - GENERAL

1. ORGANIZATION	2. STATION	3. CONVOY COMMANDER
100th Trans Co (Lt Mdm Trk)	Fort Eustis, Virginia 23604	John J. Jones 1LT, TC

4. PERSONNEL STRENGTH a. OFFICER	b. ENLISTED	5. POINT OF ORIGIN	6. DESTINATION
1	47	Fort Eustis, Virginia	Camp A. P. Hill, Virginia

7. DATE AND TIME	7a. DEPARTURE	7b. ARRIVAL	8. RATE OF MARCH
	15 0700 Jan XX	15 1002 Jan XX	40 MIH

SECTION II - CONVOY COMPOSITION

9. NUMBER OF EACH TYPE OF VEHICLE AND DESCRIPTION (Include towed equipment)

1 1/4-ton Truck, Utility
20 5-ton Tractor W/19 Stake and Platform Semitrailers (1 Bobtail)
1 5-ton Wrecker

SAMPLE

10. TOTAL NUMBER OF VEHICLES	11. NUMBER OF OVERSIZE/ OVERWEIGHT VEHICLES	12a. NO. OF SERIALS	12b. TIME INTERVAL	13a. NO. OF MARCH UNITS	13b. TIME INTERVAL
22	21	1	NA	2	2 min.

SECTION III - ROUTE DATA

14. PROPOSED ROUTING (Indicate US Routes, State Routes, etc)

Interstate 64, State Route 168, State Route 33, Interstate 64, Interstate 95, State Route 207, U. S. 301 to Camp A. P. Hill

15. ETA AND ETD AT STATE LINES, MAJOR ROAD JUNCTIONS, MAJOR BRIDGES AND TUNNELS, METROPOLITAN AREAS AND OVERNIGHT HALT SITES (Continue on a separate sheet if additional space is required)

LOCATION	ETA	DATE	ETD	DATE
I-64	0700		0705	15 Jan XX
Rt # 168	0732		0737	
15 min-Rest Halt. Rt # 33	0754		0814	
I-64	0835		0840	
I-95	0859		0904	
207-301	0957		1002	

SECTION IV - LOGISTICAL DATA

16. BRIEF GENERAL DESCRIPTION OF CARGO (Brief general description, i. e., organizational impedimenta, etc.) (Within security limitations)

Class I (packaged rations)

DD FORM JAN 80 1265

Figure 3-5. DD Form 1265 (Request for Convoy Clearance) (sample)

WWW.SURVIVALEBOOKS.COM

17. ARE EXPLOSIVES TO BE TRANSPORTED? ☐ YES ☐ NO *(If YES, describe below)*

CLASS	AMOUNT	DESCRIPTION	VEHICLES TO BE USED	
			NO.	TYPE
		NA		

18. STATEMENT WHY EXPLOSIVES CANNOT BE TRANSPORTED COMMERCIALLY *(Movements involving explosives and/or other dangerous articles are required to comply with all applicable regulations or directives)*

NA

19. LOGISTICAL SUPPORT REQUIRED AT OVERNIGHT HALT SITES? ☐ YES ☐ NO *(If YES, complete the following) (Use separate sheet if additional space is required)*

DATE	INSTALLATION	GAS (gals)	OIL (gals)	RATIONS	BILLETS	OTHER
	NA					

20. REMARKS

ETA is the time the first vehicle clears the referenced point.

ETD is the time the last vehicle clears the referenced point.

SAMPLE

21. REQUESTING AGENCY		22. APPROVING AGENCY	
100th Trans Co (Lt Mdm Trk)			
23. REQUESTED BY *(Typed name, grade and title)*		24. APPROVED BY *(Typed name, grade and title)*	
CHARLES C. CHESTNUT			
25. DATE	26. SIGNATURE	27. DATE	28. SIGNATURE
1 Jan XX	Charles C. Chestnut		

INSTRUCTIONS: In cases where bona-fide emergencies exist, the information contained on DD Form 1265 and DD Form 1266 may be transmitted to the appropriate headquarters by telephone or electric transmission. In this event, reference will be made to item numbers in the sequence in which they appear on the form. Items which do not apply will be so indicated.

Figure 3-5. DD Form 1265 (Request for Convoy Clearance) (sample) (cont)

WWW.SURVIVALEBOOKS.COM

Special Hauling Permit. In CONUS, use DD Form 1266 (Request for Special Hauling Permit) to request permission to move oversize or overweight vehicles over public roads. Prepare the form in four copies with an additional copy for each state to be crossed. The request must reach the approving authority at least 15 days before the planned move. Only identical

REQUEST FOR SPECIAL HAULING PERMIT — DATE: 1 Jan XX

SECTION I - GENERAL

1. ORGANIZATION	2. STATION	3. DATE OF MOVEMENT: a. STARTING	b. COMPLETION
100th Trans Co (Lt Mdm Trk)	Fort Eustis, Virginia 23604	0700 15 Jan XX	1830 16 Jan XX

4. POINT OF ORIGIN	5. DESTINATION
Fort Eustis, Virginia	Fort Drum, New York

6. ARRIVAL AT STATE LINES

DATE	TIME	STATE LINE
15 Jan XX	1308	Va/Md
15 Jan XX	1440	Md/Pa
16 Jan XX	1145	Pa/NY

7. ROUTING (Stipulate US Routes, State Routes, etc.): IS 64, Va 168, Va 33, IS 64, IS 95, IS 495E, US 1, IS 695, IS 83, IS 81, US 11

8. ESCORT REQUIREMENTS: None

SECTION II - VEHICLE AND LOAD DATA

DESCRIPTION (a)	TYPE (2-ton etc) (b)	NO. OF VEHICLES (c)	REGISTRATION NUMBER (d)	HEIGHT (e)	WIDTH (f)	LENGTH (g)	WEIGHT (h)
9. VEHICLE							
A. TRUCK							(Empty)
B. TRUCK-TRACTOR	5-ton	8	See Item 12	103.5	98.3	158.3	(Empty) 18,560
C. TRAILER							(Empty)
D. SEMI-TRAILER	12-ton	8	See Item 12	108.3	97.3	348.5	(Empty) 14,240
E. OTHER (Specify)							(Empty)
10. LOAD Orgn Impediments				-	-	-	5,000
11. OVERALL (Vehicle and load)				108.3	98.3	526	(Gross) 37,800

12. DESCRIPTION OF LOAD (Brief general description: Organization impediments, etc.) (Within security limitations)

Organization impedimenta.

Registration Numbers

Trac	Tlr	Trac	Tlr
5E5551 -	5T9991	5E5555 -	5T9995
5E5552 -	5T9992	5E5556 -	5T9996
5E5553 -	5T9993	5E5557 -	5T9997
5E5554 -	5T9994	5E5558 -	5T9998

SAMPLE

13. LOAD OVERHANG	a. FRONT	b. REAR	c. LEFT SIDE	d. RIGHT SIDE
	NA	NA	NA	NA

DD FORM 1 JAN 66 1266

Figure 3-6. DD Form 1266 (Request for Special Hauling Permit) (sample)

WWW.SURVIVALEBOOKS.COM

vehicles with loads of uniform weight and dimensions may be listed on the same DD Form 1266. See Figure 3-6 for a sample request. See FM 55-312 for detailed preparation instructions.

14. NUMBER OF AXLES: (1) A (2) B ( ) C ( ) D ( ) E ( ) F ( ) G ( )

	AXLE 1 a	AXLE 2 b	AXLE 3 c	AXLE 4 d	AXLE 5 e	AXLE 6 f	AXLE 7 g	AXLE 8 h	TOTAL i
15. NUMBER OF TIRES	2	4	4	4	4				18
16. TIRE WIDTH (Inches)	11	11	11	11	11				
17. TIRE SIZES	1100x20	1100x20	1100x20	1100x20	1100x20				
18. AXLE LOAD (Empty)	8,244	6,958	6,958	5,320	5,320				32,800
19. AXLE LOAD (Loaded)	9,044	8,058	8,058	6,320	6,320				37,800

SAMPLE

20. AXLE SPACING (Use item 11 for identification)	A SPACING	B SPACING	C SPACING	D SPACING	E SPACING	F SPACING	G SPACING
	140	54	162	52			

21. REMARKS

22. MOVEMENT BY HIGHWAY IS ☐ ESSENTIAL TO NATIONAL DEFENSE ☑ IN THE INTEREST OF NATIONAL DEFENSE

23. REQUESTING AGENCY	24. APPROVING AGENCY
100th Trans Co (Lt Mdm Trk)	
25. REQUESTED BY (Typed name, grade and title)	**26. APPROVED BY (Typed name, grade and title)**
Charles C. Chestnut, Cpt, TC, Commanding	
27. DATE	**28. SIGNATURE**
1 Jan XX	Charles C. Chestnut
29. DATE	**30. SIGNATURE**

INSTRUCTIONS

GENERAL:

DD Form 1266 "Request for Special Hauling Permit" will be used to obtain special hauling permits for the movement of oversize/overweight vehicles over public highways when accompanying a convoy or when traveling separately.

This form, in duplicate and accompanied by letter of transmittal, will be forwarded through the local transportation officer so as to reach the appropriate headquarters not less than ten (10) working days prior to the starting date of the movement. Letters of transmittal will contain complete itinerary and explanation of the movement. One (1) letter of transmittal is sufficient when several DD Forms 1265 and 1266 involving one (1) movement are forwarded to the appropriate headquarters.

In cases where bona-fide emergencies exist, the information contained in this form and DD Form 1265 may be transmitted to the appropriate headquarters by telephone or electric transmission. In this event, reference will be made to item numbers in the sequence in which they appear on the forms. Items which do not apply will be so indicated.

SPECIFIC:

Item 9A, B, C, and D - Complete nomenclature of vehicles involved. More than one unit may be included, provided units are identical in equipment, load characteristics, routing and movement date. Total number of units shall be indicated prominently.

Item 9E - Note all units other than standard highway vehicles, road equipment, guns, etc.

Item 9 (d) - Indicate the registration number for each unit or combination of units. Use additional page if required.

Item 14 - Indicate appropriate number of axles by inserting number in proper circles. Black out circles not applicable.

Item 21 - For movement through the District of Columbia, include name of manufacturer of equipment.

Figure 3-6. DD Form 1266 (Request for Special Hauling Permit) (sample) (cont)

WWW.SURVIVALEBOOKS.COM

PLANNING

Unit/Vehicle Capabilities

General factors. Motor transport planning, particularly in its earliest stages, must often be based on broad planning factors and assumptions. However, because of the varied services performed, loads carried, and terrain crossed, use general planning factors with caution and only in the absence of specific data on the local situation. When specific data is not available, use the following estimates to compute vehicle and truck company requirements:

- Average number of assigned task vehicles not in maintenance and available for daily operations — 83 percent (short-range), 75 percent (long-range).

  NOTE: Short-range figure is for maximum sustained effort only. It is not to be used for periods of more than 30 days.

- Anticipated payload per vehicle — rated cargo capacity of vehicle (but 3,000-gal capacity for 5,000-gal-tank semitrailers).

- Average daily round-trips per vehicle (will vary with running time and delay times) — two per day (one per operating shift) (line-hauls), four per day (two per operating shift) (local hauls).

- One-way hauling distance — 90 miles/144 kilometers one way per operating shift (line-hauls), 15 miles/24 kilometers one way per trip (local hauls).

- Average number of miles covered in an hour (including short halts) – 10 MIH/16 KIH (poor roads), 20 MIH/32 KIH (good roads).

  NOTE: Under actual road conditions, consider not only the road's surface, but also terrain, weather, and hostile activity, all of which may affect rate of march.

- Turnaround time — time consumed for round-trip movement, including delays.

- Delay time (includes loading, unloading, and line-haul relay time; also includes halts and delays en route, such as mess halts or ferrying operations, which can be anticipated but are not included in the rate of march).

  – 2.5 hours loading/unloading time per round-trip (cargo trucks).

  – 2.5 hours loading/unloading time per round-trip (semitrailers).

  – 1 hour per relay round-trip per line-haul leg (tractor trucks in semitrailer relay operations).

- Use per day of vehicles with drivers — 10 hours (one shift), 20 hours (round-the-clock, two shifts).

  NOTE: The remaining 4 hours of the 24-hour day is scheduled for maintenance.

- Unit lift and daily lift — the amount of cargo a truck company can move at one time (unit lift); the amount it can move in a day, making a number of trips (daily lift).

- Ton- or passenger-miles — the product of the number of tons or passengers times the number of miles moved.

TOE capabilities. For planning purposes, in the absence of other specific operational data, see Section II for motor transport unit tonnage and passenger capabilities estimated from TOE capabilities. Also refer to Section II for estimated vehicle payload capacities.

Fuel Requirements. NATO uses the fuel consumption unit (FCU) method to calculate fuel requirements (STANAG 2115). This is an easy method which uses current data. The FCU is the quantity of fuel required for operation by a given piece of equipment under average operating conditions, based on —

- 100 kilometers of movement per day for wheeled and tracked vehicles over solid, level, dry roads.

- 3 hours of flying time per day for aircraft.

- 12 hours of normal operating time for stationary equipment.

Use the FCU method to compute fuel consumption requirements for a brigade, division, or corps:

WWW.SURVIVALEBOOKS.COM

- List each type of equipment on the organizationTOE by nomenclature and quantity on hand.
- Multiply the number of pieces of each type of equipment by the rate of consumption for the equipment. (See appropriate technical manual for rate.)
- Add the gallons of each type of fuel used to obtain estimated fuel requirement for each type of fuel.
- Under combat conditions, the total number of gallons consumed is multiplied by factors representing the type of combat, terrain, and climate present. See Table 3-2 for a list of these factors. Use them *only* in combat situations.

Table 3-2. FCU factors (combat conditions)*

Situation	Multiplication Factor
Combat:	
Attack	2.5
Delay/Withdrawal	2.0
Defense	1.5
Terrain:	
Flat	1.0
Hilly	1.2
Mountain	1.5
Cross-Country	1.5
Climate:	
Hot	0.9
Temperate	1.0
Cold	1.3

*Use these factors *only* if unit is involved in combat.

For example: An organization's total diesel fuel requirement under average conditions is 109,784 gallons per day. During combat, additional calculations are required for combat (delay), terrain (hilly), and climate (hot). Compute the fuel consumption rate for the organization using the following formula:

Combat (delay) X terrain (hilly) X climate (hot) X total gallons diesel fuel per day (average operating conditions) = diesel fuel consumption for the organization

2.0 X 1.2 X 0.9 X 109,784 = 237,132 gal/day total diesel fuel consumption

Movement Requirements

Use the following formulas to compute unit and vehicle requirements on the basis of planning estimates, actual operational data, or a combination of both. If the load you are computing is not in tons, substitute the particular unit (gallons, persons, other) for tons in the formulas.

One-time lifts. To determine the number of truck companies or vehicles required to move a given number of tons in one lift, substitute appropriate values in the following formulas:

$$\text{companies required} = \frac{\text{tons to be lifted}}{\text{tons per veh} \times \text{veh aval per company}}$$

$$\text{vehicles required} = \frac{\text{tons to be lifted}}{\text{tons per veh}}$$

Turnaround time. To determine turnaround time, use the following formula:

$$\text{turnaround time} = \frac{2 \times \text{distance}}{\text{rate of march (MIH)}} + \text{delays}$$

The delay factor must be accurate. Round off turnaround time to the nearest tenth.

Line-haul leg. Use the following formula to determine the distance to allow between trailer, transfer points (TTPs) (that is, the length of a line-haul leg):

$$\text{distance} = \frac{\left(\text{hr per operating shift} - \text{hr of delay}\right) \times \text{rate (MIH)}}{2}$$

The numerator in the formula equals the total distance a driver can travel in one round-trip shift. Division by 2, therefore, results in a driver's one-way distance. One-way distance equals the length of a line-haul leg.

Sustained operations. Use the following formula to determine the number of truck companies required to move a given daily tonnage in sustained operations. The formula applies to both local and line-haul operations.

$$\text{companies required} = \frac{\text{daily tonnage} \times \text{turnaround time}}{\text{tons per veh} \times \text{veh aval per company} \times \text{operational day}}$$

WWW.SURVIVALEBOOKS.COM

The number of vehicles required can be determined by omitting vehicles available per company from the formula.

$$\text{vehicles required} = \frac{\text{daily tonnage} \times \text{turnaround time}}{\text{tons per veh} \times \text{operational day}}$$

Specific loads. A transport mission may require movement of specific loads which, because of their peculiarities, involve a variation in the normal planning process. The loads may be one or more items, packaged or not packaged, with unusual size, shape, cube, or weight. Examples are aircraft engines and missile components. In such cases, determine vehicle requirements by test loading or by using operational data available from previous similar operations. If test loading is not feasible or operational data is unavailable, use the method described here.

First, determine the number of items that can be transported by one vehicle. This can be computed from the cargo weight or cube. If circumstances warrant, calculate the load both ways to arrive at the lesser figure:

$$\frac{\text{veh payload capacity}}{\text{weight of item}} = \text{number of items, by weight, in a single-vehicle load}$$

$$\frac{\text{veh cargo compartment cube}}{\text{cube of item}} = \text{number of items, by cube, in a single-vehicle load}$$

If the value using cargo weight is the lesser value, the weight of the computed load will exceed the vehicle payload capacity before all available cargo space is filled. If the value using cargo cube is the lesser, the computer cargo load will "cube out" (exceed the cubic cargo space available in the vehicle) before it "weighs out" (exceeds the vehicle payload capacity).

Obtain the vehicle payload capacity and the cargo compartment cubic capacity from the vehicle data plate, vehicle technical manual, or Section II of this chapter. The weight and cubic volume of a specific item or load can be obtained from the shipper, the service representative, or the applicable technical manual.

Knowing the single-vehicle load, compute the number of vehicles required:

$$\frac{\text{number of items to be transported}}{\text{number of items in single-veh load}} = \text{vehicles required}$$

The calculation may be for a one-time lift or a day-to-day lift, depending on the mission.

Line-Haul Operational Planning Exercise

The following procedure demonstrates how to plan and set up a motor transport line-haul move involving trailer transfer operations. See Figure 3-7 for a diagram of the route including length of line-haul, locations of support facilities, and tonnages to be moved.




Figure 3-7. Route and location of facilities

Tonnages. Information provided by the staff movements officer establishes tonnages to be moved by highway:

- l 3,600 STONs daily from Port Alpha to Depot 301.

WWW.SURVIVALEBOOKS.COM

- 2,400 STONs daily from Red Beach to Depot 101.
- 1,500 STONs daily from Depot 101 to Depot 301.

The daily forward movement of 3,600 STONs from Port Alpha and 1,500 STONs from Depot 101 have been combined at the point on the route where these forward movements coincide. Figure 3-7 provides a realistic picture of the tonnage flow over the road and a working aid in planning this type of operation.

Planning factors. For purposes of this exercise, assume cargo is a type that can be loaded to rated weight capacities of vehicles without exceeding cube capacities of cargo compartments. Use the following operational planning factors:

- Round-the-clock operation — two 10-hour shifts.
- Vehicles available per unit — 45 (at 75 percent availability rate).
- Load per 2 l/2-ton truck — 2.5 tons (off-road weight only).
- Load per 34-ton M872 semitrailer — 22 tons.
- Load per 22 l/2-ton M871 semitrailer — 15 tons.
- Load per 12-ton cargo semitrailer — 10 tons.
- Rate of march:

  — 20 MIH/32 KIH — main supply route between origin and destination terminals.
  — 15 MIH/24 KIH — Port Alpha to origin terminal, Depot 101 to origin terminal, destination terminal to Depot 301.
  — 10 MIH/16 KIH – Red Beach to Depot 101.

- Delay times:

  — 2.5 hours per round-trip (1.25 hours for loading, 1.25 hours for unloading).
  — 1 hour per relay (round-trip per leg) for truck tractors.

Truck terminals. Truck terminals are normally located in or near centers of concentrated trucking activities at both ends of a line-haul. They form the connecting link between local pickup and delivery service (local haul) agencies and the line-haul operations. They provide assembly points and dispatch centers for line-haul motor transport equipment. Truck terminals may be used for in-transit storage or freight sorting, but this use should be held to an absolute minimum.

Figure 3-8 shows a typical origin truck terminal. Arrangement of facilities may deviate from the diagram, but consider the facilities indicated to be the minimum necessary for effective terminal operation.

In this line-haul exercise, distances and operating factors require short-haul/shuttle tractor operations in conjunction with a trailer relay operation. Therefore, the approximate locations of the origin and destination truck terminals must be found for the line-haul task. This is needed to separate the line-haul from local operations and to identify specific work loads and tasks.

The origin truck terminal should be centrally located near the road intersection between Port Alpha and Depot 101, provided a suitable site is available. The destination truck terminal should be located near the intersection above Depot 301. This would place the destination terminal on the main route near the cargo's destination and would allow for expansion forward without relocation. Refer back to Figure 3-7. Note that there is no requirement for an intermediate truck terminal.

Trailer transfer points. Trailer transfer points are located at predetermined locations along the route of a line-haul operation. They form the connecting links between various operating units' areas of responsibility. Trailer transfer points tie the overall operation into one continuous, efficient movement procedure.

Before determining and computing the type and number of truck units required for each task for the line-haul, locate the trailer transfer points to divide the line-haul into legs. Then compute total delays and total turnaround time for the entire line-haul. To determine the distance of each leg for a turnaround time of 10 hours in around-the-clock operation, allow a 1- hour relay time per line-haul leg.

WWW.SURVIVALEBOOKS.COM




Figure 3-8. Typical origin truck terminal layout

$$\text{distance} = \frac{\left(\frac{\text{10 hr per}}{\text{operating shift}} - \frac{\text{1 hr}}{\text{delay}}\right) \times \text{20 MIH}}{2}$$

$$= \frac{(10\text{-}1) \times 20}{2}$$

$$= \text{90 miles between trailer transfer points}$$

Trailer transfer points are then located as shown in Figure 3-9. In addition to allowing the most desirable turnaround time, the planner must consider suitable sites for locating these facilities. Note also that the short leg (53 miles) has been placed forward. This is to avoid relocating any but the most forward trailer transfer point if the operation is expanded.

Types of units. Specific tasks, work loads, and types of units required for the exercise can not be determined from the preceding information. A study of the overall operation is needed, including types of hauls, operating areas, and daily tonnage requirements, to indicate the kinds of units most suitable for the various transport missions. For this exercise, the units required are medium truck companies (34-ton semitrailer) and light truck companies (2 1/2-ton truck) (see Figure 3-10).

WWW.SURVIVALEBOOKS.COM

Number of units. Medium truck companies were selected for the line-haul and three local hauls:

- Origin truck terminal to destination truck terminal.
- Port Alpha to origin truck terminal.
- Depot 101 to origin truck terminal.
- Destination truck terminal to Depot 301.

The medium truck companies may be equipped with the 12-ton M127A2 semitrailer, the 22 1/2-ton M871 semitrailer, or the 34-ton M872 semitrailer. The M872 is used primarily by theater army units. A light truck company was selected for the local haul from Red Beach to Depot 101.

The planner now calculates the number of medium and light truck companies needed for the operation.

1. Line-haul, origin to destination truck terminal, 5,100 STONs by medium truck company:

- Vehicles per company — 45 tractors with semitrailers (stlr) (at 75 percent vehicle availability).
- Average payload per vehicle — 22 STONs (34-ton stlr).
- Given 1 hour delay for each of three relays, 233 miles distance from OTT to DTT —

$$\text{turnaround time} = \frac{(2 \times 233 \text{ mi})}{20 \text{ MIH}} + 3 \text{ hr} = 26.3 \text{ hr}$$

- Operational day — 20 hours.
- Number of companies required —

$$\frac{5{,}100 \text{ STONs} \times 26.3 \text{ hr}}{22 \text{ STONs} \times 45 \text{ veh} \times 20 \text{ hr}}$$

$$= \frac{134{,}130}{19{,}800}$$

$$= 6.77 \text{ medium truck companies}$$




Figure 3-9. Location of trailer transfer points




Figure 3-10. Types of units

WWW.SURVIVALEBOOKS.COM

2. Local haul, Port Alpha to origin truck terminal, 3,600 STONs by medium truck company:

- Vehicles per company — 45
- Average payload per vehicle — 22 STONs (34-ton stlr).
- Given 1 hour delay time, 15 miles distance—

$$\text{turnaround time} = \frac{(2 \times 5 \text{ miles})}{15 \text{ MIH}} + 1 \text{ hour} = 1.67 \text{ hours}$$

- Operational day — 20 hours.
- Number of companies required —

$$\frac{3{,}600 \text{ STONs} \times 3 \text{ hr}}{22 \text{ STONs} \times 45 \text{ veh} \times 20 \text{ hr}} = \frac{10{,}800}{19{,}800}$$

= .55 medium truck company

3. Local haul, Depot 101 to origin truck terminal, 1,500 STONs by medium truck company:

- Vehicles per company — 45.
- Average payload per vehicle — 22 STONs (34-ton stlr).
- Given 1 hour delay time, 5 miles distance—

$$\text{turnaround time} = \frac{(2 \times 5 \text{ miles})}{15 \text{ MIH}} + 1 \text{ hr} = 1.67 \text{ hr}$$

- Operational day — 20 hours.
- Number of companies required —

$$\frac{1{,}500 \text{ STONs} \times 1.67 \text{ hr}}{22 \text{ STONs} \times 45 \text{ veh} \times 20 \text{ hr}} = \frac{2{,}505}{19{,}800}$$

= .13 medium truck company

4. Local haul, destination truck terminal to Depot 301, 5,100 STONs by medium truck company:

- Vehicles per company — 45.
- Average payload per vehicle— 22 STONs (34-ton stlr).
- Given 1 hour delay time, 10 miles distance—

$$\text{turnaround time} = \frac{(2 \times 10 \text{ mi})}{15 \text{ MIH}} + 1 \text{ hr} = 2.33 \text{ hr}$$

- Operational day–20 hours.
- Number of companies required—

$$= \frac{5{,}100 \text{ STONs} \times 2.33 \text{ hr}}{22 \text{ STONs} \times 45 \text{ veh} \times 20 \text{ hr}} = \frac{11{,}883}{19{,}800}$$

= .60 medium truck company

5. Local haul, Red Beach to Depot 101, 2,400 STONs by light truck company:

- Vehicles per company — 45.
- Payload per vehicle — 2.5 STONs.
- Given 2.5 hours per round-trip for loading/unloading, 15 miles distance —

$$\text{turnaround time} = \frac{(2 \times 15 \text{ mi})}{10 \text{ MIH}} + 2.5 \text{ hr} = 5.5 \text{ hr}$$

- Operational day — 20 hours.
- Number of companies required —

$$\frac{2{,}400 \text{ STONs} \times 5.5 \text{ hr}}{2.5 \text{ STONs} \times 45 \text{ veh} \times 20 \text{ hr}} = \frac{13{,}200}{2{,}250}$$

= 5.87 light truck companies

A total of six light truck companies is needed for the local haul from Red Beach to Depot 101. When less than a full company is required, teams from TOE 55-540 may be used for augmentation.

Determine the total number of medium truck companies by adding the numbers for each haul.

6.77	line-haul, origin to destination truck terminal
.55	local haul, port Alpha to origin truck terminal
.13	local haul, Depot 101 to origin truck terminal
.60	local haul, destination truck terminal to Depot 301
8.05	or 9 total number of medium truck companies

In this operation all medium truck companies share the work load since all are connected with the semitrailer relay operation. Therefore, the fractional part of the unit requirement for each task is retained and included in the total. The total is then rounded

WWW.SURVIVALEBOOKS.COM

off to the next higher whole number. However, where the work load cannot be shared among units doing varied tasks, the unit requirement for each task must be rounded off to the next higher whole number.

Control units. Based on the preceding computations, nine medium truck companies and six light truck companies are required for the operation. In addition, four teams (Team GE, TOE 55-540) are required to operate the two trailer transfer points and the transfer operations in the truck terminals. Three motor transport battalions and one motor transport group are required for command and control. (See FM 101-10-2 for basis of allocation.) The group commander has overall responsibility for the operation and assigns a specific geographic area to each battalion. The group commander assigns responsibility for operating each truck terminal to a specific battalion.

TRANSPORT OPERATIONS

Motor Pool Facility

The basic layout of motor pools varies, depending on space and conditions. For new construction, a single structure should be built to economize on construction costs and operating expenses. The typical motor pool should include these facilities:

- ***Motorpool office.*** This office should be in the motor pool operations area.
- ***Dispatch office.*** All vehicular operations are controlled through this office. If at all possible, it should be at the exit of the motor pool. This allows the dispatcher to visibly check vehicles leaving the parking area.
- ***Drivers' room.*** For convenience and orderly operation, the drivers' room should be near, but separate from, the dispatch office.
- ***Emergencg repair facility.*** This facility performs minor and emergency repairs not serious enough to warrant removing the vehicle from operation. The repair facility is usually in a section of the general repair shop or at the POL point.
- ***Vehicle-washing facilities.*** These facilities should be available under all weather conditions. Facilities should be located so that drainage flows away from parking areas and buildings. Automatic washing facilities should be considered when feasible.
- ***Preventive maintenance and general repair shop.*** The number of vehicles to be serviced is a deciding factor in the type of shop used. Primary functions of the shop are to carry out regularly scheduled preventive maintenance, lubrication, and general repair activities.
- ***Allied trade shops.*** These are shops for spot painting, minor body work, carpentry, and welding. Fire hazards in some trade shops require that these shops not be collocated. For example, painting and welding activities must be in separate areas.
- ***Supply and parts room.*** This facility is centrally located within the main shop building to provide easy access to parts and tools. Parts, bins, tool racks, and an appropriate issue counter should be provided.
- ***Public address system.*** A public address system helps to control the motor pool and parking area. Interoffice communication between the dispatch office and key locations within the pool area eliminates many unnecessary, time-consuming trips and promotes orderly operation.

Vehicle Loading

The driver is responsible for his vehicle being loaded properly. Follow these loading rules:

- Place heavy supplies at the bottom of the load and distribute them evenly over cargo floor.
- Place the load so that it will not shift; distribute the weight equally.
- Do not distribute load loosely or build it up too high. High, loosely distributed loads cause swaying. This makes the vehicle difficult to handle and increases the danger of losing the cargo or overturning the vehicle.
- If the truck has an open body, put a tarpaulin over the cargo when practicable to protect against sun, dust, rain, and pilferage.
- If possible, place barrels and drums on their sides parallel with the length of the truck. Brace and pyramid them. If the possibility of leakage prohibits this placement, set the

WWW.SURVIVALEBOOKS.COM




Figure 3-11. Motor pool facility layout

drums upright. Not as many drums can be loaded in the same space with the upright arrangement.

- Combine boxed, crated, and packaged cargo as much as possible with like items or items of compatible shapes.
- Load sacked cargo separately or so it will not be punctured by odd-shaped items; stack it in overlapping layers to prevent shifting.

See Figure 3-12 for correct placement of load in truck.

WWW.SURVIVALEBOOKS.COM




WRONG

RIGHT


Select the right vehicle for the right job.

CAB-OVER-ENGINE (COE) TRUCK

CONVENTIONAL TRUCK



Tires, axles, and frame are designed to carry a load distributed as shown.




WRONG

This load bends the frame, overloads front tires, and makes steering harder.

RIGHT

Place heavy part of load near rear axle for proper tire loading and to keep frame from bending.



WRONG


This load bends the frame, overloads rear tires, and makes steering almost impossible.

RIGHT

Set a concentrated load just ahead of the rear axle with the longest side on the floor, if possible.

Figure 3-12. Load placement in trucks and semitrailers

WWW.SURVIVALEBOOKS.COM




Distribute trailer loads equally between the rear tires and the fifth wheel. This placement transfers the load to the tractor.




WRONG

This placement overloads one spring and set of tires. Brakes lock on the light side, causing skids.



RIGHT

Nothing is overloaded; frame will not twist and loosen cross-member rivets.



WRONG

This placement shortens tire life and bends the truck rear-axle housing. Applying the trailer brakes may lock the wheels and cause flat spots and skidding.



WRONG

This placement overloads trailer rear wheels so that brakes will not function properly and rubber scuffs away.



RIGHT

Distribute the load over the full trailer floor.

Figure 3-12. Load placement in trucks and semitrailers (cont)

WWW.SURVIVALEBOOKS.COM

Road Movement Table

A road movement table is a convenient way to let subordinates know about schedules and other essential details. The table is particularly useful if including these details in the body of the operation order would complicate it or make it unduly long. Road movement tables frequently require a wider distribution than normal operation orders. Copies are issued to convoy operating personnel, traffic-regulating personnel, and traffic control posts. For security reasons, it may not be desirable to include dates or locations. A security classification is assigned according to the contents of the road movement table. This classification is not necessarily the same as the operation order's. The road movement table may be issued as an annex to the operation order. If issued alone, the table must be signed and authenticated in the same way as other orders.

As illustrated in Figure 3-13, the road movement table shows the date of the move, units involved, number of vehicles, and load class of the heaviest vehicle. It also shows the routes and the times when serials will arrive at and clear critical points.

(CLASSIFICATION)

Annex B - "Movement Table" to Operation Order for Movement No

Map:

General Data:

1. Average speed:
2. Traffic density:
3. Halts:
4. Routes (between start points and release points):
5. Critical points:
   (a) Start points.
   (b) Release points.
   (c) Other critical points.
6. Main routes to start points:
7. Main routes from release points:

Copy No
Issuing HQ
Place of Issue
Date-Time Group of Signature
Message Reference No

Serial or Movement Number	Date	Unit/Formation	Number of Vehicles	Load Class of Heaviest Vehicles	From	To	Route	Route to Start Point	Critical Points			Route from Release Point	Remarks
									Ref	Due (hr)	Clear (hr)		
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)

Authentication:

Appexdixes:

Distribution:

(CLASSIFICATION)

Figure 3-13. Suggested format for road movement table.

A strip map may also be published as an annex to an operation order. When a strip map is used, its details should correspond to the data in the road movement table, and it should be distributed to the lowest practical level. Where practical and appropriate, a strip map may include —

- Start point.
- Release point.
- Route numbers.
- Town names.
- Critical points.
- Distance.
- Total distance.
- North orientation.

See Figure 3-14 for a sample strip map.

WWW.SURVIVALEBOOKS.COM




Figure 3-14. Sample strip map

Route Reconnaissance

A route reconnaissance overlay is an accurate and concise report of the conditions affecting traffic flow along a specified route and is the preferred method of preparing a route reconnaissance report. An overlay normally satisfies the requirements of hasty route reconnaissance. If, however, more detail is required to support the reconnaissance, the overlay is supplemented with written reports describing critical route characteristics in more detail. For additional information, see FM 5-36. See Figure 3-15 for an example of a route reconnaissance overlay. See Figure 3-16 for an explanation of route reconnaissance symbols.

Consider the following checklist when preparing reconnaissance reports:

- Identification and location of the reconnoitered route.
- Distance between points, which should be easily recognized both on the ground and on the map.
- Percent of slope and length of grades which have a 7 percent slope or greater.
- Sharp curves with a radius of 100 feet or less.
- Bridge military load classifications, limiting dimensions, and suitable bypasses.
- Locations and limiting data for fords and ferries.
- Route restrictions, such as underpasses, which are below minimum standard and any additional distances caused by these restrictions.
- Locations and limiting dimensions of tunnels and suitable bypasses.
- Suitable areas for short halts and bivouacs which offer drive-off facilities, adequate dispersion, cover, and concealment.
- Areas of rockfalls and rockslides which may present a traffic hazard.

WWW.SURVIVALEBOOKS.COM






Figure 3-15. Sample route reconnaissance overlay

WWW.SURVIVALEBOOKS.COM

Explanation	Symbol	Remarks/Reference*
Civil or military route designation		Designation written in parentheses along route.
Critical point		Critical points are numbered and described in legend. They may be used to point out features not adequately covered in other reconnaissance symbols.
Limits of sector		Limits of reconnoitered sector of route.
Route classification formula	10.5m X 120 6m Z 8 (OB) 9m Y 20 (OB)(W)	Formula designates, in order, width, type, military load classification, obstructions, and regular flooding or snow blockage. Legend: X—All-weather route Y—all-weather route (limited traffic) Z—fair-weather route T—regular snow blockage W—regular flooding
Grades		Arrows point uphill; actual percentge of slope is shown to the right of symbol. Length of arrow represents length of grade if map scale permits.
Sharp curve		Vertex of triangle points to map location of curve; number indicates radius.
Series of sharp curves		Left figure indicates number of curves. Right figure indicates radius of the sharpest curve.

*All dimensions are in meters.

Figure 3-16. Route reconnaissance symbols

WWW.SURVIVALEBOOKS.COM







Explanation	Symbol	Remarks/Reference
Full bridge symbol		Arrow extends to bridge location on map. Minimum width is placed below, overhead clearance to the left, and overall length to the right of basic symbol. Lower portion of symbol indicates bridge serial number; upper portion, military load classification. Underlined values are those below minimum standard.
Abbreviated bridge symbol		Arrow extends to bridge location on map. Lower portion of symbol indicates bridge serial number; upper portion, military load classification. Class number must be underlined if width or overhead clearance is below minimum standard.
Bypass easy		Used in conjunction with bridge and tunnel reconnaissance symbols.
Bypass difficult		Used in conjunction with bridge and tunnel reconnaissance symbols.
Bypass impossible		Used in conjunction with bridge and tunnel reconnaissance symbols.
Ford		Arrow extends to ford location on map. Data above line indicates, in order, serial number, ford type, stress velocity per second, and seasonal limitations. Data below line indicates, in order, length, width, bottom type, and depth. Question marks indicate unknown information. Difficult approaches are represented by zigzag lines and correspond to shore position of approach. Ford type: V—vehicular P—pedestrian Seasonal limiting factors: X—none Y—significant Bottom type: M—mud C—clay S—sand G—gravel R—rock P—artificial paving

Figure 3-16. Route reconnaissance symbols (cont)

WWW.SURVIVALEBOOKS.COM





Explanation	Symbol	Remarks/Reference
Ferry		Arrow extends to ferry location on map. Data above symbol indicates, in order, ferry serial number and type. Data inside symbol indicates, in order, military load class of deck and dead weight capacity in tons. Data below symbol is turnaround time in minutes. Question mark indicates unknown information. Difficult approaches are represented by zigzag lines corresponding in position to shore approach. Ferry type: V—vehicular P—pedestrian
Width constriction		Figure to the left indicates the width of the route constriction; figure to the right, the total constricted length.
Arch underpass constriction		Figure to left indicates width of constriction; figure to right, overhead clearance. If different, both minimum and maximum overhead clearances are given.
Rectangular underpass constriction with sidewalks		Numbers indicate width of traveled way followed by total width, including sidewalk, to left of symbol. Overhead clearance appears on right.
Tunnel with sidewalks		Arrow extends to tunnel location on map. Serial number is placed inside symbol; width of traveled way, followed by total width including sidewalks, is placed below symbol. Overhead clearance is placed to the left of symbol, total tunnel length to the right. A question mark represents unknown information. Bypasses are shown by standard symbol notations.
Railroad grade crossing		Grade crossing is level; passing trains will interrupt traffic flow. Number indicates height of power line (if present) above the ground.
Concealment		Road lined with trees, deciduous on left, evergreen on right.

Figure 3-16. Route reconnaissance symbols (cont).

WWW.SURVIVALEBOOKS.COM





Explanation	Symbol	Remarks/Reference
Concealment		Woods bordering road, deciduous trees on left, evergreen trees on right.
Side road turnoff Additional information: •Wheeled vehicle •Tracked vehicle •Dead-end road over 1 km		Arrow indicates direction of turnoff. Number indicates length of turnoff.
Roadblock, craters, and blown bridges •Proposed •Prepared but passable •Completed		Center of the symbol indicates position of block.
Lateral route		Broken lines indicate lateral route identified by even number.
Axial route		Solid line indicates axial route identified by odd number.
Unknown or doubtful information		
Parking area		
Traffic control point		

Figure 3-16. Route reconnaissance symbols (cont)

WWW.SURVIVALEBOOKS.COM

Traffic Circulation Plan

A traffic circulation plan is a map that shows a roadnet and gives necessary information and traffic restrictions. The circulation plan establishes one-way, two-way, and alternating routes of traffic flow. Routes must be available for a circular flow in the required directions. A one-way route normally requires a return route in the opposite direction. Adequate access and egress routes must be provided to prevent congestion of main supply routes.

Normally, the traffic circulation plan contains—

- Route designations and the most restrictive route features.
- Direction of movement.
- Location of boundaries, unit highway regulation points, traffic control posts, and principal supply activities.
- Major geographic features.
- Light lines, if applicable.

Circulation plans frequently combine a standard map with an overlay to give the needed information. If the necessary information is too much to put on one overlay, use separate overlays for different types of information. See Figure 3-17 for a sample traffic circulation plan.

Tonnage capacities of roads and bridges are important considerations when selecting routes. The gross weight of the heaviest loaded vehicle should not exceed the rated tonnage capacity of the weakest bridge. It is difficult to determine exact tonnage capabilities of highways for sustained operations because conditions will vary. Also, the volume of tactical, administrative, and local traffic using supply routes may exceed that of cargo-hauling vehicles. This traffic further restricts highway transport capabilities.

In the absence of more accurate data, use Table 3-3 as a guide for highway tonnage capabilities. The table provides estimates of supply support tonnage capabilities for various conditions. Sustained operations, adequate road maintenance, and two-way traffic are assumed. When more than one limiting condition is involved, apply the reduction factors in the same order as they appear in the table (left to right):

- First, narrow roadway.
- Second, terrain (rolling, hills, or mountains).
- Third, weather (if conditions are sustained).

Size and weight limits change periodically as a result of road and bridge construction. Planners must verify local limits and clearance and exemption methods with local military or civilian agencies before putting vehicles on the road.

Military Load Classification System

The military load classification system is a load-capacity rating system based on the vehicle's weight and its effect on routes and bridges. In this classification system, whole numbers are assigned to vehicles, bridges, and

Table 3-3. Highway tonnage capabilities

Highway Type	Daily Tonnage Forward (STONs)			Reduction Factors for Various Conditions (%)				
	Optimum Dispatch (Rear Area)	Supply Traffic (COMMZ)	Supply Traffic (CZ)	Narrow Roadway (Less than 24 ft or 7.20 m)	Rolling Terrain	Hills With Curves	Mountains	Seasonal Bad Weather
Concrete	60,000	36,000	8,400	25	10	30	60	20
Bituminous	45,000	27,000	7,300	25	10	30	60	30
Bituminous-treated	30,000	18,000	5,800	25	20	40	65	40
Gravel	10,150	6,090	3,400	25	20	50	70	60
Dirt	4,900	2,940	1,600	25	25	60	80	90

WWW.SURVIVALEBOOKS.COM




Figure 3-17. Sample traffic circulation plan

WWW.SURVIVALEBOOKS.COM

routes. Most allied military vehicles are externally marked with their respective classification number. Military load classifications are assigned to bridges and routes based on their safe-load capacity and physical dimensions. For a detailed discussion of the military load classification system, see FM 5-36.

Vehicles. Except for prime movers, self-propelled vehicles in Class 3 or higher and towed vehicles in Class 1 or higher are marked to indicate their class. Prime movers are marked either with their own class or the class of the normal combination of prime mover with trailer or semitrailer. Markings on trucks should be on the right front, on or above the bumper, and below the driver's vision. Markings are lusterless black numerals on a lusterless forest green backgound. See Figure 3-18 for examples. For weight classification listings of specific vehicles, see FM 5-36.




Figure 3-18. Vehicle classification markings

WWW.SURVIVALEBOOKS.COM

Bridges. Every military bridge is posted with a number capacity to indicate the highest weight-class vehicle that can safely cross. Heavier vehicles are barred except in special cases; for example, crossing at reduced speed or in limited numbers. Fixed bridges may also be marked with the length in feet of the span which corresponds to the posted capacity.

There are two types of bridge signs: classification (circular) signs and information (rectangular) signs. In both types, symbols or letters appear in black on a yellow background. See Figures 3-19 and 3-20 for examples.

Routes. Routes are classified according to the route classification formula. The formula is a brief description of the route, which is used with a route reconnaissance overlay. The route classification formula reflects a route's—

- Minimum traveled-way width.
- Weather restistance type.
- Lowest military load classification.
- Obstructions (if any).






Figure 3-19. Typical bridge signs

WWW.SURVIVALEBOOKS.COM



SINGLE—LANE BRIDGE



TWO-LANE, DUAL-CLASS BRIDGE

Figure 3-20. Typical placement of bridge signs

WWW.SURVIVALEBOOKS.COM

Width. Minimum route widths for wheeled and tracked vehicles in single- and double-flow traffic are:

	Widths	
Traffic Flow	Wheeled Vehicles	Tracked Vehicles
Single	18 to 23 ft (5.5 to 7 m)	19.5 to 26 ft (6 to 8 m)
Double	Over 23 ft (7 m)	Over 26 ft (8 m)

Type. For classification purposes, the type of route is based on its resistance to the effects of weather. The worst section of the route determines its type:

- Type X — an all-weather route which, with reasonable maintenance, is passable throughout the year to traffic that is never appreciably less than the maximum capacity of the route. Roads on a Type X route normally have waterproof surfaces and are only slightly affected by precipitation and temperature fluctuations. At no time is the route closed to traffic due to weather except for temporary snow or flood blockage.

- Type Y — an all-weather route which, with reasonable maintenance, can be kept open in all weather but may limit traffic in some kinds of weather. Roads on a Type Y route usually do not have waterproof surfaces and are considerably affected by precipitation and temperature fluctuations. Traffic may be completely halted for short periods. Heavy, unrestricted use during adverse weather may cause complete collapse of the surface.

- Type Z — a fair-weather route which quickly becomes impassable in adverse weather and can then be kept open only by major repairs. A Type Z route is so seriously affected by weather that traffic maybe brought to a halt for long periods.

Load. Route load classification is determined by the lowest bridge classification number, regardless of vehicle type or traffic conditions. Using the lowest bridge classification number ensures that the route will not be overloaded. When a proposed route has a lower military load classification than that of the vehicles which must cross it, this fact is shown on the route reconnaissance overlay. A special reconnaissance determines if a change in traffic control procedures, such as a single-flow crossing, would make the route safe for these vehicles. If there is no bridge on the route, the worst section of road governs the route's classification.

Obstructions. Obstructions affect the type, amount, and speed of traffic flow. Route obstructions are indicated in the route classification formula by the letters *"OB"*. (An exception is bridge capacities reported separately as a military load classification.) Reconnaissance symbols are used on the route reconnaissance overlay to describe each obstruction. Obstructions that must be included in the route classification formula are —

- Overhead obstructions, such as bridges, tunnels, underpasses, wires, and overhanging buildings, which have an overhead clearance under 14 feet (4.25 m).

- Reductions in traveled-way widths which are below the standard minimums prescribed in FM 5-36 for the type of traffic flow. Examples are width reduction due to bridges, tunnels, craters, mines, and projecting buildings or rubble.

- Gradients of 7 percent or greater.

- Curves with radii of curvature of less than 100 feet (30 m).

- Ferries.

- Fords.

If an obstruction appears in the route classification formula, refer to the route reconnaissance overlay to determine the exact type and location of the obstruction.

WWW.SURVIVALEBOOKS.COM

Formulas. Following are examples of typical route classification formulas:

Formula	Minimum Width of Traveled Way	Route Type	Military Load Classification	Remarks
20 ft Z 10	20 ft	fair weather	10	Based on 20-ft min width of traveled way, accommodates wheeled and tracked, single-flow traffic. No obstruction.
20 ft Z 10 (OB)	20 ft	fair weather	10	If used for double-flow traffic, min width of traveled way (20 ft) is considered an obstruction.
7 M Y 50 (OB)	7 m	limited all-weather	50	If used for wheeled or tracked vehicles in double-flow traffic, min width of traveled way (7 m) is considered an obstruction.
10.5 M X 120 (OB)	10.5 m	all-weather	120	Based on 10.5-m min width of traveled way, accommodates wheeled and tracked vehicles in double-flow traffic

NATO Military Vehicle Markings

NATO armed forces have agreed to use standard markings for vehicles. These markings are not necessarily used at all times but, when used, should conform to the guidelines below. The rear of a trailer is marked in the same manner as its prime mover; there is no need to mark the front of a trailer. If necessary for security reasons, vehicle markings may be covered or removed when directed by the field commander or his superior authority. Standard NATO markings include:

- Registration numbers — numbers or a combination of letters and numbers, as required by the nation concerned.
- National symbols — shown, at a minimum, front and rear to identify each country's vehicles. Service symbols may be superimposed on national symbols or appear separately.
- Speed limits — placed on vehicles as directed by the nation concerned.
- Tactical markings — stripes and geometrical figures, sometimes with a name, for identification within units. Markings should be large enough to make ground-to-ground identification of vehicles possible; colors may be used. The design and position of these markings are prescribed by the field commander for easy battlefield recognition. They are removed when vehicles are permanently released from the jurisdiction of the same commander.
- Ground-to-air recognition markings — red and yellow fluorescent panels, approximately 6 feet by 2 feet 3 inches (1.80 meters by 0.68 meters), equipped with tie cords. Panels are draped on vehicles in a standard, unchanging pattern that differs from displays prescribed for other recognition purposes (frontlines, targets, and so forth). Theater commanders prescribe the arrangement of panels and conditions under which they will be used.
- Special-purpose vehicle identification:

  — Military police and other traffic control vehicles — prescribed markings placed front and rear.

  — Ambulances and other vehicles used exclusively for medical purposes — marked according to Geneva convention rules with a red cross or crescent on a square white background

WWW.SURVIVALEBOOKS.COM

painted on side body panels, body roof, cab roof, and rear doors or panel.

– Bomb disposal unit vehicles – all fenders painted red.

• Red flag — indicates danger.

• Priority-vehicle markings — equilateral triangles with red borders and symbols on white backgrounds placed on the front and rear of a vehicle. The commander may mark any vehicle which has priority over all other vehicles. Examples of priority vehicles are those carrying special liaison officers, priority dispatches, and damage-assessment personnel. A single priority sign may be used if visible from both front and rear. The sign should be as large as the vehicle's dimensions permit. The symbol inside the triangle identifies the authorizing commander. Priority signs must be removable to avoid misuse. They are used only on direct orders of the commander concerned. See Figure 3-21 for an example of a vehicle priority sign.




Figure 3-21. NATO vehicle priority sign

Geneva Convention Road Signs

The Geneva convention road signs discussed here were agreed to at the United States Conference on Road and Motor Transport in 1949. Although not military, these signs should be familiar to Army personnel, who will encounter them overseas.

Dimensions of the signs are standardized in each country for uniformity. In general, there are two sizes for each type of sign — standard and reduced. The reduced size is used where conditions preclude, or safety does not require, the standard size. In exceptional cases, a small sign may be used in built-up areas or to repeat the main sign.

Danger signs (Class I). Danger signs are red-bordered equilateral triangles with black or dark-colored symbols on white or yellow backgrounds. The triangles point upward except the "priority road ahead" sign, which points downward. The length of each standard side is not less than 0.9 meters (35.4 inches); of each reduced side, not less than 0.6 meters (23.6 inches). Overall height of signs is not more than 2.2 meters (86.6 inches) above ground. Away from built-up areas, signs are placed not less than 0.6 meters (23.6 inches) above ground. Signs are placed to be clearly visible without impeding pedestrians. See Figure 3-22 for examples of Class I signs.

Instructional signs (Class II). There are two types of instructional signs —prohibitory (Class II A) and mandatory (Class II B). Class II A signs are red-bordered circles with black or dark-colored symbols on a white or yellow background. Class II B signs are blue circles with white symbols. Standard size is at least 0.6 meters (23.6 inches) in diameter; reduced size, 0.4 meters (15.7 inches). Bottom of sign must be at least 0.6 meters (23.6 inches) above ground; top of sign must not be more than 2.2 meters (86.6 inches) above ground. Signs are placed close to the point where the requirement starts and at intervals along the route. See Figure 3-23 for examples of Class II signs.

WWW.SURVIVALEBOOKS.COM




Figure 3-22. Class I (danger) signs — Geneva convention

WWW.SURVIVALEBOOKS.COM




Figure 3-23. Class II (instructional) signs — Geneva convention

WWW.SURVIVALEBOOKS.COM

Informational signs (Class III). There are three types of informational signs — indication (Class III A), direction and advance direction (Class III B), and place identification (Class III C). Signs are usually rectangular. Colors may or may not be specified. If they are not specified, red may be used but is not the dominant color. See Figure 3-24 for examples of Class III signs.

Class III A. These signs are blue rectangles with variously colored symbols, except for priority-road signs. Priority-road signs are diamond-shaped, either white with black rims or yellow with dark rims. Standard size is at least 0.6 meters (23.6 inches) square; reduced size, 0.4 meters (15.7 inches). If signs are repeated within built-up areas, square size is 0.25 meters (9.8 inches). Class III A signs indicate parking, hospitals, first aid stations, telephones, service stations, and priority roads.

Class III B. These rectangular signs have either light backgrounds with dark symbols or dark backgrounds with light symbols. They are large enough to be easily understood by drivers in time for them to comply. Advance direction signs are placed from 100 to 250 meters (328 to 820 feet) from the intersection on normal roads. On special roads, such as concrete multilane roads, the distance is increased to 500 meters (1,640 feet). Direction signs are rectangular; the longer side is horizontal and ends in an arrowhead. Names of places lying in the direction of the arrow may be added to the sign. Figures indicating distances, if given, are inscribed between the name of the place and the arrowhead.

Class III C. These rectangular signs have light backgrounds with dark symbols or dark backgrounds with light symbols. The signs are placed with the long side horizontal. Their size and location are adequate for nighttime visibility. Class III C signs are placed before the beginning of built-up areas and at other points necessary to indicate place locations.




Figure 3-24. Class III (informational signs) — Geneva convention

WWW.SURVIVALEBOOKS.COM




Figure 3-24. Class III (informational signs) — Geneva convention (cont)

NATO Road Signs

To aid movement of NATO forces in any territory controlled by operational military command or national authority, member governments have adopted a standard system of military route signs. This system includes the signs prescribed by the Geneva convention as well as others not included in that group. There are three standard types of NATO road signs – hazard signs, regulatory signs, and guide signs. See Figure 3-25 for examples of standard NATO road signs.

Hazard signs. These diamond-shaped signs are yellow with black symbols. Hazard signs indicate traffic hazards and are used only in areas under military authority. A purely military sign not included in the international (Geneva convention) system or host country's system has a yellow background with the legend or symbol in black. If the sign is included in the international system or host country's system, the international or host country's sign is used on the same yellow background instead of the black symbol or legend.

Regulator signs. These square-shaped signs are black with white symbols except for bridge classification, stop signs, and signs of various shapes, used by the military to control civilians under specified conditions. Regulatory signs are used to regulate and control traffic and to define the light line. See STANAG 2010 for descriptions of regulatory signs.

Guide signs. These signs indicate locations, distances, directions, routes, and similar information:

- Route guide signs are rectangular with white symbols on black backgrounds. Signs are placed with the long side vertical. Odd numbers indicate axial routes; even numbers, lateral routes.

WWW.SURVIVALEBOOKS.COM

- Casualty evacuation route guide signs are either rectangular or cross-shaped with red symbols on white backgrounds.
- Detour signs are diamond-shaped with a white arrow (barred or not) on a blue background.
- Directional disks are circular, less than 0.41 meters (16 inches) in diameter, with a black arrow (barred or not) on a white background. Eight equally spaced holes around its circumference allow the disk to be nailed with the arrow pointing in any direction. Directional disks supplement other guide signs or major unit signs to indicate route direction. Battalions and lower units are not permitted to install directional disks.




Figure 3-25. Standard NATO road signs

WWW.SURVIVALEBOOKS.COM

NATO Warning Signs

Roads and areas within NATO nations containing contamination, minefield, booby traps, or unexploded bombs are marked with triangular signs according to STANAG 2002. See Figure 3-26 for examples.




Figure 3-26. NATO contaminated dangerous land area signs

Convoy Movement

A convoy is a group of at least 6 vehicles moving at the same time, or 10 vehicles moving within a l-hour period, under a single commander over the same route in the same direction. To aid in control, large columns may be broken down into serials; serials may be further broken down into march units. Each column and each organized element must include a —

- Commander, whose place in the column varies.
- Pacesetter in the first vehicle in the first element to lead the column and regulate its speed.
- Trail officer in the last vehicle of the last element to deal with problems that occur at the tail of the column.

Column identification. Each column is identified according to STANAG 2027 guidance; for example, a blue flag on leading vehicle, a green flag on last vehicle. When moving at night, the leading vehicle also shows a blue light and the last vehicle a green light. The column commander's vehicle displays a flag bisected by a diagonal line to form two triangles. The upper triangle is white; the lower is black. In areas where vehicles drive on the left side of the highway, the flags are mounted on the right side of the vehicle; otherwise, they are mounted on the left side.

Each column is identified by a number known as a "movement number," or "identification serial number," which is assigned at the same time as the movement credit by the authority organizing the movement. This number identifies the column during the entire movement. The number is placed on both sides and, if possible, on the front of all vehicles in the column to be clearly visible. The movement number is broken down into three parts:

- Two digits indicating the day of the month when movement is scheduled.
- Three or four letters indicating the organizing authority. First two letters are the national symbols shown in STANAG 1059.
- Two digits indicating the serial number assigned by the responsible authority.

WWW.SURVIVALEBOOKS.COM

For example, movement number 03-JSV-08 identifies column number 8, composed of V Corps vehicles, which will be moved by United States authority on the third day of the current month. The elements of a column may be identified by adding a letter behind the movement number.

Movement credit. A movement credit is the time allotted to one or more vehicles to move over a supervised, dispatch, or reserved route. Besides the allocation of a movement number or identification serial number, a movement credit indicates times at which the first and last vehicle of a column are scheduled to pass the entry and exit points. These are the points where the column enters and leaves the controlled route.

Movement Calculations

The three basic factors involved in march calculations are distance (D), rate (R), and time (T). When values are known for two factors, the unknown factor can be computed:

$$D = R \times T$$

$$R = \frac{D}{T}$$

$$T = \frac{D}{R}$$

Corresponding units of measure must be used throughout each calculation.

See Figure 3-27 for space and time factors used in the formulas. The length of any column or element of a column is the length of roadway which is occupied, measured from front to rear, inclusive. For planning purposes, the average length of one motor transport vehicle is 10 yards (about 9 meters).

March rate (R) can be calculated in yards per minute, meters per minute, miles in the hour, or kilometers in the hour.

$$R = \frac{D \text{ (length in yd)}}{T \text{ (pass time in min)}} = \text{yd/min}$$

$$= \frac{D \text{ (length in m)}}{T \text{ (pass time in min)}} = \text{m/min}$$

$$= \frac{D \text{ (road distance in mi)}}{T \text{ (time distance in hr)}} = \text{MIH}$$

$$= \frac{D \text{ (road distance in km)}}{T \text{ (time distance in hr)}} = \text{KIH}$$

Pass time, time lead, time gap, or time space (T) can be calculated in minutes or hours.

$$T = \frac{D \text{ (length in yd)}}{R \text{ (yd/min)}} = \text{pass time in min}$$

$$= \frac{D \text{ (length in m)}}{R \text{ (m/min)}} = \text{pass time in min}$$

$$= \frac{D \text{ (lead in yd)}}{R \text{ (yd/min)}} = \text{time lead in min}$$

$$= \frac{D \text{ (lead in m)}}{R \text{ (m/min)}} = \text{time lead in min}$$

$$= \frac{D \text{ (gap in yd)}}{R \text{ (yd/min)}} = \text{time gap in min}$$

$$= \frac{D \text{ (gap in min)}}{R \text{ (m/min)}} = \text{time gap in min}$$

$$= \frac{D \text{ (road space in mi)}}{R \text{ (MIH)}} = \text{time space in hr}$$

$$= \frac{D \text{ (road space in km)}}{R \text{ (KIH)}} = \text{time space in hr}$$

$$= \frac{D \text{ (road distance in mi)}}{R \text{ (MIH)}} = \text{pass time in h}$$

$$= \frac{D \text{ (road distance in km)}}{R \text{ (KIH)}} = \text{pass time in h}$$

Distance (D) (length, lead, gap, road space, or road distance), can be calculated in yards, meters, miles, or kilometers.

$$D = R \text{ (yd/min} \times T \text{ (pass time in min)} = \text{length in yd}$$

$$= R \text{ (m/min)} \times T \text{ (pass time in min)} = \text{length in m}$$

$$= R \text{ (yd/min)} \times T \text{ (time lead in min)} = \text{lead in yd}$$

$$= R \text{ (m/min)} \times T \text{ (time lead in min)} = \text{lead in m}$$

$$= R \text{ (yd/min)} \times T \text{ (time gap in min)} = \text{gap in yd}$$

$$= R \text{ (m/min)} \times T \text{ (time gap in min)} = \text{gap in m}$$

$$= R \text{ (MIH)} \times T \text{ (time space in hr)} = \text{road space in mi}$$

$$= R \text{ (KIH)} \times T \text{ (time space in hr)} = \text{road space in km}$$

$$= R \text{ (MIH)} \times T \text{ (time distance in hr)} = \text{road distance in mi}$$

$$= R \text{ (KIH)} \times T \text{ (time distance in hr)} = \text{road distance in km}$$

WWW.SURVIVALEBOOKS.COM




Figure 3-27. Space and time factors

WWW.SURVIVALEBOOKS.COM

Calculations for D, R, and T are plotted graphically in Figure 3-28. When the rate (MIH or KIH) is known, the time in minutes or the distance in miles or kilometers traveled can be quickly determined from the time-distance graph. For example, if a convoy moves at a rate of 15 MIH for 2 hours, the distance traveled can be determined by —

- Locating the oblique line marked 15 MIH.
- Locating the horizontal coordinate representing the 2 hours traveled.
- Determining the point at which these two lines intersect and reading the distance in miles from the bottom scale or kilometers from the top scale. For this example, the distance traveled would be 30 miles (48 km).




Figure 3-28. Time-distance graph

According to circumstances, the following conversion factors may be required:

Length + gap = lead

Pass time (time length) + time gap = time lead

Distance (mi) X 1,760 = distance (yards)

Distance (km) X 1,000 = distance (m)

Time (hr) X 60 = time (rein)

Rate (MIH) X 30 = approximate yards per min

Rate (KIH) X 17 = approximate meters per min

These factors are substituted in the basic formulas in these examples:

$$T\text{ (pass time in min)} = \frac{D\text{ (mi} \times 1{,}760)}{R\text{ (MIH} \times 30)} = \frac{D\text{ (yd)}}{R\text{ (yd/min)}}$$

WWW.SURVIVALEBOOKS.COM

$$= \frac{D\ (km \times 1{,}000)}{R\ (KIH \times 17)} = \frac{D\ (m)}{T\ (m/min)}$$

$$R\ (\text{speed in yd/min}) = \frac{D\ (mi \times 1{,}760)}{T\ (hr \times 60)} = \frac{D\ (yd)}{T\ (min)}$$

$$R\ (\text{speed in m/min}) = \frac{D\ (km \times 1{,}000)}{T\ (hr \times 60)} = \frac{D\ (m)}{T\ (min)}$$

Road Movement Graph

A road movement graph is a time-space diagram used to control foot and road marches and to prepare or check road movement tables. The graph helps the planner foresee possible conflicts and discrepancies in planning.

Road movement graphs may be used to indicate –

Position of mixed traffic on a route at a particular time.

Passing schedule of traffic elements at a particular time.

Conflicts between traffic elements at junctions, intersections, bridges, and defiles.

Deviations of columns from prescribed schedule.

Reverse directions of march, either by simultaneous turn of all column elements or by circling.

- Two-way traffic over a route and alternating traffic through defiles.
- Variations in actual running speeds.
- Changes in a route's traffic flow and traffic density.

Preparation. Preparation of a road movement graph begins with an analysis of the route on the map. Note important items, such as cities, towns, road junctions, and distances between major points. Select graph paper with enough squares to plot distance and time factors. Across the bottom coordinate, mark off time increments; on the vertical coordinate, distance increments.

If the origin, destination, march rate, and departure time of a movement are known, the head of the column can be plotted on the road movement graph. See Figure 3-29, Serial B, for an example. Assume that a unit is marching from Mount Royal (at the 25-mile mark on the vertical scale). The unit will leave at 0700 hours and proceed at 15 MIH to a point 5 miles beyond Tavistock, a distance of 60 miles. At 15 MIH, the trip will take 4 hours. Place a point at the intersection of the 25-mile coordinate and the 0700-hour coordinate. This point represents the place and hour of departure: Mount Royal at 0700 hours. Place a second point at the intersection of the 85-mile coordinate and the 1100-hour coordinate. This second point represents the destination and scheduled arrival time: location 5 miles past Tavistock at 1100 hours (0700 plus 4 hours).

Unless the unit is very small, it is usually desirable to show the schedule for the column tail as well as the head. After charting the schedule of the head, schedule the tail if the time length of the column is known or can be computed. Use the following formulas:

$$\text{road space (length)} = \frac{\text{number of vehicles}}{\text{density}} + \frac{\text{time gaps} \times \text{rate}}{60}$$

$$\text{pass time (time length)} = \frac{\text{road space} \times 60}{\text{rate}} + \text{EXTAL}$$

or

$$\text{time length} = \frac{\text{number of vehicles} \times 60}{\text{density} \times \text{rate}} + \text{time gaps} + \text{EXTAL}$$

where EXTAL (extra time allowance) is calculated as an additional 1-minute allowance for each 25 vehicles in a serial:

Number of Vehicles	EXTAL (min)
24 or less	0
25 - 37	1
38 - 62	2
63 - 87	3

Assume that the time length of Serial B, including extra time allowance, is 30 minutes. Draw a line from point representing the column's clearance at origin (0730 hours) to its arrival at destination (1130 hours) to represent the column tail's schedule past all points en route.

WWW.SURVIVALEBOOKS.COM




Figure 3-29. Road movement graph

WWW.SURVIVALEBOOKS.COM

To determine what time the column must start to complete the movement and arrive at the destination at a certain hour, reverse the above procedure.

Use. Use the road movement graph to find length of column, pass time (time length), rate of march, and other factors:

- Length of column — a vertical line connecting the head and tail lines, measured on the mile or kilometer scale. This line shows the planned length of the column at the prescribed rate of march at any hour during the movement, provided any extra time allowance is converted to distance and subtracted from the measurement.

Example: When the head of the column (Serial B, Figure 3-29) is at Stevens (the 45-mile mark of the vertical scale), the tail will be approximately at the 38-mile mark.

- Pass time (time length) — a horizontal line connecting the head and tail lines, measured on the hour scale. This line shows the planned pass time of the column as it passes any point on the road.

Example: If the head of Serial B arrives at Tavistock at 1040 hours, the tail will not clear that point until half an hour later at 1110 hours.

- Rate of march — a diagonal line intersecting any two vertical lines spanning a l-hour period. This line indicates the distance in that hour (rate of march).

Example: For Serial B, the diagonal line from 0700 to 0800 on the time scale spans a 15- mile distance on the mile scale. The rate of march, therefore, is 15 MIH. For Serial A, the rate is 20 MIH; for Serial C, 10 MIH.

- Halt time — halts are graphed to show if they are on or off the road. For graphing purposes a halt beside the road is classed as an on- road halt if it impedes the forward movment of other traffic.

Example: In Figure 3-30, Serial A is an on- road halt; Serial B, an off-road halt.

Multiple movements. A number of serials or columns over the same route can be plotted on the road movement graph. The commander of a large unit or the highway regulation officer




Figure 3-30. On- and off-road halts

should be notified as each serial reaches or clears HRPs along the route of march. The commander can keep an accurate record on the road movement graph of each serial's location. Filling in the space between the lines representing the scheduled head and tail of each column with color or tape enables the headquarters to see each serial's location at a glance. This method is used to follow the progress of each movement and to correct situations which may cause congestion and delay. The method is especially useful should it be necessary to issue new orders.

Pencils, crayons, ink, or adhesive tape in different colors may be used to indicate various schedules, plot movements in progress, and show relative priority. For example, use black to outline the head and tail schedule. Fill in green for each serial's progress and red for failure to adhere to schedules.

See Figure 3-31 for the progress of serials which were shown scheduled in Figure 3-29. Note the changes and adjustments in schedules. This is what happened:

- Serial A — element went through as scheduled.

- Serial B — change in orders required that Serial B continue to Dundalk. The column head arrived at its new destination on schedule at noon.

WWW.SURVIVALEBOOKS.COM




Figure 3-31. Adjusted road movement graph

WWW.SURVIVALEBOOKS.COM

- Lateral movement — because of a change in orders for Serial B, the lateral movement was delayed outside McLean. After a noon halt, the movement crossed the route 3 hours behind its original schedule, not clearing until 1830 hours.

- Serial C — at 1200 hours it became obvious that if Serial C continued on schedule, it would conflict with the delayed lateral movement at about 1730 hours. Also, Serial C had lost priority because of Serial B's arrival at Dundalk with critically needed supplies. Therefore, Serial C was halted from 1200 to 1400 hours before continuing at a slower rate of march. At 1700 hours, Serial C halted again to let Serial D pass.

- Serial D (D-1, D-2, D-3) — all elements went through on schedule.

Traffic Density and Flow

Traffic density — vehicles per mile/kilometer (VPM/KPM) – is the average number of vehicles that occupy 1 mile or 1 kilometer of road space. VPM/VPK is based on an average vehicle length and a constant vehicle gap.

Traffic flow – vehicles per hour (VPH) – is the total vehicles which will pass a designated point in a given time, normally an hour. VPH is based on a constant operating speed, an average vehicle length, and a constant vehicle gap. With a constant vehicle gap, traffic flow increases as speed increases and decreases as speed decreases.

To find vehicle gap in yards, multiply the speedometer reading by the speedometer multiplier (SM). The speedometer multiplier is a whole number (1, 2, 3, or higher) determined by the commander, which signifies whether the distance between vehicles will be one, two, three, or more times the rate of speed. The choice of an SM is based on conditions (of the driver, the vehicle, the road, or combat). For example, with an SM of 2, vehicles traveling at 25 MPH would maintain a vehicle gap of 50 yards between them. Vehicle gap changes with speed. The column will close (gap decreases) as speed is reduced and will open (gap increases) as speed is increased.

Formulas. Determine any traffic density desired for dispersion or for maintaining maximum capacity of a route by selecting an appropriate vehicle gap and using the following formulas:

$$\frac{\text{1 mi (1,760 yd)}}{\text{veh gap (yd)} + \text{avg veh length (yd)}} = \text{VPM}$$

or

$$\frac{\text{1 km (1,000 m)}}{\text{veh gap (m)} + \text{avg veh length (m)}} = \text{VPK}$$

Example: If vehicles are dispersed every 100 yards (91 meters) and the average vehicle length is 10 yards (9 meters), then the traffic density is –

$$\frac{1{,}760}{100 + 10} = 16\ \text{VPM} \quad \text{or} \quad \frac{1{,}000}{91 + 9} = 10\ \text{VPK}$$

When the speed and SM are known, use the following formulas to find traffic density:

$$\frac{\text{1 mi (1,760 yd)}}{(\text{MPH} \times \text{SM}) + \text{avg veh length (yd)}} = \text{VPM}$$

or

$$\frac{\text{1 km (1,000 yd)}}{(\text{KPH} \times \text{SM}) + \text{avg veh length (m)}} = \text{VPK}$$

Example: If the speed of a colunn is 20 MPH (32 KPH) with an SM of 2, the traffic density is —

$$\frac{1{,}760}{(20 \times 2) + 10} = 35.2 = 35\ \text{VPM}$$

or

$$\frac{1{,}000}{(32 \times 2) + 9} = 13.69 = 14\ \text{VPK}$$


At a constant speed, traffic density can also be determined by counting the number of vehicles passing a given point in a period of time. Use the following formulas:

$$\frac{\text{VPH passing point}}{\text{MPH}} = \text{VPM}$$

or

$$\frac{\text{VPH passing point}}{\text{KPH}} = \text{VPK}$$

WWW.SURVIVALEBOOKS.COM



WWW.SURVIVALEBOOKS.COM

Example: If 500 vehicles pass a given point in 1/2 hour at 20 MPH (32 KPH), traffic density is –

500 vehicles per 1/2 hour = 1,000 VPH

$$\frac{1{,}000}{20} = 50 \text{ VPM}$$

or

$$\frac{1{,}000}{32} = 31.25 = 31 \text{ VPK}$$

Use the following formula to find traffic flow:

$$\frac{\text{MPH} \times 1{,}760 \text{ yd}}{\text{veh lead (yd)}} = \frac{\text{yd per hr}}{\text{veh lead (yd)}} = \text{VPH}$$

where veh lead = distance in yards of vehicle gap and vehicle

Example: For a convoy moving at 30 MPH, the individual vehicle length is 10 yards and the vehicle gap is 20 yards.

$$\frac{30 \times 1{,}760}{10 + 20} = 1{,}760 \text{ VPH}$$

Density-flow graph. Use the graph in Figure 3-32 as a convenient means to determine traffic density and traffic flow for movements at various speeds and gaps. The planner must know the vehicle gap and operating speed for the particular operation. The planner should then –

- Read across the bottom scale to the column indicating the appropriate vehicle gap.
- Read up the vehicle gap column to the block opposite the appropriate speed. The block at the intersection of these coordinates contains two figures separated by a diagonal line. The upper figure is the traffic density for the operation in VPM; the lower figure, the traffic flow in VPH.

The following examples illustrate how to use the traffic density and flow graph.

Example 1: Assume that a convoy is to move over a road with a vehicle gap of 40 yards at a speed of 25 MPH. Read across the bottom scale (vehicle gap) to the 40-yard column. Then read up the column to where it intersects the horizontal coordinate for 25 MPH. The box at that point reads —



Traffic density (VPM of roadway) for this operation is 35; traffic flow (VPH past a given point) is 875.

When vehicle gap and speed are in meters and kilometers, the traffic density figure on the chart must be converted from VPM to VPK. To convert to VPK, multiply the figure shown on the chart by 0.62. No adjustment is needed for traffic flow since it is based on a constant factor of 1 hour at a given point along the route.

Example 2: Assume that a convoy is to move over a road at 32 KPH with a vehicle gap of 32 meters. Read across the bottom scale (vehicle gap) to the 32-meter column. Then read up the column until it intersects the horizontal coordinate of 32 KMH. The box at that point reads —



Traffic density for this move is 39 VPM. To convert to VPK, multiply VPM by 0.62:

39 X 0.62 = 24.18 or 24 VPK. VPH is 780.

No adjustment is needed for this figure.

The traffic density and flow graph in Figure 3-32 has other applications. For example, the planner/operator can use the graph to determine vehicle gaps and operating speeds compatible with restrictions imposed on an operation. Instructions from higher headquarters or operating conditions may limit the number of VPH arriving at a designated point (a critical road junction, a river crossing point, or a loading/unloading point). Or the VPM on a certain route may be restricted. Correlate these restrictive figures with the values in the graph to determine suitable operating gaps and speeds.

Example 3: Assume that higher headquarters has ordered that forward-moving traffic passing a critical point on a route be kept to no more than 400 VPH. This traffic flow must

WWW.SURVIVALEBOOKS.COM

be maintained as nearly as possible. Scan the traffic flow figures on the graph. There are several speed-gap combinations which will meet the restriction:

- 10 MPH at a 35-yard vehicle gap — 390 VPH.
- 15 MPH at a 60-yard vehicle gap — 375 VPH.
- 20 MPH at an 80-yard vehicle gap — 400 VPH.
- 25 MPH at a 100-yard vehicle gap — 400 VPH.

Example 4: Assume that higher headquarters orders traffic density over a given route be kept to no more than 30 VPM and no less than 25 VPM. This density must be maintained as nearly as possible. Scan the traffic density figures on the table. There are a number of vehicle gaps which will meet this restriction:

- At 50 yards — 29 VPM.
- At 5 yards — 27 VPM.
- At 60 yards — 25 VPM.

Although the density flow graph is set up in speed increments of 5 MPH (8 KPH), traffic flows for intermediate speeds may be inferred. Divide the difference in traffic flow between two consecutive speeds by either 4 for MPH or 8 for KPH. Multiply the result by the difference in speed. Then add that result to the lesser traffic flow figure used. Round off any fraction of a vehicle to the next whole number.

Example 5: Assume that a planner/operator must determine traffic flow for a motor move at 23 MPH with a 50-yard vehicle gap. First, determine the difference between traffic flow at 20 MPH and 25 MPH for a vehicle gap of 50 yards:

$$\begin{array}{rl} & 725 \text{ (VPH at 25 MPH)} \\ - & 580 \text{ (VPH at 20 MPH)} \\ \hline & 145 \end{array}$$

Divide 145 by 5 (the numerical difference between 20 and 25 MPH) to determine the traffic flow for l-MPH increments between these speeds:

$$\frac{145}{5} = 29$$

Multiply 29 by 3 (the numerical difference between 20 and 23 MPH):

$$\begin{array}{rl} & 29 \\ \times & \underline{3} \\ & 87 \end{array}$$

Finally, add 87 to the traffic flow at 20 MPH to determine the traffic flow at 23 MPH:

$$\begin{array}{rl} & 580 \\ + & \underline{87} \\ & 667 \text{ VPH at 23 MPH} \end{array}$$

Example 6: Assume that a planner/operator must determine the traffic flow for a motor move at 45 KPH with a 64-meter vehicle gap. First, determine the difference between traffic flow at 40 KPH and 48 KPH for a vehicle gap of 64 meters:

$$\begin{array}{rl} & 660 \text{ (VPH at 48 KPH)} \\ - & 550 \text{ (VPH at 40 KPH)} \\ \hline & 110 \end{array}$$

Divide 110 by 8 (the numerical difference between 40 and 48 KPH) to determine the traffic flow for 1-KPH increments between these speeds:

$$\frac{110}{8} = 13.75$$

Multiply 13.75 by 5 (the numerical difference between 40 and 45 KPH):

$$\begin{array}{rl} & 13.75 \\ \times & \underline{5} \\ & 68.75 = 69 \end{array}$$

Finally, add 69 to the traffic flow at 40 KPH to determine the traffic flow at 45 KPH:

$$\begin{array}{rl} & 550 \\ + & \underline{69} \\ & 619 \text{ VPH at 45 KPH} \end{array}$$

Preparing for Vehicle Air Movement

Units which must be ready for immediate air movement should make preparations well in advance to avoid delays in loading vehicles on transporting aircraft. Essential items of information which should be known beforehand for each vehicle are –

- Weight with load.

WWW.SURVIVALEBOOKS.COM

- Dimensions.
- Center of balance (CB).

Weight and dimensions. TB 55-46-1 includes the weight and dimensions of almost all Army equipment. If TB 55-46-1 is not available but a scale is, weigh the item. If an item of equipment is too big to manhandle onto a scale, load it on a vehicle and weigh it on a vehicle scale. Make sure that scales are calibrated.

Center of balance. The center of balance of cargo items must be determined before the weight and balance of a loaded aircraft can be computed. The shipping agency is responsible for marking each item of cargo with the correct gross weight and a CB point. Mark all items measuring 10 feet or longer and those having a balance point other than at center. Mark vehicles with load-carrying capability to show an empty or loaded CB, whichever is appropriate. Items not marked according to these guidelines will not be accepted for airlift.

Determine weight and CB of a vehicle after all secondary loads are secured. Secondary loads are items of baggage or cargo transported in truck beds and trailers, which must be included in total vehicle weight. Nothing can be added to or removed from a vehicle that has been weighed without afterwards reweighing the vehicle.

To compute CB of a vehicle, multiply the weight of each axle by its distance from the reference datum line (RDL). This result is called the moment. Then divide the moment by the gross weight of the vehicle. The resulting CB figure is the number of inches measured aft from the RDL to the point where the vehicle will balance. See Figure 3-33 for an explanation of terms used in measuring and weighing vehicles. Compute CB to the nearest whole inch.

$$\frac{(W_1 \times D_1) + (W_2 \times D_2)}{\text{gross weight}} = CB$$

where W_1 = front axle weight

W_2 = rear axle weight

D_1 = distance from RDL to front axle

D_2 = distance from RDL to rear axle

- RDL (reference datum line) — predetermined point from which all measurements are taken.
- FOH (front overhang) — distance in inches from front bumper to center of front axle.
- WB (wheelbase) — distance in inches from center of front axle to center of rear axle or center of tandem axles.
- ROH (rear overhang) — distance from rear or center of tandem axles to rear bumper.
- FAW (front axle weight in pounds).
- RAW (rear axle weight in pounds).
- MOMENT — the product obtained by multiplying the weight at a given point by its distance in inches from the RDL.




Figure 3-33. Weight and measurement points

After computing CB, mark both sides of the vehicle with masking tape to form a "T" shape. Use a grease pencil or magic marker to write the gross weight in the crossbar of the "T." Write the letters "CB" in the vertical bar to mark exact CB position. Mark axle weights above each axle.

WWW.SURVIVALEBOOKS.COM





Figure 3-34. Center of balance marker


The following examples illustrate methods to determine weight and CB of typical cargo. The examples include single-axle, multiaxle, and tracked vehicles and skid-mounted cargo.

EXAMPLE 1 — vehicles:

STEP 1. Determine front and rear axle weights.



STEP 2. Determine distance from front and rear axles to the RDL.



STEP 3. Enter the weights and distances into the CB formula:


$$\frac{(5{,}000 \times 60) + (10{,}000 \times 180)}{15{,}000} =$$

$$\frac{300{,}000 + 1{,}800{,}000}{15{,}000} =$$

STEP 4. Divide the total moment by the gross weight.

$$\frac{2{,}100{,}000}{15{,}000} = 140 \text{ inches}$$


The CB of the vehicle measured from the front end (RDL) is 140 inches.



EXAMPLE 2 — trailers:


When using the formula to compute CB of a trailer, consider the tongue to be the front axle; consider the actual axle to be the rear axle.

STEP 1. Weigh tongue and axle.



STEP 2. Measure the distance from the end of the tongue to the center of the axle.

WWW.SURVIVALEBOOKS.COM




STEP 3. Enter the weights and distances into the formula.

$$\frac{(150 \times 1) + (3{,}600 \times 80)}{3{,}750} =$$


$$\frac{150 + 288{,}000}{3{,}750} = \frac{288{,}150}{3{,}750} = 76.84$$

The CB of the trailer measured from the tongue (RDL) is 77 inches.




EXAMPLE 3 — multiaxle vehicles:

STEP 1. Determine all axle weights.



STEP 2. Determine distance from each axle to the RDL.



STEP 3. Enter the weights and distances into the formula.


$$\frac{(3{,}000 \times 24) + (5{,}300 \times 104) + (2{,}400 \times 184)}{10{,}700}$$

$$= \frac{72{,}000 + 551{,}200 + 441{,}600}{10{,}700} = \frac{1{,}064{,}800}{10{,}700}$$

STEP 4. Divide the total moment by the gross weight.

$$\frac{1{,}064{,}800}{10{,}700} = 99.5 \text{ inches}$$


The CB of the vehicle measured from the front end (RDL) is 100 inches.




EXAMPLE 4 — tracked vehicles:

STEP 1. Weigh the vehicle on a platform scale (truck scale, coal yard scale) large enough to accommodate the entire vehicle. Record weight.

WWW.SURVIVALEBOOKS.COM




STEP 2. Drive the vehicle onto a wooden beam or pole until the vehicle tilts forward. Mark the CB and gross weight on the side of the vehicle at the point of tilt.




EXAMPLE 5 — skid-mounted cargo:

STEP 1. If the skid-mounted cargo will fit on the scale, weigh the whole load.




STEP 2. Place the load on a pipe and center it until it balances. Mark the CB at the balance point.




EXAMPLE 6 — skid-mounted cargo:


If the skid-mounted cargo is too large to fit on a scale at one time, use the CB formula. Consider the support braces between the skids to be axles.




STEP 1. Support the overhang at the same height as the scale with a block of wood.



WWW.SURVIVALEBOOKS.COM



STEP 2. Measure the distance from the RDL to the front and rear points of support (same as axles).




STEP 3. Enter the weights and distances into the formula.

$$\frac{(1{,}500 \times 50) + (2{,}050 \times 110)}{3{,}550} =$$

$$\frac{75{,}000 + 225{,}500}{3{,}550} =$$

$$\frac{300{,}500}{3{,}550} = 84.6 \text{ inches}$$

The CB of the cargo measured from the RDL is 85 inches.



Section II. MOTOR TRANSPORT DATA

The following data provides the motor transport planner with vehicle characteristics and capabilities. Other planning information includes statistics on safe vehicle distances, local and line-haul operations, and highway tonnage capabilities.

VEHICLE CHARACTERISTICS

Tables 3-4 through 3-17 list mechanical data on authorized motor transport vehicles. This information includes truck performance data; CB of single-unit trucks; and axle weights, dimensions, and capacities for prime movers and towed vehicles.

WWW.SURVIVALEBOOKS.COM

Table 3-4. Truck performance data

Vehicle	Payload (lb)	Maximum Grade (%) w/Towed Load	Maximum Grade (%) w/o Towed Load	Maximum Safe Speed (MPH)	Cruising Range (mi)	Towed Load Allowance (lb)	Fording Depth (in) w/o Kit	Fording Depth (in) w/Kit
Truck, utility, ¼-T, 4X4, M151	800	60	—	66	300	1,500	21	60
Truck, utility, ¼-T, 4X4, M151A1	800	75	—	65	300	1,500	21	60
Truck, cargo, 1¼-T, 4X4, M998	2,500	—	60	60	300	3,400	60	30
Truck, utility, ¾-T, 4X4, M1009	1,200	—	30	55	250	[1]3,000	20	—
Truck, cargo, 1¼-T, 6X6, M561	2,500	—	60	58	340	2,840	NA — swim cap	
Truck, cargo, 1¼-T, 4X4, M880	2,500	—	30	55	200	3,000	20	—
Truck, cargo, 1¼-T, 4X4, M881	2,500	—	30	55	200	3,000	20	—
Truck, cargo, 1¼-T, 4X4, M882	2,500	—	30	55	200	3,000	20	—
Truck, cargo, 1¼-T, 4X4, M883, w/comm shelter	[2]2,500	—	30	55	200	3,000	20	—
Truck, cargo, 1¼-T, 4X4, M884, w/comm shelter	[2]2,500	—	30	55	200	3,000	20	—
Truck, cargo, 1¼-T, 4X4, M885, w/comm shelter	[2]2,500	—	30	55	200	3,000	20	—
Truck, cargo, 1¼-T, 4X2, M890	[1]2,500	—	30	55	200	[1]3,000	20	—
Truck, cargo, 1¼-T, 4X2, M891	[1]2,500	—	30	55	200	[1]3,000	20	—
Truck, cargo, 1¼-T, 4X2, M892	[1]2,500	—	30	55	200	[1]3,000	20	—
Truck, cargo, 1¼-T, 4X4, M1008	2,900	—	30	55	250	3,000	20	—
Truck, cargo, 1¼-T, 4X4, M1028	3,600	—	30	55	250	3,000	20	—
Truck, cargo, 2½-T, 6X6, M35	5,000	46	63	58	300	6,000	30	72
Truck, cargo, 2½-T, 6X6, M35A1	5,000	45	60	56	320	6,000	30	72
Truck, cargo, 2½-T, 6X6, M35A2	5,000	45	60	56	275	6,000	30	72
Truck, cargo, 2½-T, 6X6, M35A2C	5,000	45	60	56	275	6,000	30	72
Truck, cargo, 2½-T, 6X6, M36A2	5,000	45	60	56	320	6,000	30	72
Truck, cargo, 2½-T, 6X6, M36C	5,000	45	63	58	300	6,000	30	72
Truck, tk, fuel-svc, 1,200-gal, 2½-T, M49A1C	[3]600 gal	45	60	56	320	6,000	30	72
Truck, tk, fuel-svc, 1,200-gal, 2½-T, M49A2C	[3]600 gal	45	60	56	300	6,000	30	72
Truck, tk, water-svc, 1,200-gal, 2½-T, 6X6, M50	[4]400 gal	47	63	58	300	6,000	30	72

WWW.SURVIVALEBOOKS.COM

Table 3-4. Truck performance data (cont)

Vehicle	Payload (lb)	Maximum Grade (%) w/Towed Load	Maximum Grade (%) w/o Towed Load	Maximum Safe Speed (MPH)	Cruising Range (mi)	Towed Load Allowance (lb)	Fording Depth (in) w/o Kit	Fording Depth (in) w/Kit
Truck, tk, water-svc, 1,200-gal, 2½-T, 6X6, M50A1	[4]400 gal	45	60	56	320	6,000	30	72
Truck, tk, water-svc, 1,200-gal, 2½-T, 6X6, M50A2	[4]400 gal	45	60	56	300	6,000	30	72
Truck, tk, water-svc, 1,200-gal, 2½-T, 6X6, M50A3	500 gal	45	60	56	300	6,000	30	72
Truck, dump, 2½-T, 6X6, M342A2	5,000	45	60	56	300	6,000	30	72
Truck, van, 2½-T, 6X6, M292A1	5,000	45	60	56	300	6,000	30	72
Truck, van, expansible, 2½-T, 6X6, M292A2	5,000	45	60	56	300	6,000	30	72
Truck, van, expansible, 2½-T, 6X6, M292A5	5,000	45	60	56	300	6,000	30	72
Truck, trac, 2½-T, 6X6, M275A1	[5]7,000	36	60	56	275	[6]17,000	30	72
Truck, trac, 2½-T, 6X6, M275A2	[5]7,000	36	60	56	275	[6]17,000	30	72
Truck, van, shop, 2½-T, 6X6, M109A2	5,000	45	60	56	300	6,000	30	72
Truck, van, shop, 2½-T, 6X6, M109A3	5,000	45	60	56	300	6,000	30	72
Truck, dump, 5-T, 6X6, M51A2	10,000	47	60	54	447	15,000	30	78
Truck, dump, 5-T, 6X6, M51A1	10,000	47	60	54	447	15,000	30	78
Truck, dump, 5-T, 6X6, M51	10,000	47	70	52	488	15,000	30	78
Truck, dump, 5-T, 6X6, M929	10,000	31	61	54	300	15,000	30	78
Truck, dump, 5-T, 6X6, M930	10,000	31	61	54	300	15,000	30	78
Truck, trac, 5-T, 6X6, M52	[5]15,000	28	68	53	300	[6]37,500	30	78
Truck, trac, 5-T, 6X6, M52A1	[5]15,000	47	60	54	477	[6]37,500	30	78
Truck, trac, 5-T, 6X6, M52A2	[5]15,000	47	60	54	477	[6]37,500	30	78
Truck, trac, 5-T, 6X6, M931	[57]15,000	31	60	54	400	[67]37,500	30	78
Truck, trac, 5-T, 8X8, M757	[5]10,000	20	60	50	310	32,000	40	—
Truck, trac, 5-T, 6X6, M818	[57]15,000	42	60	52	300	[67]37,500	30	78
Truck, trac, 5-T, 6X6, M932	[57]15,000	31	60	54	400	[67]37,500	30	78
Truck, cargo, 5-T, 6X6, M54	10,000	51	74	53	214	15,000	30	78
Truck, cargo, 5-T, 6X6, M54A1	10,000	47	60	54	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M54A1C	10,000	47	60	54	350	15,000	30	78

WWW.SURVIVALEBOOKS.COM

Table 3-4. Truck performance data (cont)

Vehicle	Payload (lb)	Maximum Grade (%) w/Towed Load	Maximum Grade (%) w/o Towed Load	Maximum Safe Speed (MPH)	Cruising Range (mi)	Towed Load Allowance (lb)	Fording Depth (in) w/o Kit	Fording Depth (in) w/Kit
Truck, cargo, 5-T, 6X6, M54A2	10,000	47	60	54	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M54A2C	10,000	47	60	54	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M656	10,000	20	60	50	310	13,000	NA — swim cap	
Truck, cargo, 5-T, 6X6, M55A2	10,000	47	60	54	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M55	10,000	47	60	54	220	15,000	30	78
Truck, cargo, 5-T, 6X6, M55A1	10,000	47	60	54	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M813	10,000	42	67	52	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M813A1	10,000	42	67	52	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M814	10,000	38	61	52	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M923	10,000	42	67	54	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M925	10,000	42	67	54	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M927	10,000	38	60	54	350	15,000	30	78
Truck, cargo, 5-T, 6X6, M928	10,000	38	60	54	350	15,000	30	78
Truck, wkr, 5-T, 6X6, M62	7,000	36	58	53	214	20,000	30	78
Truck, wkr, 5-T, 6X6, M936	7,000	31	46	54	500	20,000	30	78
Truck, van, expansible, 5-T, 6X6, M291A1	5,000	—	60	58	350	15,000	—	—
Truck, van, expansible, 5-T, 6X6, M291A1C	5,000	—	60	58	350	15,000	—	—
Truck, van, expansible, 5-T, 6X6, M291A1D	5,000	—	60	58	350	15,000	—	—
Truck, van, expansible, 5-T, 6X6, M291A2C	5,000	—	60	58	350	15,000	—	—
Truck, van, expansible, 5-T, 6X6, M934	5,000	41	65	54	300	15,000	30	78
Truck, van, expansible, 5-T, 6X6, M935	5,000	40	61	54	300	15,000	30	78
Truck, stake, 5-T, 6X6, M821	5,000	40	49	52	300	15,000	30	78
Truck, cargo, 8-T, 4X4, M520	16,000	27	60	30	300	20,000	NA — swim cap	
Truck, cargo, 8-T, 4X4, M877	16,000	27	60	30	300	20,000	NA — swim cap	
Truck, cargo, 10-T, 8X8, M977	22,000	30	60	55	300	[8]30,000	48	—
Truck, cargo, 10-T, 8X8, M985	22,000	30	60	55	300	30,000	48	—
Truck, trac, 10-T, 6X6, M916	[5]28,000	25	—	50	300	[6]76,980	20	—

WWW.SURVIVALEBOOKS.COM

Table 3-4. Truck performance data (cont)

Vehicle	Payload (lb)	Maximum Grade (%) w/Towed Load	Maximum Grade (%) w/o Towed Load	Maximum Safe Speed (MPH)	Cruising Range (mi)	Towed Load Allowance (lb)	Fording Depth (in) w/o Kit	Fording Depth (in) w/Kit
Truck, trac, 10-T, 8X6, M920	[5]44,730	25	—	50	300	[6]99,620	20	—
Truck, trac, 10-T, 6X6, M123A1C	[5]30,000	47	60	40	350	[6]80,000	78	30
Truck, trac, 10-T, 6X6, M123C	[5]30,000	52	60	42	260	[6]80,000	78	30
Truck, trac, 10-T, 6X6, M123D	[5]30,000	52	60	42	260	[6]80,000	78	30
Truck, trac, 14-T, 6X4, M915	[5]40,000	—	17	55	—	—	20	—
Truck, trac, 22½-T, 8X8, M746	[5]41,000	37	—	38	200	[6]137,000	48	—
Truck, trac, 22½-T, 8X6, M911	[5]48,000	20	—	43	173	[6]137,000	28	—

[1]Highway requirement only.
[2]Increased loads authorized for several specific S250 shelter payloads.
[3]1,200-gal capacity for cross-country authorized by DA waiver, subject to local commander's discretion.
[4]1,000-gal capacity for cross-country authorized by DA waiver, subject to local commander's discretion.
[5]Vertical loads on the fifth wheel only.
[6]Towed load is the total weight of the semitrailer and payload.
[7]Vehicles approved for use with M871 semitrailer carrying loads up to 44,800 lb.
[8]Reduced payload required for this towed load.

Table 3-5. Vehicle axle weights

Vehicle	Curb Weight (lb)						Gross Weight, Payload & Personnel (lb)					
	Axle Load w/Winch			Axle Load w/o Winch			Axle Load w/Winch			Axle Load w/o Winch		
	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total
Truck, cargo, 2½-T, 6X6, M34	5,900	6,280	12,180	5,400	6,370	11,770	6,320	11,210	17,530	5,830	11,290	17,120
Truck, cargo, 2½-T, 6X6, M35	5,810	7,070	12,880	5,310	7,150	12,460	6,250	11,970	18,220	5,761	12,050	17,811
Truck, cargo, 2½-T, 6X6, M35A1	6,580	7,320	13,900	5,980	7,420	13,400	7,470	16,830	24,300	6,970	16,820	23,790
Truck, cargo, 2½-T, 6X6, M35A2	6,340	7,290	13,630	5,700	7,530	13,230	6,600	16,930	23,530	5,990	17,040	23,030
Truck, cargo, 2½-T, 6X6, M35A2C	6,630	7,530	14,160	6,030	7,630	13,660	7,630	16,930	24,560	7,030	17,030	24,060
Truck, cargo, 2½-T, 6X6, M36A2	6,850	8,260	15,110	6,250	8,360	14,610	7,700	17,810	25,510	7,100	17,910	25,010
Truck, cargo, 2½-T, 6X6, M36C	6,140	9,100	15,240	5,640	9,190	14,830	6,750	13,840	20,590	6,150	14,030	20,180
Truck, cargo, 2½-T, 6X6, M211	5,740	7,840	13,580	5,300	7,870	13,170	6,070	12,870	18,940	5,630	12,890	18,520
Truck, tk, fuel-svc, 1,200-gal, 2½-T, 6X6, M49A1C	6,490	8,630	15,120	5,890	8,730	14,620	7,200	17,320	24,520	6,600	17,420	24,020
Truck, tk, fuel-svc, 1,200-gal, 2½-T, 6X6, M49A2C	6,260	8,180	14,440	5,070	8,540	13,610	7,480	16,200	23,680	6,680	16,270	22,950
Truck, tk, water, 1,000-gal, 2½-T, 6X6, M50	—	—	—	5,405	9,779	15,184	—	—	—	5,715	14,819	20,534
Truck, tk, water, 1,000-gal, 2½-T, 6X6, M50A1	6,550	8,070	14,620	5,950	8,170	14,120	7,370	15,650	23,020	6,770	15,750	22,520
Truck, tk, water, 1,000-gal, 2½-T, 6X6, M50A2	6,410	8,170	14,580	5,790	8,290	14,080	7,220	15,710	22,930	6,700	15,730	22,430
Truck, tk, water, 1,000-gal, 2½-T, 6X6, M50A3	6,260	8,180	14,440	5,070	8,540	13,610	7,480	16,200	23,680	6,680	16,270	22,950
Truck, wkr, 2½-T, 6X6, M60	—	—	—	6,880	17,080	23,960	—	—	—	7,250	20,570	27,820
Truck, van, shop, 2½-T, 6X6, M109	—	—	—	5,480	9,750	15,230	—	—	—	5,850	14,730	20,580
Truck, van, shop, 2½-T, 6X6, M109A2	6,550	8,980	15,530	5,950	9,080	15,030	7,110	16,320	23,430	6,510	16,420	22,930
Truck, van, shop, 2½-T, 6X6, M109A3	6,500	8,940	15,440	5,880	9,050	14,930	7,220	15,710	22,930	6,700	15,730	22,430
Truck, van, shop, 2½-T, 6X6, M220	—	—	—	5,300	9,780	15,080	—	—	—	5,690	14,740	20,430
Truck, repair, shop, van, 2½-T, 6X6, M185A3	—	—	—	5,980	10,820	16,800	—	—	—	6,290	15,910	22,200
Truck, van, expansible, 2½-T, 6X6 M292	—	—	—	7,490	13,110	20,600	—	—	—	8,080	17,870	25,950
Truck, van, expansible, 2½-T, 6X6 M292A1	—	—	—	8,050	13,160	21,210	—	—	—	8,640	17,970	26,610
Truck, van, expansible, 2½-T, 6X6 M292A2	—	—	—	8,050	13,160	21,210	—	—	—	8,640	17,970	26,610
Truck, van, expansible, 2½-T, 6X6 M292A5	—	—	—	7,520	15,410	22,930	—	—	—	8,110	20,220	28,330
Truck, trac, 2½-T, 6X6, M275A1	6,470	5,640	12,110	5,870	5,740	11,610	7,070	17,440	24,510	6,470	17,540	24,010

WWW.SURVIVALEBOOKS.COM

WWW.SURVIVALEBOOKS.COM

Table 3-5. Vehicle axle weights (cont)

Vehicle	Curb Weight (lb)						Gross Weight, Payload & Personnel (lb)					
	Axle Load w/Winch			Axle Load w/o Winch			Axle Load w/Winch			Axle Load w/o Winch		
	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total
Truck, trac, 2½-T, 6X6, M275A2	6,470	6,090	12,560	5,900	6,220	12,120	7,070	17,440	24,510	6,470	17,540	24,010
Truck, dump, 2½-T, 6X6, M342A2	6,920	8,580	15,500	6,560	8,440	15,000	6,950	18,490	25,440	6,800	18,200	25,000
Truck, cargo, 5-T, 6X6, M54	8,730	11,210	19,940	7,880	11,340	19,220	9,400	20,890	30,290	8,550	21,030	29,580
Truck, cargo, 5-T, 6X6, M54A1	8,730	11,210	19,940	7,880	11,340	19,220	9,400	20,890	30,290	8,550	21,030	29,580
Truck, cargo, 5-T, 6X6, M54A1C	8,730	11,210	19,940	7,880	11,340	19,220	9,400	20,890	30,290	8,550	21,030	29,580
Truck, cargo, 5-T, 6X6, M54A2	8,700	11,700	20,400	7,720	11,820	19,540	9,930	30,870	40,800	8,950	30,990	39,940
Truck, cargo, 5-T, 6X6, M54A2C	8,720	11,940	20,660	7,740	12,060	19,800	9,890	31,170	41,060	8,910	31,290	40,200
Truck, cargo, 5-T, 6X6, M55	9,000	15,060	24,060	8,150	15,200	23,350	9,180	24,880	34,060	—	—	—
Truck, cargo, 5-T, 6X6, M55A2	8,840	15,060	23,900	7,880	15,160	23,040	9,450	34,850	44,300	8,490	34,950	43,440
Truck, cargo, 5-T, 8X8, M656	12,200	5,100	17,300	10,500	5,650	16,150	13,480	14,220	27,700	11,660	14,890	26,550
Truck, cargo, 5-T, 6X6, M813	10,250	11,870	22,120	9,330	12,130	21,460	11,980	30,540	42,520	11,060	30,800	41,860
Truck, cargo, 5-T, 6X6, M813A1	10,250	11,890	22,140	9,340	12,140	21,480	11,980	30,560	42,540	11,060	30,820	41,880
Truck, cargo, 5-T, 6X6, M814	10,780	14,790	25,570	10,020	14,890	24,910	12,510	33,460	45,970	11,740	33,570	45,310
Truck, cargo, 5-T, 6X6, M923	—	—	—	9,630	11,910	21,540	—	—	—	10,360	31,906	42,266
Truck, cargo, 5-T, 6X6, M925	9,630	11,916	21,546	—	—	—	10,962	31,916	42,878	—	—	—
Truck, cargo, 5-T, 6X6, M927	—	—	—	10,158	14,828	24,986	—	—	—	11,884	33,502	45,386
Truck, cargo, 5-T, 6X6, M928	10,760	14,828	25,588	—	—	—	12,488	33,500	45,988	—	—	—
Truck, dump, 5-T, 6X6, M51	9,300	13,360	22,660	8,460	13,520	21,980	8,660	23,320	31,980	9,500	26,160	35,660
Truck, dump, 5-T, 6X6, M51A1	9,300	13,360	22,660	8,460	13,520	21,980	8,660	23,320	31,980	9,500	26,160	35,660
Truck, dump, 5-T, 6X6, M51A2	9,150	13,550	22,700	8,260	13,660	21,920	9,610	33,490	43,100	8,720	33,600	42,320
Truck, dump, 5-T, 6X6, M817	10,700	13,730	24,430	9,760	14,000	23,760	12,050	32,770	44,820	10,980	33,180	44,160
Truck, dump, 5-T, 6X6, M929	—	—	—	10,080	13,750	23,830	—	—	—	11,510	33,040	44,550
Truck, dump, 5-T, 6X6, M930	10,680	13,760	22,440	—	—	—	12,110	33,050	45,160	—	—	—
Truck, trac, 5-T, 6X6, M52	9,010	9,990	19,000	8,160	10,150	18,310	9,380	24,610	33,990	8,540	24,770	33,310
Truck, trac, 5-T, 6X6, M52A1	9,220	10,230	19,450	8,500	10,560	19,060	9,510	24,940	34,450	8,730	25,330	34,060
Truck, trac, 5-T, 6X6, M52A2	8,800	9,900	18,700	7,810	10,030	17,840	9,430	34,270	43,700	8,440	34,400	42,840
Truck, trac, 5-T, 6X6, M757	11,900	4,750	16,650	10,200	5,300	15,500	18,310	7,740	26,050	16,150	8,750	24,900
Truck, trac, 5-T, 6X6, M818	10,460	10,490	20,950	9,670	10,620	20,290	11,850	33,680	45,530	10,910	33,960	44,870
Truck, trac, 5-T, 6X6, M819	11,890	22,050	33,940	—	—	—	13,280	37,060	50,340	—	—	—
Truck, trac, 5-T, 6X6, M931	—	—	—	10,077	13,751	23,828	—	—	—	11,509	33,039	44,548
Truck, trac, 5-T, 6X6, M932	10,679	13,761	22,440	—	—	—	12,111	33,049	45,160	—	—	—
Truck, trac, wkr, 5-T, 6X6, M246	12,790	20,040	32,830	—	—	—	13,030	36,150	49,180	—	—	—
Truck, trac, wkr, 5-T, 6X6, M62	9,320	24,000	33,320	—	—	—	5,020	35,300	40,320	—	—	—

Table 3-5. Vehicle axle weights (cont)

Vehicle	Curb Weight (lb)						Gross Weight, Payload & Personnel (lb)					
	Axle Load w/Winch			Axle Load w/o Winch			Axle Load w/Winch			Axle Load w/o Winch		
	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total
Truck, wkr, 5-T, 6X6, M543A1	9,300	25,100	34,400	—	—	—	—	—	—	—	—	—
Truck, wkr, 5-T, 6X6, M543A2	9,300	25,100	34,400	—	—	—	—	—	—	—	—	—
Truck, wkr, 5-T, 6X6, M816	12,010	24,120	36,130	—	—	—	13,060	35,470	48,530	—	—	—
Truck, wkr, 5-T, 6X6, M936	11,990	24,150	36,140	—	—	—	13,060	35,470	48,530	—	—	—
Truck, van, expansible, 2½-T, 6X6, M292	—	—	—	7,490	13,120	20,610	—	—	—	8,090	17,870	25,960
Truck, van, expansible, 5-T, 6X6, M291A2	—	—	—	9,000	17,100	26,100	—	—	—	9,960	31,540	41,500
Truck, van, expansible, 5-T, 6X6, M820	—	—	—	9,580	17,920	27,500	—	—	—	10,880	32,020	42,900
Truck, van, expansible, 5-T, 6X6, M820A2	—	—	—	9,730	19,520	29,250	—	—	—	11,030	33,620	44,650
Truck, van, expansible, 5-T, 6X6, M934	—	—	—	9,560	17,960	27,520	—	—	—	10,860	32,060	42,920
Truck, van, expansible, 5-T, 6X6, M935	—	—	—	9,710	19,560	29,270	—	—	—	11,010	33,660	44,670
Truck, van, expansible, 8-T, 4X4, M520	17,360	7,240	24,600	24,270	7,410	31,680	21,460	19,110	40,570	40,240	19,280	59,520
Truck, van, expansible, 8-T, 4X4, M877	17,480	7,950	25,430	25,100	8,120	33,220	21,700	19,700	41,400	41,070	19,870	60,940
Truck, trac, 5-T, 6X6, M931	—	—	—	10,077	13,751	23,828	—	—	—	11,509	33,039	44,548
Truck, trac, 5-T, 6X6, M932	10,679	13,761	22,440	—	—	—	12,111	33,049	45,160	—	—	—
Truck, trac, wkr, 5-T, 6X6, M246	12,790	20,040	32,830	—	—	—	13,030	36,150	49,180	—	—	—
Truck, trac, wkr, 5-T, 6X6, M62	9,320	24,000	33,320	—	—	—	5,020	35,300	40,320	—	—	—
Truck, wkr, 5-T, 6X6, M543A1	9,300	25,100	34,400	—	—	—	—	—	—	—	—	—
Truck, wkr, 5-T, 6X6, M543A2	9,300	25,100	34,400	—	—	—	—	—	—	—	—	—
Truck, wkr, 5-T, 6X6, M816	12,010	24,120	36,130	—	—	—	13,060	35,470	48,530	—	—	—
Truck, wkr, 5-T, 6X6, M936	11,990	24,150	36,140	—	—	—	13,060	35,470	48,530	—	—	—
Truck, van, expansible, 2½-T, 6X6, M292	—	—	—	7,490	13,120	20,610	—	—	—	8,090	17,870	25,960
Truck, van, expansible, 5-T, 6X6, M291A2	—	—	—	9,000	17,100	26,100	—	—	—	9,960	31,540	41,500
Truck, van, expansible, 5-T, 6X6, M820	—	—	—	9,580	17,920	27,500	—	—	—	10,880	32,020	42,900
Truck, van, expansible, 5-T, 6X6, M820A2	—	—	—	9,730	19,520	29,250	—	—	—	11,030	33,620	44,650

WWW.SURVIVALEBOOKS.COM

WWW.SURVIVALEBOOKS.COM

Table 3-5. Vehicle axle weights (cont)

Vehicle	Curb Weight (lb)						Gross Weight, Payload & Personnel (lb)					
	Axle Load w/Winch			Axle Load w/o Winch			Axle Load w/Winch			Axle Load w/o Winch		
	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total
Truck, van, expansible, 5-T, 6X6, M934	—	—	—	9,560	17,960	27,520	—	—	—	10,860	32,060	42,920
Truck, van, expansible, 5-T, 6X6, M935	—	—	—	9,710	19,560	29,270	—	—	—	11,010	33,660	44,670
Truck, van, expansible, 8-T, 4X4, M520	17,360	7,240	24,600	24,270	7,410	31,680	21,460	19,110	40,570	40,240	19,280	59,520
Truck, van, expansible, 8-T, 4X4, M877	17,480	7,950	25,430	25,100	8,120	33,220	21,700	19,700	41,400	41,070	19,870	60,940
Truck, van, expansible, 10-T, 8X8, M977	20,930	17,240	38,170	20,430	16,840	37,270	27,740	32,430	60,170	27,240	32,030	59,270
Truck, van, expansible, 10-T, 8X8, M985	20,160	19,140	39,300	19,660	18,740	38,400	26,970	34,330	61,300	26,470	33,930	60,400
Truck, van, expansible, 10-T, 8X8, M983	24,220	14,750	38,970	23,730	14,340	38,070	24,220	26,750	50,970	23,730	26,340	50,070
Truck, trac, 10-T, 6X6, M123A1C	12,650	17,580	30,230	—	—	—	13,750	46,490	60,240	—	—	—
Truck, trac, 10-T, 6X6, M123C	12,650	17,580	30,230	—	—	—	13,750	46,490	60,240	—	—	—
Truck, trac, 10-T, 6X6, M123D	12,650	17,580	30,230	—	—	—	13,750	46,490	60,240	—	—	—
Truck, trac, 10-T, 6X6, M916	13,880	14,000	27,880	—	—	—	14,220	42,340	56,560	—	—	—
Truck, trac, 10-T, 8X6, M920	26,020	10,180	36,200	—	—	—	27,920	43,640	71,560	—	—	—
Truck, trac, 14-T, 8X4, M915	—	—	—	9,920	9,710	19,630	—	—	—	11,055	36,660	48,915
Truck, trac, 22½-T, 8X8, M746	29,320	19,530	48,850	—	—	—	37,130	52,570	89,700	—	—	88,000
Truck, trac, 22½-T, 8X8, M911	19,580	19,630	39,210	—	—	—	29,230	51,120	80,350	—	—	—
Stlr, stake, 6-T, 2-whl, M118A1	—	—	—	—	4,750	7,100	—	—	—	—	15,030	25,100
Stlr, van, 6-T, 2-whl, M119	—	—	—	—	4,920	7,180	—	—	—	—	14,160	23,380
Stlr, van, 6-T, 2-whl, M119A1	—	—	—	—	5,600	8,140	—	—	—	—	12,600	20,140
Stlr, van, shop, 6-T, 2-whl, M146	—	—	—	—	4,880	6,950	—	—	—	—	11,880	18,950
Stlr, van, shop, 6-T, 2-whl, M146F	—	—	—	—	4,880	6,950	—	—	—	—	11,880	18,950
Stlr, van, elct, 6-T, 2-whl, M373A2	—	—	—	—	6,040	9,430	—	—	—	—	12,540	21,430
Stlr, van, elct, 6-T, 2-whl, M348A2	—	—	—	—	5,090	9,810	—	—	—	—	12,930	21,810
Stlr, van, expansible, 6-T, 4-whl, M313	—	—	—	—	11,220	15,350	—	—	—	—	20,000	27,350
Stlr, van, stor, 6-T, 4-whl, M749	—	—	—	—	9,160	16,510	—	—	—	—	12,700	20,800
Stlr, van, stor, 6-T, 4-whl, M750	—	—	—	—	9,160	16,510	—	—	—	—	12,700	20,800
Stlr, stake, 6-T, 4-whl, M127	—	—	—	—	9,950	14,240	—	—	—	—	30,200	50,240
Stlr, stake, 12-T, 4-whl, M127A1	—	—	—	—	10,230	14,240	—	—	—	—	23,500	38,240

Table 3-5. Vehicle axle weights (cont)

Vehicle	Curb Weight (lb)						Gross Weight, Payload & Personnel (lb)					
	Axle Load w/Winch			Axle Load w/o Winch			Axle Load w/Winch			Axle Load w/o Winch		
	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total
Stlr, stake, 12-T, 4-whl, M127A1C	—	—	—	—	10,230	14,240	—	—	—	—	23,500	38,240
Stlr, stake, 12-T, 4-whl, M127A2C	—	—	—	—	10,080	13,840	—	—	—	—	23,930	37,840
Stlr, van, cargo, 12-T, 4-whl, M128A1C	—	—	—	—	10,800	15,600	—	—	—	—	24,000	39,600
Stlr, van, cargo, 12-T, 4-whl, M128A2C	—	—	—	—	10,600	15,220	—	—	—	—	24,570	39,220
Stlr, van, supply, 12-T, 4-whl, M129A1C	—	—	—	—	10,800	15,600	—	—	—	—	15,600	39,600
Stlr, van, supply, 12-T, 4-whl, M129A2C	—	—	—	—	10,700	15,400	—	—	—	—	24,670	39,400
Stlr, low-bed, wkr, 12-T, 4-whl, M269	—	—	—	—	10,520	14,200	—	—	—	—	28,040	38,200
Stlr, low-bed, wkr, 12-T, 4-whl, M269A1	—	—	—	—	10,520	14,200	—	—	—	—	28,040	38,200
Stlr, tk, fuel, 12-T, 4-whl, M967	—	—	—	—	9,720	14,040	—	—	—	—	29,220	39,840
Stlr, tk, fuel, 12-T, 4-whl, M969	—	—	—	—	10,980	16,060	—	—	—	—	30,780	41,860
Stlr, tk, fuel, 12-T, 4-whl, M970	—	—	—	—	11,490	16,810	—	—	—	—	30,900	42,610
Stlr, tk, fuel, 12-T, 4-whl, M131A2	—	—	—	—	8,900	12,400	—	—	—	—	26,200	42,900
Stlr, tk, fuel, 12-T, 4-whl, M131A4	—	—	—	—	9,470	12,900	—	—	—	—	29,520	48,150
Stlr, tk, fuel, 12-T, 4-whl, M131A4C	—	—	—	—	10,150	13,850	—	—	—	—	30,200	49,100
Stlr, tk, fuel, 12-T, 4-whl, M131A5	—	—	—	—	9,380	12,780	—	—	—	—	22,550	48,030
Stlr, low-bed, 22½-T, 4-whl, M871	—	—	—	—	10,220	15,900	—	—	—	—	35,320	60,700
Stlr, low-bed, 25-T, 4-whl, M172A1	—	—	—	—	10,850	15,500	—	—	—	—	40,850	65,500
Stlr, low-bed, 25-T, 4-whl, M172	—	—	—	—	10,850	15,500	—	—	—	—	40,850	65,500
Stlr, flat-bed, 34-T, 6-whl, M872	—	—	—	—	13,400	19,030	—	—	—	—	57,020	85,420
Stlr, low-bed, 40-T, 6-whl, M870	—	—	—	—	11,000	16,500	—	—	—	—	56,500	96,500
Stlr, low-bed, 55-T, 9-whl, M524E2	—	—	—	—	20,460	32,620	—	—	—	—	87,020	142,620
Stlr, tk, trans, 50-T, 8-whl, M15A2	—	—	—	—	28,520	41,790	—	—	—	—	81,890	141,790
Stlr, HET 60-T, 8-whl, M747	—	—	—	—	26,000	32,000	—	—	—	—	106,000	152,000
Trailer, cargo, ¼-T, 2-whl, M416	—	—	—	—	480	570	—	—	—	—	960	1,070
Trailer, cargo, ½-T, 2-whl, M416A1	—	—	—	—	540	670	—	—	—	—	1,020	1,170
Trailer, cargo, ¾-T, 2-whl, M101	—	—	—	—	1,240	1,340	—	—	—	—	2,670	2,840
Trailer, cargo, ¾-T, 2-whl, M101A1	—	—	—	—	1,220	1,340	—	—	—	—	2,640	2,840

WWW.SURVIVALEBOOKS.COM

Table 3-5. Vehicle axle weights (cont)

Vehicle	Curb Weight (lb)						Gross Weight, Payload & Personnel (lb)					
	Axle Load w/Winch			Axle Load w/o Winch			Axle Load w/Winch			Axle Load w/o Winch		
	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total	Front	Rear	Total
Trailer, ammo, 1½-T, 2-whl, M332	—	—	—	—	2,430	2,800	—	—	—	—	5,360	5,800
Trailer, cargo, 1½-T, 2-whl, M105A2	—	—	—	—	2,520	2,750	—	—	—	—	5,380	5,750
Trailer, tk, water, 1½-T, 2-whl, M107A1	—	—	—	—	2,010	2,280	—	—	—	—	5,340	5,610
Trailer, tk, water, 1½-T, 2-whl, M107A2	—	—	—	—	2,100	2,380	—	—	—	—	5,710	5,440
Trailer, tk, water, 1½-T, 2-whl, M149	—	—	—	—	2,260	2,500	—	—	—	—	5,570	5,830
Trailer, tk, water, 1½-T, 2-whl, M149A1	—	—	—	—	2,350	2,710	—	—	—	—	5,690	6,040
Trailer, tk, water, 1½-T, 2-whl, M149A2	—	—	—	—	2,400	2,730	—	—	—	—	5,730	6,060

WWW.SURVIVALEBOOKS.COM

WWW.SURVIVALEBOOKS.COM

Table 3-6. Center of balance: location on single-unit vehicles

Vehicle	CB Without Payload				CB With Evenly Distributed Payload			
	Location w/Winch		Location w/o Winch		Location w/Winch		Location w/o Winch	
	Above Ground (in)	Behind Front Axle CL (in)	Above Ground (in)	Behind Front Axle CL (in)	Above Ground (in)	Behind Front Axle CL (in)	Above Ground (in)	Behind Front Axle CL (in)
Truck, amb, 1¼-T, 4X4, M1010	—	—	36.4	66.0	—	—	—	—
Truck, cargo, 1¼-T, 4X4, M715	31.0	56.6	31.0	60.7	32.0	80.4	32.0	84.4
Truck, cargo, 1¼-T, 4X4, M725	—	—	39.0	71.0	—	—	42.0	84.0
Truck, cargo, 1¼-T, 4X4, M1008	—	—	30.5	57.6	—	—	—	80.5
Truck, cargo, 1¼-T, 4X4, M1028	—	—	30.5	54.9	—	—	—	83.9
Truck, cargo, 2½-T, 6X6, M35	37.7	77.0	37.5	81.0	48.0	97.0	48.0	100.0
Truck, cargo, 2½-T, 6X6, M35A1	38.0	81.0	38.0	85.5	46.0	110.0	46.5	113.0
Truck, cargo, 2½-T, 6X6, M35A2	38.0	82.0	38.7	86.5	47.7	100.2	47.0	104.0
Truck, cargo, 2½-T, 6X6, M35A2C	38.0	82.0	38.7	86.5	47.7	100.2	47.0	104.0
Truck, cargo, 2½-T, 6X6, M36A2	37.0	80.5	37.7	83.7	48.0	95.0	47.0	101.5
Truck, cargo, 2½-T, 6X6, M36C	34.7	95.0	34.3	98.5	43.0	110.0	42.6	113.5
Truck, cargo, 2½-T, 6X6, M211	37.0	89.0	37.0	89.0	49.0	106.0	49.0	106.0
Truck, cargo, 2½-T, 6X6, M135	38.0	85.0	38.0	88.0	48.0	102.0	48.0	105.0
Truck, tk, gas, 2½-T, 6X6, M49	41.1	90.2	41.0	94.0	49.8	105.8	50.0	109.0
Truck, tk, fuel-serv, 1,200-gal, 2½-T, 6X6, M49A1C	—	—	41.0	92.0	—	—	50.0	113.0
Truck, tk, fuel-serv, 1,200-gal, 2½-T, 6X6, M49A2C	40.5	87.0	41.0	91.5	44.0	93.0	44.5	97.0
Truck, tk, water, 1,000-gal, 2½-T, 6X6, M50	—	—	41.0	95.0	—	—	48.0	113.0
Truck, tk, water, 1,000-gal, 2½-T, 6X6, M50A1	41.0	85.0	41.0	89.0	50.0	105.0	50.0	109.0
Truck, tk, water, 1,000-gal, 2½-T, 6X6, M50A2	40.5	86.2	41.0	90.7	45.0	83.2	45.5	87.0
Truck, wkr, 2½-T, 6X6, M60	42.0	110.0	—	—	49.0	114.0	—	—
Truck, van, shop, 2½-T, 6X6, M109	—	—	41.2	102.0	—	—	54.0	113.5
Truck, van, shop, 2½-T, 6X6, M109A2	46.0	89.0	46.5	93.0	59	108.0	59.5	111.0
Truck, van, shop, 2½-T, 6X6, M109A3	46.0	89.2	46.5	93.5	54.5	101.5	55.5	104.5
Truck, van, repair shop, 2½-T, 6X6, M185A3	—	—	48.0	99.0	—	—	56.6	115.5
Truck, van, expansible, 2½-T, 6X6, M292A2	—	—	57.0	120.0	—	—	65.0	134.0
Truck, van, expansible, 2½-T, 6X6, M292A5	—	—	58.0	125.0	—	—	65.0	143.0
Truck, trac, 2½-T, 6X6, M275A1	38.0	66.0	38.0	70.0	—	102.0	—	105.0
Truck, trac, 2½-T, 6X6, M275A2	38.0	66.0	38.0	70.0	—	102.0	—	105.0
Truck, dump, 2½-T,6X6, M215	36.0	89.0	36.0	92.0	45.0	108.0	45.0	110.0
Truck, dump, 2½-T, 6X6, M342A2	40.0	85.5	40.5	84.5	45.0	102.0	45.2	101.7
Truck, cargo, 5-T, 6X6, M54	39.9	99.8	40.1	105.9	54.1	124.4	54.7	128.8
Truck, cargo, 5-T, 6X6, M54A2	40.0	103.0	40.5	108.0	54.0	135.0	54.5	139.0
Truck, cargo, 5-T, 6X6, M54A2C	40.0	104.0	40.5	109.0	54.0	136.0	54.5	140.0
Truck, cargo, 5-T, 6X6, M55	40.3	134.8	—	—	49.1	157.1	—	—
Truck, cargo, 5-T, 6X6, M55A2	40.5	135.5	40.0	141.5	55.0	170.2	54.5	173.0
Truck, cargo, 5-T, 8X8, M656	—	42.2	—	50.6	—	76.2	—	83.0
Truck, cargo, 5-T, 6X6, M813	38.1	96.1	38.5	101.2	60.0	128.5	60.5	131.7

WWW.SURVIVALEBOOKS.COM

Table 3-6. Center of balance: location on single-unit vehicles (cont)

Vehicle	CB Without Payload				CB With Evenly Distributed Payload			
	Location w/Winch		Location w/o Winch		Location w/Winch		Location w/o Winch	
	Above Ground (in)	Behind Front Axle CL (in)	Above Ground (in)	Behind Front Axle CL (in)	Above Ground (in)	Behind Front Axle CL (in)	Above Ground (in)	Behind Front Axle CL (in)
Truck, cargo, 5-T, 6X6, M813A1	38.1	96.1	38.5	101.2	60.0	128.5	60.5	131.7
Truck, cargo, 5-T, 6X6, M814	38.1	131.5	38.7	141.1	61.2	158.2	61.5	161.5
Truck, cargo, 5-T, 6X6, M923	—	—	38.6	101.2	—	—	60.5	131.7
Truck, cargo, 5-T, 6X6, M925	38.1	96.1	—	—	59.9	128.5	—	—
Truck, cargo, 5-T, 6X6, M927	—	—	38.7	141.1	—	—	61.6	161.5
Truck, cargo, 5-T, 6X6, M928	38.1	131.5	—	—	61.2	158.2	—	—
Truck, dump, 5-T, 6X6, M51	38.7	98.3	38.9	102.7	47.4	118.4	47.7	121.7
Truck, dump, 5-T, 6X6, M51A2	38.7	99.7	38.7	104.0	58.0	130.0	58.0	133.0
Truck, dump, 5-T, 6X6, M817	37.0	93.8	37.0	98.4	49.0	122.1	49.2	125.5
Truck, dump, 5-T, 6X6, M929	—	—	37.0	98.4	—	—	49.2	125.5
Truck, dump, 5-T, 6X6, M930	36.9	93.8	—	—	48.9	122.1	—	—
Truck, trac, 5-T, 6X6, M52	34.5	87.8	34.0	92.6	46.2	120.7	45.7	124.0
Truck, trac, 5-T, 6X6, M52A2	34.0	88.5	34.5	94.0	—	131.0	—	134.0
Truck, trac, 5-T, 8X8, M757	36.3	43.6	36.0	51.8	—	67.3	—	73.3
Truck, trac, 5-T, 6X6, M818	33.0	83.5	33.2	87.4	—	126.8	—	129.1
Truck, trac, wkr, 5-T, 6X6, M819	56.5	127.0	—	—	—	127.0	—	—
Truck, wkr, 5-T, 6X6, M62	—	124.5	—	—	—	156.4	—	—
Truck, wkr, 5-T, 6X6, M543A2	47.0	131.0	—	—	—	—	—	—
Truck, wkr, 5-T, 6X6, M816	43.2	125.1	—	—	—	165.2	—	—
Truck, wkr, 5-T, 6X6, M936	43.2	125.1	—	—	—	165.1	—	—
Truck, van, expansible, 5-T, 6X6, M291A2	—	—	56.2	141.0	—	—	64	163
Truck, van, expansible, 5-T, 6X6, M820	—	—	54.3	138.0	—	—	—	161.2
Truck, van, expansible, 5-T, 6X6, M820A1	—	—	54.3	138.0	—	—	—	161.2
Truck, van, expansible, 5-T, 6X6, M934	—	—	54.3	138.0	—	—	—	161.2
Truck, van, expansible, 5-T, 6X6, M935	—	—	55.5	148.5	—	—	—	169.7
Truck, cargo, 10-T, 8X8, M977	44.7	95.0	—	—	62.4	113.2	—	—
Truck, cargo, 10-T, 8X8, M985	45.3	100.7	—	—	67.4	117.6	—	—
Truck, trac, 10-T, 8X8, M983	43.0	59.7	—	—	—	—	—	—
Truck, trac, 10-T, 6X6, M916	43.7	94.7	—	—	—	—	—	—
Truck, trac, 10-T, 6X6, M920	41.2	107.0	—	—	—	—	—	—
Truck, wkr, 10-T, 8X8, M984	45.5	101.0	—	—	—	—	—	—
Truck, fuel, svc, 10-T, 8X8, M983	49.0	65.6	—	—	—	—	—	—
Truck, trac, 22½-T, 8X8, M746	51.0	62.7	—	—	—	—	—	—
Truck, trac, 22½-T, 8X8, M911	59.5	119.0	—	—	—	—	—	—
Truck, utility, ¾-T, 4X4, M1009	—	—	30.5	57.6	—	—	—	80.5

WWW.SURVIVALEBOOKS.COM

Table 3-7. Dimensions and loading capacity for cargo truck bodies

Vehicle Type	Cargo Deck Dimensions: Length (in)	Width (in)	Height Above Ground (in)	Cargo Body Loading Measurements: Under (in)	Bows (cu ft)	Top of Side Racks (in)	Top of Side Racks (cu ft)	Top of Steering Wheel (in)	Top of Steering Wheel (cu ft)
¼-ton:									
M37	78.0	64.0	35.2	54.0	1 2 3 134.8	35.4	1 2 84.3	29.3	1 2 66.7
M37B1	78.0	64.0	35.2	54.0	1 3 146.1	35.4	1 95.7	29.3	1 78.0
1¼-ton:									
M561	87.8	81.0	30.8	62.4	4 5 235.4	41.1	4 152.4	36.7	4 6 134.2
M715	92.8	64.0	36.5	55.5	7 8 182.0	38.5	7 129.0	22.8	7 78.4
M880	98.6	69.9	34.0	NA	NA	NA	NA	39.5	9 10 151.9
M881	98.6	69.9	34.0	NA	NA	NA	NA	39.5	9 10 151.9
M882	98.6	69.9	34.0	NA	NA	NA	NA	39.5	9 10 11 124.6
M883	98.6	69.9	34.0	NA	NA	NA	NA	39.5	9 10 151.9
M884	98.6	69.9	34.0	NA	NA	NA	NA	39.5	9 10 151.9
M885	98.6	69.9	34.0	NA	NA	NA	NA	39.5	9 10 12 151.9
M890	98.6	69.9	31.0	NA	NA	NA	NA	39.5	9 10 151.9
M891	98.6	69.9	31.0	NA	NA	NA	NA	39.5	9 10 151.9
M892	98.6	69.9	31.0	NA	NA	NA	NA	39.5	9 10 13 151.9
2½-ton:									
M34	147.0	80.0	44.0	60.0	14 15 389.0	36.5	(16)	38.0	14 245.9
M35	146.8	88.0	51.9	60.0	15 441.9	36.5	272.8	28.9	216.0
M35A1	146.8	88.0	51.9	60.0	15 441.9	36.5	272.8	28.9	216.0
M35A2	146.8	88.0	51.9	60.0	15 441.9	36.5	272.8	28.9	216.0
M35A2C	147.0	87.6	52.5	60.0	15 440.5	36.5	272.0	28.8	214.6
M36	210.0	88.0	51.8	71.8	17 759.3	36.4	389.2	28.7	306.9
M36A2	210.0	88.0	51.8	71.8	17 759.3	36.4	389.2	28.7	306.9
M135	147.0	80.0	44.5	60.0	15 18 391.0	36.4	18 237.7	35.3	18 229.5
M211	147.0	88.0	51.0	60.0	15 442.5	36.5	273.2	26.0	194.6
M602	147.0	88.0	53.0	60.5	15 446.3	36.5	273.2	27.9	208.8
5-ton:									
M41	165.0	88.0	49.2	60.0	19 20 21 446.2	36.5	(16)	38.8	19 20 275.0
M54	168.0	88.0	56.5	60.0	22 23 480.2	36.5	22 286.1	29.0	22 222.0
M54A1	168.0	88.0	56.5	60.0	22 23 480.2	36.5	22 286.1	29.0	22 222.0
M54A1C	168.0	88.0	55.5	60.0	22 23 482.5	36.5	22 287.5	30.0	22 231.7
M54A2	168.0	88.0	56.5	60.0	22 23 480.2	36.5	22 286.1	29.0	22 222.0
M54A2C	168.0	88.4	55.5	60.0	22 23 482.5	36.5	22 287.5	30.0	22 231.7
M55	244.0	88.0	56.3	61.3	24 751.5	36.5	453.5	28.0	360.3
M55A1	244.0	88.0	56.3	61.3	24 751.5	36.5	453.5	28.0	360.3
M55A2	244.0	88.0	56.2	61.3	24 751.5	36.5	453.5	28.0	360.3
M328A1	219.3	97.8	64.8	50.5	25 626.7	25	(25)	(25)	(25)
M656	181.0	88.0	56.8	60.0	23 546.0	27.0	248.8	(26)	(27)
M812A2	210.0	120.0	60.0	28 79.0	29 1,152.0	(28)	(29)	(28)	(29)
M813	168.0	88.3	56.8	57.2	24 30 468.0	36.5	30 298.8	29.3	30 237.0
M813A1	168.0	88.3	56.8	57.4	24 30 468.0	36.5	30 298.8	29.3	30 237.0
M814	243.8	87.8	57.3	60.0	24 733.0	36.3	449.6	31.3	387.5
M821	218.8	97.8	64.0	48.8	25 604.3	(25)	(25)	(25)	(25)
M923	168.0	88.3	56.8	57.4	24 30 468.0	36.5	30 298.8	29.3	30 237.0
M924	168.0	88.3	56.8	57.4	24 30 468.0	36.5	30 298.8	29.3	30 237.0
M925	168.0	88.3	56.8	57.4	24 30 468.0	36.5	30 298.8	29.3	30 237.0

WWW.SURVIVALEBOOKS.COM

Table 3-7. Dimensions and loading capacity for cargo truck bodies (cont)

Vehicle Type	Cargo Deck Dimensions			Cargo Body Loading Measurements					
	Length (in)	Width (in)	Height Above Ground (in)	Under (in)	Bows (cu ft)	Top of Side Racks (in)	Top of Side Racks (cu ft)	Top of Steering Wheel (in)	Top of Steering Wheel (cu ft)
5-ton: (cont)									
Bridge transporter	213.0	97.8	64.8	50.5	[25]608.7	(25)	(25)	(25)	(25)
8-ton:									
M520	197.5	97.8	43.3	88.5	23 [31]888.4	(32)	(16)	55.0	6 [31]520.9
M877	197.5	97.8	43.3	[28]88.5	19 [33]867.5	(32)	(16)	55.0	19 [33]500.0
10-ton:									
M125	180.0	96.0	68.0	62.0	34 [35]590.0	42.0	[34]398.1	23.8	[34]216.0
M125A1	180.0	96.0	68.0	62.0	34 [35]590.0	42.0	[34]398.1	23.8	[34]216.1
M977	216.0	90.0	65.0	[28]48.0	[36]540.0	(31)	(32)	[10]38.0	[10]427.5
M985	216.0	90.0	65.0	[28]48.0	[36]540.0	(32)	(16)	[10]38.0	[10]427.5

[1]Cubic capacity reduced 6.6 cubic feet for wheel wells.
[2]Cubic capacity reduced 11.3 cubic feet for spare tire and carrier in cargo body.
[3]Cubic capacity reduced 3.3 cubic feet for curve of bows.
[4]Cubic capacity reduced 16.8 cubic feet for wheel wells.
[5]Cubic capacity reduced 4.6 cubic feet for curve of bows.
[6]Top of hood is higher than steering wheel.
[7]Cubic capacity reduced 2.4 cubic feet for wheel wells.
[8]Cubic capacity reduced 3.9 cubic feet for curve of bows.
[9]Cubic capacity reduced 5.6 cubic feet for wheel wells.
[10]Height and cube measured to top of cab.
[11]Cubic capacity reduced 27.3 cubic feet for communication kit.
[12]Cubic capacity reduced 0.8 cubic feet for communications tie-down brackets.
[13]Cubic capacity reduced 40.1 cubic feet for communication kit.
[14]Cubic capacity reduced 12.7 cubic feet for wheel wells.
[15]Cubic capacity reduced 6.6 cubic feet for curve of bows.
[16]See top of Steering Wheel column for cube.
[17]Cubic capacity reduced 8.5 cubic feet for curve of bows.
[18]Cubic capacity reduced 10.7 cubic feet for wheel wells.
[19]Cubic capacity reduced 24.0 cubic feet for wheel wells.
[20]Cubic capacity reduced 27.0 cubic feet for spare tire and carrier in cargo body.
[21]Cubic capacity reduced 6.9 cubic feet for curve of bows.
[22]Cubic capacity reduced 26.1 cubic feet for spare tire and carrier in cargo body
[23]Cubic capacity reduced 7.0 cubic feet for curve of bows.
[24]Cubic capacity reduced 10.2 cubic feet for curve of bows.
[25]Height and cube measured to top of bulkhead.
[26]See Top of Side Racks column for height.
[27]See Top of Side racks column for cube.
[28]Height over spare tie.
[29]Cubic capacity over materials-handling crane mounted in body.
[30]Cubic capacity reduced 14.5 cubic feet for spare tire and carrier in cargo body.
[31]Cubic capacity reduced 93.8 cubic feet for wheel wells.
[32]See top of Steering Wheel column for height. Steering wheel is higher than side racks.
[33]Cubic capacity reduced by 20.0 cubic feet for crane in cargo body.
[34]Cubic capacity reduced 21.9 cubic feet for spare tire and carrier in cargo body.
[35]Cubic capacity reduced 7.5 cubic feet for curve of bows.
[36]Cube measured to top of spare tire.

WWW.SURVIVALEBOOKS.COM

Table 3-8. Dimensions and loading capacity for dump truck bodies

Vehicle Type	Cargo Deck Dimensions: Length (in)	Width (in)	Height Above Ground (in)	Cargo Body Loading Measurements: Top of Side Panels (in)	(cu ft)	Top of Steering Wheel (in)	(cu ft)	Top of Cab Shield (in)	(cu ft)
2½-ton:									
M47	108.0	70.0	54.0	24.5	[1]	27.0	[1]	48.5	212.2
M59	108.0	70.0	54.8	24.5	[1]	26.5	[1]	49.0	214.3
M215	108.0	70.0	52.0	24.5	[1]	26.5	[1]	56.0	245.0
M342A2	132.0	70.0	55.2	24.5	[1]	26.5	[1]	47.1	251.8
5-ton:									
M51	123.0	82.0	59.0	25.0	[1]	27.0	[1]	51.0	297.6
M51A1	123.0	82.0	59.0	25.0	[1]	27.0	[1]	51.0	297.6
M51A2	123.0	82.0	59.0	25.0	[1]	27.0	[1]	51.0	297.6
M817	124.8	81.9	59.0	25.0	[1]	27.1	[1]	51.8	306.3
M929	124.8	81.9	59.0	28.0	[1]	27.1	[1]	51.8	306.3
M930	124.8	81.9	59.0	25.0	[1]	27.1	[1]	51.8	306.3
20-ton:									
F5070	191.5	85.1	66.5	34.3	[2]	NA	[2]	58.8	[3,4]537.0
M917	216.0	84.0	68.0	31.0	[2]	NA	[2]	[2]	[3]753.6

[1]Removed cab shield stowed in dump body. See Top of Cab Shield column for cube.
[2]Cab shield cannot be removed. See Top of Cab Shield column for Cube.
[3]Cube capacity reduced 12.9 cubic feet for hoist doghouse in dump body.
[4]Cube capacity reduced 1.8 cubic feet for ribs in dump body.

Table 3-9. Dimensions and loading capacity for cargo trailer bodies

Vehicle Type	Cargo Deck Dimensions: Length (in)	Width (in)	Height Above Ground (in)	Cargo Body Loading Measurements: Under Bows (in)	(cu ft)	Top of Side Racks (in)	(cu ft)	Top of Side Panels (in)	(cu ft)
¼-ton:									
M100	71.5	37.8	24.5	NA	NA	NA	NA	18.0	[1]29.7
M416	72.0	41.3	26.0	NA	NA	NA	NA	18.0	[1]31.8
¾-ton:									
M101	94.8	65.3	31.7	49.0	[2,3]170.5	33.3	[2]114.6	18.3	[2]60.9
M101A1	94.8	65.3	31.7	49.0	[2,3]170.5	33.3	[2]114.6	18.3	[2]60.9
1½-ton:									
M104	110.0	74.0	38.3	59.3	[4,5]273.2	45.3	[4]207.7	18.0	[4]79.1
M104A1	110.0	74.0	38.3	59.3	[4,5]273.2	45.3	[4]207.7	18.0	[4]79.2
M105	109.8	74.0	37.0	60.0	[4,5]276.0	45.0	[4]205.0	18.0	[4]79.0
M105A1	109.8	74.0	37.0	60.0	[4,5]276.0	45.0	[4]205.9	18.0	[4]79.0
M105A2	109.8	74.0	37.0	60.0	[4,5]276.0	45.0	[4]205.9	18.0	[4]79.0

[1]Cubic capacity increased because top 4.5 inches of side panels are 46.0 inches wide.
[2]Cubic capacity reduced 4.6 cubic feet for wheel wells.
[3]Cubic capacity reduced 0.4 cubic feet for curve of bows.
[4]Cubic capacity reduced 5.6 cubic feet for wheel wells.
[5]Cubic capacity reduced 0.5 cubic feet for curve of bows.

WWW.SURVIVALEBOOKS.COM

Table 3-10. Dimensions and loading capacity for stake and platform semitrailer cargo bodies

Vehicle Type	Cargo Deck Dimensions			Cargo Body Loading Measurements	
	Length (in)	Width (in)	Height Above Ground (in)	Height (in)	Capacity (cu ft)
6-ton:					
M118	268.8	88.5	54.0	48.0	660.8
M118A1	268.8	88.5	54.0	48.0	660.8
12-ton:					
M127	335.8	88.8	60.6	47.8	824.8
M127A1	335.8	88.8	60.5	47.8	824.8
M127A1C	335.8	88.8	60.5	48.0	828.3
M127A2C	335.8	88.8	59.8	48.0	828.3
M270A1	459.8	84.0	51.8	48.8	1,090.7
22½-ton:					
M871	349.3	87.3	55.4	48.0	874.1
34-ton:					
M872	484.8	93.0	58.0	49.0	1,278.5
M872A1	484.8	93.0	58.0	49.0	1,278.5
M872A2	484.8	93.0	58.0	49.0	1,278.5
M872A3	484.8	93.0	58.0	49.0	1,278.5

Table 3-11. Dimensions and loading capacity for van semitrailer cargo bodies

Vehicle Type	Cargo Deck Dimensions			Cargo Body Loading Measurements	
	Length (in)	Width (in)	Height Above Ground (in)	Height (in)	Capacity (cu ft)
6-ton:					
M119	264.0	89.6	56.5	73.8	1,010.2
M119A1	264.0	89.6	56.5	73.8	1,010.2
M146	264.0	90.0	56.0	76.0	1,045.0
12-ton:					
M128	335.5	89.0	57.0	78.5	1,356.4
M128A1	333.5	89.0	57.0	78.5	1,356.4
M128A1C	336.0	89.0	60.0	78.5	1,358.4
M128A2C	337.5	89.5	60.0	78.5	1,372.2

WWW.SURVIVALEBOOKS.COM

Table 3-12. Shipping dimensions and cube for cargo trucks

Vehicle Type	Length (in)	Width (in)	Top of Side Racks Height (in)	Top of Side Racks Cube (cu ft)	Top of Steering Wheel Height (in)	Top of Steering Wheel Cube (cu ft)
¾-ton:						
M37	185.5	73.5	[1]70.6	[2]557.1	[1]64.5	[2]508.9
M37 WWN	190.3	73.5	[1]70.6	[2]571.5	[1]64.5	[2]522.1
M37B1	185.5	75.3	[1]70.6	[2]570.7	[1]64.5	[2]521.4
M37B1 WWN	190.3	75.3	[1]70.6	[2]585.5	[1]64.5	[2]534.9
1¼-ton:						
M561	226.3	85.3	[1]71.9	[2]803.2	1 [3]67.3	[2]754.0
M561 WWN	231.1	85.3	[1]71.9	[2]820.2	1 [3]67.5	[2]770.0
M715	210.3	85.3	[1]75.0	[2]778.6	[1]59.3	[2]615.6
M715 WWN	220.5	85.3	[1]75.0	[2]816.3	[1]59.3	[2]645.5
M880	218.5	79.8	NA	NA	[4]73.5	[4]741.6
M881	218.5	79.8	NA	NA	[4]73.5	[4]741.6
M882	218.5	81.3	NA	NA	[4]73.5	[4]755.6
M883	218.5	79.8	NA	NA	[4]73.5	[4]741.6
M884	218.5	79.8	NA	NA	[4]73.5	[4]741.6
M885	218.5	79.8	NA	NA	[4]73.5	[4]741.6
M890	218.5	79.8	NA	NA	[4]70.5	[4]711.4
M891	218.5	81.3	NA	NA	[4]70.5	[4]711.4
M892	218.5	81.3	NA	NA	[4]70.5	[4]725.7
2½-ton:						
M34	261.3	88.0	[1]80.5	(2 5)	[1]82.0	[2]1,091.2
M34 WWN	274.8	88.0	[1]80.5	(2 5)	[1]82.0	[2]1,147.5
M35	264.8	95.4	[1]88.4	[2]1,292.3	[1]80.8	[2]1,181.2
M35 WWN	278.5	95.4	[1]88.4	[2]1,359.2	[1]80.8	[2]1,242.3
M35A1	264.8	95.4	[1]88.4	[2]1,292.3	[1]80.8	[2]1,181.2
M35A1 WWN	278.5	95.4	[1]88.4	[1]1,359.2	[1]80.8	[2]1,242.3
M35A2	264.8	95.4	[1]88.4	[2]1,292.3	[1]80.8	[2]1,181.2
M35A2 WWN	278.5	95.4	[1]88.4	[2]1,359.2	[1]80.8	[2]1,242.3
M35A2C	264.5	97.5	[1]89.0	[2]1,328.2	[1]81.3	[2]1,213.3
M35A2C WWN	278.5	97.5	[1]89.0	[2]1,398.5	[1]81.3	[2]1,277.5
M36	329.0	95.1	[1]88.2	[2]1,597.0	[1]80.5	[2]1,457.6
M36 WWN	343.1	95.1	[1]88.2	[2]1,665.4	[1]80.5	[2]1,520.0
M36A2	329.0	95.1	[1]88.2	[2]1,597.0	[1]80.5	[2]1,457.6
M36A2 WWN	343.1	95.1	[1]88.2	[2]1,665.4	[1]80.5	[2]1,520.0
M135	266.8	88.0	[1]81.0	[2]1,100.6	[2]79.8	[2]1,084.2
M135 WWN	266.8	88.0	[1]81.0	[2]1,100.6	[1]79.8	[2]1,084.2
M211	267.5	96.5	[1]87.5	[2]1,307.1	[1]77.0	[2]1,150.3
M211 WWN	267.5	96.5	[1]87.5	[2]1,307.1	[1]77.0	[2]1,150.3
M602	264.3	95.3	[1]89.5	[2]1,304.6	[1]80.9	[2]1,179.2
M602 WWN	277.8	95.3	[1]89.5	[2]1,371.2	[1]80.9	[2]1,239.5
5-ton:						
M41	297.3	96.0	[1]85.7	(2 5)	[1]88.0	[2]1,453.5
M41 WWN	312.5	96.0	[1]85.7	(2 5)	[1]88.0	[2]1,527.8
M54	297.0	98.0	[1]93.0	[2]1,566.5	[1]85.5	[2]1,440.1
M54 WWN	313.5	98.0	[1]93.0	[2]1,653.5	[1]85.5	[2]1,520.1
M54A1	297.0	98.0	[1]93.0	[2]1,566.5	[1]85.5	[2]1,440.1

WWW.SURVIVALEBOOKS.COM

Table 3-12. Shipping dimensions and cube for cargo trucks (cont)

Vehicle Type	Length (in)	Width (in)	Top of Side Racks		Top of Steering Wheel	
			Height (in)	Cube (cu ft)	Height (in)	Cube (cu ft)
5-ton (cont):						
M54A1 WWN	313.5	98.0	[1]93.0	[2]1,653.5	[1]85.5	[2]1,520.1
M54A1C	297.8	98.5	[1]92.0	[2]1,561.7	[1]85.5	[2]1,451.4
M54A1C WWN	314.5	98.5	[1]92.0	[2]1,649.3	[1]85.5	[2]1,532.8
M54A2	297.0	98.0	[1]93.0	[2]1,566.6	[1]85.5	[2]1,440.1
M54A2 WWN	313.5	98.0	[1]93.0	[2]1,653.5	[1]85.5	[2]1,520.1
M54A2C	297.8	98.5	[1]92.0	[2]1,561.7	[1]85.5	[2]1,451.4
M54A2C WWN	314	98.5	[1]92.0	[2]1,649.3	[1]85.5	[2]1,532.8
M55	376.1	98.0	[1]92.8	[2]1,979.4	[1]85.3	[2]1,819.4
M55 WWN	389.0	98.0	[1]92.8	[2]2,047.3	[1]85.3	[2]1,881.8
M55A1	376.1	98.0	[1]92.8	[2]1,979.4	[1]85.3	[2]1,819.4
M55A1 WWN	389.0	98.0	[1]92.8	[2]2,047.3	[1]85.3	[2]1,881.8
M55A2	376.1	98.0	[1]92.8	[2]1,979.4	[1]85.3	[2]1,819.4
M55A2 WWN	389.0	98.0	[1]92.8	[2]2,047.3	[1]85.3	[2]1,881.8
M328A1	372.3	115.1	[1]115.3	[2 6]2,859.3	(1 6)	(2 6)
M656	278.5	95.5	[1]82.8	[2]1,274.4	(1 7)	(2 8)
M656 WWN	229.0	95.5	[1]82.8	[2]1,368.2	(1 7)	(2 8)
M812	398.5	124.0	[9]139.0	[9]3,974.8	(10)	(9)
M813	304.0	98.0	[1]93.3	[2]1,608.1	[1]86.1	[2]1,484.4
M813 WWN	319.5	98.0	[1]93.3	[2]1,690.6	[1]86.1	[2]1,560.1
M813A1	306.8	98.1	[1]93.3	[2]1,625.0	[1]86.1	[2]1,499.6
M813A1 WWN	322.3	98.1	[1]93.3	[2]1,707.1	[1]86.1	[2]1,575.3
M814	377.8	98.0	[1]93.5	[2]2,003.4	[1]88.5	[2]1,896.2
M814 WWN	395.4	98.0	[1]93.5	[2]2,067.7	[1]88.5	[2]1,984.6
M821 WWN	378.3	114.3	[16]112.8	[2 6]2,822.6	(1 6)	(2 6)
M923	313.1	97.5	[1]93.3	[2]1,648.2	86.1	1,521.1
M924	313.1	97.5	[1]93.3	[2]1,648.2	86.1	1,521.1
M925 WWN	326.3	97.5	[1]93.3	[2]1,717.4	86.1	1,585.2
M926 WWN	326.3	97.5	[1]93.3	[2]1,717.4	86.1	1,585.2
M927	389.0	97.5	[1]93.5	[2]2,052.2	90.6	1,988.6
M928 WWN	402.0	97.5	[1]93.5	[2]2,120.8	90.6	2,455.0
Bridge Transporter	372.3	115.1	[16]115.3	[2 6]2,859.3	(1 6)	(2 6)
8-ton:						
M520	381.5	108.6	(1 11)	(2 5)	1 [3]98.3	[23]2,356.9
M520 WWN	381.5	108.6	(1 11)	(2 5)	1 [3]98.3	2 [3]2,356.9
M877 WOWN	381.5	108.6	(1 11)	(2 5)	1 [3]98.3	2 [3]2,356.9
M877 WWN	381.5	108.6	(1 11)	(2 5)	1 [3]98.3	2 [3]2,356.9
10-ton:						
M125 WWN	318.5	114.0	[1]110.0	[2]2,311.3	[1]91.8	[2]1,928.9
M125A1 WWN	318.5	114.0	[1]110.0	[2]2,311.3	[1]91.8	[2]1,928.9
M977	396.3	96.0	(11)	(5)	[4]103.0	[4]2,267.7
M977 WWN	396.3	96.0	(11)	(5)	[4]103.0	[4]2,267.7
M985 WOWN	396.3	96.0	(11)	(5)	[4]103.0	[4]2,267.7
M985 WWN	396.3	96.0	(11)	(5)	[4]103.0	[4]2,267.7

[1]For height over bows or top of cab shield, use operational height of vehicle listed in TB 55-46-1.

[2]For shipping cube over side racks/bows and/or top of cab shield, use operational cube of vehicle listed in TB 55-46-1.

WWW.SURVIVALEBOOKS.COM

Table 3-12. Shipping dimensions and cube for cargo trucks (cont)

[3]Top of hood is higher than steering wheel.
[4]Height and cube measured to top of cab.
[5]See Top of Steering Wheel Column for cube.
[6]Height and cube measured to top of bulkhead.
[7]Side racks stowed in cargo body are higher than steering wheel. See Top of Side Racks column for height.
[8]See Top of Side Racks column for cube.
[9]Cube capacity over materials-handling crane mounted in body.
[10]Height over spare tie.
[11]Steering wheel is higher than side panels. See Top of Steering Wheel cplumn for height.

Table 3-13. Shipping dimensions and cube for dump trucks

Vehicle Type	Length (in)	Width (in)	Top of Steering Wheel Height (in)	Top of Steering Wheel Cube (cu ft)	Top of Side Panels Height (in)	Top of Side Panels Cube (cu ft)
2½-ton:						
M47	235.0	84.3	(1 2)	(3 4)	2 5 81.5	4 6 934.3
M47 WWN	248.5	84.3	(1 2)	(3 4)	2 5 81.5	4 6 988.0
M59	237.1	95.8	(1 2)	(3 4)	2 5 79.3	4 6 1,042.4
M59 WWN	249.5	95.8	(1 2)	(3 4)	2 5 79.3	4 6 1,096.9
M215	240.3	96.0	(1 2)	(3 4)	2 5 78.5	4 6 1,048.0
M215 WWN	240.3	96.0	(1 2)	(3 4)	2 5 78.5	4 6 1,048.0
M342A2	260.3	95.6	(1 2)	(3 4)	2 5 82.3	4 6 1,185.2
M342A2 WWN	273.0	95.6	(1 2)	(3 4)	2 5 82.3	4 6 1,243.0
5-ton:						
M51	266.0	97.8	(1 2)	(3 4)	2 5 88.8	4 6 1,336.9
M51 WWN	281.5	97.8	(1 2)	(3 4)	2 5 88.8	4 6 1,414.8
M51A1	266.0	97.8	(1 2)	(3 4)	2 5 88.8	4 6 1,336.9
M51A1 WWN	281.5	97.8	(1 2)	(3 4)	2 5 88.8	4 6 1,414.8
M51A2	266.0	97.8	(1 2)	(3 4)	2 5 88.8	4 6 1,336.9
M51A2 WWN	281.5	97.8	(1 2)	(3 4)	2 5 88.8	4 6 1,414.8
M817	273.3	98.0	(1 2)	(3 4)	2 5 91.0	4 6 1,410.5
M817 WWN	288.3	98.0	(1 2)	(3 4)	2 5 91.0	4 6 1,487.9
M929	273.0	97.5	(1 2)	(3 4)	2 5 90.6	4 6 1,395.5
M930 WWN	288.5	97.5	(1 2)	(3 4)	2 5 90.6	4 6 1,474.8
20-ton:						
F5070	312.8	102.1	(2)	(3 4)	2 5 125.0	4 6 2,310.2
M917	350.6	98.0	(2)	(3 4)	2 141.0	4 2,803.6

[1]Side panels stowed in cargo body are higher than steering wheel. See Top of Side Panels column for height.
[2]For height over bows or top of cab shield, use operational height of vehicle listed in TB 55-46-1.
[3]See Top of Side Panels column for cube.
[4]For shipping cube over side racks/bows and/or top of cab shield, use operational cube of vehicle listed in TB 55-46-1.
[5]Height of cab shield stowed in dump body.
[6]Cube with cab shield stowed in dump body.

WWW.SURVIVALEBOOKS.COM

Table 3-14. Shipping dimensions and cube for cargo trailers

Vehicle Type	Length (in)	Width (in)	Top of Side Racks Height (in)	Top of Side Racks Cube (cu ft)	Top of Side Panels Height (in)	Top of Side Panels Cube (cu ft)
¼-ton:						
M100	107.5	56.3	NA	NA	[1]42.5	[2]148.9
M416	108.5	61.5	NA	NA	[1]44.0	[2]169.9
¾-ton:						
M101	147.0	73.5	[1]65.0	[2]406.4	[1]50.0	[2]312.6
M101A1	147.0	73.5	[1]65.0	[2]406.4	[1]50.0	[2]312.6
1½-ton:						
M104	165.3	83.5	[1]83.6	[2]667.8	[1]56.3	[2]449.7
M104A1	165.3	83.5	[1]83.6	[2]667.8	[1]56.3	[2]449.7
M105	166.0	83.0	[1]82.0	[2]653.8	[1]55.0	[2]438.5
M105A1	166.0	83.0	[1]82.0	[2]653.8	[1]55.0	[2]438.5
M105A2	166.0	83.0	[1]82.0	[2]653.8	[1]55.0	[2]438.5

[1] For height over bows or top of cab shield, use operational height of vehicle listed in TB 55-46-1.

[2] For shipping cube over side racks/bows and/or top of cab shield, use operational cube of vehicle listed in TB 55-46-1.

Table 3-15. Shipping dimensions and cube for stake and platform semitrailers

Vehicle Type	Length (in)	Width (in)	Top of Side Racks Height (in)	Top of Side Racks Cube (cu ft)	Top of Cargo Floor Height (in)	Top of Cargo Floor Cube (cu ft)
6-ton:						
M118	281.0	95.8	102.0	1,589.0	54.0	NA
M118A1	281.0	95.8	102.0	1,589.0	54.0	NA
12-ton:						
M127	345.5	97.3	108.3	2,106.9	60.5	NA
M127A1	345.5	97.3	108.3	2,106.9	60.5	NA
M127A1C	348.3	98.0	108.5	2,143.2	60.5	NA
M127A2C	351.5	97.8	107.8	2,144.6	59.8	NA
22½-ton:						
M871	358.0	96.0	103.0	2,048.6	55.0	NA
34-ton:						
M872	489.5	96.0	106.1	2,885.3	58.0	NA
M872A1	489.5	96.0	106.1	2,885.3	58.0	NA
M872A2	489.5	96.0	106.1	2,885.3	58.0	NA
M872A3	489.5	96.0	106.1	2,885.3	58.0	NA

WWW.SURVIVALEBOOKS.COM

Table 3-16. Shipping dimensions and cube for van semitrailers

Vehicle Type	Length (in)	Width (in)	Top of Van	
			Height (in)	Cube (cu ft)
6-ton:				
M119	275.5	98.0	133.8	2,090.5
M119A1	275.5	98.0	133.8	2,090.5
M146	276.0	96.0	129.0	1,978.0
12-ton:				
M128	344.3	96.8	139.1	2,682.8
M128A1	345.5	96.8	140.0	2,709.4
M128A1C	349.5	98.3	142.5	2,833.2
M128A2C	346.3	98.3	145.3	2,862.4

Table 3-17. Shipping dimensions and cube for cargo carriers

Vehicle Type	Length (in)	Width (in)	Height Top of Side Panels (in)	Shipping Cube (cu ft)
1½-ton:				
M116	188.0	84.5	63.3	772.2
6-ton:				
M548	232.0	100.0	[1]76.8	[2] 1,031.1

[1]For height over bows or top of cab shield, use operational height of vehicle listed in TB 55-46-1.
[2]For shipping cube over side racks/bows and/or top of cab shield, use operational cube of vehicle listed in TB 55-46-1.

PLANNING STATISTICS

Tables 3-18 and 3-19 include average vehicle stopping distances, unit capabilities, and payload capacities for prime movers and towed vehicles.

See Table 3-18 for average values to use to determine safe vehicle gaps at various speeds on average, hard-surfaced roads. Since well-trained drivers can reduce the distance traveled during the perception and reaction periods, the planner should consider the physical condition and training of drivers for a particular operation. Keep in mind that rain, snow, or ice present special conditions. Braking distances are based on the assumption that vehicles are loaded and have good brakes, tires, and traction. The average values in Table 3-18 have been determined from the standpoint of safety only; the tactical situation may require larger or smaller gaps. In the absence of definite information, the rule of thumb method may be used for certain speeds to determine the gap between vehicles in a convoy: speedometer reading (MPH) X 2 = gap in yards (or speedometer reading (KPH) X 1.2 = gap in meters). Use this method only for speeds marked with an asterisk in Table 3-18.

WWW.SURVIVALEBOOKS.COM

Table 3-18. Average vehicle stopping distances

Speed			Average Distance							
			Perception		Reaction		Braking		Total[1]	
(MPH)	(KPH)	(ft/sec)	(ft)	(m)	(ft)	(m)	(ft)	(m)	(ft)	(m)
Passenger vehicles[2]:										
20*	32.2	29.3	22	6.7	22	6.7	25	7.6	69	21.0
25*	40.3	36.7	28	8.5	28	8.5	35	10.7	91	27.7
30*	48.3	44.0	33	10.0	33	10.0	48	14.6	114	34.6
35*	56.3	51.3	39	11.9	39	11.9	67	20.4	145	44.2
40*	64.4	58.7	44	13.4	44	13.4	90	27.4	178	54.2
45*	72.4	66.0	50	15.3	50	15.3	117	35.7	217	66.3
50*	80.5	73.4	55	16.8	55	16.8	148	45.2	258	78.8
55	88.5	80.7	61	18.6	61	18.6	185	56.4	307	93.6
60	96.6	88.0	66	20.1	66	20.1	228	69.6	360	109.8
65	104.6	95.4	72	21.9	72	21.9	275	83.9	419	127.7
70	112.6	102.7	77	23.5	77	23.5	332	102.5	486	149.5
Single-unit vehicles (gross weight less than 10,000 pounds):										
20*	32.2	29.3	22	6.7	22	6.7	30	9.2	74	22.6
25*	40.3	36.7	28	8.5	28	8.5	42	12.8	98	29.8
30*	43.3	44.0	33	10.0	33	10.0	58	17.7	124	37.7
35*	56.3	51.3	39	11.9	39	11.9	80	24.4	158	48.2
40*	64.4	58.7	44	13.4	44	13.4	106	31.4	194	58.2
45*	72.4	66.0	50	15.3	50	15.3	138	42.1	238	72.7
50	80.5	73.4	55	16.8	55	16.8	177	54.0	287	87.6
55	88.5	80.7	61	18.6	61	18.6	222	67.5	344	104.7
60	96.6	88.0	66	20.1	66	20.1	273	83.3	405	123.5
Single-unit, two-axle vehicles (gross weight 10,000 pounds or more):										
20*	32.2	29.3	22	6.7	22	6.7	40	12.2	84	25.6
25*	40.3	36.7	28	8.5	28	8.5	64	19.5	120	36.5
30	48.3	44.0	33	10.0	33	10.0	92	28.0	158	48.0
35	56.3	51.3	39	11.9	39	11.9	126	38.4	204	62.2
40	64.4	58.7	44	13.4	44	13.4	165	50.3	253	77.1
45	72.4	66.0	50	15.3	50	15.3	208	63.4	308	94.0
50	80.5	73.4	55	16.8	55	16.8	256	78.1	366	111.7
55	88.5	80.7	61	18.6	61	18.6	310	94.5	432	131.7
60	96.6	88.0	66	20.1	66	20.1	372	113.5	504	153.7
Single-unit, multiaxle vehicles and combination vehicle[3] (gross weight 10,000 pounds or more):										
20*	32.2	29.3	22	6.7	22	6.7	50	15.3	94	28.7
25	40.3	36.7	28	8.5	28	8.5	80	24.4	136	41.1
30	48.3	44.0	33	10.0	33	10.0	115	35.1	181	55.1
35	56.3	51.3	39	11.9	39	11.9	157	47.9	235	71.7
40	64.4	58.7	44	13.4	44	13.4	205	62.5	293	89.3
45	72.4	66.0	50	15.3	50	15.3	260	79.3	360	109.9
50	80.5	73.4	55	16.8	55	16.8	320	97.6	430	131.2
55	88.5	80.7	61	18.6	61	18.6	388	118.3	510	155.5
60	96.6	88.0	66	20.1	66	20.1	465	141.9	597	182.1

[1]Add 30 feet or 9 meters to each total stopping distance shown to determine actual gap to use between vehicles.
[2]Does not include buses. Refer to section with weights and axles corresponding to buses.
[3]Tractor trucks, semitrailers, and trailers.
*Rule of thumb method may be used at this speed.

WWW.SURVIVALEBOOKS.COM

Table 3-19. Motor transport units capabilities on surfaced roads

Unit	TOE	Equipment	Pieces Auth	Pieces Aval (75%)	Planning Figure And Unit	Local Hauls		Line-Hauls	
						Trips Per Day	Capacity Per Day	Trips Per Day	Capacity Per Day
Light truck company	55-17H510 (2 shifts)	2½-T cargo truck	60	45	4 STONs or 20 pax*	4	720 STONs or 3,600 pax	2	360 STONs or 1,400 pax (16 pax/veh)
	55-17H520 (2 shifts)	5-T cargo truck	60	45	6 STONs or 20 pax*	4	1,080 STONs or 3,600 pax	2	540 STONs or 1,620 pax (18 pax/veh)
	55-17H530 (1 shift)	2½-T cargo truck	60	45	4 STONs or 20 pax*	2	360 STONs or 1,800 pax	1	180 STONs or 720 pax (16 pax/veh)
	55-17H540 (1 shift)	5-T cargo truck	60	45	6 STONs or 20 pax*	2	540 STONs or 1,800 pax	1	270 STONs or 810 pax (18 pax/veh)
Medium truck company (container/ cargo)	55-18H610	5-T tractor (M915)	60	45	NA	NA	NA	NA	NA
		34-T semitrailer	120	90	22 STONs or 2 20-ft containers or 35 pax**	4	3,960 STONs or 360 20-ft containers or 6,300 pax	2	1,980 STONs or 180 20-ft containers or 3,150 pax
		or							
		12-T S&P semitrailer	120	90	12 STONs or 50 pax**	4	2,160 STONs 9,000 pax	2	1,080 STONs 4,500 pax
(POL)	55-18H620	5-T tractor (M915) w/5,000-gal fuel tank semitrailer	60	45	5,000 gal	4	900,000 gal	2	450,000 gal
(Refrigerator)	55-18H630	5-T tractor (M915) w/7½-ton refrigerator semitrailer	60	45	6 STONs	4	1,080 STONs	2	540 STONs
Medium truck company (container/ cargo, 40-foot)	55-18J410	14-T tractor (M915)	60	45	NA	NA	NA	NA	NA
		34-T semitrailer	120	45	2 20-ft containers or 22 STONs gen cargo or 50 pax**	4	360 20-ft containers or 3,960 STONs gen cargo or 9,000 pax	2	180 20-ft containers or 1,980 STONs gen cargo or 4,500 pax
(POL)	55-18J411	Collapsible fabric water tank, 4,750-gal	60	45	4,750 gal	4	855,000 gal	2	427,500 gal
Command transport company	55-19H210	¼-T truck (M1009)	40	30	¼ STON or 2 pax	2	45 STONs or 120 pax	1	22½ STONs
		1¼-T truck (M1008)	20	15	1¼ STONs or 9 pax	2	37½ STONs or 270 pax	1	18¾ STONs or 135 pax
Command transport company, airborne corps	55-19H220	¼-T truck (M1009)	30	22	¼ STON or 2 pax	2	33 STONs or 88 pax	1	16½ STONs or 44 pax
		1¼-T truck (M1008)	30	22	1¼ STONs or 9 pax	2	55 STONs or 396 pax	1	27½ STONs or 198 pax
Command transport company	55-19J310	¼-T truck (M1009)	40	30	¼ STON or 2 pax	2	45 STONs or 120 pax	1	22½ STONs or 60 pax
		1¼-T truck (M1008)	20	15	1¼ STONs or 9 pax		37½ STONs or 270 pax	1	18¾ STONs or 135 pax
Command transport company, airborne corps	55-19J320	¼-T truck (M1009)	20	15	¼ STON or 2 pax	2	22½ STONs or 60 pax	1	11¼ STONs or 30 pax
		1¼-T truck (HMMWV)	20	15	1¼ STONs or 9 pax		37½ STONs or 270 pax	1	18¾ STONs or 135 pax
Medium truck company	55-23J410	5-T tractor	60	45	NA	NA	NA	NA	NA
(container/ cargo, 20-foot)		22½-T semitrailer	150	112	15 STONs or 1 20-ft container	4	2,700 STONs or 180 20-ft containers	2	1,350 STONs

WWW.SURVIVALEBOOKS.COM

Table 3-19. Motor transport units capabilities on surfaced roads (cont)

Unit	TOE	Equipment	Pieces Auth	Pieces Aval (75%)	Planning Figure And Unit	Local Hauls		Line-Hauls	
						Trips Per Day	Capacity Per Day	Trips Per Day	Capacity Per Day
	55-23J411	Collapsible fabric water tank, 3,000-gal	60	45	3,000 gal	4	540,000 gal	2	270,000 gal
Cargo carrier (tracked)	55-27H510	6-T tracked cargo carrier	48	36	6 STONs	4	864 STONs	2	432 STONs
(POL)	55-27H511	6-T tracked cargo carrier, w/pump and tank unit	48	36	1,200 gal	4	172,800 gal	2	86,400 gal
Heavy truck company	55-28H510 (2 shifts)	Truck tractor (M911) HET, w/60-T low-bed semitrailer	24	18	1 tank or 40 STONs gen cargo	4	72 tanks or 2,880 STONs gen cargo	2	36 tanks or 1,440 STONs gen cargo
	55-28H520 (1 shift)	Truck tractor (M911), HET, w/60-T low-bed semitrailer	24	18	1 tank or 40 STONs gen cargo	2	36 tanks or 1,440 STONs gen cargo	1	18 tanks or 720 STONs gen cargo
Light-medium truck company	55-67H7	5-T cargo truck	60	45	6 STONs or 20 pax*	4	1,080 STONs or 3,600 pax	2	540 STONs or 1,620 pax (18 pax/veh)
		5-T truck tractor (M818)	10	7	NA	NA	NA	NA	NA
		22½-T semitrailer	20	14	1 container or 15 STONs or 35 pax**	4	28 containers or 420 STONs or 980 pax	2	14 containers or 210 STONs or 490 pax (18 pax/veh)
Light-medium truck company	55-67J4	5-T tractor (M818)	10	7	NA	NA	NA	NA	NA
		22½-T semitrailer	20	14	1 20-ft container or 15 STONs or 35 pax**	4	28 20-ft containers or 420 STONs or 980 pax	2	14 20-ft containers or 210 STONs or 490 pax (18 pax/veh)
		5-T cargo truck	50	37	6 STONs or 20 pax*	4	888 STONs or 2,960 pax	2	444 STONs or 1,480 pax
Transportation motor transport company, air assault division	55-69J0	5-T cargo truck	18	13	6 STONS or 20 pax*	2	156 STONs or 520 pax	1	78 STONs or 260 pax
		1½-T cargo trailer	18	13	1½ STONs	2	39 STONs	1	19½ STONs
		5-T tractor (M818) w/22½-T semitrailer or	8	6	1 container or 15 STONs or 35 pax**	2	12 containers or 30 STONs or 70 pax	1	6 containers or 15 STONs or 35 pax
		5-T tractor (M818) w/12-T S&P semitrailer (M127)	8	6	12 STONs or 50 pax	2	144 STONs or 600 pax	1	72 STONs or 300 pax
		10-T tractor w/ 25-T low-bed semitrailer	2	1	25 STONs	2	50 STONs	1	25 STONs
		5-T tractor w/ 5,000-gal fuel tank semitrailer	10	7	5,000 gal	2	70,000 gal	1	35,000 gal
		5-T cargo truck w/tank and pump unit w/1½-T cargo trailer w/ tank unit	2	1	1,800 gal	2	3,600 gal	1	1,800 gal
Transportation motor transport company, infantry division (mechanized)	55-84H0	5-T tractor w/ 5,000-gal fuel tank semitrailer	34	25	5,000 gal	2	250,000 gal	1	125,000 gal
		5-T tractor	10	7	NA	NA	NA	NA	NA

WWW.SURVIVALEBOOKS.COM

Table 3-19. Motor transport units capabilities on surfaced roads (cont)

Unit	TOE	Equipment	Pieces Auth	Pieces Aval (75%)	Planning Figure And Unit	Local Hauls Trips Per Day	Local Hauls Capacity Per Day	Line-Hauls Trips Per Day	Line-Hauls Capacity Per Day
	55-84H0 (cont)	12-T S&P semitrailer	20	15	12 STONs or 50 pax**	2	254 STONs or 1,500 pax	1	127 STONs or 750 pax
		or							
		22½-T semitrailer	20	15	1 20-ft container or 15 STONs or 35 pax**	2	14 20-ft containers or 210 STONs or 1,050 pax	1	7 20-ft containers or 105 STONs or 525 pax
		5-T cargo truck w/ tank and pump unit w/1½-T cargo trailer w/tank unit	6	4	1,800 gal	2	144,000 gal	1	7,200 gal
		5-T cargo truck	60	45	5 STONs or 20 pax*	2	450 STONs or 1,800 pax	1	225 STONs or 900 pax
Transportation motor transport company	55-87H0	5-T cargo truck	60	45	5 STONs or 20 pax*	2	450 STONs or 1,800 pax	1	225 STONs or 900 pax
		5-T tractor	10	7					
		12-T S&P semitrailer	20	15	12 STONs or 50 pax**	2	168 STONs or 1,500 pax	1	84 STONs or 750 pax
		or							
		22½-T semitrailer	20	15	1 20-ft container or 15 STONs or 35 pax**	2	14 20-ft containers or 210 STONs or 1,050 pax	1	7 20-ft containers or 105 STONs or 525 pax
		5-T tractor w/ 5,000-gal fuel tank semitrailer	34	25	5,000 gal	2	250,000 gal	1	125,000 gal
		5-T cargo truck w/pump and tank unit and 1½-T cargo trailer w/tank unit	6	4	1,800 gal	2	144,000 gal	1	7,200 gal
Transportation motor transport company, heavy division	55-87J4	5-T cargo truck	36	27	6 STONs or 20 pax**	4	648 STONs or 2,160 pax	2	324 STONs or 864 pax (16 pax/veh)
		5-T tractor	33	24	NA	NA	NA	NA	NA
		22½-T semitrailer	66	49	1 20-ft container or 15 STONs or 35 pax**	4	96 20-ft containers or 1,440 STONs or 6,860 pax	2	48 20-ft containers or 720 STONs or 3,430 pax
		HET tractor w/ transporter	24	18	1 tank or 40 STONs gen cargo	4	72 tanks or 2,880 STONs gen cargo	2	36 tanks or 1,440 STONs gen cargo
Transportation motor transport company, infantry	55-88H0	5-T cargo truck	60	45	6 STONs 20 pax*	2	540 STONs or 1,800 pax	1	260 STONs or 720 pax (16 pax/veh)
		5-T tractor (M818) w/5,000-gal fuel tank semitrailer	16	12	5,000 gal	2	120,000 gal	1	60,000 gal
		5-T tractor	10	7	NA	NA	NA	NA	NA
		22½-T semitrailer	20	15	1 20-ft container or 15 STONs or 35 pax**	2	14 20-ft containers or 210 STONs or 490 pax	1	7 20-ft containers or 105 STONs or 245 pax
		or							
		12-T S&P semitrailer (M127)	20	15	12 STONs or 50 pax**	2	168 STONs or 700 pax	1	84 STONs or 350 pax

WWW.SURVIVALEBOOKS.COM


Table 3-19. Motor transport units capabilities on surfaced roads (cont)

Unit	TOE	Equipment	Pieces Auth	Pieces Aval (75%)	Planning Figure And Unit	Local Hauls Trips Per Day	Local Hauls Capacity Per Day	Line-Hauls Trips Per Day	Line-Hauls Capacity Per Day
	55-88H0 (cont)	5-T cargo truck w/ pump and tank unit w/ 1½-T cargo trailer w/tank unit	6	3	1,800 gal	2	10,800 gal	1	5,400 gal
Transportation motor transport company, infantry, division, light	55-88J8	5-T cargo truck	33	24	6 STONs or 20 pax*	2	288 STONs or 960 pax	1	144 STONs or 384 pax (16 pax/veh)
		5-T tractor w/ 22½-T semitrailer	8	6	1 20-ft container or 15 STONs or 35 pax**	2	12 20-ft containers or 180 STONs or 420 pax	1	6 20-ft containers or 90 STONs or 210 pax


*Recommended in emergencies only; no troop seats provided.

**Number of trips based on tactical employment of unit (short turnaround times). For general troop movements, plan on four trips per day.


See Figure 3-35 for illustrations of Army motor transport vehicles.



TRUCK, UTILITY, 1/4-TON, M151A2



TRUCK, UTILITY, 1/2-TON, M274 (MULE)




TRUCK, UTILITY, 4X4, 3/4-TON, M1009 (CUCV)




TRUCK, UTILITY-CARGO/TROOP CARRIER, 1 1/2-TON, M1038 (HMMWV)

Figure 3-35. Army motor transport vehicles


WWW.SURVIVALEBOOKS.COM




TRUCK, COMMERCIAL, 1 1/4-TON, M880




TRUCK, CARGO, 1 1/4-TON, M561 (GAMMA GOAT)




TRUCK, CARGO, 2 1/2-TON, M35A2




TRUCK, CARGO, 5-TON, M813




TRUCK, CARGO, 5-TON, M924



TRUCK, CARGO, 8-TON, M520 (GOER)




CARGO CARRIER, TRACKED, 6-TON, M548




TRUCK, 8X8, 10-TON, M977 (HEMTT)

Figure 3-35. Army motor transport vehicles (cont)


WWW.SURVIVALEBOOKS.COM




TRUCK-TRACTOR, 5-TON, M818




TRUCK-TRACTOR, 5-TON, M931




TRUCK-TRACTOR, LINE HAUL, 6X4, M915




TRUCK-TRACTOR, 6X6, 10-TON, w/DUAL REAR WINCHES, M123E2




TRUCK-TRACTOR, 8X6, M911, COMMERCIAL HEAVY EQUIPMENT TRANSPORTER (CHET)



TRUCK-TRACTOR, 8X8, 22 1/2-TON, M746, HEAVY EQUIPMENT TRANSPORTER (HET)




SEMITRAILER, LOW-BED, M172A1




SEMITRAILER, STAKE, 12-TON, M127A2

Figure 3-35. Army motor transport vehicles (cont)


WWW.SURVIVALEBOOKS.COM




SEMITRAILER, FLATBED, BREAK-BULK/CONTAINER TRANSPORTER, 22 1/2-TON, M871




SEMITRAILER, 34-TON, DUAL-PURPOSE BREAK-BULK/CONTAINER TRANSPORTER, M872



SEMITRAILER, LOW-BED, 60-TON, M747, HEAVY EQUIPMENT TRANSPORTER (HET)



SEMITRAILER, FUEL TANK, 5,000-GALLON, M131A4C



SEMITRAILER, REFRIGERATOR VAN, 7-TON, M349A4

Figure 3-35. Army motor transport vehicles (cont)

WWW.SURVIVALEBOOKS.COM

CHAPTER 4

RAIL TRANSPORT

CONTENTS

		Page
Section I.	ORGANIZATION AND OPERATIONS	
	Railway Units	4-1
	Administration	4-7
	Planning	4-9
	Equipment Requirements	4-13
	Loading	4-14
	Construction, Maintenance, and Supply	4-17
II.	RAIL TRANSPORT DATA	
	Locomotive Classification	4-21
	Railway Equipment Characteristics	4-22
	Clearances and Track Gages	4-34
	Bridge Capacity	4-40
	Maximum Bulk Loads	4-43

Section I. ORGANIZATION AND OPERATIONS

RAILWAY UNITS

The term "transportation railway service" (TRS) applies to railway units assigned or attached to the major transportation organization, normally a transportation command. Composed of supervisory, operating, and maintenance units, the TRS operates trains, maintains rail lines of communication, and performs direct support and general support maintenance on locomotives and rolling stock. Depending on the extent of the operation, any TRS supervisory unit may perform staff and planning functions and serve as the highest echelon of the military railway service in a theater.

A breakdown of the railway units according to TOE, mission, assignment, and capability is outlined in Table 4-1. For a detailed discussion of these units, see FM 55-20.

WWW.SURVIVALEBOOKS.COM

Table 4-1. Tables of organization and equipment—railway units

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
Headquarters and headquarters company, transportation railway brigade	55-201H	MISSION: To command and provide operational planning, supervision, coordination, and control of transportation railway group or facility activities in the US and foreign nations. ASSIGNMENT: To a theater army. Normally attached to a transportation command. CAPABILITY: At level 1, this unit commands and supervises up to eight transportation railway groups as well as— • Provides planning for command and staff. • Supervises railway facility operations of US or foreign nations. • Supervises and assists in administrative and supply matters. • Plans for and supervises security of all buildings, structures, equipment, and in-transit (by rail) supplies. • Provides technical control over train movements, terminal operations, railway shops and enginehouses, car distribution, track and structure maintenance, and motive power allocation. • Allocates maintenance of way supplies and equipment.
Headquarters and headquarters company, transportation railway group	55-202H	MISSION: To command, administer, and supervise the operation of railway battalions and attached supporting units. ASSIGNMENT: To a theater army. Normally attached to a transportation railway brigade but may operate directly under a transportation command. CAPABILITY: This unit commands and supervises three to eight transportation railway battalions and attached supporting units as required.
Headquarters and headquarters company, transportation railway battation	55-226H	MISSION: To command, administer, and supervise the operation of railway and attached supporting units of the transportation railway battalion. ASSIGNMENT: Organic to a transportation railway battalion. CAPABILITY: This unit— • Provides command, staff planning, administration, control, and supervision of a railway battalion and its assigned and attached units. • Dispatches all trains. • Supervises on-line operations. • Operates the railway station and signal towers within its responsibility. • Operates two dining facilities to support all elements of the battalion.
Transportation railway engineering company	55-227H	MISSION: To maintain and repair railway track, bridges, and buildings within a railway division.

WWW.SURVIVALEBOOKS.COM

Table 4-1. Tables of organization and equipment—railway units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		ASSIGNMENT: Organic to a transportation railway battalion. CAPABILITY: At level 1, this unit performs maintenance, repair, and limited construction of track, bridges, buildings, and structures of a railway division approximately 90-150 miles (145-240 kilometers) long.
Transportation railway equipment maintenance company	55-228H	MISSION: To inspect, service, and make running repairs on diesel-electric locomotives and rolling stock. ASSIGNMENT: Organic to a transportation railway battalion. CAPABILITY: At level 1, this unit— • Performs daily and annual running repairs on 40 diesel-electric locomotives. • Performs daily running inspections on approximately 800 railway cars. • Performs limited repairs to railway-peculiar tools and equipment within the railway division. • Provides wreck train support to the railway division.
Transportation train-operating company	55-229H	MISSION: To operate railway locomotives and trains. ASSIGNMENT: To a transportation command. Normally attached to a transportation railway battalion. May operate separately under supervision of the appropriate transportation element. CAPABILITY: At full strength, this unit provides 50 train crews daily for road or terminal operations, including switching, classifying, and making up trains for the road.
Transportation electric power transmission company	55-217H	MISSION: To maintain and repair electric power transmission facilities for electrified railway operations. ASSIGNMENT: To a transportation command. Normally attached to a transportation railway battalion. CAPABILITY: At level 1 this unit— • Maintains and repairs electric power transmission facilities, including power substations and catenary, for a system of 200 miles (320 kilometers) of electrified railway comprising main lines, passing tracks, yard tracks, and sidings. • Operates power substations on a 24-hour basis.
Diesel-electric locomotive repair company	55-247H	MISSION: To perform general support maintenance on diesel-electric locomotives and railway cranes. ASSIGNMENT: To a transportation command, theater army. Normally attached to a transportation railway group.

WWW.SURVIVALEBOOKS.COM

Table 4-1. Tables of organization and equipment—railway units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		CAPABILITY: At level 1 this unit— • Provides the following annual man-hours of productive maintenance: - Air brake repair—13,320 - Diesel engine repair—146,520 - Diesel-electric engine repair—109,890 - Welding—3,330 • Provides internal Class IX supply; however, does not provide supply to supported units. • Provides technical assistance and maintenance support teams to user units on an exception basis for specific items of equipment. These are items which require GS maintenance but, because of operations, cannot be readily evacuated to a GS maintenance shop. • Provides GS maintenance for repair and return of diesel-electric locomotives and railway-crane-peculiar stocks to the Army system.
Transportation railway car repair company (general support)	55-248H	MISSION: To perform general support maintenance on railway equipment. ASSIGNMENT: To a transportation command, theater army. Normally attached to a transportation railway group. CAPABILITY: At level 1, on a 24-hour basis, the unit— • Provides the following annual man-hours of productive maintenance: - Air brake repair—13,320 - Fabric repair—13,320 - Electrical repair—6,660 - Machining—29,970 - Railway car repair—259,740 - Metal work (blacksmithing)—59,940 • Provides GS maintenance to support approximately 2,500 railway cars, including stripping, fabricating, milling, assembling, erecting, and painting. • Receives, stores, and issues 8,000 line items of railway supplies and repair parts per month to support four to six railway battalions.
Transportation railway service teams:	55-520H	ASSIGNMENT: To a transportation battalion or comparable unit.
EA, railway station team		MISSION: To operate an on-line railway station. CAPABILITY: This unit operates a railway station.
EB, railway terminal detachment		MISSION: To operate a railway terminal on a 24-hour basis. CAPABILITY: This unit operates a railway terminal with a capacity of ten trains per day.
EC, railway section crew		MISSION: To perform railway maintenance of way.

WWW.SURVIVALEBOOKS.COM

Table 4-1. Tables of organization and equipment—railway units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		CAPABILITY: This unit maintains approximately 15 to 24 track-miles (tracks, roadbeds, switches, and miscellaneous railway facilities).
ED, diesel-electric locomotive maintenance crew (direct support)		MISSION: To perform DS maintenance on diesel-electric locomotives. CAPABILITY: This unit performs DS maintenance on approximately seven diesel-electric locomotives per year. The unit provides the following annual man-hours of maintenance: • Air brake repair—3,330 • Electric component repair—3,330 • Nonelectric component repair—6,660
EE, railway car repair crew (direct support)		MISSION: To inspect and maintain railway cars at distant points from fixed facilities. CAPABILITY: This unit inspects and performs DS maintenance on approximately 400 railway cars per year. The unit provides the following annual man-hours of maintenance: • Air brake repair—9,990 • Electrical repair—3,330 • Metal working—6,660 • Railway car repair—19,980
EF, railway-yard-operating detachment		MISSION: To operate a rail yard. CAPABILITY: This unit— • Operates a railroad yard on a 24-hour basis when yard train crews are provided and when not more than two receiving and classification yards, including humps, are to be operated. • Inspects and makes running repairs on rolling stock crossing the yard. • Inspects and, if necessary, adjusts or secures loads on cars passing through the yard.
EG, bridge and building maintenance detachment (direct support)		MISSION: To maintain railway bridges and buildings. CAPABILITY: This unit maintains bridges and buildings along 45 to 75 track-miles.
EH, railway-train-operating section		MISSION: To operate trains. CAPABILITY: This unit— • Operates two trains in either road or switching service, on a 24-hour basis. • When augmented by six additional brakemen (team EK), operates two trains in switching service on a 24-hour basis.
EI, railway workshop mobile detachment (direct support)		MISSION: To perform DS maintenance of diesel-electric locomotives and rolling stock in areas with inadequate or no static facilities. CAPABILITY: This unit performs inspection and DS maintenance on 20 diesel-electric

WWW.SURVIVALEBOOKS.COM

Table 4-1. Tables of organization and equipment—railway units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		locomotives and 100 railway cars. The unit provides the following annual man-hours of maintenance: • Air brake repair—6,660 • Electrical repair—3,330 • Electrical component repairs—19,980 • Nonelectric component repairs—19,980 • Machining—16,650 • Metal working—3,330 • Railway car repair—13,330
EJ, railway maintenance of way crew		MISSION: To perform maintenance of way functions. CAPABILITY: This unit maintains approximately 40 track-miles (including track, bridges, buildings, railway signals, and communications lines) in a large terminal area.
EK, railway-train-operating section		MISSION: To augment railway-train-operating section (team EH) when it is required to operate two trains in switching service on a 24-hour basis. CAPABILITY: Provides the brakemen necessary to operate two trains in switching service.

WWW.SURVIVALEBOOKS.COM

ADMINISTRATION

Phases of Operation

There are three phases of military railway operation:

- Phase I, which is conducted exclusively by military railway personnel.

- Phase II, during which railway lines are operated and maintained by military railway personnel augmented with and assisted by local civilian railway personnel.

- Phase III, which is begun as soon as local conditions permit. Under this arrangement, local national civilian railway personnel operate and maintain railway lines under the direction and supervision of the highest military railway echelon in the theater. This arrangement releases railway unit personnel for other duties.

Standing Operating Procedures

See Figures 4-1 and 4-2 for sample SOP formats for rail movements and the transportation railway service respectively.

(Classification)

STANDING OPERATING PROCEDURE

1. GENERAL. *Policies and factors involved in selecting and carrying out rail movements.*

2. SUPPLY MOVEMENTS

   a. Releases. *Date required, procurement methods, formats, dissemination, action required.*
   b. Routing. *Responsibilities and procedures.*
   c. Diversions and reconsignments. *Authority and initiating procedures for method used.*
   d. Records and reports. *Responsibilities and methods for maintaining specific records; appropriate references to reports.*

3. TROOP MOVEMENTS

   a. Current situation (for example, war, peace, partial or full mobilization, civil unrest).
   b. Distance to be traveled.
   c. Origin and destination points.
   d. Security requirements.
   e. Tactical situation.
   f. Types and amount of equipment available.
   g. Priority.

(Classification)

Figure 4-1. Sample format for rail movements SOP

WWW.SURVIVALEBOOKS.COM

(Classification)

STANDING OPERATING PROCEDURE

1. GENERAL

a. Rail transportation integration in the theater transportation net.
b. Operational control.
c. Coordination with adjacent commands for rail use and support of operating units.
d. Coordination of the theater rail plan for selection, rehabilitation, and operation of rail lines to support theater strategic plans.

2. MISSION. *Rail net and facilities operated; terminals, installations, and commands supported.*

3. ORGANIZATION. *Available operating units, location, and operating limits.*

4. FUNCTIONS. *Responsibilities for operation and maintenance of military railways and equipment, as well as for freight, passenger, and special trains.*

5. PLANNING

a. Long-Range.
(1) Responsibilities and procedures.
(2) Primary and alternate rail routes selection.
(3) Line capacity, troop equipment, and supply requirements.
(4) Rehabilitation and projected requirements.
(5) Communication and security requirements.
(6) Demolition plans.
b. Short-Range.
(1) Current operational plans.
(2) Current rail-line capacity and requirements.
(3) Phases of operation.
(4) Selection and rehabilitation of new or additional railheads, yards, and installation facilities.

6. OPERATIONS

a. Disseminating and implementing movement programs.
b. Coordinating with the transportation movements officer.
c. Setting priorities for rail equipment and its use.
d. Preparing and compiling operational and situation reports.
e. Ordering cars and documenting their use.
f. Scheduling special trains.
g. Constructing and using railcar spanners.
h. Loading, blocking, and bracing cars and inspecting loaded cars.

7. MAINTENANCE. *Responsibilities, procedures, inspections, reports, and standards for maintaining military and utility railway facilities and equipment.*

8. SUPPLY. *Responsibilities and procedures for requisitioning, stocking, distributing, maintaining levels of, disposing of excess, and accounting for railway operating and maintenance supplies; requirements and priorities for major items, including locomotives and rolling stock.*

Figure 4-2. Sample format for transportation railway service SOP

WWW.SURVIVALEBOOKS.COM

9. INTELLIGENCE AND RECONNAISSANCE. *Responsibilities and procedures for collecting, processing, disseminating, and using intelligence.*

10. SECURITY. *Procedures, responsibilities, and coordination of security requirements for trains and rail line-of-communication facilities, defense and demolition plans, and supplies en route by rail.*

11. RECORDS AND REPORTS. *Responsibilities and procedures for records and reports of railway operations, situation, personnel status, equipment maintenance and inspection, equipment status, and project status.*

12. TRAINING. *Responsibility for conducting unit and technical training.*

(Classification)

Figure 4-2. Sample format for transportation railway service SOP (cont)

PLANNING

When planning the most effective use of a railway system, you will need to consider—

- Line length.
- Roadbed and track condition.
- Track gage.
- Track type (single, double, or multiple).
- Rail weight.
- Ballast type and depth.
- Tie type (if wood, treated or untreated).
- Tie spacing.
- Axle load limitations (track and bridge).
- Line profile showing location and length of ruling grade.
- Line alignment showing location and length of minimum-radius curves.
- Location and description of bridges and tunnels.
- Location and length of passing tracks.
- Location, type, and quantity of fuel supply.
- Location, quantity, and quality of water supply.
- Location and capacity of yards.
- Location and capacity of car repair shops and enginehouses.
- Type and availability of motive power (weight in working order, expected working tractive effort, drawbar pull, and age).
- Type and availability of rolling stock (capacity, dimensions, and age).
- Climatic and prevailing weather conditions.
- Diagrams showing minimum structure, maximum unrestricted loading, and equipment gages.
- Signal system (wire or radio requirements and coordinating responsibilities).
- Dispatching facilities.
- Route junctions.
- Availability of new equipment and repair parts.
- Local labor resources.

Since the direction of military supply movements is primarily forward, military rail-line capacity estimates are generally based on net tonnage moved in one direction. However, since total capacity is based on train density, the movements of trains in both directions must be considered. When the railway net under consideration includes several divisions and branch lines, a separate estimate should be made for each. The limiting factors to consider when estimating rail-line payload capacity are

WWW.SURVIVALEBOOKS.COM

power (locomotive) and resistance (rolling, grade, curve, and weather). Use the following planning formulas and factors in the order in which they are listed.

Weight on Drivers

The weight on drivers of a locomotive is that weight which is supported by the driving (powered) wheels when they rest on a straight and level track. Weight on drivers does not include any of the remaining portion of the locomotive's weight.

Weight on drivers is expressed in short tons (STONs). Different types and classes of locomotives differ in weight. All locomotives are constructed to specifications issued by the purchaser, the using railroad, or the manufacturer. The weight on drivers of some common types of diesel-electric locomotives used by the Army is included here for ready reference. See FM 55-20 for a complete breakdown of Army locomotives' characteristics.

Locomotive Type	Weight on Drivers (STONs)	HP
Multigage, O-6-6-O	120	1,600
Standard gage, 0-4-4-0	60	500

Tractive Effort

Tractive effort (TE) is the horizontal force which a locomotive exerts if the wheels do not slip. Expressed in pounds, TE measures a locomotive's potential power. The TE is sup plied by the locomotive's manufacturer. See FM 55-20 for TEs of Army locomotives. When TE data are not available, use the formulas below to compute TE. Be sure to allow for the locomotive's age and condition.

Starting TE is the power that a locomotive has available to move itself and its load from a stopped position. Continuous TE is the effort required to keep a train rolling after it has started. As train momentum increases, needed TE diminishes rapidly. In steam locomotives, there is no difference between starting and continuous TE. A steam locomotive can generally continue to pull what it can start. However, a diesel-electric locomotive cannot continue to exert the same force achieved in starting without damaging its power unit. The continuous TE of a diesel-electric locomotive is about 50 percent of its starting TE.

Starting TE corresponds to the adhesion of the driving wheels to the rails. If the TE expended exceeds this adhesion element, the drivers will slip. Normally, the adhesion element is 30 percent of the weight on drivers for dry rails and 20 percent for wet rails–for an average of 25 percent.

The estimated starting TE for a locomotive is, therefore, 25 percent of its weight on drivers.

For an 80-ton (160,000-pound) locomotive on drivers:

Starting TE = 25% X 160,000 lb = 40,000 lb

For a steam locomotive with starting TE of 40,000 pounds:

Continuous TE = Starting TE = 40,000 lb

For a diesel-electric locomotive with starting TE of 40,000 pounds:

Continuous TE = 50% X 40,000 lb = 20,000 lb

Drawbar Pull

Drawbar pull is the pulling ability of a locomotive, less the effort needed to move the locomotive. Tests have shown that 16 to 20 pounds of pull per ton are needed to start the average locomotive or freight car on straight, level track under favorable weather and temperature conditions. A locomotive or car having roller bearings will start with somewhat less effort. For railway planning, use 20 pounds per ton. Resistance drops after equipment starts rolling. However, to establish pulling ability (drawbar pull) available for starting and pulling a train, subtract 20 pounds per ton of locomotive weight from the continuous TE of the locomotive. A diesel-electric locomotive having a weight on drivers of 80 tons and a continuous TE of 20,000 pounds has a drawbar pull of 18,400 pounds (20,000 pounds minus 1,600 pounds).

Maximum drawbar pull is exerted only at very low speeds—up to about 10 MPH—after

WWW.SURVIVALEBOOKS.COM

which it drops off sharply. To obtain drawbar pull at given speeds, apply a speed factor to the maximum drawbar pull. Remember that speeds differ for different types of locomotives. For one type of steam locomotive, drawbar pull was found to diminish in inverse ratio to speed: drawbar pull was 80 percent at 20 MPH, 50 percent at 50 MPH, and 20 percent at 80 MPH. Use this inverse ratio as a rule of thumb for estimating drawbar pull of steam locomotives at various speeds. Drawbar pull diminishes more rapidly at higher speeds for diesel-electric locomotives than for steam locomotives.

Resistance Factors

Rolling resistance. Rolling resistance includes the forces which act on a train in a direction parallel to the track and tend to hold or retard the train's movement. The components of rolling resistance are friction between the railheads and the wheel treads and flanges, resistance due to undulation of track under a moving train, internal friction of rolling stock, and resistance in still air. There is no absolute figure to use for rolling resistance. Experience has led to safe average values for rolling resistance in the theater of operations. These values are:

Average Value	Track Condition
5	Excellent
6	Good to fair
7	Fair to poor
8	Poor
9-10	Very poor

Grade resistance. Grade resistance is 20 pounds times the percent of grade (20 X % grade).

Curve resistance. No entirely satisfactory theoretical discussion of curve resistance has been published. However, engineers in the United States usually allow from 0.8 to 1 pound per degree of curve. Military railway planning allows 0.8 pound per degree of curve.

Weather resistance. Weather is another factor in train resistance. Experience and tests have proven that below-freezing temperatures diminish the hauling power of locomotives. Following are the effects of specific temperatures shown in percent of hauling power loss:

Temperature (°F)	Loss in Hauling Power (%)
Above +32	0
+31 to +16	5
+15 to 0	10
–l to –l0	15
–ll to–20	20
–21 to–25	25
–26 to–30	30
–31 to–35	35
–36 to–40	40
–41 to–45	45
–46 to–50	50

Ordinarily, wet weather is regarded as local and temporary. Disregard it in normal planning. However, in countries with extended wet seasons, loss of tractive effort due to slippery rails may prove serious if sanding is inadequate. The applicable reduction in TE is a matter of judgment. However, in general, TE will not be less than 20 percent of weight on drivers.

Gross Trailing Load

Gross trailing load (GTL) is the maximum tonnage that a locomotive can move under given conditions, such as curvature, grade, and weather. Determine GTL by combining all of the factors discussed in the preceding paragraphs. Use this formula to calculate GTL:

$$GTL = \frac{DBP \times W}{RR + GR + CR}$$

where GTL = gross trailing load
DBP = drawbar pull
W = weather resistance
RR = rolling resistance
GR = grade resistance
CR = curve resistance

When using two steam locomotives (either double-heading them or having one pull and the other push), find GTL by taking 90 percent of the total GTL of both locomotives. The 90 percent figure is based on the difficulty in

WWW.SURVIVALEBOOKS.COM

perfectly coordinating the actions of two locomotive operators. However, when diesel-electric locomotives are used in multiple-unit operation, the GTL will be 100 percent of the total GTL for both locomotives since they are operated by one person from a single control.

Net Trainload

Net trainload (NTL) is the payload carried by the train. NTL is the difference between gross weight (total weight of cars under load) and tare weight (total weight of cars empty). In military railway planning:

$$NTL = 50\% \times GTL$$

Train Density

Train density (TD) refers to the number of trains that may be safely operated over a division in each direction during a 24-hour period. Work trains are not included when computing TD. However, their blocking the main track can reduce the density of a rail division. Train density may vary greatly over various divisions due to—

- Condition and length of the main line.
- Number and location of passing tracks.
- Yard and terminal facilities.
- Train movement control facilities and procedures.
- Availability of train crews, motive power, and rolling stock.

On a single-track line, passing tracks are normally 6 to 8 miles apart. Multiple tracks (three or more) are generally considered double track for planning purposes since it is often necessary to remove a portion of the third and fourth tracks to maintain the double-track line.

The capacity and turnover of cars and trains operating in and out of terminal yards must be considered, either from definite experience and intelligence factors or by inference from other related information.

Use the following formulas for reasonably accurate estimates of freight TD for lines with 20 percent passenger trains.

For a single-track operation, use this formula:

$$TD = \frac{(NT + 1)}{2} \times \frac{24 \times S}{LD}$$

where TD = train density
NT = number of passing tracks
1 = constant (number of trains that could be run if there were no passing tracks)
2 = constant to convert to one direction
24 = constant (number of hours per day)
s = average speed (FM 55-20)
LD = length of division

When determining the number of passing tracks, do not include those less than 5 miles apart. The passing tracks selected should be uniformly spaced throughout the division.

Double-track operations must be fluid and flexible. Therefore, the number of trains operated should not exceed the number of trains which could be cleared off either main track at any given time in an emergency. Use the factors given for single tracks to find double-track TD (TD_2):

$$TD = (NT + 1) \times \frac{24 \times S}{LD}$$

If there is not enough information available to evaluate the potential TD of a rail line, use a TD of 10 for single track and 15 for double track as a rule of thumb.

Tonnage

Net division tonnage (NDT) is the payload tonnage (in short tons) which can be moved over a railway division (90 to 150 miles) each day. NDT includes railway operating supplies, which must be programed for movement the same as the supplies of any other service. To determine NDT, multiply the NTL by the TD of the particular division. Compute NDT separately for each division.

When calculating NDT, certain other factors must be considered. For example, troop, passenger, or hospital trains will replace an equal number of tonnage (cars with loads) freight trains. When the operation of such

WWW.SURVIVALEBOOKS.COM

trains is expected, allowance in NDT estimates is made by adjusting the TDs of the divisions concerned.

End-delivery tonnage in military operations is that tonnage (in short tons) delivered at the end of the railway line (railhead) each day. In all rail movements, end-delivery tonnage is the same as the NDT of the most restrictive division.

EQUIPMENT REQUIREMENTS

Rolling Stock

Freight cars. Compute requirements separately for operations between major supply installations and areas on each line of communication:

$$\text{number of cars} = \frac{\text{daily tonnage}}{\text{average tons per car}} \times \text{turnaround time} \times 1.10$$

Use these average planning factors for net load per car:

	Standard/Broad Gage (Tons)	Narrow Gage Tons
US equipment	20	15
Foreign equipment	10	7.5

Turnaround time is the estimated total number of days required for a car to complete a round-trip—the time from placement for loading at point of origin to destination and back. Allow 2 days at origin, 1 day at destination, and 2 days' transit time for each division, or major part of a division, which the cars must cross. Use this method rather than an actual hour basis to incorporate delays due to terminal and way station switching as well as to in-transit rehandling of trains. Dispatch times required are:

Location or Type of Operation	Dispatch Time (Days)
At base of operation	2
Forward traffic	1 per division
Return traffic	1 per division
At railhead	1

Tank cars. Compute tank car requirements separately, based on bulk POL requirement and turnaround time.

Passenger cars. Passenger car requirements vary, depending on policies for troop movement, evacuation, and rest and recuperation. Theater passenger car requirements are fulfilled with local equipment.

Road locomotives. Use this formula to determine the number of road locomotives required for operation over a given railway division:

$$\text{locomotives} = TD \frac{(RT + TT)}{24} \times 2 \times 1.20$$

where TD = train density
RT = running time (length of division divided by average speed)
TT = terminal time (time for servicing and turning locomotive)
24 = number of hours per day
2 = constant for two-way traffic
1.20 = constant allowing 20 percent reserve

"RT + TT" (called the locomotive factor) is the percent of time during a 24-hour period in which a road locomotive is in use. The locomotive factor provides for the pooled use of motive power which may make one or more trips per day over a short division. Estimates of downtime at terminals are 8 hours for steam locomotives and 3 hours for diesel-electric locomotives.

Switch engines. The number of switch engines required at a terminal is based on the number of cars dispatched, received, or passed through the terminal per day. As a reserve to allow for maintenance and operational peaks, add 20 percent to the total number of switch engines required for the railway line.

Average Speed

For planning purposes, use the following chart to estimate average speed values. Select the most restrictive factor of the eight factors shown. If the restrictive factor is not known, use an average speed value of 8 MPH (13 KPH) for single track and 10 MPH (16 KPH) for double track. If the most restrictive factor affects only a comparatively short distance (10 percent, or less) of the division, use the next

WWW.SURVIVALEBOOKS.COM

higher average speed. If the average speed falls below 6 MPH (10 KPH) because of the gradient, reduce tonnage to increase speed. (A 2 percent reduction in gross tonnage increases speed by 1 MPH.) If the ruling grade materially affects tonnage, consider using helper service.

Restrictive Factors	Average Speed Single Track MPH	KPH	Double Track MPH	KPH
Condition of Track				
Exceptionally good	12	19.3	14	22.5
Good to fair	10	16.1	12	19.3
Fair to poor	8	12.9	10	16.1
Poor	6	9.6	8	12.9
Grade (%)				
1 or less	12	19.3	14	22.5
l to l.5	10	16.1	12	19.3
1.5 to 2.5	8	12.9	10	16.1
2.5 to 3	6	9.6	8	12.9

LOADING

Open-Top Cars

Military equipment loaded on DOD-owned cars traveling on common carrier lines in CONUS must meet the individual railroad's loading standards as well as those of the Association of American Railroads (AAR). This requirement also holds for military equipment loaded on common carrier cars. Loads on foreign railroads must meet the blocking and lashing standards of the country involved. Standardization Agreements (STANAGs) govern loading military equipment on NATO rail lines. The AAR's ***Rules Governing the Loading of Department of Defense Material on Open-Top Cars*** is on file at all ITOs in CONUS. See TM 55-2200-001-12 for a detailed discussion of loading standards.

Explosives and Other Hazardous Materials

Regulations. The US Code establishes DOT authority and responsibilities for handling and transporting hazardous materials (Section 831-835, Title 18, Chapter 39). The regulations are published in Parts 170-179, Title 49, Code of Federal Regulations (Transportation), and Bureau of Explosives Tariff 6000. The DOT is responsible for regulating interstate shipment and movement of all hazardous materials by rail, air, highway, and water through its major operating agencies. These regulations outline requirements for classifying, packaging, marking, labeling, and storing hazardous materials. The regulations also ensure comparability of materials and govern placarding containers and vehicles carrying these materials. Title 49, CFR 174, establishes requirements for hazardous materials transported by rail. These regulations cover minimum transportation requirements only. DOD and DA may supplement DOT requirements when needed.

For more specific regulations and guidance, see:

- AR 55-355—for transporting military explosives and hazardous materials by military or commercial carriers within CONUS. AR 55-355 requires compliance with all regulations, including reporting accidents (according to AR 385-40), maintaining records, tracing shipments, completing SF 361 when required, and ensuring cargo security. AR 55-355 lists AAR loading rules for safe transportation. This regulation also contains information on placarding containers and vehicles.
- AR 385-40—for information on reporting accidents.
- MIL-STD- 129 series—for guidance on marking packages.
- Bureau of Explosives (AAR) pamphlets—for loading and bracing methods. Title 49, CFR 173-56, requires approval by the BOE (AAR) of all loading, blocking, and bracing methods used in rail shipment of unboxed explosive projectiles, torpedoes, mines, and bombs exceeding 90 pounds. Only the military is authorized to ship palletized explosive projectiles of not less than 4 1/2 inches in diameter without being boxed. See—

  - Pamphlet 6—for carload and less-than-carload shipments of explosives and other dangerous articles.

  - Pamphlet 6A—for carload and less-than-carload shipments of loaded projectiles and loaded bombs.

  - Pamphlet 6C—for trailer and less-than-trailer shipments of explosives and other dangerous articles via trailer-on-flatcar (TOFC) or container-on-flatcar (COFC).

WWW.SURVIVALEBOOKS.COM

Methods of bracing and blocking other than those given in these BOE pamphlets must be submitted through military transportation channels to the BOE for approval.

- TM 9-1300-206—for information on the care, preservation, and destruction of ammunition. See also data on quantity-distance standards for manufacturing, handling, storing, and transporting mass-detonating ammunition, explosives, and small arms ammunition. This technical manual also includes quantity-distance classes and tables for all classes of ammunition and explosives.
- TM 55-602—for general guidance on transporting special freight. This technical manual identifies applicable directives and regulations as well as agencies prescribing transportation policies.
- Army Materiel Command publications—for outloading drawings of ammunition, missile systems, special weapons, and other hazardous materials.

Bracing and blocking. Use only sound lumber free from cross grain, knots, knotholes, checks, or splits, which impair the strength of the material or interfere with proper nailing. Use nails plentifully and in the proper places; balanced nailing is important. All nails should be long enough for necessary holding power and ample penetration of car walls, floors, or other bracing and blocking. To obtain the greatest holding power, nails must be long enough to penetrate, but not protrude through, the timber holding the point of the nail. Nails must not be so large that they cause splitting. Place nails along the same grain in the wood. Whenever possible, drive nails straight–not toenailed. To prevent sparks, use brass or copper hammers to nail braces around packages of explosives.

Drive nails holding sidewall blocking into the heavy uprights supporting the car lining. Car lining is only three-quarters or seven-eighths of an inch thick and has little holding power for large nails.

Basic precautions. When loading packages in a car, avoid lost space by pressing each package firmly toward the end of the car as it is loaded.

Avoid high pressure on small areas. Use the largest possible area of a package to resist pressures. Nail beveled boards to the car floor to cover defects in the floor or projecting pieces of metal or nails. Cars with corrugated or pressed metal unlined ends, as well as cars with bowed ends, must be boarded up at the inside of the ends to the height of the load.

Avoid placing a large shipment in one end of a car. Do not load a shipment exceeding 12,000 pounds in one end of a car unless other freight is to be loaded to balance the other end. Failure to observe this precaution may cause the car to leave the track.

Never load or stow incompatible chemicals or explosives together (49 CFR 170-1 79).

Never use—

- Cars with end doors.
- Cars with automobile loading devices (unless the loading device is attached to the roof of the car so that it cannot fall—applicable to shipment of Class A explosives only).
- Refrigerator cars (unless use is authorized by the carrier or owner, ice bunkers are protected by solid bracing, and nonfixed floor racks are removed).

When loading in closed cars, secure the load so that it does not come in contact with side doors or roll and shift in transit.

When lift trucks move heavy loads in and out of cars, a temporary steel plate or other floor protection device of suitable size will prevent the truck from breaking through the floor. Place the load in the car so that there is no more weight on one side than on the other. Limit the load per truck to half the load limit stenciled on the car. Cars should be loaded as heavily as possible up to the load limit stenciled on the car.

Material loaded between truck centers and the ends of the car must not exceed 30 percent of the stenciled load limit (15 percent each end) when both ends are loaded and 10 percent when only one end is loaded.

When loading, blocking, and bracing ammunition for carload and less-than-carload shipments, make sure ammunition containers are tightly wedged in place at the time of

WWW.SURVIVALEBOOKS.COM

loading. Bulkhead braces for partial layers must be long enough to permit nailing to upright braces behind car lining. Length will vary, depending on weight of lading supported. The filler strips nailed to the sides of the car must be extended across the doorway. No other doorway protection is required.

Dangerous-cargo placards. On loaded cars, labels and placards are required for containers and railcars carrying explosives and other hazardous materials. See 49 CFR 172-174 for a description of labels and placards and FM 55-70 for a detailed discussion.

Empty tank cars and boxcars are often placarded with notices warning of lingering gases and fumes. These warning cards stress that care must be used in switching the cars as well as in unloading their contents.

Cargo Security

At origin. The shipper is responsible for the security of carload freight until the car is coupled to a locomotive or train for movement. The shipper must be fully aware of this responsibility.

Before loading, the shipper should inspect the car thoroughly to ensure that it meets security and serviceability requirements. Cars with insecure doors or holes or damaged places in floors, roofs, or sides must be repaired before they are used.

The shipper is also responsible for properly loading and bracing the load and for closing and sealing the car. Improperly stowed or braced loads may be damaged in movement and so invite pilfering (see TM 55-601).

Loading should conform to the standards necessary for safe movement under existing conditions. Seal closed cars containing sensitive cargo—arms, ammunition, and explosives (AA&E)–with cable seal locks. If these locks are not available, use a Number 5 steel wire twist or a wire cable of larger or equivalent thickness, together with a ball-type, serialized seal to secure door hasps. Shipping papers furnished the carrier should specify that flame or heat-producing tools will not be used to remove sealing devices from AA&E shipments. For nonsensitive shipments (other than AA&E), a ball-type, serialized seal will suffice. Cover shipments in open cars with securely fastened tarpaulins. Fasten small items shipped on flatcars securely to the car floor.

The shipper prepares an accurate list of contents, prepares the waybill, and affixes placards to the cars. The shipper also transmits/mails an advance notice of AA&E shipments to the consignee. After a car is loaded, sealed, and documented, it should be moved as quickly as possible.

At military installations, the originating transportation officer and railway personnel must inspect all open-top cars before movement to ensure that they are loaded properly and meet clearance requirements.

In transit. The appropriate commercial railroad (in CONUS) and the TRS (in oversea theaters) are responsible for the security of all in-transit carload freight from the time the car is moved from its loading point until it reaches its designated unloading point. The originating rail carrier or the TRS prepares all car records, train documents, and other records required to speed movement and prevent loss of cars en route. When operating conditions permit, group the cars carrying pilferable freight for economical use of guards. Give special handling to mail or high-priority classified traffic.

In CONUS, the appropriate Army headquarters provides train guards. In oversea theaters, military police or other units assigned or attached to the TRS for security duties provide train guards. These units also guard cars and trains during movement in railroad yards. Sensitive supplies may be guarded by personnel assigned to the car by the loading agency. The yardmaster notifies the dispatcher on receipt of cars with special guards. The yardmaster also notes receipt on the train consist, which is transmitted to yards and terminals. This notification helps avoid delays in transit and expedites placement at the destination.

Guard crews check car seals and inspect trains for security. They prepare a record, by car number, of all guarded cars in trains and note any deficiencies or incidents en route.

WWW.SURVIVALEBOOKS.COM

When a relief guard takes over, the crews make a joint inspection and sign the record.

When a "bad-order" car containing supplies subject to pilferage is "set out," a member of the guard crew should remain with the car until properly relieved. Guard crews must be alert at all times, particularly when the train is stopped or passing through tunnels, cuts, and villages at slow speed.

At destination. When carload freight is placed at the designated depot, siding, or track, the consignee then becomes responsible for the shipment. Cars should be unloaded as quickly as possible to lessen chances of pilferage.

When removing wire seals from closed cars, be careful not to break latches on the car doors. Wire cutters are recommended for this purpose.

Do not use flame or heat-producing tools to remove sealing devices from shipments of arms, ammunition, or explosives.

CONSTRUCTION, MAINTENANCE, AND SUPPLY

Construction Requirements

For planning purposes, a railroad division includes 100 principal route miles of main line single or double track. The division includes terminal operation and maintenance facilities, fueling and watering facilities, and necessary signaling equipment or interlocking facilities. Passing sidings on single-track lines, crossovers on double-track lines, and stations are located at intervals required by traffic. Normally, there is at least one spur or siding provided at each station.

The engineer service in the theater of operations is responsible for new rail construction and large-scale rehabilitation. TRS maintenance of way personnel, however, may be required to assist engineer personnel with rehabilitation.

See Table 4-2 for the materials and man-hours required for new construction of one mile of standard-gage (56 1/2-inch), single-track railroad. See Table 4-3 for expected rehabilitation requirements for a 100-mile standard-gage, single-track division extending inland from a port. The table shows average percentage of demolition over the entire division. For further information, see FM 5-35, FM 55-20. and TM 5-370.

Maintenance Responsibilities

After railways are constructed and turned over to it for operation, the TRS is responsible for minor railway maintenance in the communications and combat zones to the forward limit of traffic. See TM 55-204 for further discussion of this subject.

The TRS is responsible for—

- Maintaining the railway communications circuits used exclusively for railway operation and administration. (Responsibility becomes effective when all circuits on the line have been turned over to the TRS.)

Table 4-2. Material and man-hour requirements for railroad construction *

ITEM	STONs	MTONs	MAN-HOURS
Grading (includes clearing average wooded terrain)	-	-	5,000
Ballast delivered, average haul—5 miles (8.05 km)	-	-	2,500
Tracklaying and surfacing	-	-	3,400
Bridging—70 linear feet (21.34 m)	128	111	3,200
Culverts, 7 per mile—280 feet (85.34 m)	8	7	1,400
Ties—2,900	218	300	-
Rail, 90-pound—ARA—A Section	79	45	-
115-pound—ARA—E Section	103	57	-
Fastening (based on 39-foot rail) (11.89 m)	33	10	-
Total	569	530	15,500

*Per 1 mile of standard-gage single track.

Table 4-3. Rehabilitation requirements per railroad division

Item	Per 100 Miles (161 km)	Percent of Demolition	Rehabilitation (quantity)	Construction Material[1] STONs	Construction Material[1] MTONs	Man-Hours[1] (Thousands)
Main line trackage	100 mi	10	7.0 mi	2,708	1,033	36.4
Port trackage[2]	–	100	3.0 mi	1,368	1,092	14.4
Passing sidings[2]	2.4 mi	80	2.4 mi	1,049	874	11.5
Station sidings[2]	1.6 mi	80	1.6 mi	730	582	7.7
Railway terminal[2 3]	1.0 ea	75	0.75 ea	8,025	4,875	160.0
Water stations	3.0 ea	100	3.00 ea	135	210	9.0
Fuel stations	1.0 ea	100	1.00 ea	19	16	0.9
Bridging (70 ft per mile)	7,000	55	2,700 linear ft	2,700	2,672	70.0
Culverts	28,000 linear ft	15	4,200 (74 ea) linear ft	63	63	13.7
Grading and ballast	–	–	–	–	–	40.5

[1] Tunnels require special consideration. To repair (by timbering) a 50-foot demolition at each end of a single-track tunnel (100 ft total per tunnel), allow 70 STONs or 87 MTONs, and 3,000 man-hours.

[2] Estimate includes ties, rails, fastenings, turnouts, tracklaying, and surfacing. It is assumed ballast is available at work sites.

[3] Includes replacing buildings 100 percent, ties 30 percent, rail and turnouts 85 percent.

WWW.SURVIVALEBOOKS.COM

WWW.SURVIVALEBOOKS.COM

- Operating railway block signals of interlocking plants and centralized traffic control devices.
- Providing unit and intermediate maintenance of signals and control devices.
- Installing, maintaining, and operating internal communications.

The TRS is normally divided into a number of divisions for maintenance and operation. Each division is assigned a railway battalion; each battalion includes personnel from the railway engineering company to perform necessary maintenance of tracks and structures.

The battalion commander has overall responsibility for railway maintenance, including maintenance procedures, instructions, and work. The railway engineering company commander is maintenance of way superintendent. The superintendent is directly responsible for inspecting and maintaining tracks and structures and for supervising all maintenance work and procedures. Platoon and section leaders supervise assigned maintenance operations.

Maintenance Categories

There are three categories of Army maintenance: unit, intermediate, and depot. They are discussed here as they apply to locomotives and rolling stock.

Locomotives. Suitable inspection pits and facilities must be provided for inspection, repair, and adjustment of locomotive parts. Locomotives must be inspected periodically and maintenance documented according to rail technical manuals. See DA Pam 738-750 and TM 55-203 for specific requirements.

Maintenance on locomotives is normally performed in an enginehouse. Enginehouses are of two general types: turnaround and maintenance. The turnaround enginehouse is small, equipped only for performing minor repairs and services usually requiring only 1 1/2 to 3 hours. The maintenance enginehouse has facilities for making major as well as minor repairs. Division locomotives are kept in good operating condition and at maximum availability. See FM 55-20 (for diesel-electric locomotives) for a general reference covering maintenance procedures at enginehouses.

Unit maintenance. Unit maintenance of locomotives consists of during-operation maintenance, inspection of visible moving parts, lubrication, and repair/replacement of parts which might otherwise interfere with efficient operation. The train-operating company performs during-operation maintenance. The engineman is responsible for the equipment he operates. The fireman maintains proper water level and steam pressure on steam locomotives. The balance of unit maintenance is the responsibility of the railway equipment maintenance company.

Intermediate maintenance. The railway equipment maintenance company and the diesel-electric locomotive repair company perform intermediate maintenance. If repairs are not too extensive, they are made and the locomotive put back into service. The mobile railway workshop supplements the railway equipment maintenance company's capability and functions under direction of the railway group headquarters. If repairs are beyond the railway workshop's capability, the unit makes only those repairs required to move the locomotive to a fixed installation for repair.

Depot maintenance. The diesel-electric locomotive repair company performs limited depot maintenance. The TRS has no units that perform full depot maintenance. This category of maintenance is beyond the capabilities of the railway car repair company and diesel-electric locomotive repair company and requires evacuation to CONUS or to an appropriate base or facility.

Rolling stock. Repair track installation (rip tracks) is normally set up at main terminals. Rip tracks are also located at other points of the division, such as junction points or heavy loading centers, to take care of repairs that cannot be made at the loading installation and to avoid moving the cars into the main terminal. The master mechanic (railway equipment maintenance company commander) is responsible for the operation of the rip tracks.

Unit maintenance. The railway battalion's train maintenance sections and crews perform unit maintenance (running repairs and inspection of rolling stock). Military or civilian car inspectors perform maintenance at the originating terminals and at inspection points

WWW.SURVIVALEBOOKS.COM

en route. Inspectors perform repairs required for safe train operation.

Intermediate maintenance. The railway battalion's train maintenance sections and crews and the railway car repair companies perform intermediate maintenance. Military or civilian maintenance personnel perform intermediate maintenance at the home terminals of the cars or at a prescribed location. Maintenance consists of running and emergency repairs that require taking the car out of service for a short time only (see TM 55-203).

Depot maintenance. The railway car repair companies perform limited depot maintenance.

Maintenance of Way

Roadway. Roadway maintenance is the work required to keep the part of the right-of-way on which the track is constructed in serviceable condition. This part of the right-of-way includes excavations, embankments, slopes, shoulders, ditches, and road/stream diversions. See TM 55-204 for a detailed discussion of roadway maintenance.

Track. In a theater of operations, the track must be operable at all times. The four primary considerations in track maintenance are gage, surface, alignment, and dress. The continual passing of trains around a curve eventually moves the track, altering the alignment and distorting the curve (see subparagraph "Determining Track Curvature"). TRS maintenance of way personnel should restore the track to its correct curvature if any distortion exists. Inspect the roadbed and track frequently to avoid operating delays because of damage by sabotage, direct enemy action, or weather.

Structures. In a theater of operations, structures essential to railway operations must be maintained according to the prescribed maintenance standards. These structures include bridges, culverts, tunnels, and fuel and water facilities. When repairing structures, always observe minimum clearances.

Determining Track Curvature

Survey method Degree of curve (D) is a measure of the sharpness of curvature and is defined as the angle subtended at the center of curvature by a chord 100 feet long. ***Radius of curvature*** (R) is the distance (in feet) from the apex of the central angle out to the curve; mathematically, R is the reciprocal of the curvature (C) of a curve. A ***chord*** is a straight line joining two points on the curve. The ***arc*** is the continuous portion of that curved line (as a part of a circle) between the same two points. The smaller the central angle (and the greater the radius), the closer the arc measurement comes to the chord measurement (100 feet).

The area of the sector of a circle is expressed in either of two ways:

$$A = \frac{R \times arc}{2} \quad \text{or} \quad A = \frac{3.1416 \times R^2 \times D}{360}$$

where: A = area
R = radius of curvature in feet
D = degrees of curvature
arc = 100 ft (since arc and chord are almost the same for a 10 curve)

To solve for R:

$$R = \frac{arc \times 360}{2 \times 3.1416 \times D} = \frac{arc \times 57.3}{D}$$

R then equals 5,730 for a 10 curve and $\frac{5,730}{D}$ for a D° curve.

The following chart shows the relationship between degree of curve and radius of curvature for simple curves.

D	R	D	R	D	R
1	5,730	7	819	13	441
2	2,865	8	716	14	409
3	1,910	9	637	15	382
4	1,433	10	573	16	358
5	1,146	11	521	17	337
6	955	12	478	18	318

String method. If a surveying instrument is not available, compute the degree of simple curvature (arc of a circle) of a track by the string method. Although this method is not exact, the degree of error is slight. A length of ordinary field "commo" wire makes an ideal string. Commo wire is readily available, will not stretch, and may be rolled up and carried in the pocket. The wire may be marked with three

WWW.SURVIVALEBOOKS.COM

dabs of white paint to indicate the beginning, middle, and end of the 62-foot length needed.

To determine the degree of track curvature by the string method—

- Select a portion of track well within the main body of the curve.
- Mark a 62-foot section on a length of wire or strong cord with dabs of white paint at the beginning (A), middle (M), and end (B) of the section.
- Secure A to inside of high rail (5/8 inch from top). Tightly stretch wire until B touches inside of rail (see Figure 4-3).
- Measure the distance R from M to inside of rail. Distance in inches equals approximate degree of curve.

If the distance R from M to rail measures 5 inches, then the degree of curve is 5. As a curve gets sharper, the distance R increases.




Figure 4-3. Determining curvature (string method).

Supply Procedures

Railway supplies are expendable supplies required for the operation and maintenance of railway divisions. Railway supplies are distinguished from organizational supplies. All operating units must submit reports of sup plies on hand at the beginning of operations.

Whenever possible, use local supply sources to reduce transportation requirements. In a theater of operations, supplies may be procured from—

- Military stocks.
- Manufacturers in or near the theater.
- Foreign railways.
- Captured enemy material and equipment.
- Parts and assemblies manufactured or repaired by the railway battalion.
- Transfers from other railway operation units.

The battalion supply officer serves as fuel agent for the railway transportation battalion. He or she must make sure that the operating TRS agencies receive enough locomotive fuel regardless of source. Requisition fuel and lubricants through normal supply channels.

The supply officer of the highest transportation railway echelon prepares tables of allowances and supplies for all units within the command. The supply officer determines a workable stock level allowance for each unit to ensure its uninterrupted operation. Normally, stock levels for the railway division are determined from past requirements.

Estimate repair parts requirements by using the factor 1.5 STONs per month for each train moving in either direction per day. Beginning with the first railway division, select the train density established for the division and multiply by 2 (for two-way travel). Then multiply the result by 1.5 for the total amount in STONs of spare parts required per month for this division. Use this process for each successive division to determine the total STONs required per month for the entire railway. This total is an estimate only. Revise as necessary to fit operation conditions.

Section II. RAIL TRANSPORT DATA

LOCOMOTIVE CLASSIFICATION

Whyte System

Locomotives are classified according to wheel arrangement. The Army uses the Whyte System. Although originally developed for steam locomotives, this system may be used for any type of motive power. Three or more digits separated by a hyphen designate the number of wheels on the locomotive. The first

WWW.SURVIVALEBOOKS.COM

digit represents the number of leading or "guide" wheels, the second the number of driving or powered wheels, and the third the number of trailing wheels. If there are no lead or trailing wheels, then the figure "0" is used in each case. If there are two separate sets of driving wheels, they are shown as two separate digits-always, of course, with a hyphen between them. For example:

- 2-8-2 Denotes a locomotive with one pair of leading wheels, four pairs of coupled driving wheels, and one pair of trailing wheels.
- 2-8-0 Denotes a locomotive with one pair of leading wheels, four pairs of coupled driving wheels, and no trailing wheels.
- 0-6-6-0 Denotes a locomotive with no leading or trailing wheels and two sets of three driving wheels each.

Continental System

The classification system commonly used in Europe and other parts of the world classifies locomotives by axles rather than wheels. Powered axles are represented by letters–"A" being one powered axle; "B," two powered axles; "C," three; and so on. Nonpowered or idling axles are represented by numerals. Using this system, the Army 0-4-4-0 would be a "B-B" and the 0-6-6-0 would be a "C-C." A 2-8-0 steam locomotive would be a l-D-0. A locomotive with two six-wheeled trucks would not necessarily be equipped with all axles powered, usually the middle axle being an idler. This locomotive would then be shown as an "A-l-A+ A-l-A," the plus sign (+) representing the separation of the front and rear trucks.

RAILWAY EQUIPMENT CHARACTERISTICS

Refer to Figure 4-4 and Tables 4-2 through 4-14 for railway equipment characteristics:

- Motive power.
  Locomotives–Table 4-4.
  Locomotive cranes–Table 4-5.
  Railway maintenance motor cars-Table 4-6.
- US rolling stock.
  Open-top cars (gondolas and hopper cars)-Table 4-7.
  Flatcars-Table 4-8.
  Boxcars–Table 4-9.
  Tank cars–Table 4-10.
  Refrigerator cars–Table 4-11.
  Special-purpose cars-Table 4-12.
- DOD Military Rail Fleet—Figure 4-4, an extract from ***The Official Railway Equipment Register*** which provides an example of data available on DOD cars under MTMC control. This publication also contains data on all US rolling stock and is updated quarterly. The ITO at each CONUS installation should have the most current edition for reference.
- West German rolling stock—Table 4-13.
- Korean rolling stock—Table 4-14.

WWW.SURVIVALEBOOKS.COM

Table 4-4. Characteristics of locomotives

Type	Gage (in)	Weight (lb)	Length Over Couplers	Extreme Width	Extreme Height	Tractive Force (lb)		Horse-power	Curvature Minimum Radius (ft)	Fuel Capacity (gal)
						Starting at 30% Adhesion	Continuous			
Diesel-Electric:										
131-T, 0-6-6-0, domestic and foreign svc	56 1/2	262,900	55'	10'0"	14'0"	75,700	37,850 at 10 MPH	1,000	231	1,600
127-T, 0-6-6-0, domestic and foreign svc	56 1/2	261,100	55'	10'0"	14'0"	75,700	37,850 at 10 MPH	1,000	231	1,600
120-T, 0-6-6-0, domestic and foreign svc	56 1/2, 60	240,000	57'5"	9'8"	13'6"	73,000	37,000 at 10 MPH	1,600	193	1,600
	63, 66	245,600 w/steam generator								800 w/steam generator
120-T, 0-6-6-0, domestic and foreign svc	56 1/2	240,000	56'9"	9'7"	13'5"	72,000	36,000 at 10 MPH	1,600	193	1,600
	60, 63	245,000 w/steam generator								800 w/steam generator
120-T, 0-4-4-0, domestic svc	56 1/2	240,000	55'9"	10'3"	14'6"	75,000	40,000 at 11 MPH	1,500	150	800
120-T, 0-4-4-0, domestic svc	56 1/2	246,000	48'10"	10'2"	14'6"	73,000	36,000 at 10 MPH	1,200	100	750
115-T, 0-4-4-0, domestic svc	56 1/2	230,000	45'6"	10'0"	14'6"	69,000	34,000 at 15 MPH	1,000	50	635
100-T, 0-4-4-0, domestic svc	56 1/2	199,040	44'6"	10'0"	14'4"	59,700	28,750 at 10 MPH	660	50	635
100-T, 0-4-4-0, domestic svc	56 1/2	200,000	44'5"	10'0"	14'7"	69,700	35,000 at 10 MPH	800	100	600
80-T, 0-4-4-0, domestic svc	56 1/2	161,000	36'10"	9'6"	13'7"	48,000	24,000 at 10 MPH	500	75	400
80-T, 0-4-4-0, domestic svc	56 1/2	161,000	36'10"	9'6"	13'7"	48,000	24,000 at 10 MPH	470	75	400
80-T, 0-4-4-0, domestic svc	56 1/2	161,600	41'0"	9'6"	13'4"	48,000	21,000 at 5.2 MPH	550	75	400
65-T, 0-4-4-0, domestic svc	56 1/2	130,000	34'0"	10'1"	13'5"	39,000	19,500 at 10 MPH	400	75	250

WWW.SURVIVALEBOOKS.COM

Table 4-4. Characteristics of locomotives (cont)

Type	Gage (in)	Weight (lb)	Length Over Couplers	Extreme Width	Extreme Height	Tractive Force (lb)		Horse-power	Curvature Minimum Radius (ft)	Fuel Capacity (gal)
						Starting at 30% Adhesion	Continuous			
Diesel-Electric:										
60-T, 0-4-4-0, domestic and foreign svc	56 1/2 60, 63, 66	122,000	38'11" (Type E) 39'3" (Willlison)	9'6"	13'4"	26,000	15,680 at 7.78 MPH	500	75	500
45-T, 0-4-4-0, domestic and foreign svc	56 1/2	90,000	33'6"	9'7"	12'0"	27,000	12,000 at 6 MPH	380	75	250
45-T, 0-4-4-0, domestic svc (side rod drive)	56 1/2	90,000	28'4"	9'6"	12'0"	27,000	13,500 at 6.2 MPH	300	50	165
44-T, 0-4-4-0, domestic svc	56 1/2	91,270	33'10"	9'4"	13'3"	26,400	11,000 at 9 MPH	380	75	250
44-T, 0-4-4-0, domestic svc	56 1/2	89,000	33'5"	10'1"	13'3"	26,400	13,000 at 7.1 MPH	380	50	250
25-T, 0-4-0, domestic svc	56 1/2	50,000	16'1"	8'7"	10'4"	15,000	6,200 at 6.2 MPH	150	50	75
Gasoline/Diesel-Mechanical:										
10-T, single-engine, 0-4-0, domestic svc	56 1/2	20,000	–	–	–	–	–	100	75	30 (diesel)

WWW.SURVIVALEBOOKS.COM

Table 4-5. Characteristics of locomotive cranes

Type	Gage (in)	Weight (lb)	Length Over Couplers	Extreme Height	Extreme Width	Boom Length (ft)	Reach Radius and Capacity	
							Main Hoist	Aux Hoist
Locomotive, steam, wrecking, 75-T, broad gage, domestic and foreign svc	56 1/2, 60 63, 66	191,000	30'10"	17'10"	10'4"	25 (2-piece, curved)	16' (75-T) 25' (34-T)	25' (10-T) 30' (8-T)
Locomotive, crane, diesel, mech, 150-T, domestic svc	56 1/2	291,700	31'0"	15'6"	10'4"	28 (2-piece, straight)	28' (67-T)	–
Locomotive, diesel, elec, 40-T, broad gage, domestic and foreign svc	56 1/2, 60 63, 66	221,500	36'1"	13'6"	10'4"	50 (2-piece, straight)	12' (40-T) 50' (6 3/4-T)	– –
Locomotive, diesel, elec, 40-T domestic svc	56 1/2	220,000	29'4"	15'1"	10'6"	50 (2-piece, straight)	12' (40-T) 50' (6 3/4-T)	– –
Locomotive, diesel, mech, 25-T, broad gage, domestic and foreign svc	56 1/2, 60 63, 66	148,000	27'7"	13'0"	8'6"	50 (2-piece, straight)	12' (25-T) 50' (4-T)	– –
Locomotive, diesel, mech, 25-T, narrow gage, foreign svc	36, 39 3/8, 42	152,000	32'6"	12'0"	8'6"	40 (2-piece, straight)	12' (25-T) 40' (6-T)	– –
Locomotive, diesel, mech, 25-T, domestic svc	56 1/2	155,000	30'0"	15'2"	10'8"	50 (2-piece, straight)	12' (25-T) 50' (4-T)	– –
Locomotive, diesel, mech, 35-T, domestic svc	56 1/2	167,000	30'0"	15'7"	10'4"	50 (2-piece, straight)	12' (35-T) 50' (5-T)	– –

WWW.SURVIVALEBOOKS.COM

Table 4-6. Characteristics of railway maintenance motor cars

Type	Gage (in)	Weight (lb)	Length (in)	Width (in)	Height (in)	Capacity	Horse-Power	Fuel Capacity (gal)
Gasoline, mech, 4 wheels, solid drawbar couplers, closed cab with hand brake	56 1/2	2,950	112	65	58 w/o cab	8 person	62.6	8
Gasoline, mech, 4 wheels, solid drawbar couplers, open body with hand brake	56 1/2	1,700	103	65	50	10 person	62 6	8

Table 4-7. Characteristics of open-top cars

Type	Gage (in)	Normal Capacity (lb)	Normal Capacity (cu ft)	Inside Dimensions Length	Inside Dimensions Width	Inside Dimensions Height	Light Weight (STONs)
Gondolas:							
High side, 8W, narrow gage, foreign svc	36, 39 3/8, 42	60,000	940	34'5"	6' 10 1/2"	4'	13.0
Low side, 8W, narrow gage, foreign svc	36, 39 3/8, 42	60,000	356	34'6"	6' 10 1/2"	1'6"	12.1
High side, 8W, broad gage, foreign svc	56 1/2	80,000	1,680	40'	8' 3 3/4"	4'	18.0
Low side, 8W, broad gage, foreign svc	56 1/2, 60, 63, 66	80,000	500	40' 4 1/2"	8' 3 1/4"	1'6"	16.0
Low side, 8W, drop ends, domestic svc	56 1/2	100,000	1,184	41'6"	9' 6 1/8"	3'	23.0
High side, std gage, domestic svc	56 1/2	100,000	1,580	41'6"	9' 6"	4'6"	25.0
Hopper Cars:							
8W, domestic svc	56 1/2	100,000	–	33'	9' 5 1/2"	9'7"	–

WWW.SURVIVALEBOOKS.COM

Table 4-8. Characteristics of flatcars

Type	Gage (in)	Normal Capacity (lb)	Platform Length	Platform Width	Platform Height Above Rail	Light Weight (STONs)
8W, narrow gage, foreign svc	36, 39 3/8, 42	60,000	34′ 8 1/2″	7′2″	3′7″	10.9
12W, domestic svc	56 1/2	200,000	54′	10′ 6 1/2″	4′ 1 1/4″	35.0
8W, domestic svc	56 1/2	140,000	49′ 11 1/2″	10′ 3 1/4″	3′ 8 1/2″	27.0
12W, broad gage, foreign svc, 80-T	56 1/2, 60, 63, 66	160,000	46′4″	9′8″	4′ 2 7/8″	35.3
12W, domestic svc (passenger train svc)	56 1/2	200,000	54′	10′ 6 1/4″	4′ 5 3/8″	–
8W, domestic svc	56 1/2	100,000	43′3″	10′6″	3′8″	25.5
8W, broad gage, foreign svc	56 1/2, 60, 63, 66	80,000	40′9″	8′ 7 1/4″	3′ 6 15/16″	14.5
8W, broad gage, depressed center, foreign svc	56 1/2, 60, 63, 66	140,000	50′7″	9′8″	NA	41.5

Table 4-9. Characteristics of boxcars

Type	Gage (in)	Capacity		Inside Dimensions			Door Dimensions	Light Weight (STONs)
		(lb)	(cu ft)	Length	Width	Height		
8W, domestic svc	56 1/2	100,000	3,975	50′6″	9′3″	10′6″	10′ wide, clear opening 8′ high, clear opening	23.0
8W, broad gage, foreign svc	56 1/2, 60, 63, 66	80,000	2,520	40′6″	8′6″	6′ 5 5/8″	6′ 8 3/4″ wide 8′ 3 1/4″ high	18.5

WWW.SURVIVALEBOOKS.COM

Table 4-10. Characteristics of tank cars

Type	Gage (in)	Length Over Tank Heads	Normal Capacity (gal)*	Inside Diameter (in)		Light Weight (STONs)
				Tank	Dome	
Nickel-clad, ICC-103-AW, 8W, domestic svc	56 1/2	31'11"	7,500	78 (approx)	45	-
ICC-103, ICC-103-W, 8W, domestic svc	56 1/2	34' (approx)	10,000	87 (approx)	59 3/8 (approx)	-
Caustic soda, ICC-103-W, 8W, domestic svc	56 1/2	34' (approx)	10,000	88 (approx)	64	-
Petroleum, 8W, narrow gage, foreign svc	36, 38 3/8, 42	38' 4 7/8"	6,000	62 1/2	54	16
Petroleum, 8W, broad gage, foreign svc	56 1/2, 60, 63, 66	38' 5 3/8"	10,000	80 3/4	66 1/2	19
Nitric acid, ICC-103-W, 8W, domestic svc	56 1/2	33' 7 1/2"	7,800	78 (approx)	33 3/8	-
Phosphorus, ICC-103-W, 8W, domestic svc	56 1/2	34' 8 1/4"	8,000	78 (approx)	64	-
Petroleum, std gage, domestic svc	56 1/2	-	10,000	-	-	23

*Specific gravity of a liquid should be checked before it is loaded to avoid exceeding weight capacity of car.

Table 4-11. Characteristics of refrigerator cars

Type	Gage (in)	Normal Capacity (lb)	Length Inside End Lining	Width Inside Side Lining	Ice Capacity (lb)	Door Dimensions
8W, disassembled, foreign svc	56 1/2	80,000	38' 9 1/2"	6'11"	11,000	4' wide 7' high
8W, disassembled, broad gage, foreign svc	56 1/2, 60 63, 66	80,000	32' 1/2"	7'8" (approx)	11,000	4' wide 7' high
8W, mechanical, foreign svc	56 1/2, 60, 63, 66	80,000	40'9" equipment compartment	7'6" (approx)	None	6' wide 7' high

Table 4-12. Characteristics of special-purpose cars

Type	Gage (in)	Weight (lb)		Over End Sills		Height Above Rail	Remarks
		Light	Loaded	Length	Width		
Car, amb unit, 8W, domestic svc	56 1/2	157,000	167,300	78'11"	10'	13'6"	Capacity: 27 patients, 6 corpsmen, 1 nurse, 1 doctor
Car, guard, domestic svc	56 1/2	92,740	99,300	57'	9'1"	14'2 1/2"	Air-conditioned, shower, toilet, kitchen, 2 sleeping compartments
Car, kitchen, troop/amb train, 8W, domestic svc	56 1/2	100,160	NA	54' 2 1/2"	9' 5 3/4"	13'6"	Width, side door opening: 6'
Car, kitchen, dining and storage, amb train, 8W, foreign svc	56 1/2, 60, 63, 66	111,400 (avg)	NA	63' 1/4"	9'	13'	Seat capacity: 24
Car, personnel, amb train	56 1/2, 60 63, 66	111,400 (avg)	NA	63' 1/4"	9'	13'	Berth capacity: 15 EM, 4 doctors, 2 nurses

Table 4-13. Characteristics of West German freight cars

Type	Number of Axles	Light Weight (STONs)	Capacity		Inside Dimensions			Door Dimensions		Height of Floor Above Top of Rail
			Weight (STONs)	Cube (cu ft)	Length	Width	Height	Width	Height	
Boxcar, G	2	11.4	16.5	1,500	25'11 3/4"	8'	7'4 9/16"	4'11 1/16"	6'6 11/16"	4' 1/16"
Boxcar, GLMHS-50	2	13.4	23.1	2,500	36'9 5/16"	8'11 1/16"	9'5/8"	6'6 1/16"	6'6 11/16"	4' 9/16"
Boxcar, GM-30	2	12.7	23.1	1,700	24'10"	8'10"	31'4"	5'6"	6'	not aval
Boxcar, GMS-54	2	12.6	23.1	2,100	30'5 11/16"	8'8 11/16"	8'9 1/2"	5'10 13/16"	6'7 1/8"	4' 1/16"
Boxcar, KMMKS-51	2	12.5	30.8	1,420	28'8 13/16"	9' 5/8"	5'6 1/8"	5'10 13/16"	4'10 5/8"	4'1 7/16"
Boxcar, KMM8KS-58	2	14.3	29.7	1,800	28'8 9/16"	8'11 1/16"	7'1 5/16"	12'8 3/4"	6'6 11/16"	4' 11/16"
Gondola, X-05 (low side)	2	not aval	23.1	320	25'7"	8'7"	1'4"	NA	NA	not aval
Gondola, XLM-57 (low side)	2	8.4	23.1	330	29'7"	8'6"	1'4"	NA	NA	4'
Gondola, OMM-37 (high side)	2	9.7	24.6	1,210	27'7"	9'	4'10"	NA	NA	4'
Gondola, OMM-52 (high side)	2	11.0	28.6	1,200	28'	8'	4'10"	NA	NA	4'
Gondola, OMM-55 (high side)	2	11.0	27.5	1,200	28'8 9/16"	9' 3/8"	4'11 1/16"	5'10 1/2"	NA	4' 7/8"
Gondola, OMM-53 (high side)	2	12.1	27.5	1,200	28'	8'9"	4'10"	NA	NA	4'
Gondola, OMM-33 (high side)	2	11.5	27.0	1,260	28'7 3/16"	9' 7/16"	5'1"	4'11 1/16"	NA	4' 5/8"

WWW.SURVIVALEBOOKS.COM

Table 4-13. Characteristics of West German freight cars (cont)

Type	Number of Axles	Light Weight (STONs)	Capacity Weight (STONs)	Capacity Cube (cu ft)	Inside Dimensions Length	Inside Dimensions Width	Inside Dimensions Height	Door Dimensions Width	Door Dimensions Height	Height of Floor Above Top of Rail
Flatcar, R-10[1]	2	10.6	16.5	NA	33' 25/16"	8' 9"	NA	NA	NA	4'
Flatcar, RM-31[1]	2	14.3	22.1	NA	34'11 9/16"	8'6 5/16"	NA	NA	NA	4'1 1/8"
Flatcar, RMM-33[1]	2	11.4	27.0	NA	34'8 3/8"	9'2 1/4"	NA	NA	NA	4'1 1/4"
Flatcar, RLMMS-56[1]	2	14.0	25.3	NA	40'	8'11"	NA	NA	NA	4'
Flatcar, SM-14[1]	2	11.9	23.1	NA	41'6"	8'9"	NA	NA	NA	not aval
Flatcar, SS-15[1]	4	21.5	40.2	NA	48'2"	8'9"	NA	NA	NA	not aval
Flatcar, SSLMA-44	4	22.7	44 1	NA	59'2 7/16"	9' 1/4"	NA	NA	NA	4'5 3/4"
Flatcar, SSLMAS-53	4	26.3	61.6	NA	60'8 5/16"	8'11 13/16"	NA	NA	NA	4'6 1/8"
Flatcar, SSKM-49	4	17.1	55.1	NA	40'8 3/4"	8'5 15/16"	NA	NA	NA	4'3 9/16"
Flatcar (USA-owned)	4	16.7	50.0	NA	40'9"	8'5 3/4"	NA	NA	NA	4'3 9/16"
Tank car	2	14.0	NA	(2)	21'2"	NA	not aval	NA	NA	5'
Tank car	4	26.4	NA	(3)	33'1/2"	NA	not aval	NA	NA	5'
		(MTs)	(MTs)	(cu m)	(m)	(m)	(m)			(m)
RS 683,684,685	4	24.0	56.0	51.3	18.5	2.77	NA	NA	NA	1 33
RS689	4	23.6	56.0	51.0	18.5	2 77	NA	NA	NA	1.33
REMMS665	4	21.4	58.5	35.1	12.6	2 78	NA	NA	NA	1.33
RES686	4	25.0	55.0	49.0	18.5	2.75	NA	NA	NA	1.23
SA705	6	22.3	67.5	35.3	11.2	2.73	NA	NA	NA	1.43
SA (h) S710	6	31.0	65.0	45.7	15.0	2.56	NA	NA	NA	1.37
SAhs 711	6	31.5	64.0	turning side jacks flooding molds	NA	2.90	NA	NA	NA	NA
SGjs 716 (w)718	4	24 0	18.8	55.0	2.7	NA	NA	NA	NA	1 24
shis	4	22.7	NA	NA	NA	NA	NA	NA	NA	NA
SAS709	6	30.6	65.0	46.0	15.0	3.09	1 37	NA	NA	NA
TS851	2	11.7	28.0	24.0	8.76	2.76	1 68	NA	NA	1.25
TCS850	2	11 6	28.0	24.0	8.66	2.76	1.68	NA	NA	1.25
TIS858	2	13.0	26.5	23.8	8.75	2 72	2.16	NA	NA	1.23
Tbis871	2	15.1	24.5	34.0	12.7	2.67	2.26	NA	NA	1.17
Tbis 869,870,875	2	14.4	25.5	34.0	12.7	2.67	2.26	NA	NA	1 17

1 Height of flatcar is determined by height of stanchion.
2 4,356 US gallons.
3 14,266 US gallons.

WWW.SURVIVALEBOOKS.COM

WWW.SURVIVALEBOOKS.COM

Table 4-14. Characteristics of Korean freight cars

Type	Number of Axles	Light Weight (STONs)	Capacity		Inside Dimensions (m)			Door Dimensions (m)		Height (m) of Floor Above Top of Rail
			Weight (lb)	Cube (cu m)	Length	Width	Height	Width	Height	
Boxcar:										
40-T	4	21	88,160	87	12.95	2.7	2.5	1.7	2.1	1.1
50-T	4	22	110,200	95	13.04	2.8	2.6	1.8	2.1	1.6
Gondola:										
40-T	4	19	88,160	40	11.00	2.6	1.4	NA	NA	1.1
50-T	4	20	110,200	49	13.04	2.7	1.4	NA	NA	1.6
Flatcar:										
40-T	4	16	88,160	NA	12.20	2.5	NA	NA	NA	1.1
50-T	6	20	110,200	NA	15.00	2.9	NA	NA	NA	1.2
Tank car (USA-owned)	4	22	88,160	(10,000 gal)	11.09	2.9	2.7	NA	NA	1.1

WWW.SURVIVALEBOOKS.COM

6310

DEPARTMENT OF DEFENSE,
MILITARY TRAFFIC MANAGEMENT COMMAND-WASHINGTON, D.C. 20315.

7-83

Reporting Marks and ACI Nos. — DODX - 1 158

GENERAL OFFICES: Headquarters, Military Traffic Management Command, Eastern Area, Attn: MTE-INR-M, Military Ocean Terminal, Bayonne, NJ 07002 (201)823-6411-6412-6413

FREIGHT EQUIPMENT

Cars are marked "DODX" and are numbered and classified as follows:

Line No	A.A.R. Mech. Desig.	DESCRIPTION (See Explanation Pages for Abbreviations & Symbols)	A.A.R. Car Type Code	NUMBERS (▸Change from Previous Issue)	DIMENSIONS: INSIDE Length ft. in.	INSIDE Width ft. in.	INSIDE Height ft. in.	OUTSIDE Length ft. in.	OUTSIDE Width: At Eaves or Top of Sides or Platform ft. in.	OUTSIDE Width: Extreme Width ft. in.	OUTSIDE Height from Rail: To Extreme Width ft. in.	OUTSIDE Height from Rail: To Eaves or Top of Sides or Platform ft. in.	OUTSIDE Height from Rail: To Extreme Height ft. in.	DOORS Side: Width of Open'g ft. in.	DOORS Side: Height of Open'g ft. in.	CAPACITY: Cubic Feet Level Full	CAPACITY: Lbs. (000)	No. of Cars
		DODX																
1	XP	Box, End Doors: Width 8'2" & Height 10'2", Removable Shipping Containers, (Heat Exchangers)	A101	▸27480-27491	40 6	9 2	10 6	44 4	9 4	10 6	13 10	14 5	15	8	9 10	3903	100	12
2	XP	Box, End Doors: Width 9'6" & Height 8'6", Removable Shipping Containers, (Heat Exchangers)	A606	▸29010-29024	59 9	9 5	9 9	65 6	9 11	10 8	12 1	14	14 9	27	8 6	5487	164	15
3	XP	Box, End Doors: Width 9'6" & Height 8'6", Removable Shipping Containers, (Heat Exchangers), 15" Freightmaster End of Car Cushioning	A606	▸29300-29314	59 9	9 5	9 9	67 10	9 11	10 8	12 1	14	14 9	27	8 6	5487	161	15
4	FMS	Flat, Std., Load Limit at Center of Car, (Navy Gun Mounts)	F211	▸32002	40	10 6	....	46 2	.....	10 6	5 8	3 11	5 8	.....	.....	....	140	1
5	FMS	Flat, Std., Load Limit at Center of Car, (Navy Gun Mounts)	F211	▸32003-32007	40	9 1	.....	43 2	.....	10 2	3 8	3 8	5	.....	.....	....	140	5
6	FM	Flat, Heavy Duty	F502	▸38016-38664	54	10 6	.....	57 4	.....	10 7	4 2	4 2	4 2	.....	.....	....	200	543
7	FM	Flat, (Diesel Locomotives)	F502	▸38063, 38429, ▸38434, 38488, 38617	54	10 6	.....	56 6	.....	10 7	4 2	4 2	4 2	.....	.....	....	200	5
8	FM	Flat, (Navy Gun Mounts)	F502	▸38148, 38176, ▸38190, 38221, 38223, 38272, 38313,	54	10 5												17
9	LF	Flat, Heavy Duty, Demountable Container	L007	▸38170, 38187, ▸38200, 38280, 38311, 38566	54	10 6												6
10	FW	Flat, Well, Four 4-Wheel Trucks, (Steam Generators), Axle Spac. 5'10", Truck Ctrs. 34'6"	F361	▸38851-38854	46 8	9												2
11	FW	Flat	F361	▸38852, 38854	46 8	9												2
12	FW	Flat, Well, Four 4-Wheel Trucks, Axle Spac. 5', Truck Ctrs. 34'6" F✦ Note 1	F362	▸38864	53 6	10 6												1
13	FW	Flat, Well, Four 4-Wheel Trucks, (Steam Generators), Axle Spac. 5', Truck Ctrs. 40'4"	F461	▸38865-38867	46 4	9 4	1 8	69 5	.....	10 8	8 3	4 2	8 3	.....	.....	.....	400	3
14	FM	Flat	F502	▸39095-39199	54	10 4	.....	57 2	.....	10 4	4 5	4 5	4 5	.....	.....	.....	200	100
15	FM	Flat	F301	▸39500-39649	50	10 3	.....	53 3	.....	10 3	3 8	3 8	3 8	.....	.....	.....	160	73
16	FMS	Flat, Chain Tie-Downs	F311	▸39503, ▸39531-39533, 39544, 39552, 39560, 39563-39566, 39571-39573, 39575-39577, 39584, 39586, 39590-39592, 39595, ▸39597, 39602-39604, 39606, 39608, 39610-39611, 39617-39620, 39624-39625, 39627, 39629-39630, 39632, ▸39634-39635, 39645, 39647-39649	50	10 3	.....	53 3	.....	10 8	3 2	3 9	3 9	.....	.....	.....	160	47
17	FM	Flat, (Navy Gun Mounts)	F301	▸39519, 39558, ▸39569, 39582, 39623, 39626, 39639	50	10 3	.....	53 3	.....	10 3	3 8	3 8	3 9	.....	.....	.....	160	7
18	LF	Flat Note 2	L007	▸39524, 39599, ▸39637	50	10 3	.....	53 3	.....	10 3	3 8	3 8	3 8	.....	.....	.....	160	3
19	LF	Flat Note 3	L007	▸39535, 39546, ▸39551, 39559, 39579, 39587-39588, 39596, 39609, 39612, 39616, 39640	50	10 3	.....	53 3	.....	10 3	3 8	3 8	3 9	.....	.....	.....	160	12
20	FD	Flat Note 4	F433	▸39800-39809	72 5	10 2	2 6	79 6	.....	10 2	4 11	4 11	6 4	.....	.....	.....	300	10
21	FD	Flat C Note 5	F432	▸39810-39832	58	9	2 1	62 10	6	10	4 1	4 3	15 4	.....	.....	.....	300	9
22	FD	Flat C Note 6	F432	▸39812, 39813, ▸39820-39821, 39824-39825	58	9	2 1	62 10	9	10	4 1	4 3	13 10	.....	.....	.....	300	6
23	FD	Flat C	F432	▸39819	58	9	2 1	62 10	9	10	4 1	4 3	15 4	.....	.....	.....	300	1
24	FD	Flat	F432	▸39826, ▸39827-39829, 39831-39832	58	9	2 1	62 10	6	10	4 1	4 3	13 10	.....	.....	.....	300	6
25	FD	Flat	F432	▸39830	58	9	2 1	62 10	.....	10	4 1	4 3	13 10	.....	.....	.....	300	1
26	FD	Flat, Well, Depressed Center C	F433	▸39833-39847	71 8	9 2	2	77 1	6	9 2	4 11	4 11	15 4	.....	.....	.....	318	4
27	FD	Flat, Well, Depressed Center C Note 7	F433	▸39833, 39838	71 8	9 2	2	77	6	9 2	4 11	4 11	15 4	.....	.....	.....	318	2
28	FD	Flat, Well, Depressed Center Note 8	F433	▸39839, 39843, ▸39847	71 8	9 2	2	77 1	.....	9 2	4 11	4 11	8 4	.....	.....	.....	318	3
29	FD	Flat C	F433	▸39840	71 8	9 2	2	77	.....	9 2	4 11	4 11	15 4	.....	.....	.....	318	1
30	FD	Flat C	F433	▸39841	71 8	9 2	2	77 1	.....	9 2	4 11	4 11	15 4	.....	.....	.....	318	1
31	FD	Flat	F433	▸39842	71 8	9 2	2	77	.....	9 2	4 11	4 11	15 1	.....	.....	.....	315	1
32	FD	Flat	F433	▸39844	71 8	9 2	2	77 1	.....	9 2	4 11	4 11	7 2	.....	.....	.....	318	1
33	FD	Flat	F433	▸39845, 39846	71 8	9 2	2	77 1	.....	9 2	4 11	4 11	15 1	.....	.....	.....	315	2
34	FMS	Flat Note 9	F411	▸39900	44	9 2	13 8	47 7	6	9 10	4 2	4 2	13 8	.....	.....	....	375	1
35	FMS	Flat Note 10	F411	▸39901-39907	44	9 2	.....	47 7	.....	9 10	4 2	4 2	4 2	.....	.....	.....	375	7
36	FMS	Flat Note 11	F421	▸39911	40	10 8	.....	70 8	.....	10 8	4 3	4 3	7 5	.....	.....	.....	621	1
37	FMS	Flat Note 12	F421	▸39912-39913	50	10 8	.....	70 8	.....	10 8	4 3	4 3	7 5	.....	.....	.....	616	2
38	FMS	Flat, Axle Spac. 4'6", Truck Ctrs. 33'	F421	▸39914-39917	50	10 8	.....	70 6	.....	10 8	4 3	4 3	4 3	.....	.....	.....	600	4
39	FMS	Flat, Std., Axle Spac 5'6", Truck Ctrs. 46'3"	F423	▸40000-40100	58	10 3	.....	72 10	.....	10 6	3 9	4	4 1	.....	.....	.....	299	101
40	FMS	Flat	F423	▸40101-40244	58	10 5	.....	72 10	.....	10 6	4 1	4 1	4 1	.....	.....	.....	299	144
		Total																1177

NOTE

Example only—not to be substituted for the register.

TANK EQUIPMENT

Cars are marked "DODX" and are numbered and classified as follows:

Line No	A.A.R. Mech. Desig.	CLASS	DESCRIPTION (See Explanation Pages for Abbreviations & Symbols)	A.A.R. Car Type Code	NUMBERS (▸Change from Previous Issue)	CAPACITY: Rated Gals. (00)	CAPACITY: Lbs. (000)	No. of Cars
			DODX					
1	T	..	Tank	T103	▸6000-6199	..	110	127
2	T	..	Tank	T543	▸8649-8744	..	110	1
3	T	..	Tank	T563	▸8813-8824	..	134	12
4	T	..	Tank	T103	▸9200-9401	..	110	177
5	T	..	Tank, Insulated, Steam Coils	T103	▸9435-9488	..	154	50
1	T	..	Tank	T103	▸9808-9817	..	110	3
2	T	..	Tank, Steam Coils	T103	▸11636-11688	..	110	19
3	T	..	Tank	T103	▸11800-12373	..	110	523
4	T	..	Tank, Steam Coils	T103	▸12600-12888	..	110	63
5	T	..	Tank	T105	▸14000-14198	..	248	120

Figure 4-4. Characteristics of DOD military rail fleet cars (Extract from The Official Railway Equipment Register)

WWW.SURVIVALEBOOKS.COM

DEPARTMENT OF DEFENSE, MILITARY TRAFFIC MANAGEMENT COMMAND-WASHINGTON, D.C. 20315.—Continued

Line No.	A.A.R. Mech. Desig.	CLASS	DESCRIPTION See Explanation Pages for Abbreviations & Symbols	A.A.R. Car Type Code	NUMBERS ▶Change from Previous Issue	CAPACITY Rated Gals. (00)	CAPACITY Lbs. (000)	No. of Cars
			DODX					
1	T	. . .	Tank, (Sulfuric Acid)	T055	▶14000, 14003. ▶14008-14010, 14012-14014, 14020. ▶14025-14026, 14029, 14039. ▶14046-14047, 14049, 14051-14052. ▶14056, 14069-14070, 14077. ▶14079-14080, 14083, 14086-14087. ▶14089, 14093, 14098-14100, 14105. ▶14107, 14111, 14113, 14118, 14122. ▶14125, 14129, 14131-14132, 14135. ▶14139-14140, 14148, 14150-14151. ▶14153, 14155, 14159-14161, 14165. ▶14167-14168, 14172, 14175, 14181. ▶14184, 14191, 14198	.	248	62
2	T	. . . . .	Tank	T105	▶ 14200-14361	..	200	162
3	T	. . . . .	Tank	T103	▶ 18004-18187	...	110	6
4	T	. . . . .	Tank	T563	▶ 18041-18084	...	136	4
5	T	. . . . .	Tank	T563	▶ 16045	.	137	1
1	T	. . .	Tank	T563	▶ 16053	.	134	1
2	T	. . . .	Tank, (Phosphoric)	T102	▶ 16330-16344	.	154	13
3	T		Tank	T103	▶ 16414-16453	.	110	34
4	T		Tank	T021	▶ 17040-17081	.	88	32
5	T	.	Tank	T021	▶ 17091	.	88	1
6	T		Tank	T103	▶ 17398-17448	.	154	10
7	T	. . .	Tank	T103	▶ 17448	...	151	1
			Total					1422
			Grand Total					2599

Note 1—Car is equipped with permanently applied container and framework as an enclosure for radioactive material. Container: empty 139, 914 lbs., cooling unit 18,000 lbs., accessories 1,057 lbs., loaded 271,000 lbs. Railcar: lt. wt. 120,000 lbs.

Note 2—Cars are equipped with permanently applied framework. Framework: length 23 ft. 8 in., width 5 ft. 8 in., and maximum height above rail 5 ft. 3 in. Framework & car are weighted as a unit: 65,600 lbs.

Note 3—Cars are equipped with permanently mounted container and framework. Container & framework: length 22 ft. 4 in., width 10 ft., and maximum height above rail 12 ft. 6 in. Railcar, container & framework are weighted as a unit: 185,000 lbs. loaded & 122,000 lbs. empty.

Note 4—Depressed center flatcars having four 4-wheel trucks with spac. between truck ctrs. 53 ft. & between axles 5 ft., length of depressed section 30 ft., height from rail to top of depressed section 2 ft. 6 in. These cars have 2 3/8" wood flooring each end & stl. flooring in depressed section. Load may equal ld. lmt. cap. if supported on two cross bearers each side of center line of car. Lt. wt. 170,000 lbs.

Note 5—Depressed center flatcars having two 6-wheel trucks with spac. between truck ctrs. 40 ft. & between axles 5 ft. Cars are equipped with permanently mounted container & framework as an enclosure for radioactive material. Container & framework: length 18 ft., width 9 ft., maximum height above rail 15 ft. 6 in., weight 231,000 lbs. loaded & 218,000 lbs. empty. Railcar lt. wt. 130,000 lbs.

Note 6—Depressed center railcars having two 6-wheel trucks with spac. between truck ctrs. 40 ft. & between axles 5 ft. Cars are equipped with permanently mounted container & framework: length 31 ft., width 10 ft. 8 in., maximum height above rail 13 ft., 10 in., weight 250,000 lbs. loaded & 96,000 lbs. empty. Railcar lt. wt. 130,000 lbs.

Note 7—Depressed center flatcars having four 4-wheel trucks with spac. between truck ctrs. 47 ft. & between axles 5 ft. 4 in. Cars are equipped with permanently mounted container & framework as an enclosure for radioactive material. Container & framework: length 18 ft., width 9 ft., maximum height above rail 15 ft. 6 in., weight 231,000 lbs. loaded & 218,000 lbs. empty. Railcar lt. wt. 122,200 lbs.

Note 8—Depressed center flatcars having four 4-wheel trucks with spac. between truck ctrs. 47 ft. & between axles 5 ft. 4 in. Lt. wt. 122,200 lbs.

Note 9—Heavy duty flatcar having four 4-wheel trucks with spac. between truck ctrs., 26 ft. & between axles 5 ft. Car is equipped with stl. loading deck & may be loaded to ld. lmt. cap. if supported on two cross bearers each side of centerline of car or provided load is distributed not less than 7 ft. on each side of centerline of car & distributed over the full width of car. Car is equipped with permanently mounted container & framework as an enclosure for radioactive material. Container & framework: length 19 ft. 8 in., width 9 ft. 6 in., maximum height above rail 13 ft. 8 in., weight 333,000 lbs. loaded & 245,000 lbs. empty. Railcar: Lt. wt. 107,000 lbs.

Note 10—Heavy duty flatcars having four 4-wheel trucks with spac. between truck ctrs. 26 ft. & between axles 5 ft. Car is equipped with stl. loading deck & may be loaded to ld. lmt. cap. if supported on two cross bearers each side of centerline of car or provided load is distributed not less than 7 ft. on each side of centerline of car & distributed over the full width of car. Lt. wt. 107,000 lbs.

Note 11—Heavy duty flatcar having four 6-wheel trucks with spac. between truck ctrs. 33 ft. & between axles 4 ft. 6 in. Lt. wt. 167,200 lbs.

Note 12—Heavy duty flatcars having four 6-wheel trucks with spac. between truck ctrs. 33 ft. & between axles 4 ft. 6 in. Cars are equipped with permanently mounted container & framework: length 35 ft. 11 in., width 10 ft. 8 in., maximum height above rail 15 ft. 1 in., weight 425,800 lbs. loaded & 225,800 lbs. empty. Railcar: lt. wt. 172,300 lbs.

Report car movements, astray cars, mileage earnings and junction reports to HQ, MTMCEA Attn: MTE-INR-O, Bayonne, NJ 07002 (DOD/HQ, MTMCEA owner-shipper)

Pay mileage earnings by check drawn in favor of "Treasurer of the United States" and forward to HQ, MTMCEA, Attn: MTE-FMF, Bayonne, NJ 07002 (DOD/HQ, MTMCEA owner-shipper).

Report cars bad ordered, damaged, destroyed or requiring materials for repair to HQ, MTMCEA, Attn: MTE-INR-M, Bayonne, NJ 07002. Phone: (201)823-6411-6412-6413.

All cars initialed "DAFX", "USA" and "USAX" and not listed above are in intraplant service and are subject to movement in interchange as a result of transfer between government installations. Repair to these cars will be billed direct to: Commander, U.S. Army Troop Support & Aviation Materiel Readiness Command, Attn: DRSTS-MPB, 4300 Goodfellow Blvd., St. Louis, MO 63120 in accordance with Rule 112, A.A.R. Interchange Rules.

All cars initialed "USNX" or "USN" and not listed above are in intraplant service. Repairs should be billed to the installation requesting repairs to the cars. If installation information is not available, send bills to Commander, Naval Facilities Engineering Command, Attn: Code 064, 200 Stovall St., Alexandria, VA 22332.

For Billing: HQ, MTMCEA, Attn: MTE-FMF-CA, Military Ocean Terminal, Bayonne, NJ 07002

Home Point(s)—

Figure 4-4. Characteristics of DOD military rail fleet cars (Extract from The Official Railway Equipment Register) (cont)

WWW.SURVIVALEBOOKS.COM

CLEARANCES AND TRACK GAGES

Standard Clearances

Overhead clearances and platform heights are measured from top of rail, side clearances from centerline of track. See Table 4-15 and Figure 4-5 for standard minimum clearances. Local conditions may call for greater clearances. Clearances below those specified are dangerous and require appropriate warning signs or devices. For example, telltales must be used for overhead clearances ranging between 18 to 22 feet.

Table 4-15. Standard minimum clearances—wires, buildings, and other structures

Item	Clearance (m)	Clearance (ft-in)
Overhead clearances:		
Wires:		
High voltage	8.53	28′0″
Other	8.23	27′0″
Structures	6.71	22′0″
Side clearances:		
Buildings	2.59	8′6″
Canopies:		
Up to 15′6″	2.59	8′6″
Higher than 15′6″	1.68	5′6″
Platforms:		
3′9″	1.88	6′2″
4′	1.52	5′0″
Refrigerator platforms:		
3′2″	1.88	6′2″
4′7″	2.59	8′6″
Enginehouse entrance:		
Overhead	5.18	17′0″
Side	1.98	6′6″

WWW.SURVIVALEBOOKS.COM




Figure 4-5. Standard minimum clearances—single-track bridges and tunnels

WWW.SURVIVALEBOOKS.COM

Composite Clearance Diagrams

Sample clearance diagrams in Figures 4-6 and 4-7 show the distances that equipment or cargo may project to the sides at various heights above track level. The diagrams are composites of the minimum dimensions of all similar structures in the countries listed (with corresponding track gages) in Table 4-16. Therefore, not all the limiting clearances shown in the composites will exist at once on any particular rail line. A clearance diagram must be obtained or made for the rail line being operated. Do not confuse horizontal distances shown in the diagrams with track gage.

For example: in Figure 4-6, a vertical clearance of 3 feet 8 inches corresponds to a width clearance of at least 9 feet 8 inches. A vertical clearance of 9 3/4 inches corresponds to a width clearance not less than 8 feet 1 1/2 inches. In Figure 4-7, a vertical clearance between 13 3/4 inches and 3 feet 4 inches results when the width clearance is not more than 8 feet.





Figure 4-6. Composite clearance diagram for standard-gage (56 1/2″) and broad-gage (60″, 63″, and 66″) track

WWW.SURVIVALEBOOKS.COM



Note 1: 2′ 8¾″ for 36-inch track gage.
3′ for 39⅜- and 42-inch track gage.

Note 2: 4′ for 36- and 39⅜-inch track gage.
4′ 5″ for 42-inch track gage.

Figure 4-7. Composite clearance diagram for narrow-gage (36″, 39 3/8″, and 42″) track

WWW.SURVIVALEBOOKS.COM

Table 4-16. Principal track gages of the world

Country	Gages (in)
Africa:	
Algeria	39 3/8, 41 9/16, 56 1/2
Angola	23 5/8, 42
Benin	39 3/8
Cameroon	39 3/8
Central African Republic	42
Chad	37 7/16, 42
Congo (Brazzaville)	39 3/8, 42
Egypt	29 1/2, 39 3/8, 56 1/2
Ethiopia	39 3/8
Gabon	39 3/8, 42
Ghana	42
Guinea	39 3/8, 56 1/2
Ivory Coast	39 3/8
Kenya	39 3/8
Liberia	56 1/2
Libya	37 7/16
Madagascar	39 3/8
Malawi	42
Mali	39 3/8
Mauritania	56 1/2
Morocco	56 1/2
Mozambique	29 1/2, 42
Niger	37 7/16, 56 1/2
Nigeria	30, 42
Reunion (France)	39 3/8
Senegal	39 3/8
Sierra Leone	30
Somalia	39 3/8
Sudan	42
Swaziland	42
Tanzania	39 3/8
Togo	39 3/8
Tunisia	39 3/8, 56 1/2
Uganda	39 3/8
Upper Volta	42, 56 1/2
Zaire (Kinshasha)	23 5/8, 24, 39 3/8, 42
Zambia	42
Zimbabwe	42
Asia:	
Afghanistan	39 3/8, 56 1/2, 60
Bangladesh	30, 39 3/8, 66
Borneo	39 3/8
Burma	39 3/8
Cambodia	39 3/8
China (People's Republic)	56 1/2
China (Taiwan)	24, 30, 41 1/2
India	24, 30, 39 3/8, 66
Indonesia	23 5/8, 29 1/2, 42
Iran	56 1/2
Iraq	39 3/8, 41 1/4, 56 1/2
Israel	56 1/2
Japan	42, 56 1/2
Jordan	41 1/4
Korea	30
Laos	39 3/8
Lebanon	41 1/4, 56 1/2
Malaysia	30, 39 3/8
Nepal	30, 39 3/8, 66
Pakistan	30, 39 3/8, 66
Saudi Arabia	41 1/4, 56 1/2
Sri Lanka	30, 66
Syria	41 1/4, 56 1/2
Thailand	39 3/8
Tibet	39 3/8
Turkey	29 1/2, 39 3/8, 41 1/2, 56 1/2, 60
USSR	39 3/8, 60
Vietnam	39 3/8
Europe:	
Albania	56 1/2
Austria	30, 39 3/8, 56 1/2
Belgium	39 3/8, 56 1/2
Bulgaria	23 5/8, 29 1/2, 30, 56 1/2
Czechoslovakia	39 3/8, 56 1/2, 60
Denmark	56 1/2
Estonia (USSR)	60
Finland	29 1/2, 60
France	39 3/8, 56 1/2
Germany	23 5/8, 29 1/2, 39 3/8, 56 1/2
Greece	29 1/2, 39 3/8, 56 1/2
Hungary	30, 56 1/2, 60
Ireland (Republic)	63
Italy	37 5/8, 56 1/2
Latvia (USSR)	23 5/8, 29 1/2, 56 1/2, 60
Lithuania (USSR)	23 5/8, 29 1/2, 56 1/2, 60
Luxembourg	56 1/2
Netherlands	56 1/2
Norway	39 3/8, 42, 56 1/2
Poland	29 1/2, 56 1/2, 60
Portugal	39 3/8, 66
Rumania	36, 56 1/2, 66
Spain	23 5/8, 36, 39 3/8, 66
Sweden	35, 42, 56 1/2
Switzerland	39 3/8, 56 1/2
Turkey	56 1/2

WWW.SURVIVALEBOOKS.COM

Table 4-16. Principal track gages of the world (cont)

Country	Gages (in)
USSR	23 5/8, 39 3/8, 42, 56 1/2, 60
United Kingdom	23 5/8, 24, 30, 42, 56 1/2
Yugoslavia	23 5/8, 30, 39 3/8, 56 1/2
Central America and West Indies:	
Costa Rica	42
Cuba	36, 56 1/2
Dominican Republic	30, 42, 56 7/8
El Salvador	36
Guatemala	36
Haiti	30, 42
Honduras	36, 42
Jamaica	56 1/2
Nicaragua	42
Panama	36, 60
Puerto Rico	39 3/8
Trinidad	56 1/2
North America:	
Alaska (US)	56 1/2
Canada	36, 42, 56 1/2
Mexico	36, 56 1/2
Newfoundland (Canada)	42
United States (CONUS)	56 1/2
South America:	
Argentina	29 1/2, 39 3/8, 56 1/2, 66
Bolivia	30, 39 3/8
Brazil	30, 39 3/8, 56 1/2, 63
Chile	23 5/8, 30, 39 3/8, 42, 56 1/2, 66
Colombia	36
Ecuador	30, 42
Guyana	56 1/2
Paraguay	24, 29 1/2, 30, 39 3/8, 56 1/2
Peru	23 5/8, 36, 56 1/2
Suriname	39 3/8
Uruguay	56 1/2
Venezuela	24, 30, 39 3/8, 42, 56 1/2
Pacific Ocean:	
Australia	30, 42, 56 1/2, 63
Hawaii (US)	36
New Caledonia (France)	39 3/8
New Zealand	42
Philippines	42
Tasmania (Australia)	42

WWW.SURVIVALEBOOKS.COM

BRIDGE CAPACITY

Cooper's E-Rating

The weight, in thousands of pounds, which a bridge can support for each driving axle of a locomotive is referred to as the Cooper's E-rating of the bridge. Military railroad bridges are normally designed for a Cooper's E-45 rating but may be built for lighter or heavier loads as required. Determine the required Cooper's E-rating of a bridge for a particular locomotive by dividing the locomotive's weight on drivers by its number of driving axles.

For example, for a 2-8-0 (steam) locomotive weighing 140,000 pounds on drivers to cross a bridge safely, the bridge must have a rating of E-35 or above:

$$\frac{140{,}000}{4} = 35{,}000$$

Steel I-Beam Bridges

Use Table 4-17 to determine capacity of steel I-beam bridges constructed with two, four, six, or more steel stringers or girders of equal dimensions. One stringer per rail is assumed. Measure the width and thickness of the lower flange of one stringer at the center of the span length (see Figure 4-8). Also measure the depth and length of the stringer. Then select the steel stringer that is nearest to these dimensions and find the corresponding E-rating of the bridge. The age and condition of a bridge can reduce its E-rating. The quantity of this reduction must be determined by qualified personnel, normally from the Corps of Engineers. For additional information concerning bridge capacities, refer to TM 5-312.

Wooden Bridges

Use Table 4-18 to determine capacity of railway bridges with wooden stringers. Measure the width of each stringer under one track at the center of the longest span and add the measurements to obtain total stringer width. In Figure 4-9, the total stringer width is 2 X W. Also measure the depth and length of one stringer. Then refer to the table to find the corresponding E-rating.




Figure 4-8. Dimensions of a steel stringer




Figure 4-9. Dimensions of a wood stringer

Table 4-17. Capacity (E-ratings)—steel I-beams bridges

Stringer Dimensions (in)			Bridge Capacity (E-Rating) Span Length (ft)														
Thickness	Width	Depth	10	11	12	13	14	15	16	17	18	19	20	22	24		
3/8	8 3/8	18	E-42	E-41	E-41	E-41											
3/8	10 3/8	24		E-59	E-48	E-40	E-35	E-31	E-27								
1/2	10 3/8	30				E-61	E-59	E-51	E-46	E-41	E-37	E-33	E-30	E-27			
1/2	12 1/2	30						E-62	E-56	E-50	E-45	E-41	E-37	E-31	E-26		
			17	18	19	20	22	24	26	28	30	35	40	44	50	54	60	64
1	14	36	E-60	E-58	E-55	E-54	E-51	E-48	E-43	E-39	E-34	E-26						
1/2	12 3/8	42			E-60	E-54	E-45	E-39	E-34	E-30	E-26							
1 1/8	14	42				E-63	E-60	E-57	E-54	E-51	E-45							
1 1/8	16	42								E-60	E-54	E-42	E-32					
1 1/2	16	48									E-59	E-52	E-47	E-43	E-33			
1	16	48								E-66	E-57	E-45	E-35	E-30				
1 5/8	14	54										E-54	E-43	E-36	E-28			
1 3/4	14	60											E-60	E-54	E-43	E-37	E-30	E-27
1 1/2	14	60											E-57	E-48	E-38	E-33	E-27	
			50	54	60	64	70	74	80	84	90							
2 1/8	15	66	E-57	E-54	E-46	E-41	E-34	E-31	E-26									
2	14	66	E-56	E-48	E-40	E-35	E-30	E-26										
2	14	72	E-62	E-54	E-44	E-39	E-32	E-29	E-25									
2 1/2	15 1/2	72			E-55	E-51	E-43	E-38	E-33	E-29								
2 1/8	14	78		E-64	E-52	E-46	E-39	E-35	E-30									
2 1/2	16	84				E-64	E-54	E-49	E-41	E-38	E-30							
2 11/16	20	96								E-59	E-51							

WWW.SURVIVALEBOOKS.COM

WWW.SURVIVALEBOOKS.COM

Table 4-18. Capacity (E-ratings)—wooden bridges

Stringer Dimensions (in)		Bridge Capacity (E-Rating) Span Length (ft)						
Width	Depth	10	12	14	16	18	20	22
18	12	E-16	E-12					
18	14	E-22	E-18	E-10				
18	16	E-28	E-20	E-15	E-10			
18	18	E-38	E-26	E-18	E-14	E-12		
20	12	E-18	E-12					
20	14	E-25	E-17	E-12				
20	16	E-33	E-23	E-16	E-12	E-10		
20	18	E-43	E-29	E-21	E-16	E-13	E-10	
24	12	E-22	E-15	E-11				
24	14	E-30	E-21	E-14	E-11			
24	16	E-40	E-28	E-20	E-15	E-12		
24	18	E-52	E-36	E-25	E-19	E-15	E-12	E-10
36	12	E-34	E-23	E-17	E-12	E-10		
36	14	E-47	E-32	E-23	E-17	E-14	E-11	
36	16	E-62	E-43	E-30	E-23	E-19	E-15	
36	18	E-78	E-53	E-30	E-30	E-24	E-20	E-16
40	12	E-38	E-26	E-19	E-14	E-11		
40	14	E-52	E-36	E-26	E-20	E-16	E-12	
40	16	E-69	E-47	E-35	E-26	E-21	E-17	E-17
40	18	E-87	E-60	E-44	E-34	E-27	E-22	E-18
48	12	E-46	E-31	E-23	E-17	E-13		
48	14	E-63	E-43	E-31	E-24	E-19	E-15	
48	16	E-69	E-47	E-35	E-26	E-21	E-17	E-17
48	18	E-105	E-73	E-53	E-41	E-33	E-27	E-22
54	12	E-52	E-35	E-27	E-19	E-15		
54	14	E-72	E-49	E-35	E-22	E-18		
54	16	E-94	E-65	E-46	E-36	E-29	E-24	
54	18	E-119	E-42	E-60	E-46	E-38	E-30	E-25
60	12	E-58	E-40	E-30	E-22	E-17		
60	14	E-79	E-55	E-39	E-30	E-35	E-20	
60	16	E-104	E-72	E-52	E-40	E-33	E-27	
60	18	E-132	E-92	E-67	E-52	E-42	E-34	E-28

WWW.SURVIVALEBOOKS.COM

MAXIMUM BULK LOADS

The rated weight capacity of a car does not mean that the car can carry the rated tonnage of all items. For many types of cargo, the cubic capacity of the car is reached ahead of the rated weight capacity. When this occurs, the tonnage of the maximum cubic capacity of the car represents its actual capacity.

Freight cars loaded with high-density items can nearly always be loaded to their rated capacity. Examples of high-density items are ammunition, barbed wire, cement, flour, gravel, corrugated iron, rails, rifles in chests, sand, stone, sugar, telephone wire, and engineer tools.

See Table 4-19 for rated and actual car capacities for some lighter bulk items.

Table 4-19. Car capacity for some low-density items

	Car Capacity (STONs)		
	Rated		
	30	40	50
Item	Actual		
Blankets, baled	27	32	40
Bread	19	24	30
Canned goods, boxed	30	36	45
Clothing, baled	27	32	40
Meat	15	24	35
Motor vehicle parts	24	28	40
Sandbags	21	24	30
Tentage	15	20	30
Ties, railroad	19	26	32

WWW.SURVIVALEBOOKS.COM

CHAPTER 5

WATER TRANSPORT AND TERMINAL OPERATION

CONTENTS

		Page
Section I.	**ORGANIZATION AND PLANNING**	
	Water Transport and Terminal Units	5-1
	Terminal Planning	5-12
	Inland Waterway Planning	5-21
	Logistics-Over-The-Shore Planning	5-24
II.	**VESSEL DATA**	
	US Navy Ship and Service Craft Designations	5-32
	US Army Vessel Designations	5-34
	US Army Vessel Characteristics	5-34
	MARAD Classification System	5-41
III.	**TERMINAL EQUIPMENT, CARGO CONTAINERS, PALLETS, AND MARKINGS**	
	Terminal Equipment,	5-42
	Cargo Containers	5-46
	Pallets	5-47
	Cargo Address Markings	5-48

Section I. ORGANIZATION AND PLANNING

WATER TRANSPORT AND TERMINAL UNITS

Terminal commands may have any combination of assigned or attached units as required to carry out their mission:

Transportation Units:

- TOE 55-16 Headquarters and headquarters detachment, transportation motor transport battalion
- TOE 55-17 Transportation light truck company
- TOE 55-18 Transportation medium truck company
- TOE 55-19 Transportation car company
- TOE 55-28 Transportation heavy truck company

WWW.SURVIVALEBOOKS.COM

- TOE 55-116 Headquarters and headquarters company, transportation terminal battalion
- TOE 55-117 Transportation terminal service company, break-bulk
- TOE 55-118H Transportation terminal transfer company
- TOE 55-118J Transportation cargo transfer company
- TOE 55-128 Transportation medium boat company
- TOE 55-129 Transportation heavy boat company
- TOE 55-139 Transportation medium amphibian company
- TOE 55-157 Transportation floating craft general support maintenance company
- TOE 55-158 Transportation lighterage maintenance company, general support
- TOE 55-500 Transportation service organization headquarters units

Other Units:

- TOE 5-129 Engineer port construction company
- TOE 5-500 Engineer administrative and headquarters teams
- TOE 8-500 Medical service organization
- TOE 10-500 Quartermaster service organization
- TOE 11-500 Signal service organization
- TOE 14-500 Finance service organization
- TOE 19-76 Headquarters and headquarters detachment, military police battalion
- TOE 19-77 Military police company

A breakdown of Army water transport and terminal units according to TOE, mission, assignment, and capability is outlined in Table 5-1.

Table 5-1a. Tables of organization and equipment—water transport and terminal units

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
Headquarters and headquarters company, transportation terminal brigade	55-111H	MISSION: To command, plan, supervise, coordinate, and control the activities of brigade transportation terminal groups and other assigned or attached units and to perform staff planning for terminal operations. ASSIGNMENT: To a theater army command. Normally assigned to the transportation command (TRANSCOM). CAPABILITY: At level 1, provides command, control, and administration for up to eight transportation terminal groups and assigned/attached supporting units of other administrative or technical services. Performs unit maintenance on all organic equipment except communications equipment.
Headquarters and headquarters company, transportation terminal group	55-112H	MISSION: To command units employed in the operation of water terminals and to perform staff planning for water terminal operations. ASSIGNMENT: To a TRANSCOM. Normally attached to a transportation terminal brigade (TOE 55-111H). CAPABILITY: At level 1, provides command and supervision of operations, training, and administration on a 24-hour basis for up to six transportation terminal battalions.
Headquarters and headquarters company, transportation terminal battalion	55-116H	MISSION: To command units employed in the operation of water terminals.

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		ASSIGNMENT: To a theater army area command. Normally attached to a transportation terminal group. May be attached to a transportation terminal brigade or may operate separately under the supervision of an appropriate commander. CAPABILITY: At level 1, provides command, control, planning, and supervision for attached units required to discharge up to four ships simultaneously at an established water terminal or up to two ships at a LOTS site.
Transportation terminal service company (break-bulk)	55-117H	MISSION: To discharge, back-load, and transship break-bulk cargo at water terminals located at ports or beaches. ASSIGNMENT: To a TRANSCOM. Normally attached to a transportation terminal battalion or may operate separately under supervision of an appropriate commander. CAPABILITY: At level 1, with 75 percent equipment availability and 24-hour operation, this unit— • Discharges one break-bulk ship in a fixed port or over beaches at the daily rate of 1,000 STONs of cargo per day, or back-loads 500 STONs of cargo per day. • Sorts cargo by destination and loads cargo from marshaling yards on land transportation. • Accounts for all cargo handled as required by MILSTAMP; prepares necessary transportation documentation. • Provides limited in-transit storage as required. • Performs unit maintenance on all organic equipment except communications equipment.
Transportation terminal transfer company	55-118H	MISSION: To transship cargo at Army air, rail, motor, and inland barge terminals. ASSIGNMENT: Normally assigned to a theater army area command, TRANSCOM, or transportation brigade. May be attached to a motor transport group or terminal group. CAPABILITY: This unit— • Operates up to three separate terminals on a round-the-clock basis (SRC 55-118H710). Each terminal transships 300 STONs of break-bulk cargo or 200 containers per day for a daily unit total of 900 STONs, 600 containers, or a mix thereof. • Operates up to three separate terminals on a single shift (SRC 55-118H720). Each terminal transships 150 STONs of break-bulk cargo or 100 containers per day for a daily unit total of 450 STONs, 300 containers, or a mix thereof. • Redocuments transshipped cargo or containers as required. • Stuffs and unstuffs containers on a limited basis.
Transportation cargo transfer company	55-118J	MISSION: To transship cargo by air, rail, and motor terminals. ASSIGNMENT: Normally assigned to a TRANSCOM or to a corps support command (COSCOM). Normally attached to a motor transport battalion, terminal, or aviation group or battalion.

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		CAPABILITY: At level 1, this unit— • Operates up to three separate terminals on a round-the-clock basis (SRC 55-118J410). Each platoon transships 1,000 STONs of break-bulk cargo or 150 containers per day for a daily unit total of 3,000 STONs of break-bulk cargo, 450 containers, or a mix thereof. • Operates a single terminal on a round-the-clock basis (SRC 55-118J420). The unit transships 1,000 STONs of break-bulk or 150 containers. • Redocuments transshipped cargo or containers as required. • Stuffs and unstuffs containers on a limited basis.
Transportation terminal service company (container)	55-119H	MISSION: To discharge, back-load, and transship containerized cargo at terminals located at beaches or fixed ports. ASSIGNMENT: To a TRANSCOM. Normally attached to a transportation terminal battalion or may operate separately under supervision of an appropriate commander. CAPABILITY: At level 1, with 75 percent equipment availability and 24-hour operations, this unit— • Discharges or back-loads 300 containers, or simultaneously discharges 150 containers and back-loads 150 containers (LOTS operation). • Discharges or back-loads 600 containers, or simultaneously discharges 300 containers and back-loads 300 containers (fixed-port operations). • Sorts containers by destination, loads containers from marshaling yards on land transportation, and stuffs and unstuffs containers on a limited basis. • Receives and processes containers for retrograde. • Accounts for all cargo handled as required by MILSTAMP and prepares necessary transportation documentation. • Provides limited in-transit storage.
Transportation terminal service company (container)	55-119J	MISSION: To discharge, back-load, and/or transship containerized cargo at water terminals located at beaches or fixed ports. On an exception basis when augmented with team JE, to discharge, back-load, and transship break-bulk cargo at water terminals located at beaches or fixed ports. ASSIGNMENT: To an HHC TRANSCOM or a COSCOM when employed to support independent corps operations. Normally attached to an HHC transportation terminal battalion. CAPABILITY: At level 1, in two shifts with four cranes operational and 75 percent availability of other mission equipment, this unit— • Discharges or back-loads 300 containers, or simultaneously discharges 300 containers and back-loads 300 containers (LOTS operation).

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		• Sorts containers by destination, loads containers from marshaling yards on land transportation, and performs limited stuffing/unstuffing of containers. Receives and processes containers for retrograde. • Accounts for all cargo handled as required by MILSTAMP and prepares necessary transportation documentation. • Provides limited in-transit storage. • Discharges one break-bulk ship in a fixed port or over the beach at a rate of 1,000 STONs of cargo per day (when augmented with team JH).
Transportation terminal service company (break-bulk and container)	55-124J	MISSION: To discharge, back-load, and transship break-bulk and containerized cargo at water terminals located at beaches or fixed ports. ASSIGNMENT: To a TRANSCOM or to a COMSCOM when employed to support independent corps operations. Normally attached to a transportation terminal battalion. CAPABILITY: At level 1—in two shifts with 75 percent operational availability of all mission equipment— • In a LOTS operation, this unit— — Discharges 1,600 STONs of break-bulk cargo or back-loads at the same rate, or simultaneously discharges 800 STONs of break-bulk cargo and back-loads 800 STONs of break-bulk cargo. — Discharges 200 containers or back-loads 200 containers, or simultaneously discharges 100 containers and back-loads 100 containers (when supported by team JJ). • In a fixed-port operation, this unit— — Discharges 400 containers or back-loads at the same rate, or simultaneously discharges 200 containers and back-loads 200 containers (when supported by team JJ). — Discharges 2,500 STONs of break-bulk cargo or back-loads at the same rate, or simultaneously discharges 1,250 STONs of break-bulk cargo and back-loads 1,250 STONs. — Sorts break-bulk and containers by destination, loads break-bulk cargo and containers from the marshaling yards on land transportation, and performs limited stuffing and unstuffing of containers. — Receives and processes containers for retrograde. — Provides limited in-transit storage.
Transportation medium boat company	55-128H	MISSION: To provide and operate landing craft for the movement of personnel and cargo in Army water terminal operations and Army waterborne tactical operations and to augment naval craft in joint amphibious operations when required. ASSIGNMENT: To a theater army command or other appropriate command in a theater of operation. Normally attached to a transportation terminal battalion (TOE 55-116) or a transportation

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		terminal group (TOE 55-112). May be attached in support of a joint amphibian operation or may operate separately under an appropriate commander. CAPABILITY: At level 1, with 75 percent equipment availability and 24-hour operations, this unit— • Transports an average of 1,000 STONs of noncontainerized cargo, based on an average of 42 STONs each for 12 landing craft making two trips daily. • Transports in a one-time maximum lift 960 STONs of noncontainerized cargo, based on 16 landing craft. • Transports In a one-time maximum lift 3,200 combat-equipped troops, based on 16 landing craft. • Transports 240 20-foot containers per day, based on one container each for 12 landing craft making 20 trips daily.
Transportation heavy boat company	55-129H	MISSION: To provide and operate landing craft for transporting personnel, containers, and outsize cargo in offshore discharge operations and for augmenting lighterage service. ASSIGNMENT: To a theater army command in a theater of operations. Normally attached to a transportation terminal battalion or a transportation terminal group. May be attached In support of a joint amphibious operation or may operate separately under an appropriate commander. CAPABILITY: At level 1, in 24-hour operations, this unit— • Transports an average of 1,500 STONs of noncontainerized cargo, 4,000 troops with individual equipment, or 540 STONs of vehicles, or 1,500 STONs of medium tanks, based on an availability of 10 landing craft, each making one trip daily. • Transports an average of 160 containers (20' x 8' x 8'), based on an availability of 10 landing craft, each making four trips daily. • Transports in a one-time maximum lift 1,800 STONs of noncontainerized cargo or 4,800 troops with individual equipment based on an availability of 12 landing craft. Each landing craft transports 150 STONs of cargo or 400 troops for a trip not exceeding 2 hours. (For trips more than 2 hours, but less than 3 hours, maximum troop lift is 4,200; for trips over 3 hours, maximum is 3,600).
Transportation medium lighter company (LACV)	55-137H	MISSION: To provide lighterage for movement of general cargo and light wheeled vehicles between ships at anchorage and inland transfer and segregation areas in LOTS operations or amphibious operations. ASSIGNMENT: To a TRANSCOM. Normally attached to a transportation terminal battalion or may operate separately under the supervision of an appropriate headquarters.

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		CAPABILITY: At level 1, this unit— • In a 24-hour operations, with 67 percent of the equipment operational, transports a daily average of 300 containers or 3,900 STONs of unitized cargo, based on eight LACVs. LACVs each average 1.87 containers per hour or 37.4 per day. • Using the operational swing crane installed on the vessel, off-loads transported containers where no cargo discharge facilities are available at a slight trade-off of cargo weight/mission endurance (fuel). • Operates inland over hastily prepared trails and barriers which are impassable to most cargo vehicles and materials-handling equipment.
Transportation medium lighter company (LACV)	55-137J	MISSION: To provide lighterage for the movement of general cargo and light wheeled vehicles between ships at anchorage and inland transfer and segregation areas in LOTS operations or amphibious operations. ASSIGNMENT: To a TRANSCOM. Normally attached to a transportation terminal battalion or may operate separately under the supervision of an appropriate headquarters. CAPABILITY: At level 1, in two shifts, this unit— • With 67 percent of the craft operational, transports a daily average of 300 containers or 4,050 STONs of cargo, based on eight LACVs. LACVs each average 1.87 containers per hour or 37.4 containers per 20-hour operating day. • Operates from ship to shore, shore to shore, and inland over marginal terrain which is impassable to most cargo vehicles and materials-handling equipment.
Transportation medium amphibian company	55-139H	MISSION: To provide lighterage for the movement of general cargo and light wheeled vehicles between ships at anchorage and inland transfer and segregation areas in LOTS or amphibious operations. ASSIGNMENT: To a theater army command. Normally attached to a transportation terminal battalion. May be attached to a transportation terminal group or a transportation terminal brigade, or may operate separately under the supervision of an appropriate headquarters. CAPABILITY: At level 1 (SRC 55-139H510), with 75 percent equipment availability (18 LARCs) and 24-hour operations, this unit— • Transports 1,080 STONs of noncontainerized cargo or light wheeled vehicles per day, each LARC carrying an average of 10 STONs of cargo per trip and averaging six trips per day (based on field experience). • Transports 360 20-foot containers (containers not exceeding 15 STONs and sea conditions not exceeding 5 feet), each LARC carrying one container and averaging 20 trips per day (based on field experience). With 75 percent equipment availability (18 LARCs), in a single shift (SRC 55-139H20), this unit—

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		• Transports 540 STONs of general cargo and light wheeled vehicles, each LARC carrying an average of 10 STONs of cargo per trip and averaging three trips per shift (based on field experience). • Transports 180-foot containers (containers not exceeding 15 STONs and sea conditions not exceeding 5 feet), each LARC carrying one container and averaging 10 trips per day (based on field experience).
Transportation floating craft general support maintenance company	55-157	MISSION: To provide intermediate maintenance for Army landing craft, amphibians, and harbor craft and to provide intermediate maintenance of radio and radar equipment organic to Army marine craft. ASSIGNMENT: Normally to a TRANSCOM or transportation terminal group. May be attached to a transportation terminal battalion. CAPABILITY: This unit— • Provides productive maintenance as listed in Table 5-1b. • Receives, stores, and issues approximately 9,000 line items of marine-peculiar repair parts and items required for its maintenance missions. • Performs marine salvage operations in conjunction with the floating craft intermediate maintenance mission.
Transportation lighterage maintenance company, general support	55-158	MISSION: To provide intermediate maintenance for wheeled amphibians and landing craft and for radio and radar equipment installed on them and to provide unit-level repair parts, components, and maintenance supplies to support lighterage units' amphibians and landing craft, including radio and radar equipment. ASSIGNMENT: To a terminal group or TRANSCOM. Normally attached to a terminal battalion but may operate separately under supervision of an appropriate commander designated by theater army. CAPABILITY: This unit— • Provides productive maintenance listed in Table 5-1b. • Receives, stores, and issues approximately 5,000 line items of marine equipment repair parts and supply items required for the company's maintenance and supply mission. • Operates a direct exchange service for selected items.
Transportation watercraft teams:	55-530H	ASSIGNMENT: To a watercraft unit or a transportation terminal headquarters.
FA, Deck cargo barge, nonpropelled		MISSION: To transport cargo other than bulk liquid. CAPABILITY: When under tow, can transport 150 STONs of deck cargo.
FB, Picketboat, 46-foot		MISSION: To provide water transportation for patrol, command, inspection, and general utility services in support of terminal or inland waterway operations.

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		CAPABILITY: In 24-hour operations, carries up to 10 passengers at an average speed of 14 knots.
FC, Deck or liquid cargo barge, 120-foot, nonpropelled		MISSION: To transport deck or bulk liquid cargo.
		CAPABILITY: In 24-hour operations, when under tow, transports up to 4,160 barrels of liquid cargo or 655 STONs of dry cargo.
FD, Harbor tug, 45-foot		MISSION: To perform tug and towing services in support of terminal and inland waterway operations.
		CAPABILITY: In 24-hour operations, shifts small nonpropelled barges at variable speeds up to 6 knots. Assists in patrolling, firefighting, and general utility use.
FE, Passenger and cargo or picketboat, 65-foot		MISSION: To provide transportation in a harbor area for personnel and cargo in support of terminal operations.
		CAPABILITY: In 24-hour operations, transports up to 27 STONs of cargo or 24 passengers at an average speed of 11 knots. Serves as a command and control craft for boat operations. Vessel patrols offshore at a speed of 12 knots with a troop capacity of five.
FF, Refrigerated cargo barge, 120-foot, nonpropelled		MISSION: To transport refrigerated cargo.
		CAPABILITY: In 24-hour operations, when under tow, transports 355 STONs of refrigerated cargo.
FG, Harbor tug, 70-foot		MISSION: To perform tug and towing service in support of terminal operations.
		CAPABILILTY: In 24-hour operations, shifts all size barges at variable speeds up to 11 knots. Assists in docking and undocking large vessels and in firefighting.
FH, Barge crane, 68-ton		MISSION: To load and discharge heavy-lift cargo that is beyond the capability of ship's gear.
		CAPABILITY: IN 24-hour operations, makes individual lifts up to 68 STONs.
FI, Barge crane, 100-ton		MISSION: To load and discharge heavy-lift cargo that is beyond the capability of ship's gear.
		CAPABILITY: Makes individual lifts up to 100 STONs. Operates on a 24-hour basis.
FJ, Harbor tug, 100-foot		MISSION: To perform tug and general towing services in support of terminal operations.
		CAPABILITY: In 24-hour operations, performs heavy tows within a harbor area or limited offshore towing between terminals. Berths and unberths oceangoing vessels. Transports itself with a qualified escort in transoceanic voyages
FK, Oceangoing tug, 126-foot		MISSION: To make ocean tows of barges and vessels.
		CAPABILILTY: In 24-hour operations, makes ocean tows of barges and vessels.
FL, Liquid or dry cargo barge, self-propelled		MISSION: To transport liquid or dry cargo in terminals or along coastwide routes not served by MSC.
		CAPABILITY: In 24-hour operations, along coastwide routes not served by MSC.
FM, Beach discharge lighter		MISSION: To transport large quantities of mobile or outsize equipment, unitized cargo, and containers from ships offshore to the beach.

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		CAPABILITY: This team— • Marries with and discharges nine RO/RO vessels where port facilities for the vessel are not available. • Transports pier to pier one hundred 20-foot containers with an average weight of 15 STONs each; transports ship to pier 50 containers; or transports 200 empty containers. • Provides its own unit-level administration, supply, and food service and its own DS and GS maintenance.
FN, Lighter, amphibian, LARC-LX		MISSION: To provide amphibious lighterage service primarily for heavy, outsize, or bulky equipment. CAPABILITY: In 24-hour operations, with an amphibian availability rate of 75 percent, this unit— • Transports daily 450 STONs of heavy, outsize, or bulky noncontainerized cargo in five trips. • Transports daily twenty-one 20-foot containers or 2,625 combat-equipped troops in seven trips. • Provides its own unit-level administration, supply, maintenance, and surface transportation ashore. • Performs its own amphibian DS and GS maintenance.
FO, Oceangoing tug, 143-foot		MISSION: To provide ocean tow of barges and vessels. CAPABILITY: In 24-hour operations, makes ocean tows of barges and vessels.
Transportation watercraft maintenance teams:	55-550H	
IA, Diver team		MISSION: To perform deep- and shallow-water diving functions. ASSIGNMENT: To a transportation group or a transportation terminal battalion. CAPABILITY: Performs approximately 24,800 annual man-hours of diving, underwater reconnaissance missions, and underwater welding and cutting, salvage, hull repair, and structure inspection and repair.
IB, Floating craft maintenance team (GS)		MISSION: To perform GS maintenance on floating craft. ASSIGNMENT: To a transportation group or a transportation floating craft GS maintenance company. CAPABILITY: Provides personnel, skills, and equipment for the following annual man-hours of maintenance: • Hull repair/inspection—18,600 • Machinist—9,300 • Marine engine repair—12,400 • Metal work—3,100 • Plumber pipefitter—3,100 • Radio repair—3,100 • Rigger—3,100

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
IC, Lighterage maintenance team (DS)		MISSION: To perform hull and engine maintenance on amphibians and landing craft. ASSIGNMENT: To a transportation terminal battalion or a transportation lighterage DS maintenance company. CAPABILITY: Provides personnel, skills, and equipment for the following annual man-hours of maintenance: • Hull repair/inspection—24,800 • Machinist—6,200 • Hydraulic repair—3,100 • Radio repair—3,100 • Marine engine repair—52,700
Transportation terminal service teams:	55-560J	MISSION: To provide transportation terminal services. ASSIGNMENT: To a transportation command for attachment as required. CAPABILITY:
JA, Stevedore/container-handling equipment maintenance		Maintains stevedore gear and rigging equipment.
JB, Cargo documentation		Performs documentation required in the loading and discharge of 500 STONs of general cargo or 480 containers daily in a water terminal, railhead, truckhead, or airhead.
JC, Freight consolidation and distribution		Processes 100 LCL shipments daily at a consolidation and distribution point, fixed water terminal, barge site, railhead, airhead, or truckhead, or stuffs and unstuffs twenty-five 20-foot containers or equivalents daily.
JD, Transportation contract supervision		Arranges for the loading or discharge of cargo from ships or barges and the clearance of discharged cargo from the terminal by contract. Arranges for the movement of cargo from terminals, depots, or local procurement sources by inland waterways and highway transport contracts. Administers contracts made in connection with loading, discharge, terminal clearance, and transport of cargo.
JE, Cargo hatch gang		Provides personnel and equipment to handle 240 containers daily (two cranes on a one-shift basis) at a water terminal or provides personnel and equipment to handle 100 containers daily on a one-shift basis at a LOTS site (two cranes, one at shipside and one at the beach).
JF, Container-handling (ship)		Provides personnel and equipment to handle 240 containers daily (two cranes on a one-shift basis) at a water terminal or provides personnel and equipment to handle 100 containers daily on a one-shift basis at a LOTS site (two cranes, one at shipside and one at the beach). Also provides limited organizational maintenance to supporting unit.
JG, Container-handling (shore)		Provides personnel and equipment to transship 120 containers at a water terminal or 100 containers in a LOTS operation from the shore crane to the container-marshaling area and to operate the container-marshaling area in one shift.
JH, Break-bulk augmentation (container)		When attached and integrated into operations of a transportation terminal service company (container), discharges 1,000 STONs of break-bulk

WWW.SURVIVALEBOOKS.COM

Table 5-1a. Tables of organization and equipment—water transport and terminal units (cont)

UNIT	TOE	MISSION/ASSIGNMENT/CAPABILITY
		cargo per day or back-loads 500 STONs of break-bulk cargo per day.
JI, Automated cargo documentation		In two shifts, documents break-bulk cargo or containers being loaded or discharged from up to four ships in a fixed port operation or two ships in a LOTS operation.
JJ, Heavy crane platoon		• In a fixed port operation, handles 400 containers in two shifts. • In a LOTS operation, handles 200 containers in two shifts. • Performs organizational maintenance on organic equipment, except C-E; performs DS maintenance on container-handling equipment.

Table 5-1b. Capabilities for TOEs 55-157 and 55-158 (approximate annual man-hours of productive maintenance)

	TOE 55-157			TOE 55-158		
	Level 1	Level 2	Level 3	Level 1	Level 2	Level 3
Diving	21,700	21,700	18,600	-	-	-
Hull repair	86,600	74,400	65,100	68,200	52,700	49,600
Hydraulic repair	-	-	-	6,200	6,200	6,200
Instrument repair	3,100	3,100	3,100	-	-	-
Machining	24,800	21,700	18,600	9,300	9,300	6,200
Marine electrical repair	18,600	18,600	12,400	24,800	24,800	24,800
Marine engine repair	55,800	49,600	43,400	167,400	142,600	117,800
Power generator equipment repair	12,400	9,300	6,200	-	-	-
Plumbing and pipe fitting	9,300	9,300	9,300	6,200	6,200	6,200
Radar repair	9,300	6,200	6,200	6,200	3,100	3,100
Radio repair	12,400	12,400	9,300	6,200	6,200	6,200
Refrigeration	15,500	15,500	15,500	-	-	-
Rigging repair	12,400	9,300	9,300	-	-	-
Sheet metal working	12,400	9,300	9,300	-	-	-
Welding (blacksmithing)	12,400	9,300	9,300	-	-	-
Total	306,700	269,700	235,600	294,500	251,100	220,100

NOTE: Man-hours criterion for Category III (mobile) units is 3,100 available productive maintenance man-hours per repair person per year according to AR 570-2.

TERMINAL PLANNING

Reference Publications

There are several sources of information to use in the initial phases of port selection and water terminal planning—The *World Port Index (DMA Pub 150)* and *Sailing Directions.* These publications are published and updated by the Defense Mapping Agency Hydrographic/Topographic Center (DMAHTC), Washington, DC 20390. To ensure continuous updating of these references, request to be put on the DMAHTC's mailing list for *Notice to Mariners.*

World Port Index. This publication includes location, characteristics, known facilities, and available services for over 7,200 ports, shipping facilities, and oil terminals throughout the world. The 7,200 ports are listed by their present and former names, applicable Sailing Direction number, and port index number. Chartlets showing the sequence of ports and examples of harbor types are also included.

WWW.SURVIVALEBOOKS.COM

Following is a list of items found in the index:

- *Index number.* Each port and place in the text is numbered consecutively. Index numbers for ports and places are found in the alphabetical index; page numbers are not listed. If there is an alternate or more familiar name, that name will have the same index number. However, only the approved name will appear in the text. In general, ports are listed under the names approved by the US Board on Geographic Names.

- *Ports.* Ports are grouped according to country and locality in the same geographic sequence as the chartlets in the forepart of the volume. The listing of ports in off-lying islands normally interrupts the coastal listing at some convenient place near the island. River ports are listed toward the beginning of navigation, alternating from bank to bank unless local considerations make another listing more practicable.

- *Latitude and longitude.* The position of each port is obtained from the best scale chart available, expressed in degrees and minutes.

- *Sailing Directions information.* The Sailing Directions publication number for the port or area in which the port is located is normally given.

- *Chart.* The number of the best scale chart issued by the DMAHTC is listed with no prefix. In some cases foreign charts are listed when the DMAHTC provides no coverage. These charts can be obtained from the hydrographic departments or services of the countries concerned or their authorized agents.

- *Size.* Classification of port size is based on area, facilities, and wharf space.

- *Harbor type.* The harbor is the principal water area of the port. Examples of harbor classifications are coastal natural, coastal breakwater, or open roadstead.

- *Shelter.* Shelter (from wind, sea, and swell) is the area where normal port operations are conducted, usually the wharf area. Shelter for the anchorage area is given for ports where cargo is handled by lighters.

- *Entrance restrictions.* These are natural factors such as ice or heavy swell that restrict the entrance of vessels.

- *Overhead limitations.* This entry only indicates that bridge and overhead power cables exist. Refer to the chart for particulars.

- *Depths.* Depth information is given for the main channel, main anchorage, and principal cargo pier and/or oil terminal. Depths refer to chart datum. Depths are given in increments of 5 feet (1.5 meters).

- *Channel (controlling).* The controlling depth of the principal or deepest channel at chart datum is given. The channel selected should lead to the anchorage (if within the harbor) or to the wharf or pier. If the channel depth decreases from the anchorage to the wharf/pier and cargo can be worked at the anchorage, then the depth leading to the anchorage is used.

- *Anchorage.* The depth in the anchorage is the least depth in the best or principal anchorage. The depth listed is a general depth rather than an isolated shoal spot. A shoal which does not necessarily obstruct the anchorage is not considered for the least depth if the rest of the anchorage is safe and usable.

- *Cargo pier and oil terminal.* Where applicable, the greatest depth alongside the wharf/pier and oil terminal is given according to chart datum. If there is more than one wharf/pier, then the one which has greatest usable depth is shown.

- *Tide.* The mean range in feet is normally given, but the mean rise is substituted if range data is not available. The distinction between range and rise can be disregarded without affecting the general usefulness of this publication.

- *Maximum size (vessel).* Sizes of vessels that can be accommodated are indicated by an L (ships over 500 feet) or an M (ships less than 500 feet).

- *Good holding ground.* Good holding ground is indicated only where actual anchorage conditions have been reported.

- *Turning area* Entry indicates that a turning basin or other water area for turning vessels is available in the port.

- *First port of entry.* Entry indicates a port where a ship may enter and clear foreign goods through customs.

WWW.SURVIVALEBOOKS.COM

- *US representative.* Entry indicates whether the United States maintains civilian or military representation in that port.
- *ETA message.* Entry indicates whether an ETA message is required for that port.
- *Pilotage.* Entry indicates the necessity or advisability of taking a pilot. In some cases, pilotage may be compulsory although pilots are not actually stationed at the port in question and must be obtained elsewhere.
- *Tugs.* Entry indicates whether tugs are available for docking or anchorage assistance.
- *Quarantine.* Entries indicate if regular quarantine procedures are required or if further details must be found in other publications.
- *Communications.* Types of available communications are noted for the port or nearby area.
- *Load/off-load.* Entry refers to the area where normal port operations are conducted.
- *Medical facilities.* Entry indicates port has some form of medical facilities that will accommodate crew.
- *Garbage disposal.* Garbage can be disposed of at the pier or by lighters at the anchorage or mooring at indicated ports.
- *Degausser, dirty ballast, cranes, and lifts.* Facilities are available as indicated.
- *Services.* Availability y of normal port services is indicated.
- *Supplies.* The availability of provisions, water, and fuel oil is listed. Fuel oil and diesel oil are listed separately. Where the original source information fails to distinguish between the two, both kinds of fuel are presumed available and are so listed.
- *Repairs.* Repair facilities for oceangoing vessels are classified as follows:
  - A–major; extensive overhauling and rebuilding in well-equipped shipyards.
  - B–moderate; extensive overhauling and rebuilding that does not require drydocking. Suitable drydocking facilities are usually lacking or inadequate.
  - C–limited; small repair work in independent machine shops or foundries.
  - D—emergency only.
  - N—none.
- *Drydock and railway.* The general size and type of the largest underwater repair facility in a port is listed.
- *Sailing Directions.* There are 43 volumes of *Sailing Directions—35* of *Sailing Directions En Route* and 8 of *Sailing Directions (Planning Guide).* Each *Sailing Directions (Planning Guide)* covers one of the world's great land-sea areas, based on an arbitrary division of the world's seaways into eight ocean basins.

Chapter 1, Countries, contains information about all of the countries adjacent to a particular ocean basin covered by one of the eight publications. It also covers pratique, pilotage signals, and pertinent shipping regulations.

Chapter 2, Ocean Basin Environment, contains information on the physical environment of an ocean basin. Included are ocean summaries and local coastal phenomena not found in referenced atlases, as well as concise information about physical forces to consider during planning.

Chapter 3, Warning Area, includes the firing danger areas, submarine operating areas, and other cautions pertinent to an area.

Chapter 4, Ocean Routes, describes the recommended steamship routes as they originate from all major US ports and naval bases and terminate in foreign ports in the planning guide area. Applicable traffic separation schemes are also included.

Chapter 5, Navaid Systems, describes the radio-navigation systems pertaining to the ocean area described. National and international systems of lights, beacons, and buoys are described and illustrated.

Elements of Terminal Planning

Twenty-four hours is generally considered a complete, round-the-clock working day for terminal and related water transport operations. The day consists of two 10-hour shifts with the remaining 4 hours taken up in mealtime, shift changes, and maintenance. For general planning purposes, a transportation terminal service company (TOE 55-117) or its equivalent is considered capable of discharging 1,000 STONs per 24-hour working day.

WWW.SURVIVALEBOOKS.COM

The elements normally considered in terminal planning are—

- Existing terminal capacity (total tonnage and personnel that can be received, processed, and cleared through the terminal in a day).
- Terminal work load required to support the particular operation (target cargo tonnage and number of personnel per day).
- Base development requirements needed to increase terminal capacity to meet the target tonnage (requirements for construction, equipment, and personnel).

Terminal capacity. Three major factors determine throughput capacity:

- *Terminal reception capacity*— the number and type of ships that can be moved into the harbor or coastal area of the terminal per day.
- *Terminal discharge capacity*— the amount of cargo and personnel that can be discharged in the terminal per day.
- *Terminal clearance capacity*— the amount of cargo and personnel that can be moved through and out of the terminal per day.

For planning purposes, express each factor as short tons per day, containers, or square feet / measurement tons per day. In every instance, one factor will be the limiting (determining) factor. Even though the limiting factor may be obvious, be sure to estimate all three factors accurately because the estimates will point out areas that need improvement.

Two more factors that impact on throughput capacity are—

Transfer capacity— the amount of cargo and personnel that can be moved from the discharge point to the in-transit storage areas.

Storage capacity— the amount of cargo that the in-transit storage areas can hold, based on the average dwell time of the cargo.

See Figure 5-1 for a checklist to use when determing throughput capacity. For further information, see FM 55-60, FM 101-10-1, MTMC Report TE 73-44, Parts I and II, and MTMC Report TE 73-44A.

Terminal work load. The theater commander assigns the mission (terminal work load) of a particular terminal. The mission assignment is a target tonnage based on the terminal's throughput capacity. Both initial and anticipated tonnages are included in the target tonnage figure. Initial tonnage is the amount of cargo the terminal organization is expected to handle before its capability is increased by base development. Anticipated tonnage is the amount of cargo required at a future specified date to support a particular operation and to build up a reserve supply for the support of future operations. When the target tonnage assignment is made, the terminal commander estimates the construction, equipment, and personnel required to increase the terminal capacity to handle the anticipated tonnage. The actual capability of the terminal depends on its sustained ability to receive and clear the daily capacity over a period of time.

Berthing Facilities and Anchorage Areas

Terminal discharge capacity is the l-day capacity of a terminal to accommodate ships in the harbor and to discharge them. For general planning purposes, ships are discharged in two ways—by direct discharge onto the pier or wharf from vessels berthed alongside or by lighterage from vessels anchored offshore or in the stream. Deep-draft wharfage is required for pierside discharge; shallow-draft wharfage and anchorage areas are considered jointly for lighter discharge. See the glossary for definitions of anchorage, berth, mole, pier, quay, and wharf.

When planning, consider availability of harbor berths and anchorage, wharf capacity, lighterage discharge, and local conditions. Determine whether vessels can be brought into the anchorage areas and alongside the berth. Berths and anchorages are evaluated according to size of the vessels they can accommodate. Berthing capacity is then determined.

Berth capacity. Port capacity estimates are based on all available berthing facilities. Include all facilities suitable for handling cargo in the estimate. If the use of a particular berth is doubtful and its capacity has been included in the estimate, a clarification should be given. Berthing capacity is materially affected by the followilng factors.

WWW.SURVIVALEBOOKS.COM




Figure 5-1. Terminal throughput capacity checklist

Layout. The analyst must consider the layout of the facility:

- Adequacy of approaches.
- Stacking space on the landward side.
- Raised or depressed tracks.
- Stuffing and stripping sheds.
- Truck backup for stuffing and stripping sheds.
- Open storage space.
- Transit shed space.
- Number and size of transit shed doors.

Along with the berth layout, consider curbs, fences, and surfacing material, depth of water alongside at high and low water, and location of on- and off-loading ramps.

Weather. Weather has a direct bearing in berth use and capacity–especially during extreme conditions.

Alignment. Wharf face alignment is important. Consider the angle points and curvatures along the wharf face. If they are excessive, reduce the usable linear footage appropriately.

Wharf construction. Deck strengths of piers, wharves, and transit shed floors are extremely important. A rule of thumb for determining if load capacity is adequate is the current use of the area in question. If it is known that a certain cargo is normally handled, a fair load-capacity evaluation can be made. The ideal load capacity is 800 or more pounds per square feet; 500 or less pounds per square feet is considered marginal to unacceptable. Consider the height of the wharf or pier deck relation to the rise and fall of the tide. This is extremely important when considering ramp use on RO/RO ships.

WWW.SURVIVALEBOOKS.COM

Several factors limit using the stern or side ramp on RO/RO vessels. The distance between the top of the pier and the water at mean low water (MLW) may prevent ramp use. If this distance is excessive and exceeds the angle limitations of the ramps, the side or stern opening may be below the top of the pier. On the USNS Comet, USNS Admiral William M. Callaghan, and USNS Meteor, it is possible for the ramp angles to be excessive because the ramp openings are too far above the pier. The vessel draft and the range of tidal change, of course, contribute to the magnitude of this problem. This limitation must be evaluated on a case-by-case basis to ascertain whether a specific ship can use its stern or side ramps for loading at a specific time period.

The working space is determined by the type wharf; the length and width of the apron, exits, and decking; type of cargo handled; and anticipated tonnages. The working space must be large enough to allow cargo to be unloaded and cleared without delay. See MTMC Reports TE 73-44 and TE 73-44A for detailed information on computing or projecting specific types of working spaces. Local customs, specialized construction, and the pier may cause variations in berth dimensions, but the loaded draft of the ship will always be the controlling factor. Vessels require 60 to 70 feet of wharf space in addition to their measured length overall (LOA) to allow their mooring lines to be properly stretched out. Use the following berth specifications for general planning.

General Berths

Class	Length (ft)	Water Depth (ft)[1]
A	1,000	*32-36*
B	*850*	*30-34*
C	*700*	*22-30*
D	*550*	17-22
E	400	13-17
F	100	6-13

Tanker Berths

Class	Length (ft)	Water Depth (ft)[1]
T-A	1,200	50-75
T-B	800	35-50
T-C	400	20-35
T-D	250	14-20

[1]Depths are computed for MLW.

Use the following formulas to calculate diameter of anchorage berths:

Offshore anchorage (diameter) = 2(7D + 2L)

In-the-stream anchorage (diameter) = $4D + 2L \times R$

where:

D = depth of water at MLW
L = overall length of ship
R = reserve factor of 1.4

Lighterage discharge. Wharves used by lighters should be within a reasonable distance of enough anchorages and moorings. Lighterage berths are assigned in units of 100 feet for each lighter (to the nearest 100 feet). The unit measurement must be used realistically. Disregard length of wharf more than 100 feet but less than the next 100-foot unit. A 350-foot wharf accommodates three lighters at the same time. All alongside berths with depths less than 18 feet are considered lighter berths. For LASH and SEABEE barges, refer to *"Basic Cargo Load/Unload Times."*

Temporary storage. Break-bulk cargo can be temporarily stored in open or covered areas. To determine usable square foot space, allow for fire lanes and center, intersecting, and working aisles. To determine usable cubic foot space, you must allow for lost height in stocking odd-shaped items and for height restrictions caused by lighting and sprinklers. Use the following formulas for initial planning for open or closed storage:

Usable square feet = A x .55

Usable cubic feet = A x B x .45

Measurement ton capacity = $\frac{Ax\ Bx\ .45}{40}$

where:

A = available square feet
B = height available in feet

Note: Cargo dwell time will greatly influence capacity of storage areas. Dwell time can also be very detrimental to the throughput capacity of the terminal.

Open storage. Approximately 10,000 square feet of space is required for each 1,000 MTON

WWW.SURVIVALEBOOKS.COM

of cargo (10 square feet per MTON) to allow 50 percent space for surge and security. Average stock height is 6 feet or two pallets high.

Covered storage. Approximately 7,500 square feet of space is required for each 1,000 MTONs of cargo (8 square feet per MTON), allowing 50 percent space for surge and security. Average stock height is 8 feet or two pallets high. Approximately 10 percent of each day's target tonnage will require covered storage.

Long-term (open or covered) storage. In a port area where temporary storage will be for more than five days, use the following formula to compute the storage area required:

$$\frac{\text{MTON/mo}}{2} \times \text{sq ft/MTON} \times \frac{\text{days storage}}{30} = \text{sq ft space}$$

For open storage requiring 10 square feet per MTON:

$$\frac{\text{MTON/mo}}{2} \times 10 \times \frac{\text{days}}{30} = \text{sq ft open storage space}$$

For covered storage requiring 8 square feet per MTON:

$$\frac{\text{MTON/mo}}{2} \times 8 \times \frac{\text{days}}{30} = \text{sq ft covered storage space}$$

Conditions vary with localities and may sometimes be very unusual. When necessary, berth, wharf, and lighter discharge factors must be adjusted or reduced to meet emergencies caused by local conditions.

Basic Cargo Load-Unload Times

The ship load-unload times in Table 5-2 are based on a 20-hour workday. RO/RO and Seatrain load-unload times were computed from actual experience in past REFORGER (return of force to Germany) exercises. There has been enough REFORGER experience with MSC RO/RO ships to place a high reliability on the times shown.

Helicopters on RO/RO ships. Helicopter loading on RO/RO ships is a lift-on/lift-off operation. Additional effort is also required to place helicopters in their final stow position. Therefore, when transporting a significant quantity of helicopters on RO/RO vessels, allow additional load-unload time. REFORGER experience has shown that 1 hour must be added to the normal load time for each six helicopters.

Table 5-2. Load-unload times for basic cargo

Type of Ship	Time in Days[1] Load	Unload
RO/RO[2]	1.0	0.75
RO/RO SL-7[2]	1.5	1.0
Seatrain	3.0	2.0
Break-bulk:		
Ammunition	4.0	4.0
Unit equipment	4.0	2.0
General cargo	4.0	4.0
Container[3]	1 or 2[4]	1 or 2[4]
LASH[5, 6]	1 or 2[4]	1 or 2[4]
SEABEE[5, 7]	1 or 2	1 or 2

[1] Assumes 20-hour workday; excludes weather and mechanical delays.
[2] Refer to following paragraph on helicopter loading.
[3] Assume availability of at least two gantry cranes per berth. Load-unload time is exclusive of container stuffing-unstuffing time.
[4] One day required for less than 900 containers, 2 days for more than 900 containers.
[5] These are general planning times; refer to following paragraphs for loading LASH and SEABEE ships.
[6] One day to load or unload ships and two days (four for ammunition) to load or unload lighters; load-unload times for lighters should be increased to three days for a unit move involving helicopters. The ship and lighter operations may run concurrently. In any event, allow a minimum of two days for load-unload operations (including lighters) involving unit equipment or resupply.
[7] One day to load or unload ship and two days to load or unload barges when barges are loaded or unloaded at SPOE. Allow a minimum of two days for concurrent operations, depending on barge berthing and terminal throughput capabilities.

LASH and SEABEE. Loading LASH and SEABEE ships involves two separate operations: loading cargo on the lighters/barges and loading lighters/barges on the mother vessel. These operations may be concurrent, or the mother ship may be loaded after all lighters/barges are stowed with cargo. The time required to load all of the lighters/barges with cargo is a dependent upon the berth space and the number of cranes devoted to the operation. See TM 55-1520-400-14 for detailed information and procedures on loading helicopters in LASH and SEABEE lighters.

LASH loading time depends on the load (commodity) materials-handling equipment cycle time, and stevedore gang productivity. Information from various ports and terminal

WWW.SURVIVALEBOOKS.COM

operators throughout the United States indicates that an average of 4 hours is required to load a LASH lighter with military equipment. This includes the time required to remove hatch covers, load cargo, block and brace, and secure hatch covers.

Specialized Loading

When maximum unloading efficiency is the governing factor rather than economy of cargo space, the principles of combat loading should be employed. In this specialized type of loading, mixing cargo types within ships' holds is kept to a minimum and each hatch is self-sustaining.

Cargo stowage should be blocked vertically in each hatch; this saves time by reducing the number of times that cargo gear must be rerigged or shifted. Within each cargo space, drafts of cargo should be palletized, netted, or containerized; drafts should not be tiered unless MHE is available to move cargo from the wings to the hatch square. When cargo is palletized, at least four pallets in each hatch square should have bridles intact so that no time is wasted in breaking the stowage.

Vehicles should not be floored over and tiered, even if space is available, because bulling vehicles to the square on the upper tier and clearing the flooring and shoring is time consuming. As far as possible, trailers should be stowed with their prime movers. Unit cargo may be loaded in vehicles to the lower reducible height if the ship's gear capacity is not exceeded. Powered vehicles must be in running condition with fuel tanks three-quarters full.

Use a profile loading diagram for the ship to compute unloading time for each hatch at time of prestowage. Obtain information for the profile loading diagram from the storage plan. Add the time factors for hatch opening, shift of gear, and all drafts to obtain total unloading time for each hatch. Enter this total in the tabulation for the hatch on the profile loading diagram.

Rig and boom capacities differ among hatches for each design of cargo vessel. In general, 5-ton booms are installed to serve each hatch. One or more hatches are also served by 30 to 60-ton capacity jumbo booms. The limiting load factor of the rig is the safe working load of the wire rope multiplied by the number of parts. The normal safe load for a single-rigged yard-and-stay rig is 6,600 pounds for 5/8-inch wire and 8,000 pounds for 3/4-inch wire (improved plow steel) in good condition. Heavier weights must be lifted by doubled yard-and-stay rigs, swinging booms, four-boom rigs, or jumbo booms.

Average weights of drafts are–

- Palletized general cargo— 1 STON
- Palletized ammunition— 1 1/2 STONs
- CONEX—5 STONs

Vehicle weights depend upon type of preloading.

Use the following guidance to compute unloading time:

- Single-rigged yard-and-stay—5 minutes per draft (pallets, l/4-ton trucks and trailers, 1/1 2-ton trailers, empty 3/4-ton trucks).
- Doubled yard-and-stay or double-purchase swinging-boom rig— 10 minutes per draft (CONEX, empty 2 l/2-ton trucks).
- Jumbo boom rig— 15 minutes per draft (vehicles heavier than 2 l/2-ton trucks, APCs, tanks).
- Opening hatch— 15 minutes average (25 minutes for weather-deck hatch, 10 minutes for 'tween-deck hatch).
- Shifting rig—30 minutes.

Unloading time strengths for specially equipped vessels (roll-on/roll-off and LKA equipped with special ramps, elevators, pallet conveyors, monorails, or other devices) must be developed from experience.

See FM 20-12 for detailed guidance on combat loading as well as commodity loading and selective loading. Loading diagrams for US Navy Amphibious Force vessels, as well as standard maritime-commission-design vessels, should be secured from the combat cargo officer assigned to an individual vessel. While these vessels may be of the same design, their loading capacity for each hold will differ.

Container Operations

Unless local conditions dictate otherwise, container berths should be along a quay rather than a finger pier. Placing containers along a quay allows some flexibility in berth lengths.

WWW.SURVIVALEBOOKS.COM

Terminal layout. A typical container terminal consists of the ship berth, container cranes, entry facilities, marshaling area, container inspection garage, container packing shed, and equipment storage.

Containership berths require a minimum length of 1,000 feet to handle the size of vessels currently in use. A maximum length of 1,100 feet will take the largest containership presently afloat or contemplated.

Since most container vessels have no shipboard cranes to handle containers, container cranes will be required. Two or more cranes, working simultaneously, can unload and load a containership.

The truck entrance to a terminal should consist of two or three entry lanes with a corresponding number of departure lanes. Each lane should have a truck scale to weigh the containers in or out. A building will usually be located at this entry/exit point for handling necessary paperwork and assigning positions in the marshaling yard to incoming containers. Approach roads to the terminal should be generous. Container operations generate substantial truck traffic, peaking on days when ships are in port. This peak necessitates truck-holding lines at the terminal entrance.

Located near the entry building and next to the marshaling area is a small garage for the physical inspection of arriving or departing containers. Inspection is required because responsibility for the containers changes as they enter or leave the terminal. In addition, a maintenance garage is usually provided for stevedoring devices used to handle the containers in the marshaling yard.

A less-than-container load (LTCL) packing shed is usually provided. The term "container freight station" is often used for such a building. The building need not be next to the marshaling area and definitely should not assume the normal location of a transit shed. Any structures near the stringpiece tend to impair movement of containers to and from the cranes during loading and unloading operations. The size of packing sheds varies, but the general configuration resembles a typical truck terminal. Delivery trucks arrive at one side of the building cargo is moved from these trucks directly into waiting containers on the opposite side with a minimum flooring of cargo. The packing shed, therefore, tends to be long and narrow with emphasis on the necessary number of truck and container doors.

Container storage and retrieval systems. A number of storage and retrieval systems and combinations of systems are in use at container terminals. Of these, the most common are chassis storage, straddle carrier, and travel crane. Where space is limited, a vertical storage and retrieval system is used.

Chassis storage. A container discharged by a ship is placed on a semitrailer chassis. The chassis is hauled by a yard tractor to an assigned terminal position and remains there until picked up by a highway tractor. Chassis-carrying export containers are similarly stored by highway tractors and later hauled to the ship by yard tractors. Since containers are stored one level high, this system requires more terminal storage space than any other container storage system. Handling efficiency is 100 percent because every container is immediately available to a tractor unit and all required handlings are productive. This system requires more chassis than any other system.

Straddle carriers. Containers are stacked two or three levels high by straddle carriers. These carriers straddle the containers and carry them between shipside and storage areas or onto trucks or railroad cars. Less storage space is required with this system since containers can be stored two or three high. Handling efficiency, however, is reduced to 50 percent or less because an upper container must be moved to reach a lower container. In some cases the tractor-chassis system is used between shipside and stacking area.

Traveling bridge cranes. Containers are stacked up to four high by traveling bridge cranes. These cranes can stack higher than straddle carriers and so increase the capacity for a given area. However, handling efficiency is reduced by the many nonproductive handlings required for retrieval of containers. Containers are delivered to and from the cranes by tractor-chassis units.

WWW.SURVIVALEBOOKS.COM

INLAND WATERWAY PLANNING

Inland waterways include all rivers, lakes, inland channels, protected tidal waters, and canals deep enough to accommodate waterborne traffic. In a theater of operations, an inland waterway is normally operated as a complete system. The system includes locks, dams, bridges, and other structures that contribute to or affect movement of vessels carrying passengers and freight. Inland waterways are principally used by the civilian economy. Military use depends on waterway development, necessary rehabilitation, the tactical situation, and the impact of such use on the civilian economy.

Inland Waterway Service. When required, an inland waterway service may be formed to control and operate a waterway system and to formulate and coordinate plans for using inland waterway transport resources. It may also be formed to integrate and supervise local civilian facilities supporting military operations. The inland waterway organization varies in size from a single barge crew to a complete inland waterway service, depending on requirements. The service may be composed entirely of military personnel, or it may be staffed by local civilians supervised by military units of the appropriate transportation staff section.

Inland Waterway System. Three separate functional components-the ocean reception point (ORP), the inland waterway, and the inland waterway terminal-make up the inland waterway system. The transportation planner must estimate the capacity of each of these functional components; the lesser capacity becomes the capacity for the inland waterway system.

Ocean reception point (ORP). An ORP consists of mooring points for ships, a marshaling area for barges or other lighterage, and a control point. There should be at least two stake barges at each ORP–one for import cargo and one for export. LASH, SEABEE, container, and general cargo vessels may discharge at an ORP. Because of the rapid discharge capability of LASH and SEABEE vessels, the ORP should have enough berthing to handle twice the barge capacity of that type ship. The ORP should have water space with enough stake barges to accommodate the same amount of barges as the wharf space. Barges can be of the preloaded variety such as those discharged from LASH and SEABEE vessels; or they can be barges or other lighterage loaded from container or general cargo vessels. In either instance, there must be enough wharfage or stake barge space to handle barges from current working ships as well as those returning empty from previous working ships.

Reception, discharge, and clearance capacities of an ORP are computed in the same manner as for an ocean terminal-with minor differences. ORP clearance capacity is the number of personnel, containers, barges, or STONs of cargo that can be moved from the ORP via any mode. Just as terminal transfer and storage capacity influences terminal discharge capacity, so tugs and barges (terminal transfer) and wharves or stake barges (storage) influence ORP discharge capacity. Careful analysis determines the space required and available for stake barges as well as the space required to move barges to and from the stake barge. Also, transit time between the ship and the stake barge or wharf and other factors incidental to cargo (barge/lighterage) transfer and storage must be determined.

Inland waterway terminal. An inland waterway terminal normally includes facilities for mooring, cargo loading and unloading, dispatch and control, and repair and service of all craft capable of navigating the waterway. Terminals are established at the origin and terminus of the inland water route. Intermediate terminals are located along the way wherever a change in transportation mode is required.

Terminals in an inland waterway system are classified as general cargo, container, liquid, or dry-bulk-commodity shipping points. Except for the general cargo type, terminals usually include special loading and discharge equipment that permits rapid handling of large volumes of cargo.

Inland Waterway Capacity

The inland waterway's physical features affect its ability to carry cargo. Some of these features are–

- Width and depth of channel.
- Horizontal and vertical clearance of bridges.

WWW.SURVIVALEBOOKS.COM

- Number of locks.
- Method of lock operation.
- Time required to clear locks.

Freeze-ups, floods, and droughts also affect a waterway's capacity. The transportation planner must know when to look for seasonal restrictions and how long to expect them to last. Other factors to consider are speed, fluctuation, and direction of water current as well as availability of craft, labor, terminal facilities, and maintenance support. The number of craft or barges using the waterway determines the method for computing its capacity.

Estimate. Usually there are not enough craft or barges available to fill or exceed the capacity of an inland waterway. However, if there are enough, daily capacity can be estimated Determine the number of craft per day that can be passed through the most limiting restriction (lock, lift bridge, or narrow channel]; multiply this figure by the average net capacity of the barge or craft in use.

Formula. Normally the capacity of a water way is so large or the availability of barges so limited that there are not enough barges to fill or exceed the waterway capacity. In this case, use the following formula to compute the number of tons a given number of barges can move a given distance each day:

$$F = \frac{H \times G \times E}{A}$$

where

F = daily tonnage
H = number of barges required or available
G = tons per barge
E = hours of operation per day
A = turnaround time for barges in hours

Turnaround time. Turnaround time is the length of time it takes after leaving a point to return to it. If barges are being picked up at a wharf or stake barge, barge loading time is not part of the computation. If barges are picked up at shipside without marshaling at a wharf or stake barge, barge loading time is a factor in turnaround time. The following factors must be known before computing turnaround time:

- *Length of haul*— the round trip distance between the barge pickup point and barge delivery points.
- *Speed*— influenced by wind, current, power of craft, and size of load. If the craft's speed cannot be determined, assume it to be 4 miles per hour in still water (6.4 kilometers per hour). Speed and direction of current can frequently be discounted since resistance in one direction may be balanced by assistance in the other direction. However, this is not always the case.
- *Loading and unloading time*— the time it takes to load and unload a craft at origin and destination.
- *Time consumed in locks*— the time it takes a craft and its tow to pass through a lock. When exact data is lacking, assume lock time to be one hour per single lock.
- *Hours of operation per day*— usually planned as 20. Dropping barges from the tow, refueling, taking on stores, rigging up, and maintenance consume the remaining 4 hours.
- *Transit time*— the time to move the craft the length of the haul and return it to its origin. Computing transit time is strictly a mathematical function: the distance traveled divided by the speed of the craft. Transit time does not include stops or delays of any kind. Turnaround time, on the other hand, is the total time it takes for a barge or tug to go from start point to destination and return to start point, including transit time and all delays.

Use the following formulas to compute turnaround time (barge turnaround times always include unloading time; loading and unloading times do not apply to tugs):

Barges

$$K = \frac{B+C+D}{E} \qquad A = B+C+D$$

Tugs

$$L = \frac{C+D}{E} \qquad M = C+D$$

where

A = barge turnaround time in hours
B = unloading time per barge
C = transit time

WWW.SURVIVALEBOOKS.COM

D = locking time
E = 24-hours per day
K = barge turnaround time in days
L = tug turnaround time in days
M = tug turnaround time in hours

Barge and tap requirements. Barge and tug requirements for containerships, LASH and SEABEE ship, and RO/RO ships cannot be figured on the basis of tons carried. For LASH and SEABEE vessels, loading time is completely omitted from the turnaround time formula at both the ORP and the inland waterway. Discharge tonnage for containers is expressed as containers per hour. Barge and tug requirements for these vessels depend on the sizes of tugs available, restrictions on the number of barges per ton, and the number of barges available.

Barges. To determine the number of barges needed to move a specified number of tons a specified distance each day, use the following formula:

$$H = \frac{F}{G} \times \frac{A}{E}$$

where

H = number of barges required
F = daily tonnage
A = turnaround time in hours
G = tons per barge
E = hours of operation per day

Note that since turnaround time in hours must be known to determine the number of barges required, turnaround time must be computed **first.**

Tugs. Once the number of barges required to perform a given task is known, the number of tugs or towboats needed to tow the barges can be computed. When tugs are used, the arrangement of the tows must be considered. It is sometimes possible to operate with fewer tugs than tows because tugs do not have to wait in port while cargo is being transferred. Moreover, one tug can often tow more than one barge. When planning a towing operation, consider the fit of the tow in the locks. Use the following formulas:

Tows $$J = \frac{H}{I}$$

where

J = number of tows
H = number of barges required or available
I = number of barges per tow

Tugs $$M = \frac{JL}{K}$$

where

M = number of tugs required
L = turnaround time for tugs in days
K = turnaround time for barges in days

Note that turnaround times for barges and tugs must be computed first.

Inland Waterway Terminal Capacity

Inland waterway terminals are staffed by appropriate transfer units or teams. The number of terminal transfer units required depends on the results of an inland waterway terminal throughtput analysis. A throughput analysis should be conducted for each inland waterway terminal in the system. The restricting capacity (reception, discharge, or clearance) for each terminal determines its capacity. Then these individual capacities are combined into one cumulative capacity for the inland waterway terminal.

Inland Waterway System Capacity

After estimating the capacity of the three functional components of the inland waterway system. use the lesser of the three as the estimated capacity for the entire system. For example, if capacity per day is 3,000 tons (ORP), 2,000 tons (inland waterway), and 2,500 tons (inland waterway terminal), then 2,000 tons is the capacity for the inland waterway system.

Once the capacity of the inland waterway system has been determined. personnel requirements for each component of the system can be determined. If host-nation personnel will support part of the system, determine only US army personnel needs. When planning personnel and unit requirements for an inland waterway system, refer to FM 101-10-2.

When determining equipment needed to support the inland waterway system, first determine the number and capabilities barges and tugs the host nation will supply to the US Army. Then determine the US Army's augmentation requirement. When deciding which equipment is best suited for the system, refer to FM 55-50. For more complete information on Army terminal operations, refer to FM 55-60.




Figure 5-2. Typical inland barge terminal

WWW.SURVIVALEBOOKS.COM

LOGISTICS OVER-THE-SHORE PLANNING

Historically, the phrase "logistics over the shore" (LOTS) has applied where a vessel anchored in open water was discharged into ligherage with the lighterage subsequently discharged over a bare beach. This definition was narrow and restrictive. The current definition of LOTS is "any vessel discharge operation other than one conducted at a fixed-pier facility." A fixed-pier discharge operation is one where a vessel is discharged direct to land or land transportation. A LOTS operation is one where a vessel is discharged directly to other than land or land transportation. LOTS includes vessel discharge to lighterage and subsequent discharge over the shore. The type of beach or vessel anchorage plays no part in defining a LOTS operation. See FM 55-50 for a detailed discussion.

Terms. The planner should be familiar with these terms:

- ***In-the-stream anchor—*** anchorage in protected deep water such as a harbor.
- ***Offshore anchor—*** anchorage off the shoreline in unprotected deep water.

NOTE: From either of the above anchorages, the ship can discharge to lighterage for subsequent discharge to a fixed-port facility, unimproved facility, or bare beach.

- ***Fixed port facility—*** specifically designed to accommodate cargo discharge or backload operations; characterized by sophisticated equipment and procedures; frequently oriented toward a specific type of cargo such as container, RO/RO, hazardous, and general cargo, although there is a recent trend toward combination facilities; normally has extensive hardstand areas, transit sheds, shore cranes, and access to well-established, well-defined rail nets and roadnets.
- ***Unimproved facility—*** a fixed facility not specifically designed for cargo operations; for example, a pier facility frequented by fishing vessels; has hardstand or hard surface alongside a shallow body of water and perhaps some type of simple shore crane used for loading and discharging fishing boats; characterized by a marked lack of sophisticated facilities and equipment; water depth and pier length inadequate for ocean-going vessels; sparse roadnets; rail nets probably nonexistent; existing facilities might be adapted for use in cargo operations, but MHE, transit sheds, marshaling area, and communications would have to be provided to support operations.
- ***Bare beach operations—*** beach essentially as nature made it; considerable engineer support needed to provide a facility suitable for cargo operations.

NOTE: These beach facilities are inefficient and only used when fixed or unimproved facilities are unavailable or inadequate. There are no preexisting facilities, but LOTS site location should be in proximity to highway and rail facilities. All other capabilities, MHE, hardstand, communications, and support facilities would have to be provided.

Bare Beach Operations. Existing port capacities in many areas will not be enough to support theater tonnage requirements. This, coupled with the possibility of enemy insurgent activities, means that emphasis in planning will be shifted from large port complexes to widely scattered beach operations. It is estimated that upwards of 40 percent of all cargo entering a theater by surface means will be delivered through dispersed beach terminals. Therefore, the senior terminal commander in the theater must continually plan to open new beaches. These beaches will—

- Absorb the tonnage capacity of a port or unimproved facility made untenable by enemy actions.
- Relieve congested routes of communications.
- Reduce land transportation required to support combat elements.

Plans should include–

- Proposed location and layout.
- Type of lighterage used.
- Task organization needed.
- Route and methods of movement to the area.
- Construction required.
- Communications requirements.
- Logistical support procedures.

WWW.SURVIVALEBOOKS.COM

Supervision. Close attention and supervision are required at each bare beach LOTS discharge point. The success of each beach operation depends to a great extent on the efficiency of cargo operation on the beach itself. Supplies and equipment being brought to the beach must be kept moving across it toward inland destinations as rapidly as possible. A cluttered beach offers a lucrative target to the enemy and hinders cargo movement. Using amphibians or LACV-30s for lightering general cargo aids significantly in reducing beach congestion.

Each two-ship terminal will be under the direct operational supervision of a terminal battalion. As a minimum, each will be manned by two terminal service companies, two light or medium amphibian companies, and one medium boat company. In addition, one or more truck companies may be attached for intraterminal transportation and clearance assistance. Terminal transfer elements may be required to aid in clearing cargo backlogs in discharge areas. Harbor craft teams may also be attached as required. The functions of a number of these terminals, dispersed along a maximum of 150 miles of shoreline, will be coordinated by a terminal group or brigade. Lighterage maintenance is provided at group level.

The minimum troop assignments given above are based on an average planning factor of 25 percent of all cargo entering a theater being vehicles and other heavy lifts and the remainder, general or container cargo. Of the 2,000 STONs of mixed general cargo which two terminal service companies can discharge per day (1,000 STONs each), 75 percent (1,500 STONs) will be lightered by the amphibian units. The remaining 25 percent will be delivered ashore by the medium boat company.

Maintenance. Employing terminal units over widely separated distances along a coastline requires careful evaluation of the maintenance system supporting a complex of scattered operations. Increased emphasis must be placed on organizational maintenance. Unit maintenance personnel should be well-trained and every effort made to remedy minor troubles and prevent costly equipment breakdowns. The terminal group SOP should establish the procedure for providing maintenance support. Floating craft maintenance units supporting terminal operations over an extended coastline require mobile marine repair facilities and on-site repair service.

Dispersion. In dispersed beach terminal operations, terminal units, operating equip ment, cargo, and facilities are separated as widely as operational efficiency permits. All activities are spread over a wide area to avoid offering the enemy a concentrated target. Discharge operations which offer the enemy a lucrative target are scheduled as seldom as possible and for as short a time as possible. Dispersion of terminal units greatly increases reliance on radio communications for effective command, control, and coordination. Therefore, communications security (COMSEC) and electronic counter-measures (ECCM) are critical to maintaining reliable communications.

Site Selection. The first step in site selection is to determine the beach areas available. Degree of dispersion that can be attained is directly related to daily tonnage requirement and size and nature of the assigned area. As soon as practicable after designating the limiting points of the area, reconnoiter the sites to determine those most suitable for operations. Selection of sites should be based primarily on their existing capability to accommodate desired tonnage. Consider these major factors:

- Tide.
- surf.
- Beach gradients.
- Bars.
- Bottom characteristics and beach surface.
- Anchorage areas.
- Weather.
- Topographic features.

Remember that LOTS depends almost wholly on favorable weather. Also, lighterage operations alongside a vessel are particularly hazardous if more than a moderate sea is running. Heavy surf reduces the amount of cargo brought in by lighters and can cause suspension of the entire operation.

WWW.SURVIVALEBOOKS.COM

Beaches ideally suited for LOTS without prior preparation or alteration are seldom found. Therefore, some engineering support is usually required for landing craft to beach and to provide exits from the beach to discharge areas and the clearance transportation net.

Normally, the terminal group or brigade commander, in consultation with naval authorities, initially selects possible beach sites for LOTS. This is done after an extensive study of maps and hydrographic charts and an analysis of aerial reconnaissance reports. A detailed ground and water reconnaissance of the selected area determines feasibility of the sites. The reconnaissance should be as thorough as time and the situation permit. Aerial reconnaissance is useful to verify information obtained from map reconnaissance. Road nets shown on the map may have been destroyed or made impassable; new roads may have been built. Bridges may have been destroyed, or structures may have been built on the beach. It is crucial that naval authorities be consulted early in the study. This is so that advice about possible anchorage areas as well as difficulties and hazards to navigation will be available as early as possible.

Reconnaissance. The party which conducts the ground and water reconnaissance must include personnel capable of advising the terminal group commander on the following:

- Engineering effort required to prepare and maintain the area.
- Signal construction and maintenance required for communication within the beach area, as well as between the beach area and the terminal group headquarters.
- Need for and location of beach dumps, transfer points, and maintenance areas.
- Type of lighterage that could be employed most effectively.
- Need for and location of safe-haven facilities for lighterage.
- Location and desirability y of anchorage areas.
- Possibility of using spud (self-elevating, nonpropelled) piers and other special equipment.
- Vulnerability to enemy attack of the terminal area, its seaward approaches, and its connections with the interior.

The typical reconnaissance party should consist of but not be restricted to the following personnel:

- Representatives of the terminal group commander (to coordinate or supervise the reconnaissance team and to recommend task organization).
- The terminal battalion commander and appropriate staff members.
- An engineer officer (preferably from the supporting engineer unit).
- A signal officer (preferably from the supporting signal unit).
- Representatives of amphibian units (to locate desirable entrances to and exits from water, transfer points, and so forth).
- Representatives of landing craft units (to select beach areas, anchorages, maintenance areas, and navigation aids).
- Representatives of units with special equipment.
- US Navy representatives (to advise on anchorage areas and naval support required).
- A military police representative (to determine needs and plan military police support for traffic control and beach management).

In addition to gaging beach area characteristics, the reconnaissance party must determine whether the selected area has enough anchorage for the number and types of ships required to support planned beach operations. If the Navy representative indicates anchorage areas that are acceptable, they must be examined to see if lighterage can cross from the anchorage areas to the beach. For example, sandbars or reefs just offshore may preclude the use of LCMs, LCUs, or barges. These conditions may also require the use of amphibians until a channel is cleared. Important features to consider are depth, size, landmarks, and underwater obstacles.

Depth. For large cargo ships, a minimum depth of 30 feet and a maximum of 210 feet are required. Maximum draft of ships to be

WWW.SURVIVALEBOOKS.COM

discharged and the ground swell conditions decide minimum depth. The length and weight of anchor chain determine maximum depth.

Size. For planning purposes, the anchorage area should be a circle with an 800-foot radius to provide a safe free-swinging area for the standard five-hatch vessel. If larger vessels are anticipated in the operation, use the following formula:

2(7D + 2L) = R (diameter in feet)

where.

D = depth of water in feet

L = length of vessel in feet

A much larger radius may be required for dispersion if operations are being conducted under threat of nuclear warfare. Bow and stern mooring is not considered desirable in tidal areas because athwartship currents cause excessive strain on mooring gear. Also, appreciable changes in depth require continuous watching of the anchored vessels. The type of offshore bottom also has a significant bearing on how close ships can be anchored to each other because a ship will drag anchor if the bottom is too rocky or slushy.

Landmarks. Landmarks (especially those assisting navigation and location of beaches), such as prominent hills, are helpful.

Underwater obstacles. Underwater obstacles should be noted. These include bars, shoals, reefs, rocks, wrecks, and enemy installations which might interfere with the passage of vessels to and from the area. Estimate the degree of interference offered and the amount of work involved to clear channels.

During the reconnaissance, the terminal battalion commander also selects and assigns company areas and frontages, indicates areas of defense responsibilities, and tentatively organizes the area of operations. On completion of the reconnaissance, findings are analyzed and the most desirable beach areas selected. Alternate beaches are chosen and listed in order of suitability. The battalion commander submits the sites selected to the terminal group commander along with a written plan for implementing operations at the selected beach.

Beach Capacity. For general planning, determine beach capacity by applying data contained in FM 101-10-1. However, this data is based on average conditions and must be adapted to specific beach operations. For a particular discharge site, several factors must be considered. These factors fall into two groups– those which limit the cargo-handling capacity of the beach and those which restrict the flow through the area because of the nature of the beach and the hinterland. Whichever group is more limiting to the quantity of supplies that can be handled determines the capacity of the beach. Beach terminal planning requires a beach capacity estimate and involves the same steps used in planning for a fixed ocean terminal.

Personnel/equipment factors. Cargo-handling capacity is affected by the following factors:

- Availability and expertise of personnel for discharging ships and handling cargo on the beach and in the discharge areas.
- Type and availability of mechanical aids and transportation equipment for beach clearance.
- Types and amounts of lighterage available for operation.
- Ability of the enemy to interrupt operations.

Terrain factors. Most terrain factors are self-explanatory, but beach exits and the hinterland play such important roles in beach capacity that they are discussed in detail. Possible terrain limitations are—

- Length and width of beach.
- Underwater obstacles.
- Tidal range.
- Strength and direction of tidal stream (rip currents and littoral currents).
- Surf.
- Gradient of beach.
- Bearing surface of the beach.
- Availability and type of beach exits.
- Hinterland.

WWW.SURVIVALEBOOKS.COM

Beach gradient and materials. Beach gradient, or the underwater slope of the beach, is usually expressed as a ratio of depth to horizontal distance. A gradient of 1 in 50 indicates an increase in depth of 1 foot to every 50 feet of horizontal distance. For landing and amphibious craft, usually only the gradient from the water's edge seaward to a depth of 3 fathoms (18 feet) needs to be determined. A gradient slightly steeper than 1 in 50 is considered suitable for a loaded landing ship tank (LST); a gradient of 1 in 20 is satisfactory for an LCM-8.

Following are classifications of beach gradients:

- Steep—More than 1 in 15 feet
- Moderate 1 in 15 to 1 in 30 feet
- Gentle— 1 in 30 to 1 in 60 feet
- Mild— 1 in 60 to 1 in 120 feet
- Flat — Less than 1 in 120 feet

Beach materials are classified according to particle diameter:

Material	Particle diameter (in microns*)	Particle diameter (in inches)
Boulder	256,000 and over	10.24 and over
Cobble	256,000 - 64,000	10.24 - 2.56
Stone	64,000 - 4,000	2.56 - 0.16
Pebble	4,000 - 2,000	0.16 - 0.08
Very coarse sand	2,000 - 1,000	0.08 - 0.04
Coarse sand	1,000 - 500	0.04 - 0.002
Medium sand	500 - 250	0.002 - 0.001
Fine sand	250 -125	0.001 - 0.0001
Very fine sand	125 - 62.5	0.0001 - 0.000625
Silt	62.5 - 3.9	0.000625 - 0.0000156

*Micron is approximately 0.00003937 inch.

See Figures 5-3 and 5-4 for profile views of beach sites.




Figure 5-3. Profile view of typical underwater gradient




Figure 5-4. Marine beach profile diagram

WWW.SURVIVALEBOOKS.COM

Beach exits. The capacity of a beach to discharge and clear supplies and personnel is limited by the capacity of the roadnet from the waterline to inland destinations. These destinations include dumps, principal inland areas, and the interior communications net. Since the useful capacity of the beach can never exceed roadnet capacity, an early and detailed analysis must be made to determine the capacity of the existing roadnet. If the road net capacity is inadequate, new roads must be built, which will require additional engineer support both for construction and maintenance.

The number of exits required varies according to physical characteristics of the roads, the type and amount of cargo, and the type of conveyance used in beach clearance. Different types of equipment should have separate routes. The adjacent area is a factor which may limit the number of possible exits from the beach. An otherwise ideal beach may be backed by sand dunes, seawalls, swamps, or other obstacles which hamper clearance operations.

Hinterland Besides the beach and its exits, consider the following factors when selecting a beach for unloading cargo:

- Existing roadnet or rail net.
- Physical characteristics of existing roads.
- Strength and width of bridges in the existing roadnet.
- Possibility of building a roadnet (if none exists).
- Existing telephone and telegraph lines, radio stations, power lines.
- Need for new telephone lines, et cetera.
- Suitable area for heliport (if needed).

Beach Transfer Points. Beach transfer points are locations where cargo is transferred from amphibians to a clearance mode for delivery to destination. The requirement for beach transfer points is identified and their locations designated during reconnaissance. A desirable beach transfer point has the following characteristics:

- It should be located to the rear of the beach so it will not interfere with operations at the shoreline.
- It should be on the route that amphibians travel when moving from and to the water.
- It should be near the clearance route where cargo trucks moving in the traffic pattern can receive their load without interfering with other traffic and still have access to an exit from the transfer point.
- It should allow amphibians to cross the beach, which makes it unnecessary to prepare a beach roadway for cargo trucks.
- There should be room for a roadway on either side of the MHE operating at the transfer point so that there is no interference between amphibians and cargo trucks.
- It should allow for location of cranes on firm, level ground with their longer axis parallel to the direction of vehicle movement so that loads can be transferred with the least amount of movement of the boom.

Temporary Holding Areas. In general, the problems of cargo clearance in beach operations are the same as in conventional port terminals. However, physical differences in the operating areas may require different procedures and equipment. In an ideal situation, clearance transportation capacity is balanced with discharge capability; cargo is moved through and out of the terminal area as fast as it is unloaded from the ships. In reality this balance seldom occurs. Some cargo backlog must be anticipated and provided for by establishing temporary in-transit storage areas. These areas should be located near transfer points used by amphibians to accommodate cargo that cannot be immediately transferred to clearance conveyances. Cargo unloaded from landing craft that cannot be immediately cleared should also be brought to in-transit storage areas to avoid congestion and cargo pile-up on the beach.

When clearance transportation later becomes available to move cargo from in-transit storage areas, this imposes an additional burden on terminal service companies which unload lighters delivering cargo from the ship. Any effort diverted by these units to handling cargo in the in-transit storage areas

WWW.SURVIVALEBOOKS.COM

only impairs their ability to keep the lighters moving. Eventually, the entire operation will stagnate. Assigning terminal transfer elements (squads, platoons, or companies) to load backlogged cargo in the in-transit storage area onto clearance transportation will solve the problem. Then cargo will flow out of the terminal without disrupting discharge operations at the ship because of slow lighter turnaround.

Temporary in-transit storage areas should be located away from main clearance roads to minimize road congestion and present less lucrative targets. Roads leading from main clearance roads to in-transit storage areas must be kept in good condition. Each area should have a separate entrance and exit. If tracked vehicles will be used as well as trucks and amphibians, separate traffic nets may be needed. The ground should be level, firm, and dry. The surrounding area should be large enough to allow in-transit storage facilities to expand to meet the maximum requirement anticipated.

Traffic Control. Traffic control is vital to prevent congestion in the terminal area and promptly clear cargo to its initial destination. To control vehicular traffic in the beach area—

- There should be enough drivers, MHE, and supervisors for around-the-clock operations.
- Motor transport equipment should be carefully planned for maximum use (see FM 55-30).
- Motor transport units should be attached at group level to operating terminal battalions according to requirement fluctuations and degree of dispersion between beach sites.
- Vehicles should be loaded to capacity if consistent with cargo segregation requirements.
- Where practical, vehicles should be loaded so they can be unloaded completely at one discharge point to expedite turnaround time.
- Control procedures should be set up to provide readily available information on location and current use of all motor transport facilities. Equipment or units can then be quickly diverted with minimum disruption to the overall operation.

Beach Management. Requirements for clearing personnel, supplies, and equipment from beaches usually exceed available capacity. Careful planning and close supervision are needed for maximum use of equipment, personnel, and facilities. Some measures which can assist in clearing supplies and equipment from the beach area are—

- Using amphibians to the maximum.
- Continuously improving the beach in general.
- Planning handling of peak work loads so they will not disrupt operations.
- Closely coordinating with cargo transfer points and temporary holding areas to maintain near-capacity cargo flow but not exceed receiving capacity.
- Separating landing points for amphibians and landing craft.
- Keeping documentation, records, and reports to a minimum.
- Locating beach parking areas for MHE and clearance vehicles in areas readily accessible to discharge points.
- Adopting an enforced traffic circulation plan.
- Locating bivouac and messing areas to avoid time loss when moving personnel to and from working points.
- Adopting alert systems and defense plans to prevent surprise enemy attacks and maintain an adequate defense.

WWW.SURVIVALEBOOKS.COM




Figure 5-5. Typical LOTS beach layout

WWW.SURVIVALEBOOKS.COM

Section II. VESSEL DATA

US NAVY SHIP AND SERVICE CRAFT DESIGNATORS

US Navy ships and service craft fall into two major categories: combat and auxiliary/support. A letter T before the identifying classification and hull number of a naval vessel indicates that the vessel is assigned to the Military Sealift Command (MSC). A letter N after the identifying classification indicates that the vessel is nuclear-propelled. An asterisk (*) indicates that the vessel is a mobilization asset, not currently in the active fleet.

Combatant Ships

Aircraft carriers. Aircraft carriers are designed primarily to conduct combat operations by aircraft which attack airborne, surface, subsurface, and shore targets. Conventional takeoff and landing aircraft carriers include:

- Multipurpose aircraft carrier—CV
- Multipurpose aircraft carrier—CVN
- ASW aircraft carrier*-CVS

Surface Combatants. Large, heavily armed surface ships are designed primarily to engage enemy forces on the high seas:

- Battleship—BB
- Cruisers
  Gun cruiser*—CA
  Guided missile cruiser—CG
  Guided missile cruiser—CGN
- Destroyers
  Destroyer—DD
  Guided missile destroyer—DDG
- Frigates
  Frigate—FF
  Guided missile frigate—FFG

Submarines. Submarines include all self- propelled submersible vessels, whether combatant, auxiliary, or research and development, which have at least residual combat capability:

- Attack submarines
  Submarine—SS
  Guided missile submarine—SSG
  Submarine—SSN
- Ballistic missile submarine—SSBN
- Auxiliary submarine—SSAG

Patrol combatants. Patrol combatants missions may extend beyond coastal duties. Their sea keeping capability should enable them to operate more than 48 hours on the high seas without support:

- Patrol combatant*—PG
- Guided missile patrol combatant (hydrofoil)—PHM

Amphibious warfare ships. These ships have organic capability for amphibious assault and long duration on the high seas:

- Amphibious helicopter/landing craft carriers
- Amphibious assault ship (general-purpose)–LHA
- Amphibious assault ship (multipurpose)—LHD
- Amphibious assault ship (helicopter)—LPH
- Amphibious transport dock—LPD
- Landing craft carriers
  Amphibious cargo ship-LKA
  Amphibious transport–LPA
  Dock landing ship–LSD
  Tank landing ship–LST
- Miscellaneous
  Amphibious command ship—LCC
  Miscellaneous command ship (converted LPD)—AGF

Mine warfare ships. These are all ships whose primary function is mine warfare on the high seas.

- Minesweeper (ocean)—MSO
- Mine countermeasures ship—MCM

Auxiliary Ships

Mobile logistics ships. These ships have the capability to provide underway replenishment to fleet units; they also can provide direct material support to other deployed units operating far from home base:

- Underway replenishment ships
  Ammunition ship—AE/TAE
  Store ship—AF

WWW.SURVIVALEBOOKS.COM

Combat store ship—AFSFS
Oiler—AO/TAO
Fast combat support ship—AOE
Replenishment oiler—AOR

- Material support ships
  Destroyer tender—AD
  Repair ship—AR
  Submarine tender—AS

Support ships. Support ships are designed to operate in the open oceans in various sea conditions. They provide general support to either combatant forces or shore-based establishments. These ships include smaller auxiliaries which by the nature of their duties must leave inshore waters:

- Fleet support
  Salvage ship—ARS
  Submarine rescue ship—ASR
  Auxiliary ocean tug—TATF
  Salvage and rescue ship—ATS
- Other auxiliaries
  Auxiliary crane ship—T-ACS
  Miscellaneous—AG
  Deep-submergence support ship—AGDS
  Hydrofoil support ship—AGEH
  Frigate research ship—AGFF
  Missile range instrumentation ship—AGM
  Oceanographic research ship—AGOR
  Ocean surveillance ship—T-AGOS
  Patrol craft tender—AGP
  Surveying ship—AGS
  Auxiliary research submarine—AGSS
  Hospital ship*—T-AH
  Cargo ship—TAK
  Vehicle cargo ship—T-AKR
  Auxiliary lighter ship—ALS
  Gasoline tanker—AOG
  Transport oiler—T-AO
  Transport—AP
  Self-propelled barracks ship—APB
  Cable-repairing ship—ARC
  Repair ship (small)—ARL
  Aviation logistics support ship—T-AVB
  Guided missile ship—AVM
  Auxiliary aircraft landing training ship—AVT
  Repositioning ship—T-AKX

Combatant Craft

Patrol craft. Surface patrol craft are intended for use relatively near the coast or in sheltered waters or rivers:

- Coastal patrol combatants
  Patrol boat—PB
  Patrol craft (fast)—PCF
  Patrol gunboat (hydrofoil)—PGH
  Fast patrol craft—PTF
- River/roadstead craft
  Mini-armored troop carrier—ATC
  River patrol boat—PBR

Amphibious warfare craft. These amphibious craft have the capacity for amphibious assault; they operate mainly in coastal waters but may be carried aboard larger units:

- Landing craft
  Amphibious assault landing craft—AALC
  Landing craft, air-cushion—LCAC
  Landing craft, mechanized—LCM
  Landing craft, personnel, large—LCPL
  Landing craft, utility—LCU
  Landing craft, vehicle, personnel—LCVP
  Amphibious warping tug—LWT
  Side-loading warping tug—SLWT
- Naval special warfare craft
  Light seal support craft—LSSC
  Medium seal support craft—MSSC
  Swimmer delivery vehicle—SDV
  Special warfare craft, light—SWCL
  Special warfare craft, medium—SWCM

Mine warfare craft. Mine countermeasures craft have the primary function of mine warfare; they operate mainly in coastal waters but may also be carried aboard larger units:

- Minesweeping boat—MSB
- Minesweeping drone—MSD
- Minehunter—MSH
- Minesweeper, river (converted LCM-6)—MSM
- Minesweeper, Patrol—MSR

Support Craft (Service Craft). These are Navy-subordinated craft (including non-self-propelled) designed to provide general support to either combatant forces or shore-based estalishments:

- Dry docks
  Large auxiliary floating dry dock, non-self-propelled (NSP)-AFDB
  Small auxiliary floating dry dock (NSP)-AFDL

WWW.SURVIVALEBOOKS.COM

Medium auxiliary floating dry dock (NSP)—AFDM
Auxiliary repair dry dock (NSP)—ARD
Medium auxiliary repair dry dock (NSP)—ARDM
Bowdock—YBD
Yard floating dry dock (NSP)—YFD

- Tugs
  Large harbor tug, self-propelled (SP)—YTB
  Small harbor tug (SP)—YTL
  Medium harbor tug (SP)—YTM
- Tankers
  Fuel oil barge (SP)—YO
  Gasoline barge (SP)—YOG
  Water barge (SP)—YW
- Lighters
  Open lighter (NSP)—YC
  Car float (NSP)—YCF
  Aircraft transportation lighter (NSP)—YCV
  Covered lighter (NSP)—YFN
  Large covered lighter (NSP)—YFNB
  Lighter (special-purpose) (NSP)—YFNX
  Refrigerated covered lighter (SP)—YFR
  Refrigerated covered lighter (NSP)—YFRN
  Harbor utility craft (SP)—YFU
  Garbage lighter (SP)—YG
  Garbage lighter (NSP)—YGN
  Gasoline barge (NSP)—YOGN
  Fuel oil barge (NSP)—YON
  Oil storage barge (NSP)—YOS
  Sludge removal barge (NSP)—YSR
  Water barge (NSP)—YWN
- Miscellaneous
  Barracks craft (NSP)—APL
  Deep-submergence rescue vehicle—DSRV
  Deep-submergence vehicle—DSV
  Unclassified miscellaneous—IX
  Submersible research vehicle—NR
  Miscellaneous auxiliary (SP)—YAG
  Floating crane (NSP)—YD
  Diving tender (NSP)—YDT
  Ferryboat (SP)—YFB
  Dry dock companion boat (NSP)—YFND
  Floating power barge (NSP)—YFP
  Covered lighter (range tender) (SP)—YFRT
  Salvage lift craft, heavy (NSP)—YHLC
  Dredge (SP)—YM
  Gate craft (NSP)—YNG
  Patrol craft (SP)—YP
  Floating pile driver (NSP)—YPD
  Floating workshop (NSP)—YR
  Repair and berthing barge (NSP)—YRB
  Repair, berthing, and messing barge (NSP)—YRBM
  Floating dry dock workshop (Machine) (NSP)—YRDM
  Radiological repair barge (NSP)—YRR
  Salvage craft tender (NSP)—YRST
  Seaplane wrecking derrick (SP)—YSD

US ARMY VESSEL DESIGNATIONS

Designations. Each vessel in the transportation marine fleet bears an individual serial number, preceded by an applicable prefix:

- Barge, dry-cargo, nonpropelled, medium (100 through 149 feet)—BC
- Conversion kit, barge deck enclosure—BCDK
- Barge, dry-cargo, nonpropelled, large (150 feet and over)—BCL
- Crane, floating—BD
- Lighter, beach discharge—BDL
- Barge, liquid-cargo, nonpropelled—BG
  Barge, dry-cargo, nonpropelled—BK
  Barge, pier, nonpropelled—BPL
  Barge, refrigerated, nonpropelled—BR
  Ferryboat—FB
  Dry dock, floating—FD
  Repair shop, floating, marine craft, nonpropelled—FMS
  Freight and supply vessel, large (140 feet and over)—FS
  Boat, utility–J
  Lighter, air-cushion vehicle—LARC
  Lighter, amphibious, resupply, cargo—LARC
  Landing craft, mechanized—LCM
  Landing craft, utility—LCU
  Tug, large, seagoing—LT
  Tug, small, harbor—ST
  Boat, passenger and cargo—T
  Temporary crane discharge facility–TCDF
  Vessel, liquid cargo—Y

US ARMY VESSEL CHARACTERISTICS

See Tables 5-3 through 5-9 for data and characteristics of US Army vessels and amphibians. See Figures 5-6 and 5-7 for illustrations of Army watercraft and barges.

WWW.SURVIVALEBOOKS.COM

Table 5-3. Transportation floating craft

Nomenclature	Designation	Classification	Length (Overall)	Beam (Molded)	Maximum Draft	Displacement (LTONs) Light	Displacement (LTONs) Loaded	Capacity (gal) Water Potable	Capacity (gal) Water Nonpotable	Fuel	Speed (kn)	Range (NMi)	Cargo Capacity Dry (cu ft)	Cargo Capacity Refrig (cu ft)	Cargo Capacity Liquid (42-gal bbl)	Cargo Space Hatches	Cargo Space Tanks	Lift Capacity (LTONs) Std	Lift Capacity (LTONs) Heavy	Remarks
Vessel, supply, diesel, steel, 176', Design 361	FS	STD-B	176' 6"	32' 0"	10' 0"	465.0	935	2,042	11,624	21,000	12.0	5,320	—	—	—	1	0	5	15	Designed as aircraft repair vessel, not as a cargo carrier; hatch size, 6' x 16'
Vessel, special-purpose, diesel, steel, 176', Design 427	FS	STD-B	179' 10"	32' 5"	11' 3"	684.8	899	1,502	14,449	33,992	12.0	4,500	21,462	—	—	2	0	5	15	
Vessel, dry-cargo, diesel, steel, 1,000-T, 210', Design 7013	FS	STD-B	222' 9¾"	38' 0"	14' 6"	892.0	2,150	10,000	15,940	54,100	13.37	6,750	56,400 + 3,400 special	—	—	3	0	5	—	Equipped with two level luffing cranes
Vessel, liquid-cargo, diesel, steel, 11,500 bbl, 210', Design 7014	Y	STD-A	222' 9¾"	38' 0"	17' 0"	797.0	2,500	10,000	15,940	58,670	12.7	7,700	3,382 special	—	11,079.8	1	9	2,000		Has one dry cargo hatch, 3,382 cu ft; nine liquid cargo tanks. Equipped with two 800-GPM cargo pumps

Table 5-4. Boats

Nomenclature	Designation	Classification	Length (Overall)	Beam (Molded)	Depth (Molded Amidships	Displacement (LTONs) Light	Displacement (LTONs) Loaded	Maximum Draft (aft)	Fuel Capacity (gal)	Fuel Consumption (gal/hr)	Fresh Water (gal)	Speed (kn)	Cruising Range (NMi)	Capacity Cargo (LTONs)	Capacity Passenger	Remarks
Boat, picket, diesel, steel, 46' 4½", Design 4003	J	STD-A	46' 4½"	12' 3"	6' 3½"	10	12.0	2' 9"	370	19.0	50	14	245	1.33	25	Transported on cradle. Replaces 243-B.
Boat, picket, diesel, wood, 64' 11", Design 4002	Q	STD-A	64' 11"	15' 11"	8' 3"	31	34.5	5' 10"	900	24.2	400	14	468	4.0	5	Transported on cradle.
Boat, passenger and cargo, diesel, steel, 65' 6", Design 2001	T	STD-A	65' 6½"	17' 8"	8' 9¼"	66	95.0	6' 6"	1,150	18.0	400	7	397	24.0	24	Normally deck-loaded. Limited ocean sailing under good conditions.

Table 5-5. Floating cranes

Nomenclature	Designation	Classification	Length (Overall)	Beam (Molded)	Depth (Molded)	Displacement (LTONs) Light	Displacement (LTONs) Loaded	Draft Light	Draft Loaded	Capacity (gal) Fuel	Capacity (gal) Fresh Water	Cargo-Handling Equipment Capacity	Remarks
Crane, barge, diesel-electric, revolving, steel, 60 LTONs, Design 413-D	BD	STD-A	142' 0"	58' 0"	12' 0"	1,132	1,192	5' 1"	5' 6"	1,350	600	Main hoist: 60 LTONs @ 73-ft radius Aux hoist: 15 LTONs @ 100-ft radius Main hoist reach below surface: 50 ft	Can be towed overseas. Boom length, 95' 6".
Crane, barge, diesel-electric, revolving, steel, 89 LTONs, Design 264-B	BD	STD-A	140' 0"	70' 0"	12' 6"	1,407	1,497	5' 7"	5' 11"	15,000	30,200	Main hoist: 75 LTONs @ 104-ft 6-in radius, 89 LTONs @ 80-ft radius Aux hoist: 15 LTONs @ 122-ft 6-in radius Aux hoist reach below waterline 25 ft	Can be towed overseas. Boom length, 123' 6"

WWW.SURVIVALEBOOKS.COM

Table 5-6. Landing craft

Nomenclature	Designation	Classification	Length (Overall)	Beam (Molded)	Depth (Amidships)	Light Displacement (LTONs)	Draft Fwd	Draft Aft	Fuel Capacity (gal)	Fuel Consumption (gal/hr)	Speed Loaded (kn)	Operating Range (NMi)	Capacity Cargo (LTONs)	Capacity Troop	Cargo Dimensions Length	Cargo Dimensions Width	Ramp Opening	Remarks
Landing craft, utility, diesel, steel, 135', Navy Design LCU 1646 class	LCU	STD-A	135' 1"	34'	6' 0"	180.0	(Light) 2' 0" (Loaded) 3' 1"	(Light) 3' 10" (Loaded) 4' 0"	3,700	34	7.0	700	150.0	300	52'	29' 5"	14' 4"	Fresh water capacity, 9,563 gal.
Landing craft, utility, diesel, steel, 135', Navy Design LCU 1646 class	LCU	—	135' 1"	29'	[1]	65.1	(Loaded) 3' 6"	(Loaded) 6' 0"	3,290 at 95%	25	92.0	1,200[2]	170.0	[1]	105'	17' 0"	14' 0"	Fresh water capacity, not available
Landing craft, mechanized, diesel, steel, 74', Mod II, Mark VIII, Navy Design LCM 8	LCM	STD-A	74' 0"	21'	9' 4"	57.8	(Light) 3' 6" (Loaded) 3' 0"	(Light) 3' 6" (Loaded) 5' 0"	864	43	9.0	900	53.5	200[3]	42'	15' 0"	14' 6"	
Lighter, beach discharge, deck cargo, diesel, steel, 338', Design 5002	BDL	STD-A	338' 0"	65'	21' 0"	1,548.8	(Beaching) 6' 0" (Ocean) 5' 8"	(Beaching) 10' 0" (Ocean) 13' 8"	69,753	155	8.5	5,500	(Beaching) 600 (Ocean) 2,200	200 w/o berths	(Total sq ft) 15,000		22' 0" (Overhead clearance 13' 6")	Has ocean-sailing capability. Fresh water capacity, 23,941 gal.

[1] Information not available.
[2] May vary according to propulsion design
[3] Combat-equipped

Table 5-7. Amphibians

Nomenclature	Designation	Classification	Length (Overall)	Beam (Overall)	Height (Overall)	Light Displacement (LTONs)	Draft[1] Fwd	Draft[1] Aft	Fuel Capacity (gal)	Fuel Consumption (gal/hr)	Type Fuel	Speed Land (MPH)	Speed Water (kn)	Range Land (st mi)	Range Water (NMi)	Capacity Cargo (LTONs)	Capacity Troops	Cargo Dimensions	Ramp Opening	Speed Loaded	Payload/ Endurance	Remarks
Lighter, amphibious (LARC XV), self-propelled diesel, aluminum, 15-T, Design 3004	LARC	STD-A	45' 0"	14' 7"	15' 6"[2]	20.81	(Light) 4' 0" (Loaded) 4' 11"	(Light) 4' 11" (Loaded) 5' 6"	360	(Land) 16.32 (Water) 28.16	—	29.5	8.6	300	54	15	50[3]	24' 0" x 13' 6"	9' 0"			
Lighter, amphibious (LARC LX) self-propelled diesel, steel, 60-T, 61', Design 2383	LARC[4]	STD-A	62' 6"	26' 7"	19' 5"[5]	87	(Light) 6' 2" (Loaded) 7' 11"	(Light) 7' 5" (Loaded) 8' 8"	600	38	—	14.0	7.0	150	75	(Norm) 60 (Emerg) 100	(Norm) 125 (Emerg) 200	38' 3" x 13' 8"	14' 6"			
Lighter, amphibious, LACV 30 air-cushion vehicle	LACV	STD-A	(On Cushion) 76' 3"	(On Cushion) 36' 4"	(On Cushion) 24' 8" (Off Cushion) 21' 5"	—	—	—	(Main tank) 2,365 (Emerg fuel capacity) 1,584	260	Jet A-1, JP4, JP5	—	—	—	—	—	—	51' 6" x 32' 6"	—	47 MPH max 57 MPH	30 LTONs/2 hr 27.3 LTONs/5 hr 23.7 LTONs/9.1 hr	Has self-unload capability with the addition of an optional bow-mounted swing crane.

[1] Draft is calculated from tire bottoms.
[2] Reducible to 13' 8"
[3] Emergency
[4] Formerly LARC
[5] Reducible to 15' 4"

WWW.SURVIVALEBOOKS.COM

Table 5-8. Tugs


Nomenclature	Designation	Classification	Length (Overall)	Beam (Molded)	Depth (Molded Amidships)	Displacement (LTONs) Light	Displacement (LTONs) Loaded	Maximum Draft (Aft)	Fuel Capacity (gal)	Fuel Rate (gal/hr)	Fresh Water, Potable (gal)	Speed (kn)	Range[1] (NMs)	Bollard Pull (lb)	Remarks
Tug, harbor, diesel, 200 HP, steel, 45', Design 320	ST	STD-A	45' 2¼"	12' 9¾"	7' 9¾"	25	29	6' 0"	900	10.25	55	10	790	4,400	Deck loaded for overseas shipment.
Tug, harbor, diesel, 600 HP, steel, 65', Design 3004	ST	STD-A	70' 11½"	19' 6"	9' 7¾"	100	122	8' 2½"	5,844	36.1	900	12	1,700 light (142 hr w/tow)	17,500	Normally transported overseas on a larger vessel. Has ocean-sailing capability.
Tug, harbor, diesel, 1,200 HP, steel, 100', Design 3006	LT	STD-A	107' 0"	26' 6"	14' 10"	295	390	12' 2"	21,146	68.0	2,756	12	3,700 (294 hr w/tow)	27,500	

[1] Ranges estimated as free-running.


Table 5-9. Barges

Nomenclature	Designation	Classification	Length (Overall)	Beam (Molded)	Depth (Molded)	Displacement (LTONs) Light	Displacement (LTONs) Loaded	Maximum Draft Light	Maximum Draft Loaded	Cargo Liquid	Cargo Dry	Remarks
Barge, deck cargo, nonpropelled, steel, 570-T, 110', Design 7005	BC	STD-A	110' 0"	32'	9' 0"	120.0	690	1' 8"	7' 8"	—	570 LTONs	Conversion kit, barge deck enclosure, Design 7006, is adaptable to this item. Can be towed overseas.
Barge, deck cargo, nonpropelled, steel, 585-T, 120', Design 231A	BC	STD-A	120' 0"	33'	10' 6"	175.0	760	2' 4"	8' 0"	—	585 LTONs	Can be towed overseas; hull designed for relatively high-speed towing.
Barge, deck or liquid cargo, nonpropelled, steel, 578-T or 4,160 bbl, 120', Design 231B	BG	STD-A	120' 0"	33'	10' 6"	175.0	753	2' 4"	8' 6"	4,160 bbl	578 LTONs on deck	Can be towed overseas with full load provided maximum draft does not exceed 8'.
Barge, refrigerator, nonpropelled, steel, 14,200 cu ft, 120', Design 7010	BR	STD-B	120' 0"	33'	10' 6"	225.0	546	3' 0"	5' 10"	—	14,200 cu ft	Can be towed overseas.
Barge, refrigerator, nonpropelled, steel, 46,476 cu ft, 210', Design 7016	BR	STD-B	210' 0"	40'	15' 0"	1,100.0	2,250	5' 8"	8' 5"	—	46,476 cu ft	Can be towed overseas.
Repair shop, floating, marine equipment, nonpropelled, steel, 210', Design 7011	FMS	STD-A	210' 5"	40'	15' 0"	1,160.0	1,525	6' 1"	7' 9"	NA	NA	Can be towed overseas. Repair shops include electrical, carpentry, engine repair, battery, fuel injection, blacksmith, machine, refrigeration, sheet metal, welding, pipe fitting, paint, and ship fitting.
Barge, deck or liquid cargo, nonpropelled, steel, 21-T or 225 bbl, 45' knockdown, Design 218E	BK	STD-B	45' 0"	18'	3' 0"	13.0	33	0' 8"	1' 8"	225 bbl	20.98 LTONs on deck	Can be sectionalized for deck-loading and rail movement; barge is divided into two sections, each 9'2" x 45'5" x 3'0". Transports limited quantities of liquid or dry cargo on inland waters.
Barge, deck cargo, nonpropelled, steel, 130-T, 81', sectionalized, nesting, Design 7001	BK	STD-A	81' 0"	22'	7' 0"	57.5	203	1' 6"	4' 9"	—	(Deck) 130 LTONs (Hold) 150 LTONs	Can be sectionalized and nested for shipment. Lacks stability.
Pier, barge-type, self-elevating, nonpropelled, steel, 150' long, 60' wide, 10' deep, Design 7028	BPL	STD-A	150' 0"	60'	10' 0"	1,131.2	—	—	4' 8"	—	1,131.2 LTONs	Can be towed overseas. Used to construct piers and sea island terminals. Fitted with 2 compressors for 6 air jacks, 20 each 60' x 5' 11" caissons.
Pier, barge-type, self-elevating, nonpropelled, steel, 300' long, 80' wide, 13' deep, Design 7029	BPL	STD-A	300' 0"	80'	13' 0"	1,221.32	2,452.149	—	3' 9"	—	2,207.812 LTONs	Can be towed overseas. Same as Design 7028. Fitted with 2 compressors for 10 air jacks, 20 each 60' x 5' 11" caissons.


WWW.SURVIVALEBOOKS.COM




BOAT, PICKET, WOOD, DESIGN 4002




BOAT, PICKET, STEEL, DESIGN 4003




BOAT, PASSENGER AND CARGO, DESIGN 2001




VESSEL, LIQUID CARGO, DESIGN 7014



CRANE, BARGE, 60 LTONs, DESIGN 413D





CRANE, BARGE, 89 LTONs, DESIGN 264-B





LANDING CRAFT, UTILITY, 1466 CLASS







LANDING CRAFT, UTILITY, 1646 CLASS

Figure 5-6. Army watercraft


WWW.SURVIVALEBOOKS.COM




LANDING CRAFT, MECHANIZED, LCM-8




LIGHTER, BEACH DISCHARGE, DESIGN 5002




LIGHTER, AMPHIBIOUS, LARC-5



LIGHTER, AMPHIBIOUS, LARC-15




LIGHTER, AMPHIBIOUS, LARC-60




LIGHTER, AMPHIB, AIR-CUSHION VEHICLE, LACV-30

Figure 5-6. Army watercraft (cont)


WWW.SURVIVALEBOOKS.COM




BARGE, DECK CARGO, DESIGN 231A




BARGE, DECK OR LIQUID CARGO, DESIGN 231-B




BARGE, DECK CARGO, DESIGN 7001




BARGE, DECK CARGO, DESIGN 7005



TUG, HARBOR, 65-FOOT, DESIGN 3004




TUG, HARBOR, 100-FOOT, DESIGN 3006



REPAIR SHOP, FLOATING, MARINE EQUIPMENT, DESIGN 7011

Figure 5-6. Army watercraft (cont)

WWW.SURVIVALEBOOKS.COM



LASH SEABEE

Figure 5-7. LASH and SEABEE barges

MARITIME ADMINISTRATION (MARAD) CLASSIFICATION SYSTEM

The MARAD system classifies ships by design type. Three groups of letters and numbers indicate the characteristics of the Ship:

- Group 1 —type of ship and its length at the load waterline (LWL).
- Group 2—type of machinery, number of propellers, and passenger capacity.
- Group 3—chronological design number and alterations (assigned by MARAD).

For example, "C4-S-la" denotes a cargo vessel of between 500 and 550 feet with steam propulsion and one propeller, carrying less than 12 passengers. The ship is version "a" of the first design. See Table 5-10 for the code classifications for Group 1. See Table 5-11 for code classifications for Group 2, the middle digits.

Table 5-10. MARAD classification system (group 1)

		Length at Load Waterline (ft)							
	Ship	(1)	(2)	(3)	(4)	(5)	(6)	(7)	Remarks
B	Barge	up to 100	100 to 150	150 to 200	200 to 250	250 to 300	300 to 350	350 to 400	(1)
C	Cargo	up to 400	400 to 450	450 to 500	500 to 550	550 to 600	600 to 650	650 to 700	(1)
G	Great Lakes cargo	up to 300	300 to 350	350 to 400	400 to 450	450 to 500	500 to 550	550 to 600	(1)
H	Great Lakes passenger	up to 300	300 to 350	350 to 400	400 to 450	450 to 500	500 to 550	550 to 600	(2)
IB	Integrated tug-barge	up to 200	200 to 300	300 to 400	400 to 500	500 to 600	600 to 700	700 to 800	(1)
J	Inland cargo	up to 50	50 to 100	100 to 150	150 to 200	200 to 250	250 to 300	300 to 350	(2)
K	Inland passenger	up to 50	50 to 100	100 to 150	150 to 200	200 to 250	250 to 300	300 to 350	(2)
L	Great Lakes tanker (ore or grain)	up to 400	400 to 450	450 to 500	500 to 550	550 to 600	600 to 650	650 to 700	(1)
LG	Liquid gas	up to 450	450 to 500	550 to 600	600 to 650	650 to 700	700 to 750	750 to 800	(1)
N	Coastwise cargo	up to 200	200 to 250	250 to 300	300 to 350	350 to 400	400 to 450	450 to 500	(2)
OB	Combination oil-bulk/ore	up to 450	450 to 500	500 to 550	550 to 600	600 to 650	650 to 700	700 to 800	(1)
P	Passenger (100 or more)	up to 500	500 to 600	600 to 700	700 to 800	800 to 900	900 to 1000	1000 to 1100	(1)
Q	Coastwise passenger	up to 200	200 to 250	250 to 300	300 to 350	350 to 400	400 to 450	450 to 500	(2)
R	Refrigerated	up to 400	400 to 450	450 to 500	500 to 550	550 to 600	600 to 650	650 to 700	(2)
S	Special X	up to 200	200 to 300	300 to 400	400 to 500	500 to 600	600 to 700	700 to 800	(1, 3)
T	Tanker	up to 450	450 to 500	500 to 550	550 to 600	600 to 650	650 to 700	700 to 800	(1)
U	Ferries	up to 100	100 to 150	150 to 200	200 to 250	250 to 300	300 to 350	350 to 400	(2)
V	Towing vehicles	up to 50	50 to 100	100 to 150	150 to 200	200 over			

[1]Larger vessels are designated by successive numbers in 100-foot increments (C8 for 700 through 799 ft, and so forth).
[2]Longer vessels are designated by successive number in 50-foot increments (H8 for 600 through 650 ft, and so forth).
[3]The special designation X applies to certain Navy ships built by MARAD and other ships so specialized that they don't fit any other designation.

WWW.SURVIVALEBOOKS.COM

Table 5-11. MARAD classification of ship machinery, propellers, and passenger capability (group 2)

Machinery Type	Propellers	Passenger Capability 12 and Under[1]	Passenger Capability Over 12[2]
Steam	Single	S	S1
Motor	Single	M	M1
Steam and motor	Single	SM	SM1
Turboelectric	Single	SE	SE1
Diesel-electric	Single	ME	ME1
Gas turbine	Single	G	G1
Gas turboelectric	Single	GE	GE1
Nuclear	Single	N	N1
Steam	Twin	ST	S2
Motor	Twin	MT	M2
Steam and motor	Twin	SMT	SM2
Turboelectric	Twin	SET	SE2
Diesel-electric	Twin	MET	ME2
Gas turbine	Twin	GT	G2
Gas turboelectric	Twin	GET	GE2
Nuclear	Twin	NT	N2

[1]For triple- and quadruple-screw vessels, add TR or Q respectively to single-screw designation. For example, a triple-screw motor ship is MTR.
[2]For triple- and quadruple-screw vessels, make digit 3 or 4 respectively. For example, quadruple-screw steam is S4.

Section III. TERMINAL EQUIPMENT, CARGO CONTAINERS, PALLETS, AND MARKINGS

TERMINAL EQUIPMENT

See Tables 5-12 through 5-16 for data on–

- Gasoline-powered forklifts.
- Rough-terrain forklifts.
- Wheeled warehouse tractors.
- Electric-powered forklifts.
- Truck-mounted cranes.

See Figures 5-8, -9, and -10 for descriptions of the rough-terrain container handler (RTCH), the yard tractor, and other terminal equipment.

Table 5-12. Gasoline-powered forklifts

Model Number	Length (in)	Width (in)	Height (in)	Weight (lb)	Lift Height (in)	Free Lift (in)	Capacity (lb)	Tire Type[1]
FB 20-24 (131)	63¾	32	83	4,304	130	12	2,000	S
KC 51T20H-RS53 (156)	70	32½	83	4,134	130	66	2,000	S
MY40RS (170)	97½	60½	90½	8,500	144	57	4,000	P
MY40 (170)	94½	60½	90½	8,500	144	57	4,000	P
G54P-4024RS (166)	92¾	63½	91	8,420	144	57	4,000	P
540 RS (160) VI	89¾	44	83	10,500	127	57	6,000	S
Yardlift 60 RS (115)	113	68	115	9,705	168	6¼	6,000	P
MY 60 RS (171)	110¼	70	110½	9,720	168	18½	6,000	P
GLF 100- (163)	110¼	53	68	13,200	100	43	10,000	S
Yardlift 150-53RS (151)	152	96	150	22,000	210	2½	15,000	P
H 150C (178)	145	81	152	19,050	210	2	15,000	P

[1]Tire types: S—solid rubber, P—pneumatic

WWW.SURVIVALEBOOKS.COM

Table 5-13. Rough-terrain forklifts

Model Number	Length (in)	Width (in)	Height[1] (in)	Weight (lb)	Lift Height (in)	Power	Capacity (lb)	Tire Type[2]
Baker RPF060M02 (164)	204	84	96	8,000	78	Gasoline	4,000 RT	P
Anthony MLT6	229½	86	94	16,800	144	Gasoline	6,000	P
MR 100 (173)	228	102	124[4]	23,800	144	Diesel	6,000 RT	P
—	138[3]	—	—	—	—	—	—	—
Millicin	244	103	100	30,000	144	Gasoline	10,000	P
—	252	—	133[4]	—	—	—	—	—
RTL-10	203[3]	106	—	34,500	142	Diesel	10,000 RT	P

[1]With mast collapsed.
[2]P—pneumatic.
[3]Less forks.
[4]With guard.

Table 5-14. Wheeled warehouse tractors

Model Number	Length (in)	Width (in)	Height (in)	Shipping Weight (lb)	Number of Wheels	Drawbar Pull (lb)	Tire Type[1]	Power
TSSA	89½	41⅞	62	2,740	3	2,000	S	Electric
MTT-W	79	42	48½	3,500	4	3,500	S	Electric
MW-4-SE	86	42	59	3,545	4	4,000	S	Electric
Clarktor-40-RS	110	65½	56	4,700	4	4,000	P	Gasoline
J-217-E	116	66	62	5,800	4	4,000	P	Gasoline
Clarktor-75	119	69	56½	9,940	4	7,500	P	Gasoline

[1]Tire types: S—solid rubber, P—pneumatic

Table 5-15. Electric-powered forklifts


Model Number	Length (in)	Width (in)	Height[1] (in)	Weight (lb)	Lift Height (in)	Free Lift	Capacity (lb)	Tire Type[2]
FSHEYG20/48	69½	34¼	83	3,808	130	5	2,000	S
Clipper ECE2024SE	64⅞	34½	83	3,900	130	64	2,000	S
RAT 30 Type E	37¼	13	31¼	5,130	144	44	3,000	S
FTHEG 40/48	81	41½	91	6,950	144	7½	4,000	S
Carloader SE ELL 4024	77¼	41	91	6,613	144	70	4,000	S
FT 60/48	88	47½	83	8,000	127	61	6,000	S
EUT 6024 SE 50	92¼	43	133	8,550	168	6	6,000	S

[1]With mast collapsed.
[2]S—solid rubber.


Table 5-16. Truck-mounted cranes

Item	Capability (STONs)	Length (in)	Width (in)	Weight (lb)	Basic Boom Length (ft)
20-ton crane	20 @ 10' radius	326	119.0	59,860	30
140-ton crane	140 @ 12' radius	873 w/50' boom	132.5	195,000 w/120' boom	50
250/300-ton crane	250 @ 18' radius	570	144.0	370,000 w/160' boom	70


WWW.SURVIVALEBOOKS.COM




140-TON CRANE




250-TON CRANE



20-TON ROUGH TERRAIN CRANE




6,000-POUND FORKLIFT




WAREHOUSE TRACTOR AND TRAILERS

Figure 5-8. Terminal equipment


WWW.SURVIVALEBOOKS.COM




4,000-POUND ROUGH-TERRAIN FORKLIFT




6,000-POUND ROUGH-TERRAIN FORKLIFT



10,000-POUND ROUGH-TERRAIN FORKLIFT



ROUGH-TERRAIN CONTAINER HANDLER (RTCH)



YARD TRACTOR

Figure 5-8. Terminal equipment (cont)

WWW.SURVIVALEBOOKS.COM

Model: Caterpillar
Length: 423"
Width: 140"
Height: 167"
Mast height at maximum lift: 229"
Shipping weight (70% fuel): 105,120 lb
Operational weight
Without top handler: 103,230 lb
With 20' top handler: 107,030 lb
With 35' top handler: 112,350 lb
With 40' top handler: 113,160 lb

Maximum speed (forward)
With rated load: 14.5 MPH
Without rated load: 18.5 MPH
Maximum fording depth: 60"
Lifting capacity: 50,000 lb

Tophandler	Length	Width	Weight
20'	238"	100"	3,800 lb
35'	419 1/2"	100"	9,120 lb
40'	479 1/2"	100"	9,930 lb

Can lift container 118" above ground level (measured from bottom of container)

Figure 5-9. Characteristics of rough-terrain container handler

Model: Ottawa Model 50
Vehicle weight: 15,520 lb
Length: 191 1/2"
Width: 102 1/4"
Height: 129 5/8"
Fifth wheel lift capacity: 70,000 lb
Fifth wheel lift: 16 3/8"


Figure 5-10. Characteristics of yard tractor

CARGO CONTAINERS

There are three major kinds of cargo containers used in the DTS:

- CONEX (container express).
- MILVAN (military-owned remountable container).
- Commercial container.

CONEX. CONEXs are reusable metal shipping boxes mounted on skids and fitted with recessed lifting eyes or lugs at the top four corners. They are produced in two styles: full-size and half-size. See Figure 5-11.




	Type 1 (Half Size)*	Type 2 (Standard)
Inside		
Length	3' 10 5/8"	8' 1 5/8"
Width	5' 11 3/4"	5' 11 3/4"
Height	6' 3/8"	6' 3/8"
Outside		
Length	4' 3"	8' 6"
Width	6' 3"	6' 3"
Height	6' 10 1/2"	6' 10 1/2"
Cargo Capacity	9,000 lb	9,000 lb
Empty Weight	900 lb	1,500 lb

*For cargoes with overall density exceeding 45 pounds per cubic foot.

Figure 5-11. CONEX characteristics

MILVAN. MILVANs are standard 8-foot high and wide by 20-foot long remountable containers that may be moved by all modes of transportation. They conform to US and international standards. For highway movement, the container is attached to a MILVAN chassis by coupling its lower four standard corner fittings to compatible mounting blocks on the chassis. See Figure 5-12.

WWW.SURVIVALEBOOKS.COM



Outside	
Length	20' 0"
Width	8' 0"
Height	8' 0"
Inside	
Length	19' 4"
Width	7' 6"
Height	7' 1"
Cargo Capacity	41,300 lb
Empty Weight	3,500 lb

Figure 5-12. MILVAN characteristics

Commercial container. The commercial transportation industry uses many types of containers to transport different kinds of cargo. The dry-van container is the most commonly used. See Figures 5-13 and 5-14.

TYPE	LENGTH (FEET)	TYPE	LENGTH (FEET)
Dry-van	20, 24, 27, 30, 35, 40, 45	Bulk-dry	24, 40
Reefer	20, 24, 27, 30, 35	Bulk-liquid	20, 35, 40
Refrigerated	20, 27, 40	Side door	20, 40
Ventilated	24, 27	Cartainer	35, 40
Insulated	20, 24, 35, 40	Cattletainer	35
Open-top	20, 35, 40	Garmenttainer	20, 40
Open-top (1/2 high)	40	Housing and office	40
Platform	20, 24, 27, 35, 40	Display	20, 40
Platform (1/2 high)	35, 40	Communications	40

Figure 5-13. Commercial container types

20' × 8' × 8'
20' × 8' × 8'6"
24' × 8' × 8'6"
27' × 8' × 9'6"
30' × 8' × 8'6"
40' × 8' × 8'
40' × 8' × 8'6"
40' × 8' × 9'
40' × 8' × 9'6"
45' × 8' × 9'6 1/2"

Figure 5-14. Dry-van container dimensions

PALLETS

General-Purpose. The general-purpose pallet is a four-way-entry, wooden pallet 48 inches long, 40 inches wide, and about 5 1/4 inches high. It is used primarily for shipping palletized cargo. The pallet may be loaded and shipped from shipper to consignee without rehandling the cargo. The four-way-entry feature permits easy entry by forklift truck forks. See Figure 5-15.

Sled Pallet. The sled pallet consists of a heavy, timbered platform and runners on which 3,000 pounds of supplies and equipment may be secured with steel bands. The pallet

WWW.SURVIVALEBOOKS.COM




Figure 5-15. General-Purpose Pallet




Figure 5-16. Sled pallet

alone weighs 200 pounds. Cables attached to the runners permit towing. Sled pallets maybe moved through any surf or over any beach which may be crossed by LVTPs, wheeled landing vehicles, or similar craft. Rations, water, fuel in 5-gallon containers, and ammunition are the most suitable supplies for pallet loading. See Figure 5-16.

CARGO ADDRESS MARKINGS

Cargo address markings show where a shipment is coming from and where it is going. Address markings are required on all items being shipped in the DTS. There are three methods of applying addresses, depending on type of container and priority of shipment: labels, tags, and stencils.

Labels. Labels are preprinted forms glued to the package being shipped. Shipping labels are used on boxes, crates, drums, and other containers when practical.

Tags. Tags are preprinted cards that have a hole at the center of one end and a string attached through the hole for tying the tag to the cargo. Tags are used on SEAVANS/ MILVANS, cloth bags, and other items when it is impractical to apply a label or stencil.

Stencils. Stencils are used when space or material surface permits and when the shipment has a low transportation priority not requiring an expedited handling label or tag. Stencils are locally produced address markings normally produced by punching out alphanumeric characters on stencil paper using a stencil cutting machine. The stencil is held against the crate and painted over. The stencil is then removed, leaving clear block letters on the crate.

Format

Regardless of whether a label, tag, or stencil is used, the format and information contained in the address marking are basically the same. See Figure 5-17. Numbers in parentheses in the following paragraphs refer to numbers in Figure 5-17.




Figure 5-17. Sample DD Form 1387-1 (Military Shipping Tag)

WWW.SURVIVALEBOOKS.COM

Transportation control number (TCN) (1). The TCN appears on the first line of the address on a cargo shipment label. The TCN is a 17-digit number/letter code group assigned to a shipment unit to identify and control the shipment throughout the transportation system. The TCN is the most important piece of information in the address because it is the reference point for all MILSTAMP documents, shipping actions, and tracer actions.

There are two types of transportation control numbers, MILSTRIP and non-MILSTRIP. The MILSTRIP TCN, which is the most commonly used, is discussed here. See Figure 5-18 for the data contained in a MILSTRIP TCN.




Figure 5-18. Example of MILSTRIP TCN

Required delivery date (RDD) (2). The RDD is the Julian date the requisitioner expects the shipment. When necessary to expedite a shipment because of urgent demands, use the expedite-handling code "999" instead of the Julian date. Code "999" identifies the shipment as critically needed; it should receive the highest priority in processing and shipping. A red and white 999 label is put on the front and back of the container.

Project code (3). The project code is a three-position code used to identify a shipment made in suppport of a specific project, program, special exercise, or maneuver. When a project code is not assigned, the shipper leaves this block blank.

Transportation Priority (4). Each shipment moving in the DTS is assigned a transportation priority (TP) number. This priority determines the mode used to ensure delivery to the consignee by the RDD. The shipping transportation officer assigns the TP to the shipment based on information found on supply release documents.

"From" section (5). The shipper's coded, in-the-clear address is placed in this space. The coded address is taken from the Department of Defense Address Directory.

"To" section (6). When a shipment is going direct from a shipper to the requisitioner without going through an aerial or water port, the coded, in-the-clear address of the consignee (receiver) is placed in this block.

Port of embarkation (POE) (7). When a shipment is going to an aerial or water port for onward movement overseas, the coded, in-the-clear address of the POE is placed in the same block as the "to" address.

Port of debarkation (POD)(8). The POD is the coded, in-the-clear address of the aerial or water port that will discharge the cargo when it arrives in the oversea area.

Ultimate consignee (9). The "ultimate consignee or mark for" block is used only with oversea shipments. This block is not required for domestic shipments as the ultimate consignee will already have been indicated in the "to" block. Oversea shipments require the "ultimate consignee" block for the coded, in-the-clear address of the consignee because the "to" block has already been used for the POE address.

Piece Number (10) and Total Pieces (11). Pieces of cargo in a shipment are numbered 1, 2, 3, 4, 5, et cetera until each piece is assigned a number. The highest sequence number is the total pieces in the shipment. For example, if six crates of oranges are shipped to Maine, each crate (piece) will get a number. The second crate will be crate number two of six total pieces. A shipping piece number is applied to each container in a shipment except—

- Shipments of the same commodity in standard containers or packages.
- Full carload and truckload shipments of like items sent to a CONUS activity.

WWW.SURVIVALEBOOKS.COM

In addition to the individual piece number, the total number of pieces in the shipment is shown in the shipping address. When the address is stenciled on a container, the piece number is shown on the bottom line of the address followed by a slash and the total number of pieces in the shipment. When a label or tag is used, the piece number and total number of pieces are entered in the blocks provided on the bottom line of the address.

Weight (12). The gross weight (the combined weight of cargo, packing material, and container) in pounds is entered.

Cu6e (13). For shipping purposes, the cubic measurement (cube) of a piece of cargo is expressed in cubic feet. Shipments are occasionally received for transshipment that do not show the cube of the container. When this occurs, the checker should measure the container and mark the cube on it. Compute the cube by multiplying length, width, and height of the container. If the measurements are not all even feet, convert all dimensions to inches and divide the total by 1,728.

WWW.SURVIVALEBOOKS.COM

APPENDIX A

ORDERS, PLANS, AND SOP FORMATS

The formats in this appendix (Figures A-1 through A-12) have been condensed for the transportation planner. Normally, these formats apply only in the initial stages of planning. See AR 380-5 for classification procedures.

_____
(Classification)

Copy _____ of _____ copies
Issuing headquarters
Place of issue *(may be in code)*
Date-time group of signature
Message reference number

OPERATION PLAN (ORDER): Type and serial number. *(Type is usually indicated for combined or joint operations but omitted for a single service. When required, a code title may also be included.)*

References: *Maps, charts, and other relevant documents.*

Time zone used throughout the order: _____.

Task organization: *Task subdivisions or tactical components of the command. (When a task organization is not listed, this information is included in paragraph 3 or in an annex. If an annex is used, indicate "Annex A (Task Organization)."*

1. SITUATION. *General information on the overall situation required to understand current circumstances.*

a. Enemy Forces. *Composition, disposition, location, movement, estimated strength, identification, and capability.*

b. Friendly Forces. *Information on forces, other than those covered by this order, which may directly affect actions of subordinates.*

c. Attachments and Detachments. *Units attached to or detached from the issuing unit (if not shown under task organization) and effective times. (If shown under task organization, appropriate reference is listed here.)*

Figure A-1. Operation plan (order) format

WWW.SURVIVALEBOOKS.COM

2. MISSION. *A clear, concise statement of the task and its purpose.*

3. EXECUTION.

a. First Subparagraph. *The operation's concept, including the commander's general plan for developing and phasing the operation, using fire support, instructing on preparatory fires, and designating unit making the main effort.*

b. Following Subparagraphs. *Specific tasks of each element charged with tactical missions, including the combat organization (if not given under task organization).*

c. Final Subparagraph (Coordinating Instructions). *Details of coordination and control measures applicable to the command as a whole. Also—to avoid repetition—coordinating and operating instructions which apply to two or more elements.*

4. SERVICE SUPPORT. *A statement of CSS instructions and arrangements supporting the operation. Also the commander's direction to CSS commanders. If lengthy, details may be included in an annex and referenced here. At higher levels of command, reference may be made to an administrative/logistics order.*

a. Materiel and Services.
b. Medical Evacuation and Hospitalization.
c. Personnel.
d. Civil-Military Cooperation.
e. Miscellaneous.

5. COMMAND AND SIGNAL. *Command and C-E operation instructions.*

a. Command. *Command post (CP) locations and axis of CP displacement, if not shown on an accompanying overlay. Liaison requirements, designation of alternate CP, and succession of command, if not adequately covered in the SOP.*

b. Signal. *Rules on use of communications and other electronic equipment (for example, radio silence). May refer to an annex, but, as a minimum, should list the current communications-electronics operation instructions (CEOI) index.*

Acknowledgment Instructions.

/s/ _____
Commander (name and rank)

Authentication:
Annexes:
Distribution:

_____
(Classification)

Figure A-1. Operation plan (order) format (cont)

WWW.SURVIVALEBOOKS.COM

_____
(Classification)

(Change from oral orders, if any)

Copy _____ of _____ copies
Issuing headquarters
Place of issue *(may be in code)*
Date-time group of signature
Message reference number

ANNEX ____ (SERVICE SUPPORT) to OPERATION ORDER NO ____

References: *Maps, charts, and other relevant documents.*

Time zone used throughout the order: _____.

1. GENERAL
2. MATERIEL AND SERVICES
   a. Supply.
   b. Transportation.
   c. Services.
   d. Maintenance.
   e. Other (as necessary).
3. MEDICAL EVACUATION AND HOSPITALIZATION
4. PERSONNEL
5. CIVIL-MILITARY COOPERATION
6. MISCELLANEOUS

Acknowledgment instructions.

_____
Last name of commander
Rank

Authentication:
Appendixes:
Distribution:

_____
(Classification)

Figure A-2. Service support annex format

WWW.SURVIVALEBOOKS.COM

(Appendix issued with the annex)

(Classification)

APPENDIX 1 (TRAFFIC CIRCULATION AND CONTROL) to ANNEX E (SERVICE SUPPORT) to OPERATION ORDER 14 –23d Armd Div

Reference: Map, series V762, UNITED STATES, sheet 4071 (UPTON), edition 3-AMS, 1:50,000.




Figure A-3. Sample traffic circulation and control appendix to service support annex, division

WWW.SURVIVALEBOOKS.COM

_____
(Classification)

(Change from oral orders, if any)[1]

Copy _____ of _____ copies
Issuing headquarters
Place of issue *(may be in code)*
Date-time group of signature *(must include time zone suffix)*[2]
Message reference number

ADMINISTRATIVE/LOGISTICS PLAN (ORDER) NO _____[3]

RELATED OPERATION PLAN (ORDER) NO _____ *(when applicable)*

References: *Maps, charts, and other relevant documents.*[4]

Time zone used throughout the plan (order): _____

Composition and location of administrative and logistic service units. *This information may appear here, in the appropriate paragraph of the order, or in a trace or overlay. If units are not listed here, this heading may be omitted.*

Notes appear at end of plan.

1. SITUATION. *A general statement of administrative and logistic factors affecting support of the operation. Information from paragraph 1 of the related operation plan or order which is essential to combat service support.*

a. Enemy Forces. *Composition, disposition, location, movements, estimated strength, and identification. (Reference to an operation order or to the intelligence annex to an operation order, if available.) Enemy capabilities that may influence the CSS mission.*

b. Friendly Forces. *Pertinent information on own forces that may directly influence the CSS mission, if not covered by a referenced operation order or included in subsequent paragraphs.*

c. Attachments and Detachments.

d. Assumptions.[5]

2. MISSION. *A clear, concise statement of the CSS task and its purpose.*

3. GENERAL. *An outline of the general plan for CSS and any orders not covered by succeeding paragraphs (for example, location of the division support area and coordinating agencies, general instructions for movement of installation).*

4. MATERIEL AND SERVICES

a. Supply. *Subparagraphs for each class of supply, maps, water, special supplies, excess materiel, salvage materiel, and captured enemy materiel. When applicable, each subparagraph contains—*

- Location of the installations concerned with handling supplies and materiel for supported units.

Figure A-4. Administrative/logistics plan (order) format

WWW.SURVIVALEBOOKS.COM

- Opening and closing times.
- Operating units.
- Supported units.
- Levels of supply.
- Methods and schedules of distribution.
- Instructions for submission of routine reports concerning the supplies listed.
- Any other pertinent instructions or information needed by supported units.

Instructions and information for two or more classes may be included under one subparagraph if entries are limited and clarity is not sacrificed. For Class V, include designation and location of approving agency, controlled supply rate (CSR), prescribed nuclear load (PNL), and chemical munition allocations, as appropriate.

b. Transportation.

(1) Location of terminals and installations *(rail stations, airfields, ports, and beaches).*[6]

(2) Operating units.

(3) Schedules *(march tables, timetables, and entraining tables).*

(4) Area responsibilities of transportation movement officers and highway regulating teams.

(5) Traffic control and regulation measures *(regulations, restrictions, allocation priorities, regulating and control points).*

(6) Designation of main supply route (MSR).

c. Services. *Information and instructions for supported units—type of service available, designation and location of servicing unit or installation, support unit assignments, and service schedules, if applicable. Service missions for service units not covered in other orders (for example, priority of operating units and assignments to supported units). Special missions not covered in other orders.*

(1) Construction.

(2) Graves registration. *Collection points, evacuation procedures, and personal effects handling. Procedures for isolated burials and contaminated remains, if not contained in the unit SOP.*

(3) Field services. *Laundry, bath, clothing renovation and exchange, bakery, and decontamination.*

(4) Health services. *Medical, dental, veterinary services; laboratory and spectacle service, whole blood control, preventive medicine, and health and sanitation.*

(5) Installation service. *Real estate, repair and utilities, fire protection, sewage and trash disposal, and water supply.*

(6) Other. *Aviation, explosive ordnance disposal, photography, and procurement.*

d. Labor. *Policies and restrictions on using civilians, enemy prisoners of war (EPWs), and civilian internees and detainees; allocation and priorities of available labor; and designation and location of available labor units.*

e. Maintenance. *Include priority of maintenance, location of facilities, and collecting points.*

5. MEDICAL EVACUATION AND HOSPITALIZATION. *The plan for evacuation and hospitalization of sick, wounded, or injured military personnel.*

a. Evacuation. *The evacuation or holding policy. Responsibilities; evacuation routes, means, and schedules. Evacuation and en route treatment policies, when applicable. Specific policy for evacuation by air or ground and for evacuation of NBC-contaminated patients. Medical evacuation request procedures and channels, if different from SOP.*

Figure A-4. Administrative/logistics plan (order) format (cont)

WWW.SURVIVALEBOOKS.COM

b. Hospitalization. *List of all appropriate treatment facilities (dispensaries, aid stations, clearing stations, hospitals), their locations, and times of operation. Definitive treatment policies, including treatment of contaminated casualties, if established.*

c. Other Services. *Pertinent information on any other health services matters (dental, preventive medicine, medical supply, veterinary). Unit locations, support information, policies.*

6. PERSONNEL. *Information and instructions on personnel matters, including foreign civilian labor used in direct military support functions. Under each of the following subparagraphs are listed, when applicable—*

- Installation, location, and times of operation.
- Operating units.
- Units or area served.
- Rest, leave, and rotation criteria; quotas allocated to units.
- Unit responsibility for movement or administration of personnel.
- Reports, requisitions or plans.
- References to previous order, instructions, or SOP.

a. Unit Strength.

(1) Strength reports. *Instructions for submission of data required to keep the commander informed. Instructions include requirements for routine reports and special reports following a mass-destruction attack or a natural disaster.*

(2) Replacements. *A statement establishing validity of existing personnel requisitions. Instructions for submission of requisitions and for processing and moving replacements.* Location of replacement units and the units each will support. Type and location of unit replacements under control of the issuing headquarters.

b. Personnel Management.

(1) Military personnel. *Instructions on classification, assignment, promotion, transfer, reclassification, reduction, elimination, retirement, separation, training, rotation, and economic personnel use.*

(2) Civilian personnel. A list of—

- Sources of civilian labor.
- Locations of civilian personnel offices or other labor administration centers and labor pools.
- Procurement policies and procedures.
- Restrictions on use of civilian labor.
- Administrative and control procedures.
- Pay schedules, allowances, and CSS to be provided.
- Responsibilities of subordinate commanders for administation.

Reference appropriate SOP.[7]

(3) EPWs and civilian internees and detainees. *Instructions on collection, safeguarding, processing, evacuation, use, treatment, and discipline of EPWs and civilian internees and detainees and all other personnel arrested or captured but not immediately identifiable as POWs. Location of EPW and civilian internee facilities.*

c. Morale. *Instructions on leaves, rest and recreation facilities, decorations and awards, postal and finance services, chaplain activities, personal hygiene, morale support activities, post exchanges, and legal assistance.*

d. Discipline, Law, and Order. *Troop conduct and appearance. Control and disposition of stragglers, including location of straggler collecting points and special instruction for augmenting straggler control during mass-destruction attacks. Administration of military justice and relations between military and civilian personnel (fraternization, black marketing, selling government property, and respect for local laws).*

Figure A-4. Administrative/logistics plan (order) format (cont)

WWW.SURVIVALEBOOKS.COM

e. Headquarters Management. *Instructions on movement, spaced arrangement, organization, and operation. Allocation of shelter for the headquarters and for troops in the HQ area.*

f. Miscellaneous. *Personnel administrative matters not specifically assigned to another coordinating staff section or included in the preceding subparagraphs.*

7. CIVIL-MILITARY COOPERATION. *Allocation of civil affairs units, control of refugees, and feeding and treatment of the civilian population.*

8. MISCELLANEOUS. *Special instructions not covered above.*

a. Boundaries. *Location of rear boundary and any other boundary needed for CSS purposes.*

b. Protection. *Measures established for protection of CSS units and installations. Usually, an announcement of the tactical unit providing the protection, CSS units or installations receiving the protection, and any limitations to the protection.*[8] *Pertinent instructions from the rear area protection plan or reference to an annex.*

c. Special Reports. *Reports not included in previous paragraphs and those reports requiring special emphasis.*

d. Statement. *Include time or conditions under which the plan is to be placed in effect.*[2]

9. COMMAND AND SIGNAL. *Headquarters location and movements, liaison arrangement, recognition and identification instructions, and general rules on use of communications and other electronic equipment, if necessary. An annex may be used when considered appropriate.*

Acknowledgment instructions.

/s/ _____

Commander (name and rank) [9]

Authentication:[10]
Annexes:
Distribution:

---

[1] *Applicable only to an order. The phrase "No change from oral orders" or "No change from oral orders except paragraph ____" will appear here if oral orders have been issued concerning this operation. In the absence of oral orders, this space is left blank.*

[2] *This is the time the commander actually signs the plan or order and is the effective time of the order unless stated otherwise in paragraph 8.*

[3] *The type of administrative/logistics plan (order) indicates whether it is Navy, Army, Air Force, combined, or joint. For a single service, the type of administrative/logistics order is normally omitted. When required, a code title may also be included.*

[4] *Reference to a map should include the map series number and, if required, the country or geographic area, sheet number, name, edition, and scale per STANAG 2029.*

[5] *Applicable only to a plan.*

[6] *Items listed in this subparagraph are not limited necessarily to transportation operations and may include ocean, inland waterway, coastal, highway, air, rail, pipeline, and miscellaneous activities.*

[7] *Or provide specific pay scales and other conditions of employment in an annex.*

[8] *This announcement is information for CSS units, not an order to the tactical unit involved.*

Figure A-4. Administrative/logistics plan (order) format (cont)

WWW.SURVIVALEBOOKS.COM

[9]The commander's last name and rank appear on all copies. The original (copy number 1) must be signed by the commander or a specifically authorized representative. If the chief of staff signs the original, the phrase "FOR THE COMMANDER" is added. The signed copy is the historical copy that remains in the headquarters files.
[10]If the commander or his authorized representative signs a master copy which permits automatic reproduction of the signed document, no further authentication is required. If the signature is not reproduced, authentication by the preparing staff officer is required on all subsequent copies. The commander's last name and rank appear typed in the signature block.

(Classification)

Figure A-4. Administrative/logistics plan (order) format (cont)

(Classification)

(Change from oral orders, if any)

Copy _____ of _____ copies
Issuing headquarters
Place of issue *(may be in code)*
Date-time group of signature
Message reference number

ROAD MOVEMENT ORDER NO _____
(OR: ANNEX _____ (ROAD MOVEMENT) to OPERATION ORDER NO _____)
References: *Maps, tables, and other relevant documents.*
Time zone used throughout the order: _____ .
Task organization: _____ .

1. SITUATION
   a. Enemy Forces.
   b. Friendly Forces.
   c. Attachments and Detachments.
2. MISSION
3. EXECUTION
   a. Concept of Movement.
   b. Tasks of Subordinate Unit.
   c. Detailed Timings.
   d. Coordinating Instructions.
      (1) Order of march.

Figure A-5. Road movement order or annex format

WWW.SURVIVALEBOOKS.COM

(2) Routes.
(3) Density.
(4) Speed.
(5) Method of movement.
(6) Defense for move.
(7) Start, release, or other critical points.
(8) Convoy control.
(9) Harbor areas.[1]
(10) Halts.
(11) Lighting.
(12) Air support.

e. Other (as necessary).

4. SERVICE SUPPORT
   a. Traffic Control.
   b. Recovery.
   c. Medical.
   d. Petroleum, Oil, and Lubricants.
   e. Water.

5. COMMAND AND SIGNAL
   a. Commanders.
   b. Communications.
   c. Position of Key Vehicles.

Acknowledgment instructions.

Last name of commander
Rank

Authentication:
Appendixes:
Distribution:

[1] *A harbor area is a space set aside for normal halts, traffic control, and emergency congestion relief. Harbor areas are used—*

- *To hold vehicles at both ends of a crossing or defile.*
- *To make changes in density, especially at first or last light.*
- *To contain spillovers in serious delays (likely to be caused by enemy air attack or its results).*
- *To allow columns to rest and carry out maintenance and decontamination.*
- *To allow elements to change position in column if there is a change in priorities.*

(Classification)

Figure A-5. Road movement order or annex format (cont)

WWW.SURVIVALEBOOKS.COM

(Annex issued with the operation order)

(Classification)

APPENDIX 1 (ROAD MOVEMENT TABLE) to ANNEX K (ROAD MOVEMENT) to OPORD 9—20th Inf Div
Reference: Map, series M504, AFGAN, sheet 4842 (BHAD-WURST), edition 1-DMG, 1:100,000
Time zone used throughout the order: ZULU.

General Data:

1. Average Speed: 20 KPH.
2. Traffic Density: 20 VPK.
3. Halts: SOP.
4. Routes:
   a. Route RED. Serials: 1, 2, 3, and 5.
   b. Route BLUE. Serials: 2 and 6.
5. Critical Points:
   a. Route RED.
      (1) Start point: RJ 413 at MB201699.
      (2) Release point: RJ 211 at QA990628.
      (3) Other critical points.
         (a) RJ (VILLERS) at MB 330718.
         (b) RJ 242 at NB455701.
         (c) RJ (LAWST) at DA585692.
         (d) BLUE River bridge at PA683686.
      (4) Route classification: 6 x 50.
      (5) Route restrictions: BLUE River bridge—6 x 50.
   b. Route BLUE.
      (1) Start point: RJ 526 at MS229509.
      (2) Release point: RJ 105 at RS981511.
      (3) Other critical points.
         (a) RJ 592 at MS334481.
         (b) RJ (CHANCE) at NS401490.
         (c) RJ (VEGAS) at QT790501.
         (d) BLUE River bridge at RS860495.
      (4) Route classification: 10 x 50.
      (5) Route restrictions: BLUE River bridge—6 x 50.
6. Main Routes to Start Points: ***
7. Main Routes From Release Points: ***

NOTES

1. Only the minimum number of headings should be used. Include any information common to two or more movement numbers under the general data paragraphs.
2. Since the table may be issued to personnel concerned with traffic control, security must be remembered. It may not be desirable to include dates or locations.
3. If the table is issued by itself, not as an annex to a more detailed order, the table must be signed or authenticated in the normal way.
4. Critical point is defined as "a selected point along a route used for reference in giving instructions." Critical points include start points, release points, and other points along a route where interference with movement may occur or where timing is critical.
5. The movement number identifies a column (or element of column) during the whole of the movement.

Mov number	Date	Unit	No of vehicles	Load class of heaviest vehicle	From	To	Route	Route to start point	Critical points			Route from release point	Remarks
									Ref	Due	Clear		
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)
1	***	1st Bde COL Long, Comdr	***	***	BHAD area	WURST area	RED	***	SP RJ (VILLERS) RJ242 RJ (LAWST) BLUE River bridge RJ (HAINS) RP	0530 0610 0630 0715 0755 0815 0855	0635 0715 0735 0820 0900 0920 1000	***	*** PST 65 min
2	***	2d Bde COL Corley, Comdr	***	***	BHAD area	WURST area	BLUE	***	SP RJ592 RJ (CHANCE) RJ (VEGAS) BLUE River bridge RP	0530 0548 0630 0800 0840 0920	0635 0653 0735 0905 0945 1025	***	*** PST 65 min
3	***	3d Bde COL Smith, Comdr	***	***	BHAD area	WURST area	RED	***	SP RJ (VILLERS) RJ242 RJ (LAWST) BLUE River bridge RJ (HAINS) RP	0650 0730 0750 0835 0915 0935 1015	0755 0835 0755 0940 1020 1040 1120	***	*** PST 65 min
4	***	Div Arty COL Stephens, Comdr	***	***	BHAD area	WURST area	RED	***	SP RJ (VILLERS) RJ242 RJ (LAWST) BLUE River bridge RJ (HAINS) RP	0810 0850 0910 0955 1035 1055 1135	0920 1000 1020 1105 1145 1205 1245	***	*** PST 70 min
5	***	Div Trp LTC Camp, Comdr	***	***	BHAD area	WURST area	RED	***	SP RJ (VILLERS) RJ242 RJ (LAWST) BLUE River bridge RJ (HAINS) RP	0835 1015 1035 1120 1200 1220 1300	1131 1211 1231 1316 1356 1416 1456	***	*** PST 116 min
6	***	DISCOM COL Norling, Comdr	***	***	BHAD area	WURST area	BLUE	***	SP RJ592 RJ (CHANCE) RJ (VEGAS) BLUE River bridge RP	0944 1002 1044 1214 1254 1334	1200 1218 1300 1430 1510 1550	***	*** PST 136 min

Figure A-6. Sample road movement table appendix to road movement annex, division

WWW.SURVIVALEBOOKS.COM

STANDING OPERATING PROCEDURES

_____
(command)

1. PURPOSE. *Outline of purpose.*

2. SCOPE. *Application and coverage.*

3. UNIT PROCEDURES. *Action required by subordinate units in preparing unit SOP. A definite statement that SOP of subordinate units will be based on and conform to SOP of the issuing command.*

4. RESCISIONS. *Any publications superseded or rescinded by the SOP, including fragmentary SOPs, orders, memorandums, bulletins, and other directives.*

5. REFERENCES. *Publications to be used with the SOP.*

6. DEFINITIONS. *Terms defined, if required to understand and interpret the SOP.*

7. TRANSPORTATION ORGANIZATION. *Missions, organizations, and functions (unless published elsewhere) of:*
   a. Office of the Transportation Officer.
      (1) Transportation officer.
      (2) Deputy transportation officer or executive officer.
      (3) Staff sections.
      (4) Liaison officers.
   b. Field Installations.
      (1) Water terminals.
      (2) Transportation supply depots.
      (3) Transfer points and other special transportation activities.
      (4) Transportation movements branch and other transportation organizations.

8. ADMINISTRATION.
   a. General. *Command policies and directives.*
   b. Correspondence.
      (1) Types. *Instructions for preparing, forwarding, and handling; paper economy measures.*
      (2) Classified documents. *Types of classification and authority to classify; handling, delivery, and receipting methods and procedures; security measures and responsibilities.*
   c. Personnel.
      (1) General. *Command policies and directives.*
      (2) Local civilian labor. *Command policies and administrative procedures for procurement, use, and pay; Geneva convention provisions.*
      (3) Prisoners of war. *Command policies and administrative procedures for procurement as labor; use, treatment, and security; Geneva convention provisions.*
      (4) Replacements. *Responsibilities and procedures for requisitioning transportation replacements, command policies and directives.*
   d. Reports. *Types of administrative reports required; method and frequency of submission (samples to be appended); control procedures.*

9. INTELLIGENCE
   a. General. *Transportation intelligence purpose, mission, types; command directives.*

Figure A-7. Transportation SOP format for major commands

WWW.SURVIVALEBOOKS.COM

b. Information Collection. *Collection agencies, essential elements of information, sources, coordination, collection plan, methods, reporting and disposition of captured enemy material.*

c. Information Processing. *Responsibilities and procedures for recording, evaluating, and interpreting information.*

d. Dissemination. *Policies, methods, criteria, security classifications, transmissions, time considerations.*

e. Use. *General application of intelligence to transportation operations and planning; precautions against enemy counterintelligence.*

f. Counterintelligence. *Objectives, responsibilities, and application to the transportation service.*

g. Reconnaissance. *Purpose and responsibilities.*

10. PLANS

a. Transportation Requirements. *Responsibilities for maintaining current lists of transportation requirements for movement of the unit or its elements by rail, truck, inland waterway, and air.*

b. Transport Availability. *Responsibilities for maintaining current lists of available transportation—organic, assigned, or attached to the unit, including local civilian transportation.*

c. Load Plans. *Responsibilities of subordinate units for maintaining current load plans; designation of vehicles to transport personnel, supplies, and organizational equipment.*

d. Traffic Circulation Plans. *A statement that traffic circulation plans will be coordinated with traffic circulation plan of this headquarters.*

e. Special Operations. *A statement that transportation aspects of subordinate troop plans for special operations (for example, river crossing, pursuit, retrograde movement) will be coordinated with this headquarters.*

f. Plans by Units in Reserve. *Statements that plans by these units for forward or lateral movement will be coordinated with this headquarters.*

g. Organizational Transportation Pool. *Procedures, including availability reports, unit responsibilities for furnishing personnel, maintenance of equipment, and administrative support.*

h. Civil Aid. *A statement that services and subordinate units will submit plans in advance for movement of civilians and civil aid supplies and that plans will not be carried out without prior approval.*

i. Main Supply Routes and Supply and Service Installations.

11. TRAINING

a. Responsibilities and procedures for preparing and supervising training programs of transportation units.

b. Responsibilities and procedures for exercising technical supervision over transportation training throughout the command.

12. REAR BATTLE OPERATIONS. *Command policies and directives; responsibilities of units for BASE defense; defense against airborne operations, NBC attack, sabotage, infiltration, and guerrilla warfare; procedures for reporting enemy activity.*

13. AMPHIBIOUS OPERATIONS

a. General. *A statement that this SOP standardizes normal procedures for preparation and execution of amphibious operations and will apply unless otherwise prescribed.*

(1) Subordinate units will issue SOPs which conform to this SOP.

(2) References.

b. Planning.

(1) Requirements of the tactical plan and the scheme of maneuver.

Figure A-7. Transportation SOP format for major commands (cont)

WWW.SURVIVALEBOOKS.COM

(2) Availability of landing craft and ships by type, size, cargo, and personnel capacity.
(3) Establishment of close liaison with the Navy and Air Force and with task force commanders.
(4) Landing force embarkation and tonnage; equipment and supplies breakdown from tables submitted by task force commanders.
(5) Unit loading and embarkation training arrangements and coordination.
(6) Movement of the embarkation areas and delivery of equipment and supplies, including waterproofing, marking, and palletizing.
(7) Supervision within the embarkation area.
(8) Buildup period for supplies and ship turnaround time.
(9) Alternate logistical procedures or an entire alternate plan to support alternate tactical plans being considered.

c. Movement to Staging Area.
(1) Warning orders.
(2) Movement method—rail, highway, air, water.
(3) Movement control.

d. Staging Area.
(1) Reception.
(2) Spot delivery of equipment.
(3) Control points which control flow of equipment and personnel to embarkation points or assembly areas.
(4) Assembly areas for temporary storage of equipment and supplies to be loaded on transports.
(5) Transportation for supplies and equipment from assembly areas to ships.
(6) Areas for final waterproofing.
(7) Facilities to prepare cargo not already processed for loading.

e. Embarkation of Troops.
(1) Movement to embarkation point or assembly areas.
(2) Control of movement to vessels.

f. Movement to Objective Area. In accordance with naval directives.

g. Ship-to-Shore Movement.
(1) Debarkation of equipment, supplies, and service troops at the proper time to support tactical operation.
(2) Control and landing of emergency supplies.
(3) Evacuation of casualties by water.

h. Beach Organization.
(1) Transportation unit reconnaissance party.
(2) Consolidation of supplies and transportation for subsequent logistical support of the landing force.
(3) Control.
(a) Vehicular traffic.
(b) Transfer operations (buildup area).
(4) Communication between beach organization and control vessel and ships.

14. INSPECTIONS

a. Reference. *Higher headquarters SOP on inspections.*

b. Purpose.

c. Policy.

d. Types. *Vehicle use, transportation training, maintenance and maintenance support quality, operations efficiency, records system.*

e. Frequency.

Figure A-7. Transportation SOP format for major commands (cont)

WWW.SURVIVALEBOOKS.COM

f. Before-Inspection Procedures.
g. After-Inspection Procedures.
h. Reports. *A sample format, number of copies required, and distribution.*

15. AIRBORNE OPERATIONS. *Command policies and directives; responsibilities and procedures for transportation units participating in airborne operations.*

16. COMMUNICATIONS
a. Communications for coordinating transportation.
b. Air-ground communications for coordinating airdrops and land transportation.
c. Reference to communications diagram.

/s/ _____
Commander (name and rank)

Authentication:
Annexes:
Distribution:

Figure A-7. Transportation SOP format for major commands (cont)

STANDING OPERATING PROCEDURES

_____
Unit

Section I. GENERAL

1. APPLICATION. *Operations which SOP covers.*
2. PURPOSE.
3. REFERENCES. *FMs, TMs, SOPs of higher headquarters, other.*
4. RESPONSIBILITY FOR PREPARATION, CHANGES, REVISIONS.
5. EFFECTIVE DATE.

Section II. COMMAND, STAFF, LIAISON

6. ORGANIZATION.
7. COMMAND POSTS.
a. Normal location in relation to next higher headquarters.
b. Change of location—reporting; coordinates and time.

Figure A-8. Transportation SOP format for units

WWW.SURVIVALEBOOKS.COM

c. Forward command posts.
(1) Requirement.
(2) Organization.
(3) Personnel and equipment.

8. STAFF DUTIES
a. Staff officers.
b. Special staff officers.

9. LIAISON
a. Duties of liaison officers.
b. Unit's responsibilities for liaison—higher, lower, and adjacent units.

10. PLANNING. *Responsibilities.*

Section III. ADMINISTRATION

11. CHAIN OF COMMAND.

12. REPORTS.
a. Routine.
b. Special.
c. Submission.
(1) Title and reports-control symbol.
(2) Format.
(3) Date due.
(4) Number of copies.
(5) Negative report, if required.

13. PROMOTION POLICIES.
a. Officer.
b. Enlisted.
c. Battlefield.

14. COURTS-MARTIAL.
a. Location of jurisdiction.
b. Procedure for submitting cases.

15. MAIL.
a. Handling official mail.
b. Handling personal mail.

16. LEAVES AND PASSES.
a. Command policy. *Conduct, VD control.*
b. Authority.

17. JOURNALS AND HISTORY.
a. Unit journal and history.
b. Staff section journals.

18. MILITARY PUBLICATIONS. *Distribution.*

19. PRISONERS OF WAR
a. Reference.
b. Special instructions for capturing unit.

Figure A-8. Transportation SOP format for units (cont)

WWW.SURVIVALEBOOKS.COM

20. AWARDS AND DECORATIONS
    a. Channels.
    b. Form.
    c. Presentation.

21. ORDERS

22. BILLETS AND BIVOUACS
    a. Policies. *Occupation and clearance.*
    b. Billeting party.

Section IV. MOVEMENT

23. HIGHER HEADQUARTERS SOP. *Reference.*

24. MOTOR MOVEMENT
    a. Vehicles. *Preparation for movement.*
    b. Motor marches.
        (1) Strip maps.
        (2) Route reconnaissance.
        (3) Messing and refueling.
        (4) Night marches.
        (5) Makeup of march units and serials.
        (6) Vehicle gap.
        (7) Speed and rate of march.
            (a) Column rate of march.
            (b) Lead vehicle speed.
            (c) Permissible catch-up speed.
            (d) March unit or serial time length.
        (8) Posting traffic guards during halt.
    c. Infiltration.
    d. Personnel. *Conduct during movement.*
        (1) Passengers.
        (2) Drivers.

25. VEHICLE AND EQUIPMENT OPERATIONS
    a. Motor pool.
        (1) Dispatch.
        (2) Service.
        (3) Maintenance.
    b. Administrative vehicles. *Regulations.*

26. RAIL MOVEMENTS
    a. S1 Action. *Movement policy.*
    b. S2 Action.
        (1) Reconnaissance report.
        (2) Security.
    c. S3 Action.
        (1) Troop list.
        (2) Loading plan.
        (3) Transportation movement teams.

Figure A-8. Transportation SOP format for units (cont)

WWW.SURVIVALEBOOKS.COM

d. S4 Action.
(1) Transportation request.
(2) Troop and guard mess.
(3) Blocking and dunnage.
(4) Shipping documents.
(5) Rolling stock.
(6) Loading schedules and area.

27. AIR MOVEMENT
a. S1 Action.
b. S2 Action.
c. S3 Action.
(1) Aircraft required.
(2) Loading plan.
(3) Loading schedule and areas.
(4) Air-transportability technique.
d. S4 Action.
(1) Transportation request.
(2) Availability of tie-down devices or material.
(3) Weight-of-equipment data for loading computation.
(4) Shipping documents.
(5) Vehicles required to load and unload aircraft.

28. WATER MOVEMENT
a. S2 Action. *Movement policy.*
b. S2 Action.
(1) Reconnaissance report.
(2) Security.
c. S3 Action.
(1) Troop list.
(2) Loading plan.
(3) Transportation movement teams.
d. S4 Action.
(1) Transportation request.
(2) Troop mess.
(3) Shipping documents.
(4) Vessels required.
(5) Loading schedule and area.

Section V. SECURITY

29. POLICIES AND RESPONSIBILITIES

30. MOVEMENT SECURITY
a. Air guards.
b. Manning of vehicular weapons.
c. Camouflage during halts.
d. Advance, flank, and rear guards.
e. Action to be taken in attack.

31. BIVOUAC SECURITY
a. Camouflage.
b. Mines and booby traps.

Figure A-8. Transportation SOP format for units (cont)

WWW.SURVIVALEBOOKS.COM

c. Defensive positions.
d. Joint security.
e. Security plans.
f. Sentry posts and outposts.

32. ATTACK WARNING SIGNALS
a. Air.
b. Airborne.
c. Mechanized.
d. Troops.
e. Nuclear, biological, chemical.

33. FIRE SAFETY AND FIRE FIGHTING
a. Plans.
b. Fire personnel and duties.
c. Safety rules *(motor pool, kitchen, other).*

34. ALERT PLANS
a. Unit plan.
b. Alert roster.
c. Armament and equipment.
d. Alert warning phase system.

35. EQUIPMENT DESTRUCTION

Section VI. COMMUNICATIONS

36. AVAILABLE COMMUNICATIONS MEANS

37. ESTABLISHMENT OF COMMUNICATIONS
a. Organic communications.
b. Area communications support.
c. Responsibilities.

38. COMMUNICATIONS PROCEDURES
a. Voice radio.
b. Radio and wire integration (RWI).
c. Message.
d. Visual and sonic.
e. Reference to higher headquarters CEOI.

39. SIGNAL MAINTENANCE RESPONSIBILITIES
a. Commander.
b. Signal/communications officer.
c. Operators.
d. Users.

Section VII. RECONNAISSANCE, INTELLIGENCE, AND COUNTERINTELLIGENCE

40. RECONNAISSANCE. *Essential elements of information.*

41. COMBAT INTELLIGENCE
a. Definition of "spot reports."
b. Requirement for spot reports.

Figure A-8. Transportation SOP format for units (cont)

WWW.SURVIVALEBOOKS.COM

(1) Initial contact with enemy.
(2) Marked change in enemy disposition or situation.
(3) Armored, air, or airborne attack.
(4) New units identified.
(5) Enemy strength, composition, and movement.
(6) Location of enemy installations.
(7) Use of chemicals or new weapons.
(8) New materials or equipment.

42. COUNTERINTELLIGENCE
a. Mail censorship.
b. Blackout discipline.
c. Information.
(1) To enemy captors.
(2) To press representatives.
d. Signs and countersigns.
e. Classified documents destruction.
f. Civilian control.
g. Secrecy discipline.

Section VIII. SUPPLY AND MAINTENANCE

43. CLASS I SUPPLY
a. Ration pickup.
b. Daily ration return and cycle.
c. Reserve rations.
(1) Unit.
(2) Individual.

44. WATER
a. Authorized source.
b. Expedient purification methods.
c. Water economy.

45. CLASS II AND IV SUPPLY
a. Requisition days for various services.
b. Pickup procedure.
c. Salvage turn-in procedures.
d. Droppage by battle-loss certificate.

46. CLASS III SUPPLY
a. Resupply.
b. Fuel reserve.

47. CLASS IIIA SUPPLY
a. Resupply.
b. Fuel reserve.

48. CLASS V SUPPLY
a. Requisition method.
b. Required forms and certificates.
c. Basic load.
d. Salvage.

Figure A-8. Transportation SOP format for units (cont)

WWW.SURVIVALEBOOKS.COM

49. VEHICLE AND EQUIPMENT MAINTENANCE
   a. Maintenance category.
   b. Maintenance officer's responsibility.
   c. Required forms.
   d. Priorities.

50. REPAIR PARTS
   a. Requisition method.
   b. Stock level maintenance.
   c. Maintenance inspections.
   d. Parts and equipment record.

51. VEHICLE AND EQUIPMENT EVACUATION CHANNELS

/s/ _____
Commander (name and rank)

Authentication:
Annexes *(May include Wearing of the Uniform, Reports Formats, Destruction of Classified Documents, Duties of Staff Officers, Staff Section SOPs, Loading Plans, Alert Plan).*
Distribution:

Figure A-8. Transportation SOP format for units (cont)

_____
(Classification)

Issuing unit
Place of issue *(may be in code)*
Date-time group of signature

File No _____
Embarkation Plan No _____
Maps: *Those needed for understanding the plan.*
References: *SOPs, operation order, administrative order, and other relevant material.*

1. ORGANIZATION FOR EMBARKATION
   a. Troop list for each embarkation group. *May be issued as an annex.*
   b. Embarkation schedule. *Assignment of each embarkation group to shipping. Schedule shows berthing of ships and date and hour loading will begin. It also includes date and hour embarkation will be completed by each embarkation group. Other information pertinent to the embarkation schedule may be included. May be issued as an annex.*
   c. Advance parties.
      (1) Composition.
      (2) Functions.
      (3) Movement to embarkation point. *References to SOP if applicable.*

Figure A-9. Division embarkation order format

WWW.SURVIVALEBOOKS.COM

2. SUPPLIES AND EQUIPMENT

a. Amounts and types of supplies and equipment to be embarked.

b. Preparation of supplies and equipment for embarkation. *Reference may be made to appropriate SOP.*

c. Allocation of division supplies and equipment to cargo assembly areas. *May be issued as an annex with appendixes.*

3. EMBARKATION POINTS AND CARGO ASSEMBLY AREAS

a. Assignment of embarkation points and cargo assembly areas for loading. *(May be a map, sketch, or overlay issued as an annex.)*

b. Preparation of embarkation points and cargo assembly areas for loading; construction to improve embarkation exits and facilities.

c. Assignment of mechanical loading devices, such as forklift trucks, cranes, roller conveyors, warehouse pallets.

4. CONTROL

a. Establishment and functions of embarkation control officer. *Functions may be covered in SOP.*

b. Traffic circulation and control system in embarkation area and between embarkation area and base camp.

c. Establishment of security posts for prevention of fire, sabotage, aned pilferage in cargo assembly and deck areas.

d. Communications for embarkation. *References may be made to CEOI.*

5. PERSONNEL

a. Schedule and method of movement from base camp.

b. Schedule and instruction for embarkation.

6. MISCELLANEOUS

a. Embarkation responsibilities and tasks. *Responsibility of embarkation group commanders and tasks of officers. Supply officer, motor transport officer, unit loading officer, other.*

b. Special loading instructions. *Stowage of certain types of cargo, handling of fragile or dangerous items, other.*

c. Miscellaneous instructions not covered elsewhere.

Acknowledgment instructions.

By Command of

/s/ _____
Chief of Staff

Authentication:
Annexes:
—Organization of Embarkation Groups—Assignments of Shipping.
—Supplies and Equipment to be Embarked.
—Embarkation Points and Cargo Assembly Areas.
—Others as necessary.
Distribution:

OFFICIAL _____
G3

Figure A-9. Division embarkation order format (cont)

WWW.SURVIVALEBOOKS.COM

TRANSPORTATION ESTIMATE

Transportation section (unit)

Location

Date-time group

References: *Maps, charts, and other relevant documents.*

1. MISSION. Mission of the command; mission of transportation units in support of the command's tactical and logistical mission. *May be obtained from higher headquarters orders or deduced from instructions or knowledge of the situation; may be expressed in terms of personnel or tons of cargo to be transported, discharged, or outloaded.*

2. SITUATION AND CONSIDERATIONS

a. Intelligence. *Reference to pertinent intelligence estimate.*

b. Tactical situation.

(1) Reference to current operation order.

(2) Present and planned disposition of major friendly tactical elements, with emphasis on those units defending lines of communication or transportation units and operations; effect of planned troop moves on transportation operations.

(3) All possible courses of action open to the command to accomplish the mission.

(4) Concept of projecting operations once the immediate mission is accomplished.

c. Logistics.

(1) Reference to current ADMIN/LOG order or overlay.

(2) Status of supplies and equipment in all transportation organizations of the command with any inadequacies highlighted.

(3) Any projected developments likely to affect the ability of transportation units to perform their mission from the logistical standpoint.

(4) Status of supplies and equipment in other logistical support units which might adversely affect accomplishment of the mission.

(5) All possible logistical courses of action and the effects of each on possible friendly tactical courses of action.

d. Personnel.

(1) Reference to current ADMIN/LOG order or overlay.

(2) Status of personnel in all transportation units, including morale and any other considerations likely to affect their performance.

(3) Status of personnel in other support units to be employed in logistical support of transportation operations which might adversely affect accomplishment of mission.

e. Assumptions. *Logical assumptions may be made when there are not enough facts available to prepare the estimate.*

f. Transportation. *All known information, as detailed as possible, on each mode of transportation activity.*

(1) Transportation activities. *The format shown in (a) below should be modified as required for (b) through (j).*

Figure A-10. Transportation estimate format

WWW.SURVIVALEBOOKS.COM

(a) Rail.

Unit	Location	Strength Actual & Auth	Facilities Actual & Required	Equipment Lacking	Capability Actual & Potential

(b) Motor.
(c) Inland waterway.
(d) Air.
(e) Water.
(f) Transportation movements.
(g) Staging areas.
(h) Transportation depots.
(i) Pipelines *(even though not operated by transportation units.)*
(j) Troop carrier space.

(2) Transportation units courses of action. *All courses of action open to transportation units for each possible logistical course of action set forth in paragraph c(5) above.*

g. Special Factors. *Any other factors which might influence the choice of a course of action or the ability to perform the mission, from both the transportation and overall mission standpoints.*

3. ANALYSIS. *A statement and analysis of the effects of each logistical course of action on each transportation activity.*

a. Course of Action. *Use the following format for each course of action mentioned in paragraph 2c(5).*

Activity*	Effect on personnel	Effect on equipment	Effect on facilities	Effect on capabilities

b. Alternate Course of Action. *Outline of alternate courses of action, if possible. Use same format as paragraph 3a.*

4. COMPARISON

a. Dominant transportation factors and modes most likely to be used.

b. A comparison, based on the information in paragraph 3, of the various logistical courses of action, including their effects on each mode and its capabilities. The comparison will determine the most favorable course of action from a transportation standpoint.

c. Feasibility of the various lines of communications, ports, and beaches as affected by enemy capabilities, weather, terrain, et cetera.

5. CONCLUSIONS

a. Statement indicating whether the mission can be accomplished from the standpoint of transportation support.

b. Statement indicating which of the possible logistical courses of action can best be supported from the transportation standpoint.

c. Statement calling attention to any considerations required should alternate courses of action be chosen.

(1) Number and type of transportation units required over and above those available for each course of action if mission cannot be supported.

(2) Personnel and/or equipment shortages in existing units which would prevent mission accomplishment.

**Same as in paragraph 2f(1).*

Figure A-10. Transportation estimate format (cont)

WWW.SURVIVALEBOOKS.COM

(3) Any repairs or construction work essential to successful mission accomplishment from the transportation standpoint.

(4) Any other transportation considerations which should be brought to the attention of the commander.

/s/ _____
Transportation officer
(name and rank)

Authentication:
Annexes:
Distribution:

Figure A-10. Transportation estimate format (cont)

TRANSPORTATION PLAN NO[1]_____

Transportation section (unit)

Location

Date-time group of signature

Maps and references: *Sheet name, number, scale, unit of measure, and series for each map. Other references include city plans, navigation charts, and other plans bearing on the transportation plan.*

Task organization: Annex A, Task Organization.

1. SITUATION

a. Enemy Forces. *All capabilities of the enemy to hinder, disrupt, or otherwise affect operations of transportation units and other elements of the command, including damage to lines of communications, and use of mass-destruction weapons (Annex B, Intelligence).*

b. Friendly Forces. *Units to be supported, their location and strength. Emphasis on units engaged in protection of lines of communication and transportation units or activities, including higher, adjacent, and supporting units of US and allied forces.*

c. Area of Operations.

(1) Weather. *Temperatures, wind conditions, rainfall, tide and river conditions, aeronautical weather information.*

(2) Terrain and hydrography. *Critical terrain features, soil trafficability, beach gradients, and any known obstacles; their possible effects on transportation modes.*

(3) Lines of communication. *All lines of communication and their physical condition.*

d. Attachments and Detachments.

Figure A-11. Transportation plan format

WWW.SURVIVALEBOOKS.COM

e. Assumptions and Policies. *Any pertinent policies and logical assumptions needed to prepare the plan—proposed locations of major unit boundaries, troop strengths supported in different phases of the operation, et cetera.*

2. MISSION. *Mission of transportation units in support of the command.*

3. EXECUTION

a. Concept of Operation. *The transportation officer's overall concept of the operation, including probable increases in supported units and additional territory to be supported. (Annex C, Concept of Operations).*

b. Rail. *Specific tasks assigned to rail units.*[2]

c. Motor.

d. Air.

e. Water.

f. Inland Waterway.

g. Transportation Movements.

h. Staging Areas.

i. Transportation Depots.

j. Pipelines *(even though not operated by transportation units).*

k. Troop Carrier Space. *Proposed use of air capacity allocated to the command.*[2] [3] *(As indicated in b above, similar information for each mode of transportation is best submitted as an annex, the format of which should parallel that of the plan itself as much as practical.)*

l. Coordinating Instructions.

(1) Defense and security. *Reference to appropriate SOP or defense plan.*

(a) Individual.

(b) Facilities.

(c) Lines of communication.

(d) Shipments.

(e) Censorship.

(f) Communications.

(2) Counterintelligence. Annex B, Intelligence.

(3) Technical intelligence. Annex B, Intelligence.

(4) Effective time and date.

4. ADMINISTRATION AND LOGISTICS

a. Administration.

(1) Policies.

(2) Procedures. *SOPs and related guides of higher headquarters not covered elsewhere in the plan.*

(3) Required reports.

b. Logistics.

(1) Transportation supply. *The following items are covered by reference to current SOPs when applicable.*

(a) Levels of supply.

(b) Replacement factors and consumption rates.

(c) Requisition procedures and cycles.

(d) Emergency requisition procedures.

(e) Local procurement.

(f) Controlled items.

(g) Surplus material.

(h) Captured material.

(i) Salvage and scrap.

Figure A-11. Transportation plan format (cont)

WWW.SURVIVALEBOOKS.COM

(j) Interservice supply.
(k) Class IV equipment.
(2) Equipment out of commission for parts procedures.
(3) Supply support of transportation mission by other services.
(4) Transportation maintenance. *Maintenance facilities by mode, shop locations, and responsibilities of each maintenance unit.*

c. Personnel.
(1) Policies.
(a) Local civilian personnel.
(b) Prisoners of war.
(c) US civilian personnel.
(2) Strengths.
(3) Replacements.
(4) Procedures.

5. COMMAND AND SIGNAL
a. Command.
(1) Location of major command CPs.
(2) Location of transportation movements branches.
b. Annex D, Signal.

Acknowledgment instructions.

/s/ _____
Commander (name and rank)

Authentication:
Annexes:
Distribution:

---

[1] *Any paragraph or subparagraph in the plan may consist wholly or in part of references to appropriate annexes. Annexes in turn may be simplified by referring to appendixes. Each transportation mode should have a separate annex.*
[2] *Projected loads, schedules, facilities, lines of communication, and similar information are best submitted as annexes to the plan.*
[3] *Transportation organizations do not assign tasks.*

Figure A-11. Transportation plan format (cont)

Feasibility Test for Transportation Plan

1. GENERAL
a. This test is prepared to enable transportation staff planners to check the feasibility of a transportation plan (annex to administrative orders, letter of instructions, other) after the plan has been prepared.

Figure A-12. Transportation plan feasibility test format

WWW.SURVIVALEBOOKS.COM

b. The test has been prepared in checklist form. Paragraph 2 lists general considerations which apply to all modes of transportation; the remaining paragraphs list items which apply to a specific mode.

c. When using the checklist, consider the items listed in paragraph 2 in addition to the paragraph that applies to the particular mode.

2. GENERAL CHECKLIST ITEMS

a. Calculated risks. *Calculated risks involved. Effect on the mission. Governing factors.*

b. Weather and terrain. *General considerations. Favorable or adverse effect on the mission.*

c. Enemy action. *Enemy guerrilla action, clandestine action, other.*

d. Political and economic situation. *Interference with local economy. Friendly or unfriendly attitude of the civilian population.*

e. Transportation net. *Integration of transportation net elements. Portions of the net reserved for civilian use. Emergency procedures for joint civil-military use. Engineer construction support of the present net and future operations.*

f. Allocation and use of modes. *Optimum use of transport capacity. Use of supporting services's capacities. Allocation to modes of tasks corresponding to their capabilities and equipment. Adequate provisions for retrograde cargo.*

g. Logistical support. *Support of modes in quantity and time to accomplish the mission (POL products, repair parts, and so forth).*

h. Task organization.

(1) Clear definition of command relationships, missions, and functions.

(2) Troop list assignments.

(a) Strength.

(b) Training.

(c) Morale.

(d) Available transport equipment.

i. Local civilian and EPW labor. *Availability in the skills required. Requirement for mobile civilian labor units for phase II and phase III operations. Adequate administrative and logistical support.*

3. MOTOR TRANSPORT CHECKLIST

a. Requirements versus capabilities.

b. Traffic circulation plan.

(1) Road net support of planned traffic.

(2) Requirement for additional highway regulation personnel.

(3) Adequate road repair and road maintenance support.

(4) Designation of routes (restricted, dispatch, other).

(5) Possible joint use of road net. *Can both combat forces (US and allied forces) and civilian traffic use it simultaneously?*

(6) Availability of hardstand, maintenance areas, truck parks, relay stations, transfer points.

(7) Marked routes; availability of marking signs.

4. RAIL

a. Requirements versus capabilities.

b. Unusual weather or terrain factors.

(1) Are heavy rains due that may cause washouts, floods, or landslides?

(2) Is extreme subfreezing weather due?

c. Engineer maintenance and construction support for rehabilitation or for major repair of rail line.

d. Yards, roundhouse, repair shops.

Figure A-12. Transportation plan feasibility test format (cont)

WWW.SURVIVALEBOOKS.COM

e. Suitable water and fuel supplies *(if steam locomotives are used).*
f. Limiting factors.
(1) Bridge weight and clearance.
(2) Tunnel clearance.
(3) Roadbed and trackage.
(4) Rolling stock—condition, power, gage.
(5) Locomotives—condition, power, gage.
(6) Train operations communications.

5. INLAND WATERWAY
a. Requirements versus capabilities.
b. Weather and terrain. *Freeze-up or flood period, tidal ranges, currents, fogs.*
c. Obstructions. *Low bridges, types of drawbridges. Natural obstructions, such as heavy weeds, that might foul propellers.*
d. Locks. *Locks controlled by assigned permanent personnel or the individual inland waterway craft. Size of locks; amount of time required to pass through.*
e. Channels. *Required maintenance. Size, depth, and width.*
f. Navigational aids. *Enough fixed or mobile navigational aids for full use, day and night.*
g. Requirement for intermediate transfers.
h. Condition of available watercraft.
i. Marine repair and maintenance support.
j. Inland waterway facilities, docks, cranes.

6. PORTS AND BEACHES
a. Requirements versus capabilities.
b. Port facilities.
(1) Floating cranes for heavy lifts.
(2) Piers, docks, warehouses, open ground areas.
(3) Road and rail nets.
(4) Navigational aids.
(5) Protected anchorage areas.
(6) Utilities (electricity, other).
(7) Harbor craft.
(8) Berth space, lengths, and depths.
c. Beach facilities.
(1) Anchorage areas.
(2) Ingress and egress routes.
(3) Road and rail nets.
(4) Hardstand and open ground areas.
(5) Equipment *(forklifts, cranes, other).*
d. Weather and terrain.
(1) Ports.
(a) Tides and currents.
(b) Underwater obstructions.
(2) Beaches.
(a) Tides, currents, surf, gradient, tidal range.
(b) Underwater obstructions.

7. TRANSPORTATION MOVEMENTS
a. Sufficient teams to accomplish mission.
b. Adequacy (flexibility or rigidity) of transportation movements plan.
c. Location of teams for maximum use.
d. Documentation procedures.

Figure A-12. Transportation plan feasibility test format (cont)

WWW.SURVIVALEBOOKS.COM

8. STAGING AREAS
   a. Capability of processing planned work loads.
   b. Adequate facilities.

9. TRANSPORTATION DEPOTS
   a. Ability to support the mission.
   b. Adequate facilities.

10. AIR
   a. Requirements versus capabilities.
   b. Marginal weather.
      (1) Low ceilings.
      (2) Low visibility.
      (3) Snow and ice.
      (4) Temperatures.
   c. Terrain. *Altitudes (temperature and altitude affect lift capabilities).*
   d. Navigational aids.
      (1) Possibility of day and night operations.
      (2) Ground stations.
         (a) Ground-controlled approach (GCA).
         (b) Radio range.
         (c) Instrument-landing systems.
         (d) Omnidirectional range (omni range).
         (e) Radar-plotting station.
      (3) Airborne navigational equipment.
   e. Communications. *Adequacy of unit communications; augmentation required.*
   f. Flight restrictions.
      (1) Maintenance of established air routes, including fire lanes.
      (2) Degree of air superiority.
      (3) Arrangements for weather reports from Air Force.
   g. Adequacy and location of landing sites or airfields; facilities at these locations.
   h. Maintenance.
      (1) Condition of aircraft (hours of previous operation).
      (2) Maintenance units available.
      (3) Repair parts available.
      (4) Location and stock of depot support.
   i. Degree of training of supported units in use of logistical air support.

11. FLEXIBILITY
   a. Provision for rerouting or diversion.
   b. Interchange points.
   c. Transfer points.
   d. Substitution of one mode for another.
   e. Capability of handling emergency transportation tasks.

Figure A-12. Transportation plan feasibility test format (cont)

WWW.SURVIVALEBOOKS.COM

APPENDIX B

TRANSPORTATION-RELATED DATA

This appendix contains miscellaneous data that may be useful in the computations or decision-making processes of daily or long-range planning. It includes those odd pieces of information that are difficult to find or categorize.

WEIGHT REQUIREMENTS

For methods used to determine weight requirements, see FM 101-10-1. The figures shown in Table B-1 are approximate and are to be used as guides only.

Table B-1. Capabilities of transportation mediums

Medium	Tons per day STONs	Tons per day LTONs	Adequate to Maintain
Highway[1]			
Gravel	3,400		2 divisions
Medium condition	5,800		4 divisions
First-class	8,400		7 divisions
Railway, each way			
Single track	4,000	3,570	3 divisions
Double track	12,000	10,700	9 divisions
Gasoline pipeline[2]			
6-inch	2,000	1,790	5 to 8 divisions
4-inch	930	830	3 divisions
Water terminal discharge rate[3]			
Average cargo ship	720	643	1/2 division
Across beach			
Per 1,000 yards of beach	1,680	1,500	1 division plus

[1]Daily forward tonnage, assuming sustained operations, adequate road maintenance, and two-way traffic.

[2]The capacities of pipeline systems vary, depending on the size of pipe, gradient, location, size of pumps, and type of construction. Welded commercial pipelines can be operated at much greater pressures than standard military lines which have flexible couplings.

[3]Water terminal discharge rate of 1,440 STONs per day required to adequately maintain 1 division slice.

WWW.SURVIVALEBOOKS.COM

Dogs

Trained dogs may be used individually or in teams to transport cargo in arctic and subarctic areas. They also have limited use in temperate zones to carry messages and small packages of mail, usually in regions inaccessible to other means of transport. Dogs should be permitted to rest 10 minutes in each hour and should not be worked continuously for more than 16 hours per day. For planning purposes, towed loads should not exceed 100 pounds per dog, although the heavier breeds are capable of loads of 200 pounds per dog on a flat surface with good traction.

The Eskimo dog, or husky, is most commonly used in arctic and subarctic regions—the German shepherd in temperate zones. On packed snow with good traction, an individual dog in a sled team has the cargo-carrying capabilities shown in Table B-2 for carrying cargo packs, messages, and mail. These figures are for normal operating conditions and vary widely under extremes of weather and terrain.

Table B-2. Cargo-carrying capabilities of sled dogs

Terrain	Load per Dog[1] or (lb)	Distance per Hour[2] (km)	(mi)
Flat	50	9.6	6
Hilly	50	4.8	3
Mountainous	50	1.6	1

[1]Includes weight of sled
[2]Reduce 50 percent when load is doubled.

On hard surfaces with good traction, an individual dog has the capabilities shown in Table B-3 for carrying cargo packs, messages, and mail.

Table B-3. Carrying capacities of pack dogs

	Load per Dog		Distance per Hour			
	Cargo Pack	Messages or Mail	Cargo Pack		Messages or Mail	
Terrain	(lb)		(km)	(mi)	(km)	(mi)
Flat	35	5 percent	3.2	2	24	15
Hilly	30	of dog's	3.2	2	16	10
Mountainous	25	weight	1.6	1	8	5

Pack Mules

Pack mules are generally 59 to 62 inches tall and weigh 1,000 to 1,200 pounds. They can be used to transport one litter or two sitting casualties. They travel at a rate of 3.5 to 4 miles (5.6 to 6.4 kilometers) per hour and can carry from 200 to 250 pounds.

Pack mules require 10 pounds of oats and 14 pounds of hay per day. These amounts may be reduced for short periods up to 10 days without impairing capacity. Pack mules also require at least 10 gallons of water per day and can travel an average daily distance of 12 miles (19 kilometers) in mountainous terrain and 24 miles (39 kilometers) in rolling or flat terrain.

Pack mules can ascend at the rate of 1,650 vertical feet (503 meters) per hour. They are noneffective approximately 3.2 percent of the time. Carts pulled by horses or mules are capable of traveling 20 miles (32 kilometers) per day drawing a payload of 1,000 pounds.

Table B-4. Transportability criteria for transporting pack mules

Vehicle	Capacity (Horses or Mules)
Trailer, 2-horse van	2
Truck, 1 1/2-ton, cargo	2
Truck, 2 1/2-ton, cargo	4
Semitrailer, 6-ton, combination animal and cargo	8
Railroad stock car, 40-foot	Approx 25
Railroad stock car, 36-foot	Approx 20 to 25
Airplane, cargo transport	4 to 6[1]

[1]May be transported at altitudes up to 18,000 feet with no ill effects.

Human Bearers

Males can carry an average cargo load of 80 pounds. Females can carry an average cargo load of 30 to 35 pounds. Each litter team consists of 8 to 12 humans.

For average conditions on level terrain, teams can march an average of 12 miles per day. To estimate the time needed to cover a given distance in hilly or mountainous areas, use the following equation. For these conditions, cargo loads given above for males and females should be reduced from 20 to 30 percent, depending upon the steepness of the terrain.

$$T = t + a + d$$

WWW.SURVIVALEBOOKS.COM

where:

T = total time required

t = time required to march a given map distance

$a = \frac{\text{total ascent in feet during march}}{1{,}000}$

$d = \frac{\text{total descent in feet during march}}{1{,}500}$

Overloading and speeding up operations increase the sick rate and cause desertion. Human bearers are noneffective approximately 30 percent of the time and must be closely supervised to prevent pilferage.

STOWAGE FACTORS

Computation

The stowage factor is the number of cubic feet required to store 1 long ton (2,240 lb) of cargo. It may be computed by using the following formula:

$$\text{Stowage factor (cu ft)} = \frac{\text{cube of cargo (cu ft)}}{\text{weight in pounds}} \times 2{,}240$$

Weight-Volume Ratios

Weight-volume ratios are based on average cubage for each item. The measurement tonnage for any time can be found by multiplying its short ton weight by its conversion factor. Weight-volume ratios by classes of supply are shown in Table B-5. Table B-6 shows average stowage factors by service.

Table B-5. Weight-volume ratios by classes of supply

Item[1]	Conversion Factor (STONs to MTONs)	Stowage Factor
Class I:		
Rations	2.1	94
Class II:		
Chemical (incl Class IV)	2.3	103
Engineer	3.3	147
Medical (incl Classes I and IV)	2.5	112
Ordnance	1.8	80
Ordnance vehicle replacement	2.2	99
QM clothing and equipage	2.0	89

Table B-5. Weight-volume ratios by classes of supply (cont)

Item[1]	Conversion Factor (STONs to MTONs)	Stowage Factor
QM general supplies	2.8	125
Signal (incl Class IV)	3.8	170
Class III:		
Aviation fuel and lubricants (Class III A)	1.5	67
Fuel for temperate zone	2.0	89
Gas, oil, grease[2] (less aviation)	1.5	67
Class IV:		
Aviation, supply and replacement	4.0	179
Chemical (incl in Class II)		
Engineer construction material	1.5	67
Medical (incl in Class II)		
Ordnance motor maintenance	1.0	45
QM sales items	1.7	76
Signal (incl in Class II)		
Transportation	2.4	108
Class V:		
Ammunition (less aviation)	.9	40
Aviation ammunition	.9	40
Chemical ammunition	1.2	54

[1] Nongas conditions. Figures are based upon average conditions found in European and Pacific theaters; amounts will vary for polar regions.

[2] Consists of the following: 90 percent gasoline, 4 percent diesel fuel, 3 percent engine oil, 1 percent gear lube, 2 percent greases.

Table B-6. Average of stowage factors by service

Supply Service	Class of Supply	Stowage Factor
Chemical	All supplies less Class V	103
Engineer	All supplies	107
Medical	All supplies	112
Ordnance	All supplies less Class V	75
Quartermaster	All supplies	87
Signal	All supplies	170
Transportation	All supplies	108
Chemical	Class V	54
Ordnance	Class V	40

Average Densities of Common Materials and Specified Supply Items.

Figures shown in Table B-7 aid transportation planners and operators when making loading plans for any mode of transportation. The information given is for specific items. When planning loads for the general classes of supply, refer to Tables B-7, B-8, B-9, and B-10.

WWW.SURVIVALEBOOKS.COM

Table B-7. Average densities of common material

Material	Weight (lb per cu ft)
Acid	
Muriatric, 40%	75
Nitric, 91%	94
Sulphuric, 87%	112
Alcohol, 100%	
Ethyl	49
Methyl	50
Aluminum, cast-hammered	165
Apple timber	44
Asbestos	153
Ashes and cinders	40-45
Asphaltum	81
Ash timber	
Black	34
White	42
Barley	39
Barytes	281
Basalt	184
Bauxite	159
Benzine	50
Birch timber	44
Bluestone	159
Borax	109
Boxwood, dry	60
Brass, cast-rolled	534
Bronze	
Aluminum	481
Phosphor	554
Tin	509
Brick	100
Calcium	98
Cedar timber, white or red	134
Cement	
Mortar	135
Portland, loose, dry	94
Portland, set	183
Chalk	143
Chestnut timber	30
Cherry timber, wild red	27
Chloroform	95
Cinders	
Blast furnace	57
Chemical plant	100
Clay	
Damp, plastic	110
Dry	63
Marl (mineral)	137
Wet	80
With gravel, dry	100
Coal	
Anthracite	97
Bituminous	84
Charcoal, oak	33
Charcoal, pine	23
Coke	75
Lignite	78
Peat, turf, dry	47

Material	Weight (lb per cu ft)
Coal and coke, piled	
Anthracite	47-58
Bituminous or lignite	40-54
Charcoal	10-14
Coke	23-32
Peat, turf	20-26
Cobalt	546
Concrete	
Plain	140-150
Reinforced	150
Copper	
Cast-rolled	556
Ore, pyrites	262
Cork	15
Cotton, compressed	45
Dolomite	181
Earth	
Dry, loose	76
Dry, packed	95
Moist, loose	78
Moist, packed	96
Mud, flowing	108
Mud, packed	115
Ebony timber	78
Elm timber	35
Ether	46
Excelsior, baled	19
Feldspar, orthoclase	162
Fir timber	
Balsam	25
Douglas	32
Flax	26
Flint	162
Garbage	
Green	47
Tankage	27
Glass	
Common	162
Crystal	184
Flint	247
Plate or crown	161
Gneiss	175
Gold	
Cast-hammered	1,205
Coin (US)	1,073
Grain	48
Granite	165
Graphite	135
Gravel	
Damp, loose	87
Dry, compacted	120
Greenstone, trap	187
Gumwood	57
Gypsum, alabaster	159
Hay or straw (bales)	20
Hemlock timber	29

Material	Weight (lb per cu ft)
Hemp	90
Hickory timber	48
Hornblende	187
Ice	57
Indigo	63
Iridium	1,383
Iron	
Cast pig	450
Ferrosilicon	437
Gray cast	442
Ore	
Hematite	325
Hematite in bank	160-180
Hematite loose	130-160
Limonite	237
Magnetite	315
Slag	172
Spiegeleisen	468
Wrought	485
Ivory	114
Jute	30
Kerosene	50
Lead	
Pure	710
Ore, galena	465
Leather	59
Lime, gypsum, loose	53-64
Limestone	
Marble, quartz (solid)	155
Marble, quartz (quarried, pile)	95
Locust timber	45
Logwood, dry (average)	57
Lumber, structural (average)	24
Lye, soda (liquid)	106
Magnesite	187
Magnesium alloys	112
Mahogany timber	44
Manganese	
Pure	475
Ore, pyrolusite	259
Manila	26
Maple timber	
Hard or sugar	43
White	33
Marble	170
Masonry	
Ashlar	
Bluestone	153
Granite, syenite, gneiss	159
Limestone	153
Marble	162
Sandstone	143
Brick	
Hard brick	128
Medium brick	112

WWW.SURVIVALEBOOKS.COM

Table B-7. Average densities of common material (cont)

Material	Weight (lb per cu ft)
Sand-lime brick	112
Soft brick	103
Concrete	
Cement, cinder, etc	100
Cement, slag, etc	130
Cement, stone, sand	144
Dry rubble	
Granite, syenite, gneiss	130
Limestone, marble	125
Sandstone, bluestone	110
Mortar rubble	
Bluestone	147
Granite, syenite, gneiss	153
Limestone	147
Marble	156
Sandstone	137
Mercury	847
Mica	183
Monel metal, rolled	555
Mortar	
Lime, set	103
Portland cement	135
Mud (river mud)	90
Nickel	537
Oak timber	
Chestnut	46
Live	54
Red or black	42
White	48
Oats	26
Oils	
Mineral (lubricants)	57
Vegetable	58
Paper	
Books	58
Manila	37
News	38
Wrapping	10
Writing	64
Paraffin	56
Petroleum, crude (average)	54
Phosphate rock, apatite	200
Phosphoric acid	97
Pine timber	
Norway	34
Oregon	32
Red	30
Southern	40
White	27
Yellow	
Long-leaf	44
Short-leaf	38
Pitch	69
Plaster	53
Plaster of paris	140
Platinum, cast-hammered	1,330
Poplar timber	27
Porphyry (mineral)	172
Potassium	54
Pumice, natural	40
Quartz, flint	165
Rags, baled	
Cotton	18
Linen	23
Woolen	20
Redwood timber (California)	26
Riprap	
Limestone	80-85
Sandstone	90
Shale	105
Rope	42
Rosin	67
Rubber	
Caoutchouc	59
Goods	94
Pure	60
Rye	45
Salt, granulated, piled	48
Saltpeter	132
Sand and gravel	
Dry, loose	90-105
Dry, packed	105-120
Wet	126
Sandstone	143
Sandstone, quarried, piled	82
Sawdust, dry	7
Serpentine (mineral)	171
Shale	
Quarried, piled	92
Slate	172
Silver	
Cast-hammered	656
German	536
Sisal	24
Slags	
Bank	67-72
Bank screenings	98-117
Machine	96
Slag-sand	49-55
Snow	
Compacted	20
Fresh	8
Soapstone, talc	169
Soda ash	62
Soda, bicarbonate	86
Sodium	61
Soil, wet	70
Spruce timber, white or red	28
Starch	96
Steel	
Cold-drawn	489
Machine	487
Tool	481
Stone riprap, wet	65
Straw	
Baled	24
Loose	3
Sulphur	125
Sulphuric acid	115
Sycamore timber	37
Syenite (mineral)	165
Talc	170
Tallow	59
Tar, bituminous	75
Teak timber	
African	62
Indian	48
Terra-Cotta	122
Tin	
Cast-hammered	459
Ore, cassiterite	418
Tobacco	28
Tungsten	1,200
Turpentine	54
Walnut timber	
Black	37
White	26
Water	
Fresh	62
Sea	64
Wax, bees	61
Wheat	48
Willow timber	28
Wood pulp	29
Wool, packed	82
Zinc	
Cast-rolled	440
Ore, blende	253

WWW.SURVIVALEBOOKS.COM

Table B-8. Average densities of subsistence

Material	Weight (lb per cu ft)
Perishables and bulk staples	
Dairy products	
Butter	59.0
Cheese	30.0
Milk	65.0
Eggs	22.6
Fruits, fresh	
Apples	31.3
Apricots	34.8
Bananas	13.2
Blackberries	21.5
Cantaloupe	26.8
Casaba (honeydew melon)	24.0
Cherries	31.2
Cranberries	24.6
Figs	34.8
Grapefruit	31.2
Grapes	28.9
Lemons	33.2
Limes	36.9
Loganberries	21.1
Oranges	34.2
Peaches	23.3
Pears	24.9
Pineapples	22.1
Plums	25.6
Raspberries	22.0
Strawberries	22.0
Tangerines	35.5
Fruits, frozen (average for all)	36.2
Meats	
Beef	
Boneless	36.7
Chuck	35.8
Corned	37.1
Dried, canned	39.8
Forequarter	27.0
Hindquarter	19.1
Liver	45.7
Loin	18.1
Rounds	14.7
Ribs	23.3
Tenderloin	46.6
Lamb and mutton Carcass	9.4
Pork	
Bacon	36.9
Boston butt	40.2
Ham	40.2
Ham, canned	37.4
Loin	37.4
Pork shoulder	30.9
Salt pork	33.5
Spare ribs	30.9
Poultry	
Chicken, dressed	
Fryer	31.5
Hen	40.2
Chicken, cut-up	29.6
Turkey	29.3
Sausage	
Bologna	32.5
Frankfurter	35.2
Liver	36.5
Luncheon meat	37.3
Pork, bulk	46.6
Pork, link	35.2
Salami	34.8
Veal	
Carcass and sides	13.7
Seafood	
Clams	28.2
Crab meat	27.1
Fish	
Drawn	32.8
Fillet	22.1
Smoked	24.6
Smoked fillet	51.6
Oysters	26.5
Shrimp	23.9
Staples	
Bread	18.0
Cereals, bulk	
Barley	39.0
Buckwheat	42.0
Corn, rye	45.0
Oatmeal	38.0
Oats	26.0
Wheat	48.0
Coffee	37.0
Cornmeal	40.0
Fats (average)	58.0
Flour	
Loose	28.0
Packed	47.0
Honey	90.0
Lard	60.0
Molasses	38.0
Rice	50.0
Sugar	
Brown	45.0
White	42.0
Tea	16.0
Vegetables, fresh	
Asparagus	21.0
Beans	
Green or snap	14.7
Lima	18.3
Beets	
Bunched	18.1
Topped	30.9
Broccoli	17.8
Cabbage	24.5
Carrots	
Bunched	18.9
Topped	30.0
Cauliflower	18.9
Celery	23.4
Corn, sweet	16.8
Cucumbers	23.1
Eggplant	16.4
Lettuce	20.5
Onions	
Dry	30.9
Green	16.8
Peas	
Green	14.4
Shelled	26.0
Peppers, sweet, green	17.6
Potatoes	
Irish	35.7
Sweet	31.3
Radishes	21.6
Spinach	14.8
Tomatoes	33.3
Turnips	30.9
Vegetables, frozen (average for all)	27.0
Nonperishables in containers	
(No. 10 can)	40.0
(No. 2½ can)	37.9
(No. 2 can)	38.0
Apple butter	
(No. 10 can)	47.5
(No. 2½ can)	45.0
(No. 2 can)	44.5
Apples, dry (50-lb bag)	33.3
Apricots	
(No. 10 can)	43.8
(No. 2½ can)	42.1
(No. 2 can)	41.0
Bacon (12-lb slab)	37.6
Beans	
(No. 10 can)	43.8
(No. 2½ can)	42.1
(No. 2 can)	41.0
(No. 1 can)	50.7
Beans, dry (100-lb sack)	39.2
Beans, string	
(No. 10 can)	41.6
(No. 2½ can)	40.0
(No. 2 can)	39.5

WWW.SURVIVALEBOOKS.COM

Table B-8. Average densities of subsistence (cont)

Material	Weight (lb per cu ft)
Beans, canned (5-lb can)	52.0
Beef, roast (No. 10 can)	42.5
Beets	
(No. 10 can)	42.5
(No. 2½ can)	40.0
(No. 2 can)	41.0
Biscuits, type C (2-lb pack)	28.8
Bouillon cubes (100 per pack)	37.3
Butter (5-lb pack)	45.6
Cabbage, dehydrated (5-lb pack)	13.8
Candy, hard (15-lb pack)	33.1
Carrots	
(No. 10 can)	42.5
(No. 2½ can)	40.0
(No. 2 can)	41.0
Catsup	
(No. 10 can)	45.0
(No. 2½ can)	42.1
(No. 2 can)	41.0
Cereal, uncooked (22 oz.)	32.7
Cereal, individual	8.7
Cheese, processed (6-lb pack)	54.4
Chile con carne	
(No. 10 can)	42.5
(No. 2½ can)	40.0
(No. 2 can)	41.0
Cocoa (5-lb bag)	25.0
Coffee (16-lb bag)	30.0
Corn	
(No. 10 can)	43.2
(No. 2½ can)	41.1
(No. 2 can)	41.0
Crackers, Graham (2-lb pack)	30.0
Eggs, dehydrated (No. 10 can)	45.0
Figs	
(No. 10 can)	45.0
(No. 2½ can)	42.5
(No. 2 can)	36.1
Flour (98-lb sack)	36.1
Grapefruit	
(No. 10 can)	41.6
(No. 2½ can)	40.0
(No. 2 can)	39.5
Hash, corned beef (5½-lb pack)	33.1
Hash, meat and vegetable (No. 10 can)	43.8
Jam, assorted	
(No. 10 can)	52.5
(No. 2½ can)	41.0
(No. 2 can)	47.0
Lard (37-lb container)	46.8
Luncheon meat (5-lb pack)	49.5
Mackerel (14-oz can)	26.7
Milk, powdered (5-lb container)	31.3
Milk, evaporated (14½-oz pack)	42.3
Oats, rolled (48-oz pack)	20.9
Peaches, and/or pears	
(No. 10 can)	43.8
(No. 2½ can)	41.1
(No. 2 can)	42.5
Peanut butter	
(No. 10 can)	43.8
(No. 2½ can)	41.1
(No. 2 can)	41.0
Peas	
(No. 10 can)	42.8
(No. 2 can)	41.0
Pickles (1-gal jar)	48.5
Pineapple, sliced	
(No. 10 can)	43.8
(No. 2½ can)	42.1
(No. 2 can)	41.0
Pineapple juice	
(No. 10 can)	41.7
(No. 2 can)	41.0
Potatoes, dehydrated	
(No. 16-lb pack)	33.0
(No. 10-lb pack)	24.7
Prunes, dry	
(No. 25-lb bag)	60.0
(No. 5-lb bag)	44.4
Salmon (1-lb container)	47.7
Salt (100-lb bag)	39.2
Sauerkraut	
(No. 10 can)	40.9
(No. 2½ can)	38.9
(No. 2 can)	39.5
Sausage (2-lb pack)	44.3
Sausage, Vienna (1½-lb pack)	36.7
Soup, dehydrated (5-lb pack)	28.6
Spaghetti	
(No. 10 can)	43.2
(No. 2½ can)	41.1
(No. 2 can)	41.0
Spinach	
(No. 10 can)	40.6
(No. 2½ can)	38.9
(No. 2 can)	38.0
Stew, meat and vegetable	
(28-oz pack)	40.7
(30-oz pack)	43.6
Sugar, granulated	
(10-lb pack)	56.4
(100-lb pack)	40.0
Syrup	
(No. 10 can)	52.2
(1-lb container)	62.1
Tea (5-lb box)	13.0
Tomatoes	
(No. 10 can)	41.9
(No. 2½ can)	40.0
(No. 2 can)	39.5
Tomato juice	
(No. 10 can)	41.6
(No. 2½ can)	40.0
(No. 2 can)	39.5
Vegetables, mixed	
(No. 10 can)	42.5
(No. 2 can)	39.5
Vinegar (1-gal jar)	67.0

WWW.SURVIVALEBOOKS.COM

Table B-9. Average densities of clothing and individual equipment

Material	Weight (lb per cu ft)	Material	Weight (lb per cu ft)	Material	Weight (lb per cu ft)
Axe, chopping	20	Gloves, cotton	18	Pocket, magazine	25
Bag, barracks	18	Gloves, leather	25	Pole, tent, shelter	28
Bag, duffel	22	Gloves, wool	11	Pouch, first aid	15
Bag, sleeping	17	Handkerchief	25	Raincoat	30
Bar, mosquito	20	Haversack	19	Roll, bedding	32
Belt, cartridge	20	Helmet, steel, boxed	15	Rope, manila	15
Belt, pistol	22	Holster, (various types)	15	Scabbard, rifle	13
Blanket, wool, OD	16	Jacket, field	21	Shirt, cotton, khaki	20
Boots, service, combat	18	Jumper, dungaree	21	Shirt, wool, OG	23
Bunting, wool	21	Laces, shoe	20	Shoes, low quarter	11
Can, meat, aluminum	13	Liner, helmet	6	Shovel, entrenching	28
Canteen, aluminum	9	Mittens, inserts	16	Socks, cotton	16
Cap, garrison, AG 44	18	Muffler, wool, OD	12	Socks, wool	14
Cap, service, wool	4	Necktie, mohair	15	Sweater, wool	15
Carrier, pack	16	Overcoat (w/wool insert)	20	Tent, shelter half	23
Case, canvas, dispatch	13	Pack, field, cargo	19	Towel, bath	15
Coat, wool	14	Pack, field, combat	18	Trousers, cotton, khaki	22
Comforter, wool	7	Pants, sweat	20	Trousers, wool serge	23
Cover, canteen	11	Parka, field, cotton	23	Undershirt, cotton	18
Cup, canteen, aluminum	11	Pin, tent	27		
Drawers, cotton	21	Pocket, cartridge	18		
Drawers, winter	18				

Table B-10. Average density of organizational field equipment equipment

Material	Weight (lb per cu ft)	Material	Weight (lb per cu ft)
Can, galvanized		Paulin, canvas, small[1]	21.0
(10-gal)	17.6	Paulin, canvas, large[1]	43.0
(24-gal)	7.9	Pillow, feather	8.0
(32-gal)	8.4	Pillowcase	21.0
Chair, folding, metal	12.8	Pin, tent, 16-in	36.3
Chair, folding, wood	11.0	Pin, tent, 24-in	30.2
Chest, record, fiber	9.0	Pole, tent, ridge	27.0
Container, insulated	16.0	Range, field	22.7
Container, water, 5-gal	11.6	Screen, latrine[1]	27.1
Cot, canvas, folding	27.0	Table, camp, folding	9.2
Cover, mattress	24.0	Table, mess	1.8
Desk, field, empty, fiber	9.0	Tent, command post[1]	11.7
Duck, cotton[1]	32.0	Tent, GP, med[1]	23.9
Fly, tent, wall[1]	30.0	Tent, storage[1]	36.3
Kit, barber	23.0	Tent, wall, small[1]	13.0
Locker, trunk	9.0	Tent, wall, large[1]	25.0
Mattress, cotton	4.0		

[1]Figures are average. Weight will vary with different types of material.

WWW.SURVIVALEBOOKS.COM

Unit Weight for Shipment

For planning purposes, the weight in short tons of a unit is the sum of the combined weights of—

- TOE personnel and individual equipment, assuming an average weight of 240 pounds per man.
- Major items of organizational equipment,
- Class I supplies for three days, assuming 6.6 pounds per ration per man per day.
- Class III supplies necessary to move a unit 100 miles from the destination point after arrival, if authorized in shipment.
- Basic load of Class V.
- Added items that may be authorized by the theater commander or CONUS commander.

SUPPLY

Classes

The Army uses classes of supply to identify the different types of materials used for military operations. A general description of the type of material in each of the 10 classes of supply is as follows:

- Class I — subsistence.
- Class II—clothing, individual equipment, tents, tools, and other supplies.
- Class I II—petroleum, fuel, lubricants, and products.
- Class IV—construction material.
- Class V—ammunition.
- Class VI—personal demand (exchange) items.
- Class VII—major end items (tanks, vehicles, generators, and so forth).
- Class VIII—medical supplies,
- Class IX—repair parts,
- Class X—material for nonmilitary programs.

Quantities

The quantities of material used by an Army force in combat operations will vary depending on such factors as climate and terrain in the area of operations, intensity of combat, size of the force, distances to be traveled, and the type and quantity of supplies available in the host country. When the details of a combat operation are not known or rough resupply estimates are required, general pounds-per-man-per-day planning factors can be used for most of the classes of supply. The planning factors below should be multiplied by the number of men deployed to estimate resupply requirements.

Class I–4.6 lb/man/day.

Class II–6.83 lb/man/day.

Class III (packaged) *–1.28 lb/man/day.

Class IV–13.12 lb/man/day.

Class VI–O.61 lb/man/day.

Class VIII–O.35 lb/man/day.

Class IX–3.07 lb/man/day.

*Consists of lubricants in containers and is computed separately from Class III bulk petroleum.

Planning Factors

The planning factors specified will remain relatively stable regardless of size and type force, terrain, or combat intensity. However, supply Classes III, V, and VII consumption are directly dependent on these variables. At the theater level, 47.8 lb/man/day for Class III, 31.29 lb/man/day for Class V, and 18.84 lb/man/day for Class VII are frequently used for procurement and budgeting. These numbers should not, however, be used in planning for any size force less than a full theater of operations. The consumption factors in Table B-11 can be used for the type division shown and are considered valid for the European environment. Consumption factors for different size units (battalion, brigade, or corps) can be obtained from the US Army Logistics Center, Fort Lee, Virginia. Shipping data for commonly transported items are shown in Tables B-11 through B-14.

WWW.SURVIVALEBOOKS.COM

Table B-11. Consumption factors

Type Division	Class III	Class V	Class VII
Armored	229,381 gal/day	2,250,433 lb/day	1,827,354 lb/day
Infantry (Mech)	225,441 gal/day	2,245,160 lb/day	1,631,006 lb/day
Infantry	174,366 gal/day	2,006,359 lb/day	587,112 lb/day
Airborne	140,066 gal/day	1,362,222 lb/day	186,264 lb/day
Air assault	332,323 gal/day	1,975,446 lb/day	147,903 lb/day

Table B-12. Shipping data for rations

Type	Contents	Package or Case		Ration or Packet Including Packaging		Avg Calories Per Ration
		Weight (lb)	Volume (cu ft)	Avg Wt (lb)	Avg Vol (cu ft)	
Meal, Ready-to-eat, individual	12 meals	171	0.83	1.42		1,135
Food packet, long-range patrol	40 packets	36	1.84	0.90		1,100
Food packet, survival, general-purpose	24 packets	20	0.43	0.83		870
Field A[1]				6.0	0.183	4,200
Operational B[2]				6.0	0.127	4,400
Small detachment, five persons[3]	5 rations	28.5	1.1	5.8	0.2	3,600
Combat, indiv[4]	6 rations	38	1.2	6.5	0.2	3,600
Trail, frigid, indiv[5]	8 rations	34	1.6	4.0	0.2	4,400
Supplement, sundries pack (1 pack per 100 men per day)[6]		47	1.9			
Indiv, combat, meal type	4 rations	24		4.8	0.85	3,600
Supplement, aid station (100 8-oz drinks)[7]		20	1.1			
Survival						
Arctic, SA[8]	24 packets	34	0.7	1.5		2,000
Tropic, ST[9]	24 packets	36	0.7	1.5		1,700

[1] Basic field ration of approximately 200 items, including such perishables as fresh and frozen meats, vegetables, and fruit. For use primarily under stable conditions and during static phases of military operations when there are normal cooking and refrigeration facilities. Should be issued in preference to any other type of ration whenever circumstances permit. Components, weight, and volume vary.

[2] Canned or dry items or staple items: for use whenever mess facilities and personnel are available and no perishable foods are issued. Components, weight, and volume vary. SB 10-495 has information on its breakdown. Ration supplement spice pack consists of assorted spices, condiments, and leavening agents to supplement 1,000 operational B rations. The spice pack varies in weight and volume, being tailormade for different situations and scaled to the B ration.

[3] Nonperishable precooked food which may be eaten hot when organized messing is impossible but feeding in small groups is possible.

[4] Nonperishable precooked food which may be eaten hot or cold and carried and prepared by the individual soldier. For use when the tactical situation is so unstable that messing in small groups is not possible and kitchen facilities are not available.

[5] For use in extremely cold climates by small patrols or trail teams when resupply is impossible.

[6] Comfort items such as toilet articles, tobacco, and candy as a supplement to B rations for issue before the establishment of adequate sales facilities.

[7] Special nourishment in the form of hot, stimulating beverages for combat zone casualties at aid and clearing stations.

[8] For survival kits aboard aircraft operating over arctic regions, in the emergency kit forming a part of the ejection seat in combat aircraft, and in emergency kits for passengers aboard transport aircraft.

[9] Palatable food of high caloric density carried in survival kits of aircraft operating over the tropics.

WWW.SURVIVALEBOOKS.COM

Table B-13. Shipping data for ammunition

Nomenclature	Number Per Unit	Weight (lb) Crated	Weight (lb) Uncrated	Volume (cu ft) Crated	Volume (cu ft) Uncrated	Stowage Factor Crated	Stowage Factor Uncrated
Block, deml, chain	16	61.1		1.28		44	
Block, deml, 2½ lb, plastic	24	75		1.60		47	
Canister, N2, 37-mm, G	20	102		2.04		45	
Cart, AP, cal .30, in cartons	1,500	112		1.5		30	
Cart, AP, cal .30, 8-rd clip	1,440	112		1.5		30	
Cart, AP, cal .50, in cartons	300	97		1.5		35	
Cart, AP, cal .50, in cartons	350	112		1.5		30	
Cart, AP, 3-in, M78	4	153		3.22		47	
Cart, AP, 7.62-mm, in cartons, grade MG	1,200	86		1.28		33	
Cart, AP, 37-mm, M51	20	104		2.01		43	
Cart, AP, 37-mm, M74	20	91		1.01		50	
Cart, AP, 75-mm, M72	3	80	66	1.51	.83	28	28
Cart, AP, 90-mm, M77	4	237		4.43		42	
Cart, APC, 37-mm, M59	25	99		2.03		46	
Cart, APC, 75-mm, M61	3	83	70	1.84	1.03	50	33
Cart, AP, I&T, cal .30, MLB	1,200	101		1.5		33	
Cart, AP, I&T, cal .50, MLB	265	103		1.5		33	
Cart, AP&T, cal .30, w/b	1,240	98		1.5		33	
Cart, AP&T, cal .30, w/b	1,250	100		1.5		34	
Cart, AP&T, cal .30, w/b	1,200	107		1.5		31	
Cart, AP&T, cal .30, w/b (100 rd)	1,200	92		1.5		37	
Cart, AP&T, cal .30, w/b, 250-rd mag, chest	1,000	77		.9		26	
Cart, B&T, cal .30, w/b	1,200	93		1.5		36	
Cart, B&T, cal .30, w/b 25-rd mag, chest	1,000	77		.9		26	
Cart, B&T, cal .30, w/b	1,250	96		1.5		35	
Cart, B&T, 7.62-mm, 100-rd belt	800			.91			
Cart, B&T, 7.62-mm, 210-rd belt	840			.91			
Cart, B&T, 7.62-mm, 220-rd belt	880			.92			
Cart, ball, cal .30 carbine	3,000	100		.85		19	
Cart, ball, cal .30 carbine	3,450	107		.9		19	
Cart, ball, cal .30, in cartons	1,500	111		1.5		30	
Cart, ball, cal .30, 5-rd clip	1,440	117		1.5		29	
Cart, ball, cal .30, 5-rd clip	1,500	114		1.5		29	
Cart, ball, cal .30, 8-rd clip	1,344	110		1.5		31	
Cart, ball, cal .45, in cartons	1,800	97		.8		19	
Cart, ball, cal .45, in cartons	2,000	111		1.0		20	
Cart, ball, 7.62-mm, linked, grade MG	880	78		.92		26	
Cart, grenade, cal .30, M3	2,000	90		1.5		37	
Cart, HE, 3-in	4	153		3.22		47	
Cart, HE, 37-mm, M54	25	99		2.03		46	
Cart, HE, 37-mm, M63	20	91		2.04		50	
Cart, HE, 37-mm, Mk11	60	114		1.60		31	
Cart, HE, 40-mm, Mk1	16	115		1.80		35	
Cart, HE, 60-mm, M49A2	18	103	82	3.23	2.51	70	69
Cart, HE, 75-mm, M48 w/f M48	3	80	69	1.35	.92	38	30
Cart, HE, 75-mm, M48 w/f M54	3	82	68	1.84	1.03	50	34
Cart, HE, 81-mm, M43A1	6	72	58	1.65	1.08	51	42
Cart, HE, 81-mm, M56	3	55	42	1.33	.91	54	42
Cart, HE, 90-mm, M71	4	237		4.43		42	
Cart, HE, 105-mm, M1 w/f M48	3	172	154	2.37	2.06	31	30
Cart, HE, 105-mm, M54 w/f	3	172	154	2.37	2.06	31	30
Cart, cal .50 in cartons	350	108		1.5		31	
Cart, LE, 37-mm, Mk1	60	105		1.38		29	

WWW.SURVIVALEBOOKS.COM

Table B-13. Shipping data for ammunition (cont)

Nomenclature	Number Per Unit	Weight (lb) Crated	Weight (lb) Uncrated	Volume (cu ft) Crated	Volume (cu ft) Uncrated	Stowage Factor Crated	Stowage Factor Uncrated
Cart, Mk1, 75-mm, wo/f	3	72	57	1.72	.96	54	38
Cart, practice, 37-mm, Mk11	40	90		1.38		34	
Cart, practice, 60-mm, M50A2	18	103	82	2.23	2.51	70	69
Cart, smoke, 75-mm, WP, Mk2	3	72	57	1.72	.96	54	38
Cart, smoke, 75-mm, WP, M64	3	82	70	1.66	.92	45	29
Cart, smoke, 81-mm, WP, M57	3	55	45	1.65	.91	67	45
Cart, smoke, 105-mm, WP, M60	3	172	159	2.37	2.06	31	29
Cart, tracer, cal .50, in cartons	350	111		1.5		30	
Cart, tracer, 7.62-mm, M62 in cartons, grade R	400	28		.54		43	
Cart, tracer, 7.62-mm, M62 in cartons, grade R	960	72		.91		28	
Cart, tracer, 7.62-mm, M62 in cartons, grade R	1,040	78		1.28		37	
Cart, 12-gage, No. 00 buckshot	500	62		.768		28	
Cart, 12-gage, No. 7½	500	58		.768		30	
Chg, prop, M1A1 (green bag) 155H	6	67	40	3.08	1.91	103	107
Chg, prop, M3 (green bag) 155H	6	82	53	3.33	2.68	91	114
Chg, prop, M2 (white bag) 155H	6	82	73	3.26	2.63	89	81
Explosive, cratering, 40 lb	1	51		1.21		53	
Explosive, TNT, 1 lb, B1	50	67.7		1.11		37	
Fuze, det, M6A2	200	64		2.50		88	
Fuze, M10A2	200	64		2.7		95	
Fuze, PD M46	50	51		.89		39	
Fuze, PD, M47	50	53		.89		38	
Fuze, PD, M51, M51A1, M55, M55A1	25	83		1.46		39	
Fuze, PD, M67	25	78		1.46		42	
Grenade, AT, prct, M11A1	50	87		3.3		85	
Grenade, hand, frag, Mk 11	25	50		1.26		57	
Grenade, hand, off (unfused)	50	50		1.37		62	
Grenade, hand, tug, Mk1A1	24	47		.97		46	
Grenade, rifle, M9 and M9A1	10	32		1.2		83	
Grenade, rifle, prct, M11	50	108		2.8		58	
Mine, AP, blast, M25	96	30					
Mine, AP, frag, M16A1	4	44.8		.77		35	
Mine, AP, shrapnel, directional, M18A1	6	53		1.74		74	
Mine, AT, blast, metallic, hvy, M15	1	49		1.17		54	
Mine, AT, blast, nonmetallic, plastic, M19	2	71.8		1.57		49	
Mine, AT, shaped charge, metallic, M21	4	90.8		4.14		94	
Primer-detonator, M14, 1-sec delay	100	67		1.01		34	
Primer, perc, Mk11, Mk11A, Mk11A1	2,400	96		1.56		36	
Projectile, 8 in, how	1		200				
Projectile, 155-mm, AP, M112B1	1	117		1.34		26	
Projectile, 155-mm, all other	1		96		.83		19
Signal, illumination, ground M17 to M22	61			1.85			
Signal, pistol, rocket, Mk2, red & green star	103			2.57			
Signal, pistol, rocket, Mk2, red & white	31			.92			

WWW.SURVIVALEBOOKS.COM

Table B-14. Shipping data for petroleum products

Product/Container	Number Per Unit	Weight (lb)	Volume (cu ft)	Stowage Factor
Aviation gasoline				
55-gal drum, 18-gage steel	1	373	9.03	54
55-gal drum, 16-gage steel	1	389	8.8	51
55-gal drum, 18-gage light steel	1	364	9.2	56.5
5-gal can, 11-lb can	1	40.5	.81	44.8
83 octane gasoline				
55-gal drum, 18-gage steel	1	384	9.03	52.7
55-gal drum, 16-gage steel	1	400	8.8	49.2
55-gal drum, 18-gage light steel	1	376	9.2	55
5-gal can, 11-lb can	1	41.6	.81	43.6
Kerosene				
55-gal drum, 18-gage steel	1	421	9.03	48.1
55-gal drum, 16-gage steel	1	4379	8.8	45.1
55-gal drum, 18-gage light steel	1	351	9.2	58.8
5-gal can, 11-lb can	1	45	.81	40.4
Diesel fuel				
55-gal drum, 18-gage steel	1	432	9.03	47
55-gal drum, 16-gage steel	1	448	8.8	44.2
55-gal drum, 18-gage light steel	1	430	9.2	47.9
5-gal can, 11-lb can	1	46	.81	39.5
Lubricating oils				
55-gal drum, 18-gage steel	1	472	9.03	42.8
55-gal drum, 16-gage steel	1	488	8.8	40.5
55-gal drum, 18-gage light steel	1	462	9.2	44.6
5-gal can, 11-lb can	1	49	.81	37.1
1-qt cans, 12 per case (crated)	12	35	.88	56.6
1-qt cans, 24 per case (crated)	24	60	1.6	60
5-qt cans, 6 per case (crated)	6	77	1.9	55.7
Grease				
25-lb pails	1	29	.95	73.6
5-lb cans, 6 per case (crated)	6	44	1.1	56

Planning Terms

Consumption Rate. The average quantity of an item consumed or expended during a given time interval, expressed in quantities per applicable basis.

Day of Supply. That quantity of supplies estimated to be required for one day under the conditions of the operation and for the force stated.

Replacement Factor. A number expressed as a decimal which, when multiplied by the total projected quantity of an item in use, gives the quantity of that item required to be replaced during a given period of time.

Slice. An average logistical planning factor used to obtain estimates of requirements for personnel and material.

Storage

Gross Storage Area. Average ratio of open-to-covered by classes of supply.

	Ratios of Gross Storage Area	
	Open	Covered
All classes (except bulk POL)	5.5	1
Classes I, II, III (packaged and solid), and IV	4.7	1
Class V (including 10 percent of V-A)	12	1

WWW.SURVIVALEBOOKS.COM

Average Stack Height. Figures given are for use of all services in theaters of operation. For CONUS storage, the figures must be increased 25 percent.

- Covered storage—8 feet (2.4 meters).
- Open storage—6 feet (1.8 meters).

Ammunition. Ammunition storage per mile (1.6 km) of road is 1,000 short tons. Ammunition storage per square mile is 5,000 short tons. Table B-15 contains dimensions for packaged missiles and other special ammunition.

Table B-15. Packaged missiles and other special ammunition

Weapon	Container and Contents	Container Dimensions Length (in)	Width (in)	Height (in)	Volume (cu ft)	Gross Weight (lb)	Remarks
Hawk	Complete round	216	28¾	41½	149.47	1,950	
	Guidance section	90	29	34		715	Data applicable only when guidance section is shipped separately
	Igniter, rocket motor	29¼	19 3/16	18 1/32	5.96	155	Packed 24 in wooden box
	Safety and arming device, GM XM32E4 and XM326	28 1/16	14 1/16	10 25/32	2.46	72.3	Packed 8 in wooden box
	Igniter electrical power unit	17⅛	12 3/16	10 3/32	1.32	35	Packed 24 in wooden box
	Propellant grain, EPU	24⅛	15 5/16	14 7/32	3.16	65.6	Packed 24 in wooden box
	Propellant grain, inert EPU	24⅛	15 5/16	14 32	3.16	65.6	Packed 24 in wooden box
	Explosive release device	31⅛	23 3/16	10 3/32	4.32	54.5	Packed 24 in wooden box
	Accumulator, hydraulic, pneumatic (squib activated)	20	20	29	6.50	88	Packed 1 to metal drum
	Guidance section	90	29	34	51.35	715	Metal shipping container Data applicable only when guidance section is shipped separately
Pershing	Warhead section w/ or w/o inert or empty warhead	168	51½	53	260	2,596	Packed in reusable metal container XM483
	Guidance control section, GM	90	65	72	235	2,532	Packed in reusable metal container, XM474
	First stage rocket motor, GM	145	65	70	381.8	9,193	Packed in reusable metal container, XM475
	Second stage rocket motor, GM	145	65	70	381.8	7,365	Packed in reusable metal container, XM476
	Case venting	50	7	12	2.4	32	Packed in reusable metal container, two each per container
SS11	Complete round	40	28	24½	6	157	Wooden crate
SS11/B1	Complete round	36	19¼	20¾	8.3	110	Fiberglass container
Redeye	3 complete rounds	55¼	21¼	20¼	10.4	144	Shipping and storage container, GM system XM547 (tripak)
Redeye	Unipack, 1 round	56½	10	15½	5.1	60	
Shillelagh	Complete round	51	14¾	14¾	6.4	709	Metal container
Entac	Complete round	31	15	15⅜	4.1	112	Wooden container
XM454	Complete round	57	22	20	14.5	220	
Chaparral	Complete round	125	18	19	24.7	280	
Hellfire	Complete round	76¼	15½	16½	11.3	175	
Tow	Complete round	58¼	11⅜	11⅜	4.5	87	
Dragon	Complete round	47½	16	16	7.0	67	
Stinger	Complete round	67¼	13⅛	10½	5.3	77	
Roland	Complete round	120	18½	21⅜	27.5	625	

WWW.SURVIVALEBOOKS.COM

Table B-15. Packaged missiles and other special ammunition (cont)

Weapon	Container and Contents	Container Dimensions Length (in)	Width (in)	Height (in)	Volume (cu ft)	Gross Weight (lb)	Remarks
Multiple Launch Rocket System (MLRS)	Six-round pod	166	41½	33	131.5	5,078	Six-round shipping and firing container
Pershing II	Guidance Control/Adapter Section	97	72	70½	285	3,500	Packed in reusable metal container
	Radome/Radar Section	78	37	45¾	76.4	1,708	Packed in reusable metal container
	Propulsion Section (1st stage)	190	72	70	554.1	14,410	Packed in reusable metal container
Lance	Guided Missile Main Assemblage, M5 Container	161	39	43	153	3,993	Packed in M599 container
	Guided Missile Main Assemblage, M5, without Propellant, with Gas Generator	161	39	43	153	2,457	Packed in M599 container
	Power Battery Assembly	5	5	4¾	.069	3.75	Packed in wooden box
	Thermal Dry Cartridge Impulse	4¼	3	3	.219	1.25	Packed in wooden box
	Igniter Assembly, S&A	14¼	7¼	7¼	.428	6	Packed in wooden box
	Generator Assembly, Gas Pressure	46	12½	18	4.24	88	Packed in wooden box
	Battery NICAD (CSTS)	19½	16¾	19	3.58	121	Packed in wooden box
	Missile Guidance Set, AN/DJW-48	16	16	24	6.7	78	Packed in metal box
	Pulse Battery	4½	3⅛	3⅛	.024	1.5	Packed in wooden box
	Gyroscope Assembly	7¾	7¾	6⅞	.231	6.5	Packed in wooden box

Vehicles. Minimum hardstand for 2,500 vehicles is 110,000 square feet. Solid footing for a vehicle park for 2,500 vehicles is 4,000,000 square feet. Minimum hardstand for artillery and combat vehicles per item is 350 square feet.

Containerized and Bulk Cargo. Table B-16 gives the dimensions of drums, cans, and pails. Table B-17 shows bulk cargo capacities.

Table B-16. Dimensions of containers

Nomenclature	Units per Package	Type of Package	Size of Package Length (in)	Width or Diameter (in)	Height (in)
Drum					
US 55-gal, 16-gage	1	drum	0	24⅛	34¾
US 55-gal, 18-gage	1	drum	0	24⅛	34⅞
Can					
US 5-gal (gasoline)	1	can	13¾	6½	18⅜
US 5-gal (oil)	2	case	—	11 15/16	14 3/16
US 5-qt (oil)	6	case	—	14	10
US 1-qt (oil)	12	case	18	13	6
Pail					
US 25-lb (grease)	1	pail	,0	11½	11½

WWW.SURVIVALEBOOKS.COM

Table B-17. Bulk capacities

Carrier	Capacity (gallons)	Gasoline 91A (STONs)	Lube Oil (STONs)
Barge, coastwise[1]	200,000 to 400,000	45.9 to 91.8	761 to 1,522
Barge, harbor and canal[2]	15,000 to 30,000	257	57 to 114
Barge, Navy pontoon[3]	84,000	930	320
Pipeline[4]			
4-inch	304,000 per day	2,000	1,150
6-inch	655,000 per day[5]	3,500	2,500
8-inch	1,135,000 per day	614 to 1,228	4,350
Railroad tank car	8,000; 10,000; 12,000	24.1; 30.6; 36.8	30.4; 38.1; 45.7
Semitrailer, 12-ton, 4W	5,000	15.3	19
Ship, large tanker[6]	2.5 to 11 million	7,620 to 33,500	9,480 to 43,800
Ship, small tanker[7]	600,000 to 2 million	1,830 to 6,140	2,280 to 7,610
Tank, bolted-steel	10,500; 42,000; 420,000	32.2; 128; 1,280	39.9; 160; 1,600
Tank, portable, fabric[8]	10,000	30.6	38.1
Tank truck, F-3, fuel or oil	750	2.3	2.9
Tank truck, L-2, oil service	600	1.8	2.3
Trailer, fuel servicing	600	1.8	2.3
Transporter, liquid, rolling-wheel type (RLT), 1,000-gal T3[9]	1,000	3.0	3.7
Truck, tractor and trailer, F-1	4,000	12.2	15.2
Truck, tractor and two trailers, F-1A	8,000	24.4	30.4
Truck, tractor and trailer, F-2	2,000	6.1	7.6
Truck, tractor and two trailers, F-2A	4,000	12.2	15.2

[1] Molded hulls.
[2] Rectangular hulls.
[3] A 6 x 18 pontoon barge carrying three 42,000-gallon tanks loaded to two-thirds capacity.
[4] In maintaining the same volumetric pipeline capacity for gasoline and oil, more pressure is required for the heavier liquid.
[5] Based on 32,500 gallons per hour for 20 hours of operation. In an emergency it can deliver 30,000 gallons per hour for 24 hours of operation or 720,000 gallons per day.
[6] The ship tanker most commonly used is the T2-SE-A1, a 5,922,00-gallon tanker. It is 425 feet long and draws 31 feet. It has three 8-flanged discharge outlets and four discharge pumps rated 1,000 gpm at 100 psi.
[7] Draft loaded, 12 to 20 feet.
[8] When filled, 40 feet long, 12 feet wide, 3 feet high. When empty, it can be rolled to 20 inches by 12 feet; 10 can be carried in a 6 x 6 truck.
[9] A pair of removable synthetic-rubber containers (fuel cells) mounted on an axle and towing unit. Each cell has a capacity of 500 gallons.

WWW.SURVIVALEBOOKS.COM

Tentage. Table B-18 lists the different types of tents, their dimensions, ground perimeter, and total weight.

Table B-18. Tentage data

Type	Shape of Floor	Size: Floor Dimensions (in)	Size: Ground Perimeter (in)	Size: Height: Ridge (in)	Size: Height: Side wall (in)	Size: Surface Area (sq ft)	Floor Space (sq ft)	No. of Soldiers Accommodated[1]	Weight (lb): Tent Only	Weight (lb): Pins, Poles	Total Weight (lb)	Bulk Storage: Tent Only (cu ft)	Bulk Storage: Pins, Poles (cu ft)	Total Cube Packed (cu ft)	Material	Doors: No.	Doors: Height (in)	Ventilation: No. of Openings	Ventilation: No. of Windows	Stovepipe or Heater Openings	Liner	Pitching[2]: No. of Soldiers	Pitching[2]: Reqd Time (min)	Striking[2]: No. of Soldiers	Striking[2]: Reqd Time (min)
Tents																									
Arctic, 10-man	hexagon	210 dia	630	102	36	316	199	10	68	8	76	7.1	0.2	7.3	9-oz OD cotton	2	60	4	0	1	yes	6	27	6	15
Assembly	rectangular plus rounded ends	480 x 960	2,467	252	96	4,965	2,857	80	1,100	655	1,755	23.3	16.9	40.2	9.8- and 12.3-oz duck	4	96	4	0[4]	4	no	5	90	5	60
														61.4	9.8-oz duck	2	148	1	4	1	no	4	30	4	20
												5.0	3.7	8.7	12.3-oz duck	1	72	1	3	1	yes	4	20	4	15
Balloon, inflation	rectangle	159 x 182	682	148	[5]	885	201	8	110	333	443	6.3	3.6	9.9	12.3-oz duck	1	72	1	3	1	yes[7]	5	20	5	15
CP, M1942	rectangle	84 x 142	452	84	72	328	84	2	112	104	216	4.3	5.0	9.3	9-oz duck										
CP, M1945	octagon	120 x 247[6]	627	108	66	406	172[6]	3	165	92	257	7.6	4.5	12.1	9-oz duck										
Fly, squad	rectangle	240 x 251	1,382	144	63	1,673	750	15	190	62	252	21.0	7.7	69.0[12]	12.3-oz duck	2	72	2	8	3	yes	6	75	6	50
Fly, ward, hosp	rectangle	240 x 648	1,776	144	63	2,216	1,080	27	225	101	326	12.7	6.3	19.0[10]	12.3-oz duck	2	72	2	6	2	yes	4	40	4	30
GP, large	rectangle	216 x 624	1,680	144	66	2,035	936	21	420	245	665[8]	3.6	0.2	3.8	9-oz piled yarn and sateen cotton cloth	1	60	2	0	1	yes	5	15	5	10
GP, medium	rectangle	192 x 396	1,176	120	66	915	528	12	255	200	455[10]														
Hexagonal, M1950	hexagon	159 dia	477	102	24	218	113	5	40	8	48	31.5	12.2	43.7	12.3-oz duck except floor (9.8-oz duck)	2	72	2	16	3	yes	9	90	9	70
Hospital, sectional	rectangle	216 x 636[11]	1,704	144	72	2,170	954[11]	24[12]	770	327	1,097														
Hospital, ward	rectangle	192 x 600	1,584	144	54	2,162	800	20[12]	390	259	649	20.5	9.6	30.1	12.3-oz duck	2	54	2	14	3	yes	9	90	9	70
Kitchen	rectangle	144 x 216	720	144[13]	72	831	216	10	203	217	420	14.2	12.0	26.2	12.3-oz duck	1	72	ventilator screens[14]		0	no	5	60	5	45
Maint, shelter	rectangle	218 x 322	1,080	164	66	1,306	487	11	500	755	1,255														
Mountain	rectangle	54 x 82	272	43	12	112	31	2	6	4	10	26.3	58.0	84.3	12.3-, 9.8- and 6-oz duck	2	164	2[15]	0	4	no	10	75	10	60
Op, surgical	rectangle	192 x 324	1,032	144	84	1,190	432	10	252	75	327	0.5	0.2	0.7	lightweight cotton and synthetic fiber	2	27 dia (16)	2	0	0	no	2	10	2	5
Op, surgical, hv	rectangle	216 x 648	1,728	133	72	2,068	972	22	817	876	1,693														
Pyramidal	square	192 x 192	768	144	63	896	256	6	130	94	224	10.3	3.5	13.8	9.8- and 12.3-oz duck	2	84	2	8	2	yes	4	40	4	30
Pyramidal, lightweight	circle	132 dia	414	102	24	182	95	4	37	2	39	38.8	23.2	62.0	9.8- and 12.3-oz duck	2	72	2	16	3	yes	9	90	9	70
												6.2	3.6	9.8	12.3-oz duck	1	63	1	0	1	no	5	20	5	15
Squad, M1942	rectangle	192 x 384	1,152	144	54	886	512	12	255	147	402	2.5	0.2	2.7	12.3-oz duck	1		2	0	1	no	5	15	5	10
Squad, M1945	rectangle	192 x 384	1,152	144	54	886	512	12	275	150	425	10.9	5.9	16.8	9.8- and 12.3-oz duck	2	54	2		2	no	4	40	4	30
Storage	rectangle	214 x 241	910	156	63	1,008	358	8	200	202	402	11.1	6.1	17.2	12.3-oz duck	2	54	2		2	yes	4	40	4	30
Wall, large	rectangle	168 x 174	684	132	54	570	203	8	130	145	275	9.6	9.2	18.8	12.3-oz duck	2	63	2				4	40	4	30
Wall, small	rectangle	106 x 110	432	102	45	284	81	2	55	60	115	5.8	3.1	8.9	12.3- and 9.8-oz cotton duck	2	132	2	0	[17]	no	4	30	4	20
Paulins[18]																									
Fly, storage		300 x 245				512			85	20	105	3.4	4.1	7.5	12.3- and 9.8-oz cotton duck	2	102	2	0	[17]	no	4	30	4	20
Fly, wall, small		186 x 110				142			23	15	38														
Large		240 x 480				800			250		250	2.8	0.8	3.6	9.8-oz duck										
Medium		192 x 384				512			160		160	3.1	0.7	3.8	9.8-oz duck										
Screen, latrine	(19)	216 x 108 x 84[19]	660		72[20]	292	144	(21)	32		32	6.7		6.7	9.8-oz duck										
Small		144 x 204				204			57		57	4.2		4.2	9.8-oz duck										
												0.8		0.8	9.7-oz duck	1					no	6	20	6	15
												2.3		2.3	9.8-oz duck										

[1] If used as a field billet.
[2] Average for normal conditions.
[3] Six equal sides of 105 inches each.
[4] Tent also ventilated by lifting sidewalls.
[5] Arched top.
[6] The two measurements shown are the longest dimensions, including vestibule (trapezoid measuring 120 x 48 x 89.5 x 89.5 inches).
[7] Liner does not cover vestibule.
[8] Liner weighs an additional 155 pounds.
[9] Includes tent, liner, pins, and poles.
[10] Liner weighs additional 90 pounds and occupies a stored cubage of 8 cubic feet.
[11] Does not include vestibules at each end, which measure 48 x 90 inches.
[12] Bed patients on cots.
[13] Height shown is for stack section. Service section is 108 inches high.
[14] Ventilator screens on all sides of the service and stack sections to be used as required.
[15] Plus one large opening (120 x 120 inches) in roof.
[16] Tubular tunnel entrance 24 inches long.
[17] Either of the ventilator openings may be used as a stovepipe opening.
[18] Dimensions shown for flys and paulins are length and width.
[19] Screen has a 3-foot overlap on one side for an entrance.
[20] Bottom edge of screen normally 9 inches off ground.
[21] One for average company-size unit.

WWW.SURVIVALEBOOKS.COM

COLD WEATHER OPERATIONS

Consumption Rates

Fuel.

Coal stoves. For heating, coal stoves require approximately 20 pounds of coal per day for summer operations (temperatures 10°F or above) and approximately 50 pounds of coal per day for winter operations (temperatures below 10°F). For cooking, coal stoves require approximately 50 pounds of coal per day.

Generators. A 5-kw generator burns approximately 20 gallons of gasoline per day in continuous operations. A 30-kw generator burns approximately 30 gallons of diesel fuel oil (VVF 800) per day. A 45-kw generator burns approximately 35 gallons of diesel fuel oil per day (VVF 800).

Yukon Stoves. A Yukon stove burns 5 gallons of gasoline in a 10 to 12 hour period while heating the 10-man arctic tent in temperatures of 0°F and lower. This stove will also burn wood or coal.

Motors/Pumps. Based on an average of 1 hour of operation per day, 0.2 gallon of gasoline is required to start motors and pumps.

Lubrication.

Engine oil. Large, general-purpose tractors consume approximately 2 gallons of engine oil per day. The rate is considered equal for OE 30-10-5. The consumption rate for a light vehicle is 0.006 gallon per mile.

Gear oil. The rate of gear oil consumption is 0.45 gallon per mile for a large, general-purpose tractor; 0.006 gallon per mile for a light vehicle.

Grease, artillery and automotive. GAA is used as an all-purpose grease (also used for water pumps and so forth). The consumption rate is 0.005 pound per mile. Consumption rates for generators and for starting motors and pumps are based on the data shown above for those items.

Antifreeze. Initial antifreeze will be added to all vehicles embarking on a cold-weather. operation. Refer to Table B-19 to prepare antifreeze solutions.

Table B-19. Guide for preparation of antifreeze solutions

Lowest Expected Ambient Temperature (°F)	Arctic Grade Antifreeze (−90°F) (MIL-C-11755)	Ethylene-Glycol Antifreeze (−60°F) (spec O-E-771a, Type I) Pints Per Gallon of Coolant Capacity[1]	Ethylene-Glycol Antifreeze (−60°F) (spec O-E-771a, Type I) Specific Gravity (68°F)	Denatured Alcohol (Grade III)[2] Pints Per Gallon of Coolant Capacity[1]
+20	Freezing point of −90°F	1½	1.002	1½
+10		2	1.036	2¼
0	Issued ready for use and must not be mixed with any other liquid.	2¾	1.047	2¾
−10		3¼	1.055	3¼
−20		3½	1.062	3½
−30		4	1.067	4½
−40		4¼	1.073	5
−50		4½		
−60		4¾		

[1]Includes heaters, and so forth.
[2]Used as temporary emergency expedient when neither arctic grade antifreeze nor ethylene-glycol antifreeze is available.

CAUTION

Do not use ethylene-glycol full strength. It will freeze at a higher temperature than ethylene-glycol mixed with water.

WWW.SURVIVALEBOOKS.COM

Batteries

The electrolyte in acid-type storage batteries normally is composed of sulfuric acid and pure water. The proportion of these two substances determines the specific gravity of the electrolyte and the specific gravity in turn determines the state of charge of the battery. When the battery discharges, water is formed, causing a reduction in specific gravity. When the battery charges, sulfuric acid is formed, causing an increase in specific gravity. When the ratio of acid to water is such that the specific gravity is 1.275 to 1.300 at 80°F, the battery is fully charged. The proportions of acid to water shown in Table B-20 are used to make electrolytes of various specific gravities at 80°F. Freezing points of the resulting electrolytes are also shown.

Table B-20. Proportions of acid to water/used to make electrolytes

Parts concentrated sulfuric acid to one part of water		Specific Gravity	Approximate Freezing Point (°F)
By Volume	By Weight		
0.232	0.416	1.200	-16
0.250	0.545	1.210	-25
0.294	0.527	1.240	-51
0.364	0.667	1.280	-90

Extreme cold of arctic and subarctic areas has an adverse effect on storage batteries. At -30 °F, the available energy from a battery is only about 10 percent of what it would be at 80°F. For efficient operation, battery temperatures should be kept from dropping below +30°F. Normally, this is accomplished through the use of winterization kits. Also, the specific gravity must be kept in the 1.275 to 1.300 range, when corrected to a temperature of +80°F. Specific gravity changes about .002 for each 5-degree temperature change below or above 80 degrees. Specific gravities and approximate state of charge for various temperatures are given in Table B-21.


Table B-21. Specific gravities and approximate state of charge


Temperature (°F)	Specific Gravity	Approximate State of Charge (percent)	Temperature (°F)	Specific Gravity	Approximate State of Charge (percent)
-80	1.000 (water)	Fully discharged	-20	1.235-1.260	65
-80	1.130	Discharged	-15	1.237-1.262	68
-75	1.213-1.238	46	-10	1.239-1.264	70
-70	1.215-1.240	48	-5	1.241-1.266	73
-65	1.217-1.242	50	0	1.243-1.268	75
-60	1.219-1.244	52	+5	1.245-1.268	77
-55	1.221-1.246	54	+10	1.247-1.270	79
-50	1.223-1.248	56	+15	1.249-1.272	80
-45	1.225-1.250	58	+20	1.251-1.274	82
-40	1.227-1.252	60	+25	1.253-1.278	84
-35	1.229-1.254	62	+30	1.255-1.280	85
-30	1.231-1.256	63	+80	1.275-1.300	100
-25	1.233-1.258	64			

WWW.SURVIVALEBOOKS.COM

Power Vehicles and Sleds.

Specifications for power vehicles and sleds used in cold weather operations are shown below.





Power Vehicle Type — BV-206

Gross weight
- Front car — 4800 lbs
- Rear car — 2900 lbs
- TOTAL 4400 lbs

Maximum payload
- Front car — 1300 lbs
- Rear Car — 3100 lbs
- TOTAL 4400 lbs

Cargo space (LxWxH)
- Front car — 32 × 57 × 37 inches
- Rear car — 98 × 57 × 43 inches

Engine
- Ford V-6, gasoline

Max passenger
- Front car — 6
- Rear car — 11

Speed
- Road — 34 mph
- Water — 2.2 mph

Forward gradeability
- Hard surface — 31°
- Snow (32") — 17°

Cruising range on roads — 186 mi

Articulated turning radius — 23 feet

Sled type — AK10 (plastic boat type)
- Dimensions — 88 long × 25 wide × 8 inches deep
- Weight — 38 lbs
- Cargo capacity — 200 lbs

Figure B-1. Power vehicle and sled specifications

WWW.SURVIVALEBOOKS.COM

Ice

The strength of ice varies with its structure, the purity of the water from which it is formed, the cycle of formation (freezing, thawing, and refreezing), temperature, snow cover, underlying water currents, and whether or not the ice is water-supported. Although the sustaining capcity of ice cannot be determined accurately, experience and tests provide the working capacity figures for good quality freshwater ice (see Table B-22).

Table B-22. Load-bearing capacity of waterborne freshwater ice[1]

Load	Ice Thickness (in)	Distance Between Units (ft)
File of soldiers (2-pace interval)	3	
Vehicle class		
1	4	60
2	6	70
4	8	80
6	10	90
8	11.5	100
10	13	110
15	15.5	125
20	18	135
25	20	150
30	22	165
40	25	180
50	28	195
60	31	205

[1]Double figures for old sea ice and triple for young sea ice.

Temperature, Snow Cover, and Precipitation

The temperature chart in Table B-23 may be used as a guide for preliminary planning of operations in the areas shown, keeping in mind that seasonal storms may cause some of the figures to vary for short periods of time. Planners should obtain further information concerning the particular areas and should allow appropriate safety factors when planning for individual clothing, winterization of equipment, and so forth. Temperatures in the chart are not averages, but are the high and low extremes for each month for each place shown. The figures showing snow cover indicate expected snow depths since packing and partial melting reduce residual quantities. Mean annual precipitation includes snowfall and rain, with the total represented as inches of water (10 inches of snowfall equals 1 inch of water). Generally speaking, most of the precipitation above 700 latitude is snow. This rule should be used with discretion, however, since other factors (longitude, sea currents, air currents, and so forth) affect the type and quantity of precipitation.

WWW.SURVIVALEBOOKS.COM

Table B-23. Temperature and precipitation values for arctic and subarctic areas

Location	North Latitude		Temperature extremes, °F																				Precipitation, yearly						
			January		February		March		April		May		June		July		August		September		October		November		December		Snow depth (in)				Mean precipitation (in)		
	Deg	Min	Low	High	Low	High	Low	High	Low	High	Low	High	Low	High	Low	High	Low	High	Low	High	Low	High	Low	High	Low	High	Maximum depth	Month	Average depth	Period	Snow	Rain	Total
Alaska																																	
Anchorage	61	10	—40	49	—45	49	—25	54	0	64	20	84	35	84	40	84	30	84	20	74	0	64	—20	54	—35	44	27.8	Jan	6.39	Oct-Mar	—	—	14.3
Anak	61	35	—65	49	—60	49	—45	54	—30	59	— 5	74	30	84	30	94	20	84	10	69	—20	64	—40	54	—55	44	32.3	Jan	6.85	Oct-Apr	—	—	19.0
Barrow	71	18	—55	29	—55	24	—45	29	—35	34	—15	39	15	64	25	74	20	74	5	64	—15	44	—40	39	—50	29	22.5	Mar	10.70	Sep-May	—	—	5.3
Barter Island	70	7	—50	34	—60	24	—40	34	—40	34	—15	44	20	64	25	74	25	64	5	64	—20	44	—55	39	—50	34	—	—	—	—	—	—	5.0
Big Delta	64	0	—60	49	—60	49	—40	54	—20	69	15	89	20	89	35	94	20	84	5	74	—20	59	—45	54	—60	39	54.3	Jan	11.20	Sep-May	—	—	15.0
Cordova	60	30	—25	49	—35	49	—15	59	5	64	20	79	30	79	35	84	30	79	20	69	15	74	—15	54	—20	49	29.0	Jan	8.05	Oct-Apr	132.0	13.8	145.0
Fairbanks	64	49	—60	39	—60	44	—40	54	—20	69	15	89	30	94	35	94	20	84	10	74	—15	64	—40	49	—60	34	54.3	Jan	9.67	Sep-May	—	—	11.9
Gaena	64	43	—60	39	—60	39	—45	54	—30	64	— 5	84	30	89	40	89	30	84	15	69	—15	59	—50	44	—60	39	—	—	12.87	Oct-Apr	—	—	17.0
Kotzebue	66	52	—45	34	—50	39	—40	34	—25	44	—20	74	20	84	30	84	30	79	15	74	—10	54	—35	39	—45	34	48.3	Mar	13.19	Sep-May	—	—	9.0
Nome	64	30	—45	39	—50	54	—40	44	—25	54	—15	69	25	79	30	74	25	74	15	64	— 5	59	—40	44	—45	39	74.0	Mar	15.70	Oct-May	—	—	17.4
Umiat	69	22	—60	34	—60	29	—55	39	—50	59	—25	59	20	74	30	89	20	79	— 5	64	—30	49	—55	44	—60	34	22.5	Mar	10.70	Sep-May	—	—	5.0
Wales	65	37	—35	34	—40	44	—35	39	—25	44	— 5	59	20	64	35	69	30	74	25	54	10	49	—15	44	—30	34	74.0	Mar	15.69	Oct-May	—	—	10.5
Wiseman	67	26	—60	39	—60	34	—40	39	—30	49	— 5	79	30	84	35	89	25	79	5	59	—25	44	—45	34	—55	29	—	—	—	—	—	—	7.5
Canada																																	
Aklavic	68	14	—50	29	—60	44	—40	44	—35	59	—15	74	20	84	35	84	30	79	15	69	—15	59	—40	39	—55	39	48.0	Mar	14.10	Oct-Apr	40.0	5.0	9.0
Alert	82	30	—55	9	—50	14	—50	9	—40	29	—15	44	15	59	25	69	5	54	—15	44	—30	19	—40	24	—50	9	—	—	—	—	10.0	Neg	1.0
Arctic Bay	73	0	—45	24	—55	34	—50	24	—40	29	—10	39	15	59	30	64	30	59	10	49	—15	34	—40	34	—40	14	13.0	Mar	8.55	Sep-Apr	40.0	3.0	7.0
Baker Lake	64	18	—50	— 1	—50	14	—30	19	—35	34	—15	39	15	59	30	74	30	69	15	49	—10	39	—30	29	—40	19	17.5	Apr	10.34	Nov-Apr	50.0	6.0	11.0
Cambridge Bay	69	7	—55	19	—55	14	—45	19	—40	24	—15	44	15	64	30	69	25	64	10	54	—20	39	—40	24	—50	19	17.0	Apr	9.31	Sep-May	36.0	4.0	7.6
Chesterfield	63	20	—50	34	—55	29	—50	29	—40	39	—20	44	10	74	30	84	30	74	15	59	—10	49	—35	39	—50	24	32.0	Dec	13.54	Oct-May	53.0	6.0	11.3
Clyde	70	27	—40	14	—45	24	—45	24	—30	19	—10	39	20	44	25	59	25	59	20	44	— 5	34	—20	34	—40	19	25.0	Apr	14.82	Feb-Apr	65.0	4.0	10.5
Coppermine	67	49	—55	14	—55	29	—45	29	—35	39	—15	64	15	84	30	84	30	79	15	69	—25	59	—40	34	—40	24	69.0	Apr	18.82	Oct-May	40.0	5.0	9.0
Coral Harbor	64	12	—55	9	—55	29	—35	24	—35	29	—15	39	20	54	30	79	25	69	10	49	—10	34	—35	34	—50	29	40.0	Feb	17.81	Oct-May	59.0	5.0	10.9
Dawson	64	4	—60	39	—60	49	—35	49	—40	64	10	84	25	89	35	94	25	84	15	74	— 5	64	—50	49	—60	44	45.0	Feb	15.23	Oct-Apr	45.0	7.5	12.0
Eureka	80	0	—60	24	—60	— 1	—60	9	—50	29	—20	44	10	59	30	69	15	59	—15	39	—45	29	—50	29	—60	14	—	—	15.37	Oct-May	10.0	Neg	1.0
Fort Providence	61	20	—60	29	—55	24	—40	54	—25	64	10	74	25	89	35	89	25	94	5	79	10	74	—40	49	—60	49	33.0	Dec	12.83	Oct-Apr	45.0	8.0	12.5
Fort Smith	61	1	—50	44	—60	54	—40	49	10	84	—35	79	25	89	35	99	25	94	15	84	— 5	74	—35	44	—55	44	33.0	Mar	10.90	Oct-Apr	42.0	8.5	12.7
Frobisher Bay	63	45	—53	44	—50	39	—45	39	—30	39	—15	54	15	69	30	79	20	74	15	59	— 5	44	—35	29	—35	34	74.0	Mar	21.10	Oct-Apr	80.0	7.5	15.5
Holman Island	70	30	—45	9	—45	19	—35	19	—25	39	— 5	39	20	69	30	74	25	64	10	44	0	34	—25	19	—30	9	16.0	Mar	5.73	Oct-May	34.0	3.5	6.9
Isachsen	78	47	—60	19	—60	— 6	—60	9	—40	29	—15	34	10	54	25	64	10	59	—10	34	—30	29	—45	19	—55	14	—	—	—	—	10.0	Neg	1.0
Mould Bay	76	14	—60	9	—55	— 1	—55	24	—40	29	—15	34	10	59	25	59	15	59	—15	39	—25	29	—45	24	—60	14	—	—	—	—	15.0	1.0	2.5
Norman Wells	65	17	—50	24	—60	24	—30	49	—15	59	10	74	30	89	35	89	30	89	5	69	— 5	49	—35	24	—55	14	51.4	Jan	17.34	Oct-Apr	40.0	7.0	11.0
Nueltin Lake	60	30	—50	19	—55	19	—40	39	—35	49	—10	69	25	74	40	84	35	79	15	69	—20	54	—30	39	—40	24	—	—	—	—	55.0	9.0	14.5
Padloping Island	67	6	—50	29	—50	24	—45	29	—25	44	—15	49	15	59	25	74	25	64	5	64	5	59	—35	44	—40	34	65.0	Jan	49.00	Jan-Apr	—	—	15.0
Resolute	74	43	—55	24	—55	9	—55	19	—35	29	—15	39	10	59	30	64	15	59	0	44	—25	34	—40	29	—55	19	29.6	May	12.44	Oct-May	30.0	1.0	4.0
Snag	62	22	—60	34	—60	44	—40	54	—50	59	0	89	25	89	30	84	25	79	— 5	74	—20	59	—55	34	—60	34	—	—	—	—	60.0	8.0	14.0
Watson Lake	60	7	—60	44	—60	44	—40	49	—20	59	20	84	25	84	35	89	20	84	20	79	—20	69	—40	49	—60	39	37.8	Feb	15.55	Oct-Apr	60.0	9.5	15.5
Whitehorse	60	43	—60	44	—60	49	—25	49	—15	59	20	84	25	84	30	84	20	84	15	79	5	59	—45	49	—55	49	21.8	Feb	6.73	Oct-Apr	50.0	9.5	14.5
Yellowknife	62	28	—60	39	—60	34	—40	39	—25	64	0	69	30	84	40	89	35	89	20	69	0	64	—30	39	—50	39	32.0	Jan	12.79	Oct-Apr	40.0	7.5	11.5
Greenland																																	
Angmagssalik	65	37	— 5	39	—10	39	— 5	49	0	54	15	54	30	59	30	74	30	64	25	64	15	49	0	54	—10	44	—	—	—	—	—	—	15.0
Daneborg	74	18	—25	29	—35	19	—35	24	—20	29	0	49	25	54	30	54	25	59	10	44	—15	34	—25	24	—20	14	—	—	—	—	—	—	8.0
Dammarshavn	76	46	—45	34	—40	34	—30	19	—30	29	— 5	39	15	59	25	59	20	54	5	44	—20	29	—30	29	—35	19	—	—	—	—	—	—	5.0
Godhavn	69	15	—20	39	—20	44	—15	44	—15	49	10	59	25	64	35	64	20	54	25	54	10	54	5	44	— 5	44	74.4	Apr	13.87	Oct-May	—	—	7.5
Godthaab	64	10	—10	44	— 5	44	— 5	39	5	54	25	64	30	69	35	64	30	59	25	59	10	54	5	49	0	39	58.9	Apr	10.63	Sep-May	—	—	18.0
Ingefield Bay	77	25	—40	34	—40	29	—40	29	—25	39	10	44	20	49	25	59	25	54	0	49	—15	44	—35	39	—40	29	—	—	—	—	—	—	5.0
Julianehaab	60	43	—15	59	—20	49	0	49	5	59	20	64	25	64	25	74	30	64	30	69	10	54	0	54	— 5	54	43.3	Mar	7.38	Sep-Apr	—	—	40.0
Kap Tobin	70	25	—40	29	—45	34	—30	29	—15	34	5	44	25	49	25	54	25	54	20	49	0	34	—25	39	—20	29	—	—	—	—	—	—	8.0
Pearssarssuag	61	11	—30	54	—30	59	—15	59	— 5	64	15	69	30	74	35	79	30	74	20	74	5	59	—10	59	—35	59	10.6	Jan	6.15	Jan-Apr	—	—	40.0
Sondre Stromfjord	67	0	—50	49	—50	54	—45	54	—20	59	— 5	69	25	74	30	74	25	74	10	69	—10	69	—30	54	—40	48	74.4	Apr	13.87	Oct-May	—	—	14.0
Thule	76	31	—40	39	—45	34	—40	24	—30	44	— 5	49	20	59	25	64	25	59	5	49	—20	34	—30	39	—35	34	4.7	Mar	1.87	Oct-Apr	—	—	4.0
Tingmiarmiut	62	32	— 5	39	—10	39	0	44	0	44	15	49	30	54	30	69	30	59	15	59	15	49	10	39	0	39	—	—	—	—	—	—	20.0
Upernavic	72	47	—25	49	—30	49	—30	44	—20	44	0	54	20	59	30	64	30	59	20	64	10	44	0	49	—15	44	20.9	Dec	7.46	Sep-May	—	—	10.0
Iceland																																	
Reykjavic	64	8	0	54	5	54	5	49	15	59	15	64	30	64	40	69	30	64	30	64	15	59	10	54	10	54	64.0	Mar	14.00	Oct-May	—	—	34.0
Seydisfjord	65	16	— 5	64	— 5	59	5	74	15	64	20	74	10	79	20	74	25	74	30	79	— 5	64	0	59	0	59	—	—	—	—	—	—	20.0

WWW.SURVIVALEBOOKS.COM


Windchill

For windchill factors, see Table B-24.

Table B-24. Windchill chart

Wind speed Knots)	(mph)	Cooling power of wind expressed as "equivalent chill temperature" — Air temperature (°F)																				
		40	35	30	25	20	15	10	5	0	-5	-10	-15	-20	-25	-30	-35	-40	-45	-50	-55	-60
Calm	Calm	40	35	30	25	20	15	10	5	0	-5	-10	-15	-20	-25	-30	-35	-40	-45	-50	-55	-60
3- 6	5	35	30	25	20	15	10	5	0	-5	-10	-15	-20	-25	-30	-35	-40	-45	-50	-55	-60	-70
7-10	10	30	20	15	10	5	0	-10	-15	-20	-25	-35	-40	-45	-50	-60	-65	-70	-75	-80	-90	-95
11-15	15	25	15	10	0	-5	-10	-20	-25	-30	-40	-45	-50	-60	-65	-70	-80	-85	-90	-100	-105	-110
16-19	20	20	10	5	0	-10	-15	-25	-30	-35	-45	-50	-60	-65	-75	-80	-85	-95	-100	-110	-115	-120
20-23	25	15	10	0	-5	-15	-20	-30	-35	-45	-50	-60	-65	-75	-80	-90	-95	-105	-110	-120	-125	-135
24-28	30	10	5	0	-10	-20	-25	-30	-40	-50	-55	-65	-70	-80	-85	-95	-100	-110	-115	-125	-130	-140
29-32	35	10	5	-5	-10	-20	-30	-35	-40	-50	-60	-65	-75	-80	-90	-100	-105	-115	-120	-130	-135	-145
33-36	40	10	0	-5	-15	-20	-30	-35	-45	-55	-60	-70	-75	-85	-95	-100	-110	-115	-125	-130	-140	-150
Winds above 0 mph have ttle additional ffect)		LITTLE DANGER						INCREASING DANGER (Flesh may freeze within 1 minute)						GREAT DANGER (Flesh may freeze within 30 seconds)								

WWW.SURVIVALEBOOKS.COM



ZULU TIME

The letter designations shown for each time zone in Figure B-2 are those used by the US Armed Forces in communications and operational planning for the identification of zone time (ZT) in the varying time zones. Greenwich mean time (GMT) or universal time, which is the zone time at Greenwich, is designated "Z" or "Zulu time." Zones to the east of Greenwich are designated alphabetically according to longitude, starting with A and ending with M; the letter J is not used. Zones to the west of Greenwich are similarly designated, starting with N and ending with M or Y (± 12).

"Zulu" or "Z" time is used in communications when ships or activities in different time zones are involved. By looking at Figure B-2, the time anywhere in the world can easily be determined.

As an example, note that the eastern part of the United States lies in time zone R (Romeo), 5 hours later than Zulu time. Egypt lies in time zone B (Bravo), 2 hours earlier than Zulu time. Figure B-3 shows that at 1800 hours on any given day in New York, it is 0100 hours on the next day in Egypt.

It is sometimes necessary to indicate the date as well as the time in official communications. This is done by prefixing the time group and letter designator with two digits which indicate the date of the current month.. Thus, "170925Z" would indicate a date/time of GMT 0925 on the 17th of the current month. This is "Zulu time." If a month other than the current one is to be used, the date/time group with the appropriate designator is used and the name of the desired month is added as a suffix. If a year other than the current year is used, it is indicated after the month. If the date/time of the message was for 1640 on 23 May 1985, the full group would reed 231640 May 85.

WWW.SURVIVALEBOOKS.COM

TIME ZONE	HOURS OF DAY IN LOCAL MEAN TIME																																															
	PREVIOUS DAY												SAME DAY																								NEXT DAY											
Z 0	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11
A -1	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12
B -2	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13
C -3	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14
D -4	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15
E -5	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16
F -6	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17
G -7	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18
H -8	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19
I -9	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20
K -10	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21
L -11	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22
M -12	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23
N +1	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10
O +2	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09
P +3	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08
Q +4	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07
R +5	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06
S +6	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05
T +7	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04
U +8	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03
V +9	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02
W +10	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01
X +11	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00
Y +12	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23
	PREVIOUS DAY																								SAME DAY																							

Figure B-3. Worldwide time conversion chart

B-25

WWW.SURVIVALEBOOKS.COM

MEASUREMENTS, CONVERSIONS, AND EQUIVALENTS

Units of measure, their conversions, and their equivalents are shown in Tables B-25 through B-33 and Figures B-4 through B-6. Figure B-7 shows warning labels for hazardous materials.

Table B-25. Weights and measures

Dry Measure

1	pint	= 33.6 cubic inches
2	pints	= 1 quart
1	quart	= 67.2 cubic inches
8	quarts	= 1 peck
1	peck	= 537.6 cubic inches
4	pecks	= 1 bushel
1	bushel	= 2,150.42 cubic inches

Linear Measure

12	inches	= 1 foot
3	feet	= 1 yard
16½	feet	= 1 rod
5½	yards	= 1 rod
320	rods	= 1 mile
1,760	yards	= 1 mile
5,280	feet	= 1 statute mile

Cubic Measure

1,728	cubic inches	= 1 cubic foot
27	cubic feet	= 1 cubic yard

Fluid Measure

16	fluid ounces (USA)	= 1 pint
20	fluid ounces (Britain)	= 1 pint
1	pint	= 4 gills
2	pints	= 1 quart
4	quarts	= 1 gallon
1	gallon	= 8½ pounds (approximate)
42	gallons, petroleum	= 1 barrel

Nautical Measure

6	feet	= 1 fathom
100	fathoms	= 1 cable length (ordinary)
120	fathoms	= 1 cable length (US Navy)
6,080.2	feet	= 1 nautical mile

Square Measure

144	square inches	= 1 square foot
9	square feet	= 1 square yard
4,840	square yards	= 1 acre
43,560	square feet	= 1 acre
640	acres	= 1 square mile
272¼	square feet	= 1 square rod

Measurement of Surfaces and Solids

Circumference of a circle	= Diameter x 3.1416 or 6.2832 x radius
Area of a square or rectangle	= Length x width
Area of a circle	= Square of the diameter x .7854 or Square of the radius x 3.1416
Surface of a cube	= Area of one side x 6
Surface of a sphere	= Square of the diameter x 3.1416
Surface of a cylinder	= Area of two ends + (height x circumference of one circular base)
Cubic content of a cube	= Length x width x depth
Cubic content of a sphere	= Cube of the diameter x .5236
Cubic content of a cylinder	= Area of the circular base x the height of cylinder

WWW.SURVIVALEBOOKS.COM

Table B-26. Equivalent units of weight

Metric Units	US Units
Millier (tonneau, metric ton)	2,204.6 pounds
Quintal	220.46 pounds
Kilogram	2.2046 pounds
Hectogram	3.5274 ounces
Decagram	0.3527 ounces
Gram	15.432 grains
Decigram	1.5432 grains
Centigram	0.1543 grains
Milligram	0.0154 grains

Ounces to Grams		Grams to Ounces		Pounds to Kilograms		Kilograms to Pounds	
1	28.3	1	0.04	1	0.45	1	2.20
2	56.7	2	0.07	2	0.91	2	4.41
3	85.0	3	0.11	3	1.36	3	6.61
4	113.4	4	0.14	4	1.81	4	8.82
5	141.7	5	0.18	5	2.27	5	11.02
6	170.1	6	0.21	6	2.72	6	13.23
7	198.4	7	0.25	7	3.18	7	15.43
8	226.8	8	0.28	8	3.63	8	17.64
9	255.1	9	0.32	9	4.08	9	19.84
10	283.5	10	0.35	10	4.54	10	22.05

Unit	Long Tons	Metric Tons	Short Tons	Kilograms	Pounds	Cubic Feet
One long ton		1.0160	1.1200	1,016.0	2,240.0	
One metric ton	0.9842		1.1023	1,000.0	2,204.6	
One short ton	0.8929	0.9072		907.2	2,000.0	
One kilogram					2.2	
One measurement ton						40.0

WWW.SURVIVALEBOOKS.COM

Table B-27. Equivalent Units of Length

Inches to Centimeters		Centimeters to Inches	
1	2.54	1	0.39
2	5.08	2	0.79
3	7.62	3	1.18
4	10.16	4	1.57
5	12.70	5	1.97
6	15.24	6	2.36
7	17.78	7	2.76
8	20.32	8	3.15
9	22.86	9	3.54
10	25.40	10	3.94
11	27.94	11	4.33
12	30.48	12	4.72


Feet to Meters		Meters to Feet	
1	0.30	1	3.28
2	0.61	2	6.56
3	0.91	3	9.84
4	1.22	4	13.12
5	1.52	5	16.40
6	1.83	6	19.68
7	2.13	7	22.97
8	2.44	8	26.25
9	2.74	9	29.53
10	3.05	10	32.81

Yards to Meters		Meters to Yards	
1	0.91	1	1.09
2	1.83	2	2.19
3	2.74	3	3.28
4	3.66	4	4.37
5	4.57	5	5.47
6	5.49	6	6.56
7	6.40	7	7.66
8	7.32	8	8.75
9	8.23	9	9.84
10	9.14	10	10.94

Statute Miles	to	Kilometers	Kilometers	to	Statute Miles
1		1.61	1		0.62
2		3.22	2		1.24
3		4.83	3		1.88
4		6.44	4		2.49
5		8.05	5		3.11
6		9.66	6		3.73
7		11.27	7		4.35
8		12.87	8		4.97
9		14.48	9		5.59
10		16.09	10		6.21

Statute Miles	to	Nautical Miles	Nautical Miles	to	Statute Miles
1		0.87	1		1.15
2		1.74	2		2.30
3		2.61	3		3.45
4		3.48	4		4.60
5		4.35	5		5.75
6		5.22	6		6.90
7		6.09	7		8.05
8		6.96	8		9.20
9		7.83	9		10.35
10		8.70	10		11.50

WWW.SURVIVALEBOOKS.COM



1 st mi = 0.87 NM 1 NM = 1.85 km
1 st mi = 1.61 km 1 NM = 1.15 st mi

Figure B-4. Conversion scale (km, NM, and st mi)

Table B-28. Equivalent Units of Volume

Ounces to Milliliters		Milliliters to Ounces	
1	29.57	10	0.34
2	59.15	20	0.68
3	88.72	30	1.01
4	118.29	40	1.35
5	147.87	50	1.69
6	177.44	60	2.03
7	207.01	70	2.37
8	236.59	80	2.71
9	266.16	90	3.04
10	295.74	100	3.38

Quarts to Liters		Liters to Quarts	
1	0.95	1	1.06
2	1.89	2	2.11
3	2.84	3	3.17
4	3.79	4	4.23
5	4.73	5	5.28
6	5.68	6	6.34
7	6.62	7	7.40
8	7.57	8	8.45
9	8.52	9	9.51
10	9.46	10	10.57

Gallons to Liters		Liters to Gallons	
1	3.79	1	0.26
2	7.57	2	0.53
3	11.36	3	0.79
4	15.14	4	1.06
5	18.93	5	1.32
6	22.71	6	1.59
7	26.50	7	1.85
8	30.28	8	2.11
9	34.07	9	2.38
10	37.85	10	2.64

WWW.SURVIVALEBOOKS.COM

Table B-29. Conversion Factors (Metric and US units)

US or Imperial Units	×	Conversion Factor	=	Metric Units
Acres		0.4947		Hectares
Cubic feet		0.0283		Cubic meters
Cubic inches		16.3872		Cubic centimeters
Cubic inches		0.0164		Liters
Cubic yards		0.7646		Cubic meters
Feet		0.3048		Meters
Feet per second		18.288		Meters per minute
Gallons (US)		3.7854		Liters
Gallons (imp)		4.543		Liters
Grains		0.0648		Grams
Inches		2.54		Centimeters
Inches		0.0254		Meters
Inches		25.4001		Millimeters
Miles		1.6093		Kilometers
Miles per hour		0.0447		Meters per second
Ounces (avdp)		28.349		Grams
Ounces (avdp)		0.92835		Kilograms
Pints (US)		0.4732		Liters
Pints (imp)		0.568		Liters
Pounds (avdp)		0.45359		Kilograms
Square feet		0.0929		Square meters
Square inches		6.4516		Square centimeters
Square miles		2.590		Square kilometers
Square yards		0.8361		Square meters
Yards		0.914		Meters

Metric Units	×	Conversion Factor	=	US or Imperial Units
Centimeters		0.3937		Inches
Cubic centimeters		0.0610		Cubic inches
Cubic meters		35.3144		Cubic feet
Cubic meters		1.3079		Cubic yards
Decameters		3.9317		Inches
Grams		15.4324		Grains
Grams		0.03527		Ounces (avdp)
Hectares		2.4710		Acres
Kilograms		2.2046		Pounds (avdp)
Kilograms		35.2739		Ounces (avdp)
Kilometers		0.62137		Miles
Liters		61.025		Cubic inches
Liters		0.2642		Gallons (US)
Liters		0.220		Gallons
Liters		2.1134		Pints (US)
Liters		1.76		Pints (imp)
Meters		3.2808		Feet
Meters		39.37		Inches
Meters		1.0936		Yards
Meters per minute		0.0547		Feet per second
Meters per second		2.237		Miles per hour
Metric ton		2,204.6		Pounds
Millimeters		0.03937		Inches
Square centimeters		0.155		Square inches
Square kilometers		0.3861		Square miles
Square meters		1.1960		Square yards
Square meters		10.764		Square feet

WWW.SURVIVALEBOOKS.COM

Table B-8. Petroleum products weights, measures, and conversions

Product	Packaging	Weight (lb)	Volume (cubic capacity) Actual (cu ft)	Volume (cubic capacity) Planning factor (cu ft)	Conversion factors Gal to lb	Conversion factors Lb to gal	Gallons per STONs	Gallons per LTONs	Gallons per MTONs[1]	Barrels per LTONs[1]	Packaging per STONs	Packaging per LTONs	Packaging per MTONs	Vehicle capacity for carrying filled containers 1½-ton lb	Vehicle capacity for carrying filled containers 2½-ton lb	Vehicle capacity for carrying filled containers 5-ton lb
AVGAS	Bulk	—	—	—	5.90	0.169	339.0	379.7	—	9.04	—	—	—	—	—	—
	55-gal drums[2]	373.0	9.03	11	6.91	0.145	289.4	324.2	187.8	—	5.36	6.00	3.48	8	14	28
	55-gal drums[3]	389.0	8.80	11	7.20	0.139	277.8	311.1	192.8	—	5.14	5.76	3.57	8	13	26
	55-gal drums[4]	364.0	9.20	11	6.90	0.145	289.9	324.6	181.2	—	5.49	6.15	3.42	9	14	28
	5-gal cans[5]	40.5	0.81	1	8.00	0.125	250.0	280.0	200.0	—	49.40	55.30	40.00	74	124	248
Jet fuel (JP4)	Bulk	—	—	—	6.42	0.156	312.0	349.4	—	8.06	—	—	—	—	—	—
	55-gal drums[2]	399.0	9.03	11	7.39	0.135	270.0	302.4	187.8	—	5.01	5.61	3.48	8	13	25
	55-gal drums[3]	415.0	8.80	11	7.68	0.130	260.0	291.2	192.7	—	4.82	5.40	3.57	8	12	24
	55-gal drums[4]	392.0	9.20	11	7.40	0.135	270.0	302.4	181.2	—	5.10	5.71	3.42	8	14	28
MOGAS	Bulk	—	—	—	6.11	0.164	327.3	366.6	—	8.73	—	—	—	—	—	—
	55-gal drums[2]	384.0	9.03	11	7.11	0.141	281.2	315.1	187.8	—	5.21	5.83	3.48	8	13	26
	55-gal drums[3]	400.0	8.80	11	7.41	0.135	269.9	302.3	192.8	—	5.00	5.60	3.57	8	13	26
	55-gal drums[4]	376.0	9.20	11	7.09	0.141	282.1	315.9	181.2	—	5.32	5.96	3.42	8	14	28
	5-gal cans[5]	41.6	0.81	1	8.32	0.120	240.4	269.2	200.0	—	48.10	53.80	40.00	73	121	242
Diesel fuel	Bulk	—	—	—	6.99	0.143	286.1	320.5	—	7.63	—	—	—	—	—	—
	55-gal drums[2]	432.0	9.03	11	8.00	0.125	250.0	280.0	187.8	—	4.63	5.19	3.48	7	12	24
	55-gal drums[3]	448.0	8.80	11	8.30	0.120	241.0	269.9	192.7	—	4.46	5.00	3.57	7	12	24
	55-gal drums[4]	430.0	9.20	11	8.11	0.123	246.6	276.2	181.2	—	4.65	5.21	3.42	7	12	24
	5-gal cans[5]	46.0	0.81	1	9.20	0.109	217.4	243.5	200.0	—	43.50	48.70	40.00	66	109	218
Kerosene	Bulk	—	—	—	6.80	0.147	294.1	329.4	—	7.84	—	—	—	—	—	—
	55-gal drums[2]	421.0	9.03	11	7.80	0.128	256.4	287.1	187.8	—	4.75	5.32	3.48	8	12	24
	55-gal drums[3]	437.0	8.80	11	8.09	0.124	247.2	276.9	192.8	—	4.58	5.13	3.57	7	12	24
	55-gal drums[4]	351.0	9.20	11	6.62	0.151	302.1	338.3	181.2	—	5.70	6.38	3.42	9	15	30
	5-gal cans[5]	45.0	0.81	1	9.00	0.111	222.2	248.9	200.0	—	44.40	49.80	40.00	67	112	224
Lub oils	Bulk	—	—	—	7.60	0.132	263.2	294.7	—	7.02	—	—	—	—	—	—
	55-gal drums[2]	472.0	9.03	11	8.58	0.117	233.1	261.0	191.3	—	4.24	4.75	3.48	7	11	22
	55-gal drums[3]	488.0	8.80	11	8.87	0.113	225.5	252.5	196.4	—	4.10	4.59	3.57	7	11	22
	55-gal drums[4]	462.0	9.20	11	8.56	0.117	233.6	261.7	184.6	—	4.33	4.85	3.42	7	11	22
	5-gal cans[5]	49.0	0.81	1	9.89	0.102	204.1	228.6	181.2	—	40.80	45.70	40.00	62	103	206
	1-qt cans (12 per case)	35.0	0.88	1	—	—	—	—	—	—	58.00	64.90	40.00	86	143	286
	1-qt cans (24 per case)	60.0	1.60	2	—	—	—	—	—	—	33.40	37.30	20.00	50	84	168
	5-qt cans (6 per case)	77.0	1.90	2	—	—	—	—	—	—	26.00	29.10	20.00	39	65	130
Greases	25-lb pails	29.0	0.95	1	—	—	—	—	—	—	69.00	77.20	40.00	104	173	346
	5-lb cans (6 per case)	44.0	1.10	2	—	—	—	—	—	—	45.40	50.90	20.00	69	114	227
Fog oils																
SGF1	Bulk	—	—	—	7.11	0.140	281.0	314.0	—	7.49	—	—	—	—	—	—
	55-gal drums[2]	438.0	9.03	11	8.11	0.123	246.6	276.2	191.3	—	4.50	5.02	3.48	7	11	22
	55-gal drums[3]	588.0	8.80	11	8.40	0.110	238.0	266.6	196.4	—	4.32	4.84	3.57	7	11	22
	55-gal drums[4]	421.0	9.20	11	8.10	0.123	246.9	276.5	184.6	—	4.57	5.12	3.42	7	11	22
SGF2	Bulk	—	—	—	6.99	0.143	286.0	320.0	—	7.63	—	—	—	—	—	—
	55-gal drums[2]	431.0	9.03	11	7.99	0.120	250.3	280.3	191.3	—	4.54	5.09	3.48	7	11	22
	55-gal drums[3]	616.0	8.80	11	8.28	0.120	241.5	270.5	196.4	—	4.39	4.90	3.57	7	11	22
	55-gal drums[4]	478.0	9.20	11	7.90	0.121	253.1	283.5	184.6	—	4.68	5.25	3.42	7	11	23

[1] For ocean-shipping, storage, and pipeline computations, bulk petroleum products are usually measured in barrels of 42 gallons each or in LTONs.

[2] 18-gage standard weighs 54 pounds empty; filled to 54 gallons with light products, 55 gallons with heavy products.

[3] 16-gage standard weighs 70 pounds empty; filled to 54 gallons with light products, 55 gallons with heavy products.

[4] 18-gage limited standard weighs 53 pounds empty; fill to 53 gallons with light products, 54 gallons with heavy products.

[5] For planning purposes, weight of MOGAS may be taken as 42 pounds and weight of lube oil for engines as 50 pounds per 5-gallon can, excluding weight of can. Five-gallon cans weigh approximately 11 pounds empty.

NOTE: Factors in this table are based on US gallons.
1 imperial gallon = 1.2010 US gallons;
1 liter = 0.2462 US gallons.

FD #14

WWW.SURVIVALEBOOKS.COM

Table B-31. Conversion factors — petroleum products

Multiply	By	To Obtain
Cubic feet	7.48	Gallons
Cubic feet	0.1782	Barrels
Cubic feet	0.025	Tons, measurement
Cubic feet	0.01	Tons, register
Cubic feet	28.32	Liters
Cubic inches	0.0043	Gallons
Cubic meters	264.2	Gallons
Cubic meters	6.29	Barrels
Gallons	231.0	Cubic inches
Gallons	0.1337	Cubic feet
Gallons	3.7854	Liters
Gallons	0.0238	Barrels
Gallons (gasoline)	6.103	Pounds
Gallons (gasoline)	0.0031	Tons, short
Gallons (gasoline)	0.0033	Tons, measurement
Gallons (gasoline)	0.0027	Tons, long
Gallons (gasoline)	0.0026	Tons, metric
Gallons (oil)	7.434	Pounds
Kiloliters	0.159	Barrels
Liters	0.2642	Gallons
Liters	0.001	Cubic meters
Pounds	0.1639	Gallons (gasoline)
Pounds	0.1345	Gallons (oil)
Tons, long	367.21	Gallons (gasoline)
Tons, measurement	303.03	Gallons (gasoline)
Tons, measurement	1.0	Tons, short (grease)
Tons, measurement	1.1086	Tons, short (gasoline)
Tons, measurement	1.4285	Tons, short (gasoline in drums)
Tons, measurement	1.2048	Tons, short (oil in drums)
Tons, measurement	40.0	Cubic feet (gasoline)
Tons, metric	373.10	Gallons (gasoline)
Tons, short	327.8	Gallons (gasoline)
Tons, short (gasoline)	0.9195	Tons, measurement
Tons, short (gasoline in drums)	0.7	Tons, measurement
Tons, short (grease)	1.0	Tons, measurement
Tons, short (oil in drums)	0.83	Tons, measurement

WWW.SURVIVALEBOOKS.COM




Figure B-5. Conversion scale (gallons, STONs and LTONs)— petroleum products

WWW.SURVIVALEBOOKS.COM

Table B-32. Equivalent units of speed

MPH	Kn	Ft/Sec	KPH	M/Sec
1	0.8684	1.4667	1.6093	0.447
2	1.74	2.94	3.23	0.897
3	2.59	4.41	4.83	1.34
4	3.46	5.90	6.45	1.78
5	4.34	7.33	8.05	2.23
6	5.20	8.80	9.65	2.68
7	6.07	10.30	11.30	3.13
8	6.95	11.80	12.90	3.58
9	7.81	13.22	14.50	4.03
10	8.68	14.67	16.09	4.47
11	9.55	16.20	17.70	4.92
12	10.40	17.62	19.30	5.37
13	11.23	19.10	20.90	5.82
14	12.10	20.60	22.60	6.27
15	13.00	22.10	24.20	6.71
16	13.90	23.50	25.80	7.16
17	14.75	25.00	27.40	7.63
18	15.60	26.40	28.90	8.05
19	16.45	28.00	30.60	8.50
20	17.40	29.30	32.20	8.95
21	18.20	30.90	33.80	9.39
22	19.10	32.20	35.40	9.85
23	20.00	33.80	37.10	10.30
24	20.80	35.30	38.60	10.75
25	21.70	36.70	40.30	11.15
26	22.50	38.20	41.90	11.60
27	23.40	39.70	43.50	12.10
28	24.30	41.20	45.10	12.50
29	25.20	42.60	46.70	13.00
30	26.00	44.20	48.30	13.40
31	26.90	45.60	50.00	13.90
32	27.80	47.00	51.50	14.30
33	28.60	48.50	53.00	14.73
34	29.50	50.00	54.55	15.20
35	30.40	51.50	56.50	15.65
36	31.20	53.00	58.00	16.10
37	32.00	54.50	59.70	16.50
38	32.90	56.00	61.40	17.00
39	33.80	57.50	62.80	17.40
40	34.60	58.80	64.50	17.83
41	35.60	60.50	66.00	18.38
42	36.40	61.90	67.70	18.80
43	37.30	63.40	69.20	19.20
44	38.20	64.80	71.00	19.70
45	38.90	66.50	72.50	20.20
46	40.00	67.50	74.00	20.60
47	40.70	69.10	75.90	21.00
48	41.50	70.50	77.50	21.40
49	42.40	72.00	79.00	21.80
50	43.50	73.80	80.50	22.30

WWW.SURVIVALEBOOKS.COM

Table B-33. Temperature conversions—centigrade to Fahrenheit

°C	to	°F	°F	to	°C
-20		-4	0		-17.8
-10		14	10		-12.2
0		32	20		-6.7
10		50	30		-1.1
20		68	40		4.4
30		86	50		10.0
40		104	60		15.6
50		122	70		21.1
60		140	80		26.7
70		158	90		32.2
80		176	100		37.8
90		194	120		48.9
100		212	140		60.0
			160		71.1
			180		82.2
			200		93.3

°C = 5/9(°F-32)

°F = 9/5(°C + 32)




Figure B-6. Temperature conversion scale

WWW.SURVIVALEBOOKS.COM

EXPLOSIVES



FLAMMABLE LIQUIDS AND SOLIDS



POISONOUS MATERIALS





Figure B-7. Hazardous material warning labels

WWW.SURVIVALEBOOKS.COM

IRRITATING MATERIAL





COMPRESSED GASES











Figure B-7. Hazardous material warning labels (cont)

WWW.SURVIVALEBOOKS.COM

RADIOACTIVE MATERIALS



OXIDIZING MATERIALS



SPONTANEOUSLY COMBUSTIBLE MATERIAL

WATER-REACTIVE MATERIAL





Figure B-7. Hazardous material warning labels (cont).

WWW.SURVIVALEBOOKS.COM


CORROSIVE MATERIAL



EMPTY




ETIOLOGIC AGENT[1]



[1]Disease causing chemicals or organisms

BUNG[2]



[2]Used to relieve interior pressure in pressurized containers

Figure B-7. Hazardous material warning labels (cont)

WWW.SURVIVALEBOOKS.COM

GLOSSARY

Section I. ABBREVIATIONS AND ACRONYMS

AA&E	arms, ammunition, and explosives
AACG	arrival airfield control group
AAR	Association of American Railroads
abn	airborne
acft	aircraft
ACL	allowable cargo (cabin) load
ACofS	Assistant Chief of Staff
ACR	armored cavalry regiment
ADA	air defense artillery
ADC	area damage control
admin	administration
ADP	automatic data processing
ADPE	automatic data processing equipment
ADPS	automatic data processing system
AF	Air Force (USAF)
AFB	Air Force base
AFOE	assault follow-on echelon
AG	Adjutant General
AGL	above ground level
amb	ambulance
ambl	airmobile
ambt	ambulatory
ammo	ammunition
amph	amphibious
AOC	airlift operations center
AP	armor piercing
APC	armored personnel carrier
APOD	aerial port of debarkation
APOE	aerial port of embarkation
approx	approximately
APU	auxiliary power unit
AR	Army regulation
ARINC	Aeronautical Radio, Incorporated
armd	armored
arty	artillery
ASE	aircraft survivability equipment
ASG	area support group
ASP	ammunition supply point
AT	antitank
ATMCT	air terminal movement control teams
attn	attention
auth	authorized
AUTODIN	automatic digital network
aux	auxiliary
AUTOVON	automatic voice network
aval	available
avg	average
AVIM	aviation intermediate maintenance
avn	aviation
AVSCOM	United States Army Aviation Systems Command
AVUM	aviation unit maintenance
BARC	barge, amphibious, resupply, cargo
bbl	barrel
bde	brigade
BC	barge, cargo
BDL	beach discharge lighter
BMU	beachmaster unit
bn	battalion
BP	boiling point
brg	bridge
C	Celsius
cal	caliber
cap	capacity
cart	cartridge
cav	cavalry
CB	center of balance
cbt	combat

WWW.SURVIVALEBOOKS.COM

CDI	cargo disposition instructions
cdr	commander
CDWT	cargo deadweight tonnage
C-E	communications-electronics
CEOI	communications-electronics operation instructions
CEWI	combat electronic warfare intelligence
CF	convertible freighter
CG	center of gravity
cgo	cargo
chap	chapter
CHAP/VUL	CHAPARRAL/VULCAN
chg	charge
CL	centerline
co	company
COFC	container-on-flatcar
COMINT	communications intelligence
comm	communication
COMMZ	communications zone
COMPASS	Computerized Movement Planning and Status System
COMSEC	communications security
CONEX	container express
cont	continued
CONUS	Continental United States
COR	cargo outturn report
COSCOM	corps support command
CP	command post
CRAF	Civil Reserve Air Fleet
CSA	corps support area
CSR	controlled supply rate
CSS	combat service support
CS	combat service support system
cu	cubic
CVA	carrier, vertical assault
CZ	combat zone
DA	Department of the Army
DACG	departure airfield control group
DCD	Directorate of Combat Developments
DCSLOG	Deputy Chief of Staff for Logistics
DD	Department (of) Defense (form)
DDC	division data center
deml	demolition
det	detonating
DIA	Defense Intelligence Agency
DISCOM	division support command
div	division
DLA	Defense Logistics Agency
DMAHTC	Defense Mapping Agency Hydrographic/ Topographic Center
DO	director of operations
DOC	Department of Commerce
DOD	Department of Defense
DOI	Department of the Interior
DOT	Department of Transportation
DPSC	Defense Personnel Support Center
DS	direct support
DSA	division support area
DSU	direct support unit
DTO	division transportation officer
DTS	Defense Transportation System
DTT	destination truck terminal
DWT	deadweight ton(nage)
DZ	drop zone
ea	each
EAT	external air transport
ECCM	electronic counter-countermeasures
elct	electronics
elec	electric
EM	enlisted member
emerg	emergency
engr	engineer
EPW	enemy prisoner of war
equip	equipment
ETA	estimated time of arrival
ETD	estimated time of departure
ETR	export traffic release
EXTAL	extra time allowance
EZ	extraction zone
F	Fahrenheit
FA	field artillery
FASCO	forward area support coordinator
FAW	front axle weight
FCU	fuel consumption unit
FLOT	forward line of own troops
FM	frequency modulated; field manual
FOH	front overhang
FORSCOM	United States Army Forces Command
frag	fragmentation

WWW.SURVIVALEBOOKS.COM

FS	floor station
FSTC	United States Army Foreign Science and Technology Center
ft	foot, feet
ft/sec	feet per second
FTRAC	full-tracked vehicle
fwd	forward
g	gravity; unit of force
G3	Assistant Chief of Staff, G3 (Operations and Plans)
ga	gauge
GAA	grease, artillery, and automotive
gal	gallon
GBL	government bill of lading
GCA	ground-controlled approach
gen	general
GM	guided missile
GMT	Greenwich mean time
gp	group
GP	general purpose
GPM	gallons per minute
GS	general support
GSA	General Services Administration
GSU	general support unit
GTL	gross trailing load
h	height
HE	high explosive
HET	heavy-equipment transporter
hgt	height
HICHS	Helicopter Internal Cargo Handling System
HHC	headquarters and headquarters company
HHG	household goods
HMMWV	high mobility multipurpose wheeled vehicle
HMMS	HELLFIRE modern missile system
hosp	hospital
how	howitzer
HP	horsepower
HQ	headquarters
hr	hour
HRP	highway regulating point
HRPT	highway regulating point teams
HTH	highway traffic headquarters
hvy	heavy
ICC	Interstate Commerce Commission
IFR	instrument flight rules
in	inch(es)
inf	infantry
INTACS	Integrated Tactical Communications System
intel	intelligence
ITO	installation transportation office(r)
JTB	Joint Transportation Board
JTF	joint task force
km/hr	kilometers in the hour
km	kilometer(s)
kn	knot(s)
KPH	kilometers per hour
kw	kilowatt(s)
l	liter(s)
LACV	lighter, air cushion vehicle
LARC	lighter, amphibious resupply cargo
LAPES	low altitude parachute extraction system
LASH	lighter aboard ship
lb	pound(s)
LCC	landing craft, control
LCM	landing craft, mechanized
LCU	landing craft, utility
LE	low explosive
liq	liquid
LKA	amphibious cargo ship
LO	liaison officer
LOA	length overall
log	logistics
LOTS	logistics over the shore
LST	landing ship tank
lt	light
LTON	long ton
LTCL	less-than-container load
LVTP	landing vehicle, track, personnel
LWL	load waterline
LZ	landing zone
m	meter(s)
m/sec	meters per second
MAB	mobile floating assault bridge-ferry (US)
MAC	Military Airlift Command
MACOM	major Army command
mag	magazine
maint	maintenance
MAP	Military Assistance Program

WWW.SURVIVALEBOOKS.COM

MARAD	Maritime Administration
MATCO	Military Air Traffic Coordination Office
max	maximum
MCA	movement control agency
MCC	movement control center
MCO	movement control officer
MCT	movement control team
mdm	medium
mech	mechanized
MEDDAC	medical department activity
mg	machinegun
MHE	materials-handling equipment
mi	mile
MIH	miles in the hour
MILSTAMP	Military Standard Transportation and Movement Procedures
MIL-STD	military standard
MILSTRIP	Military Standard Requisitioning and Issue Procedures
MILVAN	military-owned remountable container
min	minute
Mk	mark
ml	milliliter(s)
MLB	metallic link belt
MLRS	Multiple Launch Rocket System
MLW	mean low water
mm	millimeter(s)
MMC	Materiel Management Center
mo	month(s)
MOGAS	motor gasoline
MPH	miles per hour
MSC	Military Sealift Command
MSR	main supply route
MST	mechanics support team
mtd	mounted
MTMC	Military Traffic Management Command
MTMCTEA	Military Traffic Management Command Transportation Engineering Agency
MTON	measurement ton
NA	not applicable
NATO	North Atlantic Treaty Organization
NBC	nuclear, biological, chemical
NCO	noncommissioned officer
NDT	net division tonnage
NICAD	nickel cadmium
NM	nautical mile
no	number
NSP	non-self-propelled
NTL	net trainload
OB	obstruction
OD	olive drab
off	offensive
OG	olive green
op	operator, operations, operating
OPSEC	operations security
ORP	ocean reception point
OTT	origin truck terminal
oz	ounce(s)
pax	passengers
pert	percussion
pers	personnel
PD	point detonating
PLL	prescribed load list
POC	point of contact
POD	port of debarkation
POE	port of embarkation
PNL	prescribed nuclear load
POL	petroleum, oils, and lubricants
POV	privately owned vehicle
POW	prisoner of war
prct	practice
prop	propelling
psi	pounds per square inch
pst	pass time
pt	point
PZ	pickup zone
qt	quart
qty	quantity
RAW	rear axle weight
rd	round(s)
RDD	required delivery date
RDL	reference datum line
REFORGER	return of forces to Germany
ref	reference
refrig	refrigerated
RLT	rolling liquid transporter
RMCT	regional movement control teams
ROH	rear overhang
RO/RO	roll-on/roll-off
RP	release point
RTCH	rough terrain container handler

WWW.SURVIVALEBOOKS.COM

RWI	radio and wire integration
S1	Adjutant (US Army)
S2	Intelligence officer (US Army)
S3	Operations and Training Officer (US Army)
S4	Supply Officer (US Army)
/s/	signed
S&P	stake and platform
sec	second
SF	standard form
SM	speedometer multiplier
SOP	standing operating procedure
SP	self-propelled
SPOE	seaport of embarkation
SRC	Standard Requirement Code
STANAG	Standardization Agreement
std	standard
Stir	semitrailer
st mi	statute mile
STON	short ton
stor	storage
sup	supply
svc	service, servicing
/t/	typed
T	ton
TA	theater army
TAACOM	theater army area command
TCMD	transportation control and movement document
TCN	transportation control number
TD	train density
TDA	table(s) of distribution and allowances
TE	tractive effort
tk	tank
tlr	trailer
TM	technical manual
TMO	transportation movement office(r)
TMR	transportation movement release
TMT	transportation motor transport
TNT	trinitrotoluene
TOE	table(s) of organization and equipment
TOFC	trailer-on-flatcar
TOW	tube-launched, optically tracked, wire-guided missile
TP	transportation priority
trac	tractor
trans	transporter
TRANSCOM	transportation command
trk	truck
TRS	transportation railway service
TTP	trailer transfer point
US	United States
USMC	US Marine Corps
USN	US Navy
USNS	US Naval ship (civilian manned)
util	utility
veh	vehicle
VPH	vehicles per hour
VPK	vehicles per kilometer
VPM	vehicles per mile
VSF	vessel stowage factor
w	width
w/	with
w/b	webbed belt
WB	wheelbase
wgt	weight
vhl	wheeled
wkr	wrecker
w/o	without
wown	without winch
WP	white phosphorous
WPOD	water port of debarkation
WR	wash room
wt	weight
WTCA	water terminal clearance authority
wwn	with winch
yd	yard
yr	year
ZT	zone time

Section II. TERMS

Anchorage— a harbor, river, or offshore area that can accommodate a ship at anchor either for quarantine, queuing, or discharge.

WWW.SURVIVALEBOOKS.COM

Backhaul— shipment of material to or through an area from which the material had previously been shipped.

Back loading— the act of loading outbound cargo on a semitrailer that delivered inbound cargo.

Berth— designated area alongside a wharf or anchorage.

Break-bulk— to unload and distribute a portion or all of a shipment.

Cargo offering— a requirement placed on a movement control authority by a shipping activity to obtain instructions for shipment of cargo.

Cargo transporter—reusable, metal, shipping container designated for worldwide surface and air movement of supplies and equipment.

Common service— that function performed by one military service in support of another military service for which reimbursement is not required from the service receiving support.

Common-user transportation—a point-to-point transportation service managed by a single service for common use by two or more services or other authorized agencies for which reimbursement is normally required from the service or agency receiving support.

Container— a reusable cargo container that is assigned a permanent control number; any container (for example, crate) packed with more than one shipment unit and assigned a one-time, container-control number according to Appendix B3, DOD Regulation 4500.32-R.

Container control activity— an activity exercising overall administrative control of container service and the movement of cargo transporters to, from, and within a theater. This activity is assigned to the freight movement division of the movement control agency.

Container control officer— a designated officer within an installation who receives and dispatches cargo transporters and who is responsible for control, efficient use, and report of cargo transporters at the installation to which he is assigned. He has custodial property responsibility for cargo transporters from the time received until the time he reports their dispatch.

Controlled route— a route, the use of which is subject to traffic or movement restrictions.

Control point—a position along a route of march at which men are stationed to give information and instructions for the regulation of supply or traffic.

Date shipped—the date a shipment is released by the consignor to the carrier.

Density— weight displacement of freight per cubic foot or other unit of volume.

Dispatch route— a roadway over which full control, both as to priorities of use and regulation of movement of traffic in time and space, is exercised. A movement credit is required for its use by an independent vehicle or group of vehicles, regardless of number or type.

Diversion— the rerouting of cargo or passengers to a new transshipment point or destination or to a different mode of transportation before arrival at ultimate destination.

WWW.SURVIVALEBOOKS.COM

Frustrated cargo— any shipment of supplies and/or equipment which, while en route to destination, is stopped before receipt and for which further disposition instructions must be obtained.

Highway traffic headquarters— headquarters exercising highway regulations to use highway transportation facilities and equipment most effectively according to assigned tasks. Regulations provide planning, routing, scheduling, and directing actual use of the highways by vehicles, personnel afoot (including troops, refugees, and other civilians), and animals.

Installation transportation officer— a qualified individual appointed on competent orders to serve a military installation or activity that requires commercial transportation service. He is a member of the technical staff of the commander of the activity to which assigned and serves essentially as the point of contact between the installation or activity and the representative of the movement management system.

Intertheater shipments— shipments that move into or out of the theater through water or aerial terminals.

Intratheater shipments— movements originating and terminating within the theater.

Military Airlift Command (MAC)— the single-manager operating agency for designated airlift service.

Military Road Network— includes all routes designated in peacetime by the host nations to meet anticipated military movements and transport movements, both allied and national.

Military Road Maneuver Network— the road system required by a commander for conducting a specific operation and for the required logistical support of that operation. It is defined and controlled (allotment of maneuver credits) by the military authorities, national or allied, according to the breakdown of responsibilities in the theater of operations.

Military Sealift Command (MSC)—the single manager of ocean transportation to provide, under one authority, the control, operation, and administration of sea transportation for personnel, mail, and cargo of the DOD; formerly designated Military Sea Transportation Service (MSTS).

Military terminal— any water or aerial port of embarkation operated by or for a military department as a terminal facility for receiving, loading, unloading, and forwarding military personnel or property. This term includes commercial terminals where activities are conducted under the guidance of the military.

Military Traffic Management Command (MTMC)— the jointly staffed, industrially funded major Army command, serving as the DOD single-manager operating agency for military traffic, land transportation, and common-user ocean terminal service.

Mole— a structure with a breakwater on one side and a loading/unloading facility on the other.

Movement control— the planning, routing, scheduling, and controlling of personnel and supply movements over lines of communication; also, an organization responsible for these functions.

WWW.SURVIVALEBOOKS.COM

Pier— a structure that projects from the shoreline to accommodate ships in discharge and loading. Often both sides are designed to receive ships.

Quay— a structure running parallel to the shoreline used to accommodate ships for discharge and loading.

Receiving transportation officer— the transportation officer serving the ultimate consignee.

Report of shipment (REPSHIP)— notification by the shipper to the consignee that a specific shipment is en route.

Reserved route— a route, the use of which is allocated exclusively to a particular authority or formation or which is intended to meet a particular requirement.

Route— the prescribed course to be traveled from a specific point of origin to a specific destination.

Special cargo— cargo which requires special handling or protection, such as pyrotechnics and precision instruments.

Spotting— the placing of trailers, container transporters, or railcars where required to be loaded or unloaded.

Supervised route— a roadway over which control is exercised by a traffic control authority by means of traffic control posts, traffic patrols, or both. A movement credit is required for its use by a column of 10 or more vehicles or by any vehicle of exceptional size or weight.

Ton-miles— a unit of measure expressed in number of short tons moved over a specific distance in miles.

Tracing— the act of requesting the location of a shipment to expedite its movement or to establish delivery time.

Traffic control post— point on the highway where the military police enforce highway traffic control and furnish information and directions.

Transportation control and movement document— the basic cargo movement document containing the basic information necessary to make movement management decisions through the worldwide, DOD transportation system.

Transportation movement office—an office designed to coordinate all movements to be carried out and to ensure maximum use of available resources. These movement offices are assigned to the communications zone, the field army, and the corps support brigade.

Transportation movement release (TMR)— shipping instructions issued by a movement control authority in response to a cargo offering.

Transportation officer— the person appointed or designated by the commander of a military activity to perform transportation services and movement management at a district, base, installation, or activity. This term also applies to movement management officers.

Wharf— a general term for mole, pier, or quay.

WWW.SURVIVALEBOOKS.COM

REFERENCES

REQUIRED PUBLICATIONS

Required publications are sources that users must read in order to understand or to comply with this publication.

Field Manual (FM)

101-10-1	Staff Officers' Field Manual: Organizational, Technical, and Logistic Data (Unclassified Data)

RELATED PUBLICATIONS

Related publications are sources of additional information. They are not required in order to understand this publication.

Army Regulations (ARs)

55-4	CONUS Military Installation Materiel Outloading and Receiving Capability Report
55-9	Overseas Ocean Terminal Handling and Inland Line-Haul Cargo Cost Report
55-15	Land Transportation Within Areas Outside the Continental United States
55-19	Marine Casualties
55-23	Submission of Dry Cargo Requirements and the Assignment and Allocation of Sea Transportation Space
55-36	DOD Use of Domestic Civil Transportation Under Emergency Conditions
55-167	Policy Governing Transportation of Cargo by Military Sea Transportation Service
55-174	Disposition of Equipment and/or Material Used in Securing Cargo on Vessels
55-176	Logistics Over-the-Shore Operations in Overseas Areas
55-182	Single Manager for Ocean Transportation Accessorial and Other Miscellaneous Services Relative to Dry/Reefer Cargo
55-228	Transportation by Water of Explosives and Hazardous Cargo

WWW.SURVIVALEBOOKS.COM

55-292	Planning for, and Operation of, Staging Facilities in Continental United States
55-355	Military Traffic Management Regulation
56-9	Watercraft
220-10	Preparation for Oversea Movement of Units (POM)
310-25	Dictionary of United States Army Terms (SHORT TITLE: AD)
310-31	Management System for Tables of Organization and Equipment (The TOE System)
310-49	The Army Authorization Documents System (TAADS)
310-50	Catalog of Abbreviations and Brevity Codes
380-5	Department of the Army Information Security Program
385-40	Accident Reporting and Records
570-2	Organization and Equipment Authorization Tables
708-1	Cataloging and Supply Management Data
725-50	Requisitioning, Receipt, and Issue System

DEPARTMENT OF THE ARMY FORMS (DA FORMS)

1248	Road Reconnaissance Report
1249	Bridge Reconnaissance Report
1250	Tunnel Reconnaissance Report
1251	Ford Reconnaissance Report
1252	Ferry Reconnaissance Report
2028	Recommended Changes to Publications and Blank Forms

DEPARTMENT OF THE ARMY PAMPHLETS (DA PAMS)

310-35	Index of International Standardization Agreements
738-750	The Army Maintenance Management System (TAMMS)

DEPARTMENT OF DEFENSE FORMS (DD FORMS)

1265	Request for Convoy Clearance
1266	Request for Special Hauling Permit
2133	Joint Airlift Inspection Record

WWW.SURVIVALEBOOKS.COM

DEPARTMENT OF DEFENSE REGULATIONS (DOD REGS)

4500.32-R Vol I	Military Standard Transportation and Movement Procedures
4500.34-R	Personal Property Traffic Management Regulation

FIELD MANUALS (FMs)

1-400	Aviator's Handbook
5-35	Engineer's Reference and Logistical Data
5-36	Route Reconnaissance and Classification
9-6	Ammunition Service in the Theater of Operations
10-13	Supply and Service Reference Data
10-500	Airdrop of Supplies and Equipment: Rigging Airdrop Platforms
10-501	Airdrop of Supplies and Equipment: Rigging Containers
19-25	Military Police Traffic Operations
20-12	Amphibious Embarkation
20-22	Vehicle Recovery Operations
21-26	Map Reading
21-30	Military Symbols
21-31	Topographic Symbols
21-60	Visual Signals
21-305	Manual for the Wheeled Vehicle Driver
29-51	Division Supply and Field Service Operations
31-11	Doctrine for Amphibious Operations
31-12	Army Forces in Amphibious Operations (The Army Landing Forces)
31-70	Basic Cold Weather Manual
31-71	Northern Operations
54-11	Container Movement and Handling in the Theater of Operations
55-1	Army Transportation Services in a Theater of Operations
55-2	Division Transportation Operations
55-9	Unit Air Movement Plan
55-10	Army Movement Management Units and Procedures
55-12	Movement of Army Units in Air Force Aircraft
55-17	Terminal Operations Coordinator's Handbook

WWW.SURVIVALEBOOKS.COM

55-20	Army Rail Transport Operations and Units
55-30	Army Motor Transport Units and Operations
55-40	Army Combat Service Support Air Transport Operations
55-50	Army Water Transport Operations
55-60	Army Terminal Operations
55-70	Army Transportation Container Operations
55-312	Military Convoy Operations in the Continental United States
55-450-1	Army Helicopter External Load Operations
55-450-2	Army Helicopter Internal Load Operations
55-501	Marine Crewman's Handbook
55-511	Operation of Floating Cranes
63-2	Combat Service Support Operations - Division (How to Support)
63-3	Combat Service Support Operations - Corps (How to Support)
90-6	Mountain Operations
100-5 (HTF)	Operations (How to Fight)
100-10	Combat Service Support (How to Support)
100-27	US Army/US Air Force Doctrine for Tactical Airlift Operations
101-5	Staff Organization and Operations
101-10-2	Staff Officers' Field Manual: Organizational, Technical, and Logistical Data Extracts of Non-divisional Tables of Organization and Equipment
101-20	United States Army Aviation Planning Manual

NORTH ATLANTIC TREATY ORGANIZATION (NATO) STANDARDIZATION AGREEMENT (STANAGS)

1059	National Distinguishing Letters for Use by NATO Armed Forces
2002	Warning Signs for the Marking of Contaminated or Dangerous Land Areas, Complete Equipment, Supplies, and Stores
2010	Military Load Classification Markings
2019	Military Symbols
2027	Marking of Military Vehicles
2029	Method of Describing Ground Locations, Areas, and Boundaries

WWW.SURVIVALEBOOKS.COM

2096	Reporting Engineer Information in the Field
2115	Fuel Consumption Unit
2155	Road Movement Documents
2253	Roads and Road Structures

STANDARD FORM (SF)

361	Discrepancy in Shipment Report (DISREP)

SUPPLY BULLETIN (SB)

10-495	Standard "B" Ration for the Armed Forces

TECHNICAL BULLETINS (TBs)

43-0209	Color, Marking, and Camouflage Painting of Military Vehicles, Construction Equipment, and Materials-Handling Equipment
55-46-1	Standard Characteristics (Dimensions, Weight, and Cube) for Transportability of Military Vehicles and Other Outsize/Overweight Equipment

TABLES OF ORGANIZATION AND EQUIPMENT (TOEs)

1-167J1	Combat Aviation Company
1-257J	Combat Support Aviation Company
1-258JA	Combat Aviation Company
1-259J4	Combat Aviation Company
1-259H	Heavy Helicopter Company
5-129	Engineer Port Construction Company
5-500	Engineer Administrative and Headquarters Teams
8-500	Medical Service Organizations
10-500	Quartermaster Service Organizations
11-500	Signal Service Organizations
14-500	Finance Service Organizations
19-76	Headquarters and Headquarters Detachment, Military Police Battalion
19-77	Military Police Company
55-2H	Headquarters and Headquarters Company, Transportation Command
55-3H	Transportation Movement Control Agency
55-6H	Transportation Movement Control Center, COSCOM
55-11H	Headquarters and Headquarters Company, Transportation Motor 'Transport Brigade

WWW.SURVIVALEBOOKS.COM

55-12H	Headquarters and Headquarters Company, Transportation Motor Transport Group
55-16H	Headquarters and Headquarters Detachment, Transportation Motor Transport Battalion
55-17H	Transportation Light Truck Company
55-18H	Transportation Medium Truck Company
55-18J	Transportation Medium Truck Company
55-19H	Transportation Car Company
55-19J	Transportation Command Transport Company
55-23J	Transportation Medium Truck Company
55-27H	Transportation Cargo Carrier Company, Tracked
55-28H	Transportation Heavy Truck Company
55-28J	Transportation Heavy Truck Company
55-52H	Headquarters and Headquarters Company Transportation Composite Group
55-62H	Headquarters and Headquarters Company Transportation Brigade, COSCOM
55-67H	Transportation Light-Medium Truck Company
55-67J	Transportation Light-Medium Truck Company
55-69J	Transportation Motor Transport Company, Air Assault Division
55-84H	Transportation Motor Transport Company, Mechanized Division
55-87H	Transportation Motor Transport Company, Armored Division
55-87J	Transportation Motor Transport Company, Maintenance Support Battalion, Heavy Division
55-88H	Transportation Motor Transport Company, Infantry Division
55-88J	Transportation Motor Transport Company, S&T Battalion, Light Infantry Division
55-111H	Headquarters and Headquarters Company, Transportation Terminal Brigade
55-112H	Headquarters and Headquarters Company, Transportation Terminal Group
55-116H	Headquarters and Headquarters Company, Transportation Terminal Battalion
55-117H	Transportation Terminal Service Company, Break-Bulk
55-118H	Transportation Transfer Company

WWW.SURVIVALEBOOKS.COM

55-118J	Transportation Cargo Transfer Company
55-119H	Transportation Terminal Service Company, Container
55-119J	Transportation Terminal Service Company, Container
55-124J	Transportation Terminal Service Company, Break-Bulk
55-128H	Transportation Medium Boat Company
55-129H	Transportation Heavy Boat Company
55-137H	Medium Lighter Company (Air Cushion Vehicle)
55-137J	Medium Lighter Company (Air Cushion Vehicle)
55-138H	Transportation Light Amphibian Company
55-139H	Transportation Medium Amphibian Company
55-157H	Transportation Floating Craft General Support Maintenance Company
55-158H	Transportation Lighterage Maintenance Company
55-201H	Headquarters and Headquarters Company, Transportation Railway Brigade
55-202H	Headquartrs and Headquarters Company, Transportation Railway Group
55-217H	Transportation Electric Power Transmission Company
55-226H	Headquarters and Headquarters Company, Transportation Railway Battalion
55-227H	Transportation Railway Engineer Company
55-228H	Transportation Railway Equipment Maintenance Company
55-229H	Transportation Train Operating Company
55-247H	Diesel-Electric Locomotive Repair Company
55-248H	Transportation Railway Car Repair Company, General Support
55-500H	Transportation Service Organizations
55-520H	Transportation Railway Service Teams
55-530H	Transportation Watercraft Teams
55-540H	Transportation Motor Transport Teams
55-550H	Transportation Watercraft Maintenance Teams
55-560H	Transportation Terminal Service Teams
55-560J	Transportation Terminal Service Teams
55-580H	Transportation Movement Control Teams

WWW.SURVIVALEBOOKS.COM

TECHNICAL MANUALS (TMs)

5-312	Military Fixed Bridges
5-370	Railroad Construction
9-1300-206	Ammunition and Explosives Standards
38-250	Packaging and Materials Handling Preparation of Hazardous Materials for Military Air Shipment
55-203	Maintenance of Railway Cars
55-204	Maintenance of Railroad Way and Structures
55-206	Railway Train Operations
55-500	Marine Equipment Characteristics and Data
55-601	Railcar Loading Procedures
55-602	Movement of Special Freight
55-1500-338-S	Preparation for Shipment of OH-58 Helicopter
55-1500-339-S	Preparation for Shipment of AH-1 Helicopter
55-1510-200-S	Preparation for Shipment of U-21 and RU-21 Aircraft
55-1520-214-S	Preparation for Shipment of OH-6A Helicopter
55-1520-237-23-2	Aviation Unit and Intermediate Maintenance Aircraft General Information Manual, UH-60A Helicopter
55-1520-237-23-4	Aviation Unit and Intermediate Maintenance Servicing, Ground Handling, Air Transportability, and General Maintenance Task Manual, UH-60A Helicopter
55-1520-241-S	Preparation for Shipment of CH-47 Helicopter
55-1520-242-S	Preparation for Shipment of UH-1/EH-1 Helicopters
55-1520-400-14	Transportability Guidance: Marine Transport of US Army Helicopter
55-2200-001-12	Transportability Guidance for Application of Blocking, Bracing and Tie-down Materials for Rail Transport

OTHER PUBLICATIONS

Title 46, US Code of Federal Regulations, Parts 1 through 29, Shipping*

Title 49, US Code of Federal Regulations, Parts 170 through 179, Transportation*

Rules Governing the Loading of Department of Defense Material on Open-Top Cars (Association of American Railroads)*

Bureau of Explosives (AAR) Pamphlets 6, 6A, and 6C*

Bureau of Explosives Tariff 6000*

Military Standard 129 Sections 831 through 835, Title 18, United States code (Chapter 39, Explosives and Other Dangerous Articles)*

WWW.SURVIVALEBOOKS.COM

MAC Regulation 3-3, Combat Control Team Operations and Procedures*

MTMC Report TE 73-44, Manual Procedures for Estimating Marine Terminal Throughput, Parts I and II**

MTMCTEA Report 73-44A, Marine Terminal Operations**

MTMTS Report, An Analysis of Simulated Deployment of the US Army Airmobile Division**

Sailing Directions***

Publication Number 150, World Port Index***

Notice to Mariners***

---

*Available from:
Superintendent of Documents,
US Government Printing Office,
North Capitol and H Streets, NW,
Washington, DC 20402

**Available from:
Military Traffic Management Command,
Transportation Engineering Agency,
PO Box 6276,
Newport News, VA 23606

***Available from:
Defense Mapping Agency,
Office of Distribution Services,
ATTN: DDCP,
Washington, DC 20315

WWW.SURVIVALEBOOKS.COM

INDEX

A-22 Cargo bag, 2-15
Address
  Cargo, 5-48
  MILSTAMP, 5-48
  MILSTRIP, 5-48
Administrative/Logistics plan (order), A-5
AH-1G, 2-34
AH-1S, 2-34
AH-64, 2-34
Aircraft restraint criteria, 2-41
Air density, 2-5
Airdrop
  Delivery, 2-44
  Ground-air emergency codes, 2-46
  Low altitude parachute extraction system (LAPES), 2-45
  Release methods, 2-45
  Types of airdrop, 2-44
Air movement (vehicle preparation), 3-64
Ammunition, B-14
Ammunition, Shipping Data, B-11
Ammunition storage, B-13
Amphibians
  LACV-30, 5-39
  LARC-5, 5-39
  LARC-15, 5-39
  LARC-60, 5-39
Anchorage areas, 5-26
Animals, B-1
Antifreeze, B-18
Army Aircraft
  Aircraft Preparation, 2-39
  Characteristics, 2-35
  Profiles, 2-33
  Speed and Range Factors, 2-39
Aviation Units
  Combat Aviation Company (1-257J410), 2-3
  Combat Aviation Company (1-257J420), 2-3
  Combat Aviation Company (1-257J430), 2-3
  Combat Aviation Company (1-258JA), 2-2
  Combat Aviation Company (1-259J4), 2-3
  Combat Aviation Company (7-269J), 2-3
  Combat Aviation Company (55-167J1), 2-2
  Heavy Helicopter Company (55-259H), 2-3

B707, 2-26
B747, 2-26
Barges, inland waterway, 5-22, 5-34, 5-38, 5-40
Barges, 5-40
Batteries, B-19
Beach
  Gradient, 5-28
  Operations, 5-24
  Reconnaissance, 5-26
  Transfer points, 5-29
Berth capacity, 5-15
Boat companies (See transportation units)
Boxcar characteristics, 4-27
Bridge classifications, 3-43
Bridge signs, 3-43
Boats
  Picket, wood, 5-38
  Picket, steel, 5-38
  Passenger and cargo, 5-38
Bulk capacities, B-16

C-5, 2-24
C-12, 2-33
C-130E/H, 2-22
C-141, 2-23
Capacity
  Inland waterway, 5-21, 5-23
  Water terminal, 5-15
Cargo address, 5-48
Cargo trailers, shipping dimensions, 3-89
Cargo truck, shipping dimensions, 3-86
Center of balance, 3-80
Center of gravity
  Aircraft, 2-41
  Vehicle, 3-64
Civil Reserve Air Fleet
  Aircraft
    B707, 2-26
    B747, 2-26
    DC-8, 2-26
    DC-10, 2-26
    L-1011, 2-26
  Airlift services, 2-25
  Capabilities, 2-25
  Pallet profiles, 2-27
CH-47, 2-34
CH-54, 2-34
Clearances, track, 4-34
Clothing, average density, B-8
Cold weather operations
  Consumption rates

WWW.SURVIVALEBOOKS.COM

Fuel, B-18
Lubrication, B-18
Batteries, B-19
Ice, B-21
Power vehicles, B-20
Sleds, B-21
Windchill chart, B-23
Combat Aviation Companies, 2-2
Combat conditions, planning, 3-23
Common material, average density, B-5
CONEX, 5-46
Consumption by class of supply, B-9
Consumption factors, B-10
Consumption rate, B-13
Container handler, rough terrain, 5-45 (see RTCH)
Containers, 5-46
Containers, aerial delivery, 2-45
Container operations, 5-19
Container terminals, 5-20
Continental System, 4-22
Conversion factors (metric and U.S.), B-30
Convoy clearance, 3-17
Request for, 3-18
Special hauling permit, 3-20
Convoy Commander's Report, 3-15
Cooper's E-Rating, 4-40
Covered storage, 5-18
CRAF, 2-25
Cranes
Truck-mounted
20-ton, 5-44
140-ton, 5-44
250-ton, 5-44
Floating
60-ton, 5-38
89-ton, 5-38
Locomotive, 4-25
Curve resistance, 4-11

Daily lift, 3-22
Days of supply, B-13
DC-8, 2-26
DC-10, 2-26
Delay time, 3-22
Densities, average
Clothing & individual equipment, B-8
Common material, B-4
Organizational field equipment, B-8
Subsistance, B-6
Dimensions, container, B-15
DOD freight car characteristics, 4-33
Dogs, B-2
Drawbar pull, 4-10
Drum dimensions, B-15
Dump truck, body dimensions, 3-84
Dump truck, shipping dimensions, 3-88

End delivery tonnage, 4-13
Embarkation order, A-21
Equivalent units of speed, B-34
EXTAL (extra time allowance), 3-57
External air transport
Advantages, 2-11
Cargo bags, 2-15
Cargo nets, 2-14
Equipment, 2-15
Personnel, 2-15
Responsibilities
Aviation Unit, 2-12
Receiving Unit, 2-12
Supported Unit, 2-12
Slings, 2-13
Extraction zone, 2-45

Flares, B-12
Flatcar characteristics, 4-27
FMS, 5-40
Forklifts
4,000 lb. rough terrain, 5-45
6,000 lb. commercial, 5-44
6,000 lb. rough terrain, 5-45
10,000 lb. rough terrain, 5-45
Forward load, 3-15
Freedrop, airdrop, 2-44
Fuel requirements, planning, 3-22
Fuel Consumption Unit (FCU), 3-22
Fuel requirements, 3-22

Gages, track, 4-38
General purpose pallet, 5-47
Geneva Convention road signs, 3-47
Grade resistance, 4-11
Gradient of beach, 5-28
Gross trailing load, 4-11

HALO airdrop, 2-44
Halts
On road, 3-59
Off road, 3-59
Harbor/port information, 5-12
Hazardous material labels, B-36
Heavy helicopter company, 2-3
HICHS, 2-21
High-velocity airdrop, 2-44
Highway tonnage factors, 3-40
Hinterland, 5-29
Human bearers, B-2

WWW.SURVIVALEBOOKS.COM

Individual equipment, average density, B-8
Inland waterway planning, 5-21
Internal air transport
  Advantages, 2-16
  Disadvantages, 2-16
  Helicopter Internal Cargo Handling System (HICHS), 2-21
  Responsibilities
    Aviation Unit, 2-17
    Receiving Unit, 2-17
    Support Unit, 2-17
  Tie-down rings, 2-18

KC-10A, 2-25
Korean freight car characteristics, 4-31

L-1011, 2-26
Labels, hazardous material, B-36
LACV-30, 5-39
Landing craft, 5-28, 5-31, 5-33, 5-39
Landing craft, mechanized-8, 5-39
Landing craft, utility (LCU), 5-40
Landing site
  Selection, 2-6
  Preparation, 2-9
Landing zone, 2-6
LAPES, 2-45
LARC
  -5, 5-39
  -15, 5-39
  -60, 5-39
LCM-8, 5-39
LCU, 5-40
Lighter, Aboard Ship (LASH), 5-18
Lighter, air cushion vehicle-30 (LACV-30), 5-39
Lighter, amphibious, resupply cargo (LARC)
  -5, 5-39
  -15, 5-39
  -60, 5-39
Lighter, beach discharge, 5-39
Lighterage discharge, 5-17, 5-21
Lighters, 5-17, 5-21, 5-34, 5-38, 5-39, 5-40, 5-41
Line haul leg, 3-23
Loading time, 3-22
Locomotive characteristics, 4-23
Locomotive classification
  Continental system, 4-22
  Whyte system, 5-21
Locomotive crane characteristics, 4-25
LOTS (Logistics over the shore), 5-24
Low-velocity airdrop, 2-44

MAC, 2-22
Maintenance, marine, 5-25
Maintenance of way, 4-20
Marine terminal capacity, 5-15
Maritime Administration (MARAD) classification system, 5-41
Measurements, conversions, and equivalents, B-26
Metric conversion, B-26 thru B-30
Military Airlift Command Aircraft
  C-5, 2-24
  C-130 E/H, 2-22
  C-141, 2-23
  KC-10A, 2-25
Military load classification system, 3-40
MILSTAMP address, 5-48
MILSTRIP address, 5-48
MILVAN, 5-46, 5-47
Mines, B-12
Missiles, packaged, B-14
Motor pool facility, 3-29
Motor transport data, 3-69
Motor transport unit capabilities, 3-92
Movement calculations
  Gap, 3-54
  Lead, 3-54
  Length, 3-54
  March rate, 3-54
  Pass time, 3-54
  Road distance, 3-54
  Road space, 3-54
  Time gap, 3-54
  Time lead, 3-54
  Time space, 3-54
Movement control, 1-5
Movement credit, 3-54
Mules, pack, B-2
Multiple movements, 3-59

NATO military vehicle markings, 3-46
NATO road signs, 3-51
NATO warning signs, 3-53
Navy vessels, designators, 5-32
Net delivery tonnage, 4-12
Net trainload, 4-12

Ocean reception point (ORP), 5-4
OH-6, 2-34
OH-58, 2-34
One time lifts, 3-23
Open storage, 5-17
Open-top car characteristics, 4-26
Operation orders, A-1 thru A-30
Operation plan, A-1 thru A-30
Organizational field equipment, average density, B-8

WWW.SURVIVALEBOOKS.COM

OV-1, 2-33

Pack mules, B-2
Pails, dimensions, B-15
Passenger miles, 3-22
Pallets
  General purpose, 5-47
  Sled, 5-47
Parachutes, 2-45
Petroleum products
  Bulk capacities, B-16
  Containers, B-13
  Conversions, B-32
  Measures, B-31
  Shipping data, B-13
  Weight, B-31
Pickup zone, 2-6
Planning, motor transport, 3-22
Payload capacities, planning, 3-90

Rail equipment requirements
  Average speed, 4-13
  Rolling stock, 4-13
Rail loading
  Basic precautions, 4-15
  Blocking and bracing, 4-15
  Cargo security, 4-16
  Explosives and hazardous cargo, 4-14
  Open top cars, 4-14
Rail planning factors
  Drawbar pull, 4-10
  Gross trailing load, 4-11
  Net trainload, 4-12
  Resistance factors
    Curve, 4-11
    Grade, 4-11
    Rolling, 4-11
    Weather, 4-11
  Tractive effort, 4-10
  Train density, 4-12
  Tonnage
    Net delivery, 4-12
    End delivery, 4-13
  Weight on drivers, 4-10
Rail SOP
  Movement, 4-7
  Railway service, 4-8
Rail units (See transportation units)
Rail bridge capacities, 4-40
Railway construction, 4-17
Railway maintenance motor car characteristics, 4-26
Rations
  Average calories, B-10
  Size, B-10
  Weight, B-10
Reconnaissance, LOTS site, 5-26
Refrigerator car characteristics, 4-28
Release method (airdrop)
  Door load, 2-45
  Extraction, 2-45
  Gravity, 2-45
Repair shop, floating, marine equipment (FMS), 5-40
Replacement factor, B-13
Return load, 3-16
Road movement graph, 3-57
Road movement order, A-9
Road movement table, 3-33, A-11
Rolling resistance, 4-11
Rough terrain container handler (RTCH), 5-45
Round trip data, 3-16
Route
  Classification, 3-43
  Formulas, 3-46
  Obstructions, 3-45
  Reconnaissance, 3-34
  Reconnaissance symbols, 3-36
RTCH, 5-45

Sailing directions, 5-14
Sea barge (SEABEE), 5-18
Semitrailer cargo bed dimensions, 3-85
Semitrailers, stake and platform, shipping dimensions, 3-89
Semitrailers, van, shipping dimensions, 3-90
Service support annex, A-3
Shipping data
  Ammunition, B-11
  Petroleum products, B-13
  Rations, B-10
Shipping dimensions
  Cargo trailers, 3-89
  Cargo trucks, 3-86
  Dump trucks, 3-88
  Semitrailer, stake & platform, 3-89
  Semitrailer, van, 3-90
Shipping tag, 5-48
Sled pallet, 5-47
Slings, external air transport, 2-13
Specific loads, 3-24
Special purpose car characteristics, 4-29
Standing operating procedures, A-12 thru A-21
Standing operating procedures (motor transport), 3-12
Static electric discharge probe, 2-15

WWW.SURVIVALEBOOKS.COM

Stevedore companies (See transportation units)
Stopping distances, vehicle, 3-90
Storage
  Covered, 5-18
  LOTS, 5-29
  Open, 5-17
  Terminal, 5-17
Stowage factors, B-3
Subsistance, average density, B-7
Supply
  Ammunition, B-14
  Classes, B-9
  Planning factors, B-9
  Quantities, B-9
  Storage, B-13
  Terms, B-10
Support vessels, 5-33
Sustained operations, 3-23

Tank car characteristics, 4-28
Temperature conversion, B-35
Terminal equipment, 5-42
Terminal estimates
  Berth capacity, 5-15
  Cargo load/unload time, 5-18
  Covered storage, 5-18
  Inland waterway capacity, 5-21
  Temporary storage, 5-16
  Terminal capacity, 5-15
  Transportation, A-23
Tentage data, B-17
Tie-down rings, 2-18
Time, B-24
Time conversion chart, B-25
TOE capabilities (see transportation units)
Ton miles, 3-22
Tractive effort, 4-10
Traffic, control at marine terminal, 5-30
Traffic circulation plan, 3-40
Traffic density, 3-61
Traffic density formula, 3-61
Traffic density and flow graph, 3-62
Traffic flow, 3-61
Trailer, cargo, bed dimensions, 3-84
Trailer transfer points, 3-25
Train density, 4-12
Transfer points, beach, 5-29
Transportation Command, 1-4
Transportation composite group, 1-4
Transportation control number (TCN), 5-49
Transportation estimate, A-23
Transportation mediums, capabilities, B-1
Transportation Movement Control Agency, 1-5
Transportation Service Organization Headquarters Teams, 1-4
Transportation plan, A-25
Transportation planning, 1-1
Transportation priority, 5-49
Transportation Railway Service (TRS), 4-1
Transportation Units
  Cargo Carrier Company (tracked) (55-27H), 3-5
  Cargo Transfer Company (55-118J), 5-3
  Command Transport Company (55-19J3), 3-4
  Diesel-electric Locomotive Repair Company (55-247H), 4-3
  Floating Craft General Support Maintenance Company, (55-247H), 5-8
  Heavy Boat Company (55-129H), 5-6
  Heavy Truck Company (55-28H), 3-5
  Light Truck Company (55-17H), 3-2
  Lighterage Maintenance Company, General Support (55-158H), 5-8
  Light-Medium Truck Company (55-67H), 3-6
  Light-Medium Truck Company (55-67J4), 3-6
  Medium Amphibian Company (55-139H), 5-7
  Medium Lighter Company (LACV) (55-137H), 5-6
  Medium Lighter Company (LACV) (55-137J), 5-7
  Medium Truck Company (55-18H), 3-3
  Medium Truck Company (container/cargo, 20 ft) (55-18J), 3-4
  Medium Truck Company (container/cargo, 40 ft) (55-23J4), 3-4
  Motor Transport Battalion (55-16H), 3-2
  Motor Transport Brigade (55-11H), 3-1
  Motor Transport Group (55-12H), 3-2
  Motor Transport Teams (55-540H), 3-10
    Car (55-540HGA), 3-10
    Heavy Truck (55-540HGD), 3-11
    Light Truck (55-540HGB), 3-10
    Medium Truck (55-540HGC), 3-10
    Trailer Transfer Point (55-540HGE), 3-11
  Motor Transport Company
    Air Assault Division (55-69J0), 3-7
    Armored Division (55-87H), 3-7
    Heavy Division (55-87J4), 3-8
    Infantry Division (55-88H), 3-9
    Infantry Division (Light) (55-88J8), 3-9
    Infantry Division (Mechanized) (55-84H), 3-7
  Movement Control Agency (55-004H), 1-5

WWW.SURVIVALEBOOKS.COM

Movement Control Center (COSCOM) (55-006H), 1-6
Movement Control Teams (55-580H)
Highway Regulation Point (55-580HLH), 1-8
Movement Control (55-580HLA), 1-6
Movement Control (55-580HLB), 1-6
Movement Control (55-580HLC), 1-6
Movement Control (Region) (55-580HLD), 1-7
Movement Control (Region) (55-580HLE), 1-7
Movement Control (Air Terminal) (55-580HLF), 1-7
Movement Control (Air Terminal) (55-580HLG), 1-7

Railway
Battalion (55-226H), 4-2
Brigade (55-201H), 4-2
Car Repair Company (General Support) (55-248H), 4-2
Electric Power Transmission Company (55-217H), 4-3
Engineering Company (55-227H), 4-2
Equipment Maintenance Company (55-228H), 4-3
Group (55-202H), 4-2
Service Teams (55-520H)
Bridge and Building Maintenance (55-520 EG), 4-6
Detachment (Direct Support) (55-520HEG), 4-6
Car Repair Crew (Direct Support) (55-520HEE), 4-5
Diesel-Electric Locomotive Maintenance Crew (Direct Support) (55-520HED), 4-5
Maintenance-of-Way Crew (55-520HEJ), 4-6
Section Crew (55-520HEC), 4-5
Station Team (55-520HEA), 4-5
Terminal Detachment (55-520HEB), 4-5
Train Operating Section (55-520HEH), 4-5
Workshop Mobile Detachment (Direct Support) (55-520HEI), 4-6
Yard Operating Detachment (55-520HEF), 4-5

Train Operating Company (55-229H), 4-3
Service Organizations (55-500H)
Battalion Headquarters (55-500HAD), 1-5
Company Headquarters (55-500HAC), 1-6
Platoon Headquarters (Component) (55-500HAA), 1-4
Platoon Headquarters (Separate) (55-500HAB), 1-5
Terminal Battalion (55-116H, 5-2
Terminal Brigade (55-111H), 5-2
Terminal Group (55-112H), 5-2
Terminal Service Company (Break-Bulk) (55-117H), 5-3
Terminal Service Compoany (Break-Bulk and Container) (55-124J), 5-5
Terminal Service Company (Container) (55-119H), 5-4
Terminal Service Company (Container) (55-119J), 5-4
Terminal Service Teams (55-560J)
Automated Cargo Documentation (55-560JJI), 5-12
Break-Bulk Augmentation (Container) (55-560JJH), 5-11
Cargo Documentation (55-560JJB), 5-11
Cargo Hatch Gang (55-560JJE), 5-11
Container-Handling (Ship) (55-560JJF), 5-11
Container-Handling (Shore) (55-560JJG), 5-11
Freight Consolidation and Distribution (55-560JJC), 5-11
Heavy Crane Platoon (55-560JJJ), 5-12
Stevedore/Container-Handling Equipment Maintenance (55-560JJA), 5-11
Transportation Contract Supervision (55-560JJD, 5-11
Terminal Transfer Company, (55-118H), 5-3
Transportation Command (55-002H), 1-4
Transportation Composite Group (55-028H), 1-4
Watercraft Maintenance Teams (55-550H)
Diver Team (55-550HIA), 5-10
Floating Craft Maintenance Team (General Support) (55-550HIB), 5-10
Lighterage Maintenance Team (Direct Support) (55-550HIC, 5-11
Watercraft Teams (55-530H)
Barge Crane, 68-ton (55-530HFH), 5-9
Barge Crane, 100-ton (55-530HFI), 5-9
Beach discharge Lighter (55-530HFM), 5-9
Deck Cargo Barge, Nonpropelled (55-530HFA), 5-8
Deck or Liquid Cargo Barge, 120-ft, Nonpropelled (55-530HFC), 5-9
Harbor Tug, 70 ft. (55-530HFG), 5-9
Harbor Tug, 100 ft. (55-530HFJ), 5-9

WWW.SURVIVALEBOOKS.COM

Lighter, Amphibian, LARC-LX (55-530HFN), 5-10
Liquid or Dry Cargo Barge, Self-Propelled (55-530HFL), 5-9
Oceangoing Tug, 126 ft. (55-530HFK), 5-9
Oceangoing Tug, 143 ft. (55-530HFO), 5-10
Picketboat, 46 ft. (55-530HFB), 5-8
Passenger and Cargo or Picketboat, 65 ft. (55-530HFE), 5-9
Refrigerated Cargo Barge, 120 ft. Non-propelled (55-530HFF), 5-9
Truck axle weights, 3-74
Truck body dimensions, 3-82
Truck cargo bed dimensions, 3-82
Truck center of balance, 3-80
Truck companies (see transportation units)
Truck performance data, 3-70
Truck terminals, 3-25
Tug, harbor
65-foot, 5-40
100-foot, 5-40
Turnaround time, 3-23
Type X route, 3-45
Type Y route, 3-45
Type Z route, 3-45

U-8, 2-33
U-21, 2-33
UH-1, 2-34
UH-60, 2-34
Unimproved water terminal, 5-24
Unit capability planning, 3-22
Unit lift, 3-22
Unloading time, 3-22
U.S. Army vessels, 5-34, 5-38

Vehicle axle weights, 3-74
Vehicle capabilities, planning, 3-22
Vehicle center of balance, 3-80
Vehicle classification markings, 3-42
Vehicle load placement, 3-31
Vehicle performance data, 3-70
Vehicle stopping distances, 3-91
Vessel, liquid cargo, 5-38
Vessels
Army
Characteristics, 5-35 thru 5-37
Designations, 5-34
Navy
Designations, 5-32
Vessel berthing/anchorage, 5-15, 5-21
Vessel loading, 5-18

Watercraft, 5-32
Water operations, 5-1
Water port index and information, 5-12
Water terminals, 5-12
Water terminal capacity, 5-15, 5-21
Weather resistance, 4-11
West German freight car characteristics, 4-29
Whyte system, 4-21
World Port Index, 5-12

Yard tractor, 5-45

Zulu time, B-24